

SEISMIC RESILIENCY ANALYSIS REPORT

B&V PROJECT NO. 406828

PREPARED FOR



City of Salem

AUGUST 2023



City of Salem

Seismic Resiliency Analysis Report

This Report has been prepared by or under the direct supervision of
Lani Good, P.E., Black & Veatch Corporation.

Professional
Engineer:

Lani Good
Signature

August 2023
Date

Lani Good
Printed Name

91834PE
License No.



Table of Contents

| | |
|--|------------|
| Executive Summary | 1 |
| 1.0 Introduction | 1-1 |
| 1.1 Water System Description | 1-1 |
| 1.2 Project Overview | 1-2 |
| 1.3 Study Limitations | 1-2 |
| 1.4 Background Information | 1-2 |
| 2.0 Level of Service Goals | 2-1 |
| 2.1 Purpose | 2-1 |
| 2.2 Standards and References | 2-2 |
| 2.3 Level of Service Workshop | 2-2 |
| 2.4 Community Needs Following a Major Earthquake | 2-3 |
| 2.5 Level of Service Components | 2-5 |
| 2.5.1 Functional Categories | 2-5 |
| 2.5.2 Target Time Frames for Recovery | 2-6 |
| 2.5.3 Restoration Levels | 2-6 |
| 2.6 Level of Service Goals | 2-6 |
| 3.0 Water System Backbone Definition | 3-1 |
| 3.1 Water System Backbone Workshops | 3-1 |
| 3.2 Water Supply Points for Fire Suppression | 3-1 |
| 3.3 Critical Social/Economic Needs | 3-1 |
| 3.3.1 Emergency Shelters | 3-2 |
| 3.3.2 Community Water Distribution Points | 3-3 |
| 3.3.3 Vulnerable Populations | 3-4 |
| 3.4 Water Facility Criticality Levels | 3-4 |
| 3.5 Water System Backbone | 3-6 |
| 3.6 Considerations and Future Coordination Efforts | 3-8 |
| 4.0 Water System Seismic Vulnerability Assessment | 4-1 |
| 4.1 Geohazards | 4-1 |
| 4.1.1 Pipeline Geohazards | 4-1 |
| 4.1.2 Priority Vertical Facility Geohazards | 4-2 |
| 4.1.3 Vertical Facility Hazard Rankings | 4-3 |
| 4.2 Pipeline Vulnerability Assessment | 4-5 |
| 4.2.1 Pipeline Joint Assumptions | 4-5 |
| 4.2.2 Pipeline Failure Assessment | 4-6 |
| 4.2.3 Willamette River Crossing Vulnerabilities | 4-7 |
| 4.3 Vertical Facilities Vulnerability Assessment | 4-8 |
| 4.3.1 Facility Assessment Summary | 4-8 |

| | | |
|------------|--|------------|
| 4.3.2 | Facility Seismic Deficiencies | 4-9 |
| 5.0 | Water System Risk Assessment | 5-1 |
| 5.1 | Risk Assessment of Pipelines and Vertical Facilities | 5-1 |
| 5.1.1 | Consequence of Failure..... | 5-1 |
| 5.1.2 | Likelihood of Failure for Pipelines | 5-2 |
| 5.1.3 | Risk Assessment for Vertical Facilities | 5-2 |
| 6.0 | Water System Risk Mitigation Plan..... | 6-1 |
| 6.1 | Capital Program Prioritization Methodology..... | 6-1 |
| 6.2 | Basis for Establishing Opinion of Probable Construction Costs..... | 6-2 |
| 6.2.1 | OPCC Assumptions for Pipelines | 6-2 |
| 6.2.2 | OPCC Assumptions for Vertical Facilities | 6-3 |
| 6.3 | Pipeline System Prioritization and Cost Projections..... | 6-4 |
| 6.3.1 | Prioritization Approach | 6-4 |
| 6.3.2 | Pipeline Mitigations | 6-5 |
| 6.3.3 | Cost Projections | 6-7 |
| 6.4 | Vertical Facilities Prioritization and Cost Projections | 6-8 |
| 6.4.1 | Prioritization Approach | 6-8 |
| 6.4.2 | Vertical Facility Mitigations..... | 6-8 |
| 6.4.3 | Cost Projections | 6-13 |
| 6.5 | Seismic Capital Recommendations Summary..... | 6-14 |
| 6.6 | Opportunities for Further Study and System Improvements..... | 6-14 |
| 7.0 | References..... | 7-1 |

LIST OF TABLES

| | | |
|------------|--|-----|
| Table ES-1 | Level of Service Goals following a CSZ Earthquake for City of Salem..... | 2 |
| Table ES-2 | Seismic Hazard Rankings for Critical Vertical Facilities..... | 3 |
| Table ES-3 | Pipeline Failures for PGD, PGV, Total..... | 4 |
| Table ES-4 | Seismic Improvements Phasing and Cost Summary..... | 5 |
| Table 2-1 | Phased Recovery of the Built Environment (2016 NIST CRPG)..... | 2-2 |
| Table 2-2 | Social/Economic Needs of the Community | 2-3 |
| Table 2-3 | Water System Functional Categories..... | 2-5 |
| Table 2-4 | Level of Service Restoration Levels..... | 2-6 |
| Table 2-5 | Level of Service Goals | 2-7 |
| Table 3-1 | Potential Emergency Shelter Locations | 3-2 |
| Table 3-2 | Community Water Distribution Points | 3-4 |
| Table 3-3 | Water Facility Criticality/Consequence of Failure Level Definitions..... | 3-5 |
| Table 3-4 | Storage and Pumping Facility Criticality Levels..... | 3-5 |

| | | |
|------------|--|------|
| Table 4-1 | Potable Water Pipelines Subject to Seismically-Induced Ground Movement | 4-1 |
| Table 4-2 | Facilities Assessed as Part of this Study | 4-2 |
| Table 4-3 | Seismic Hazard Rankings for Critical Vertical Facilities | 4-3 |
| Table 4-4 | Pipe Material, Length, Joint Type, and K1 and K2 Values | 4-5 |
| Table 4-5 | Pipeline Failures for PGD, PGV, and Total | 4-7 |
| Table 4-6 | Pump Station and Control Facility Deficiency Summary | 4-10 |
| Table 4-7 | Reservoirs Deficiency Summary | 4-11 |
| Table 4-8 | Facility Assessment Summary | 4-12 |
| Table 5-1 | Likelihood of Failure Scores for Pipelines | 5-2 |
| Table 5-2 | Risk Assessment for Vertical Facilities | 5-2 |
| Table 6-1 | Capital Program Terms and Priorities | 6-1 |
| Table 6-2 | Markups Associated with OPCC for Pipelines | 6-3 |
| Table 6-3 | OPCC Markups for Vertical Facilities | 6-4 |
| Table 6-4 | Pipeline Risk Matrix | 6-5 |
| Table 6-5 | Pipe Replacement Material Selection | 6-6 |
| Table 6-6 | OPCC Assumed Replacement Materials for Pipelines | 6-7 |
| Table 6-7 | Summary of Recommended Mitigations Measures at Reservoirs | 6-8 |
| Table 6-8 | Summary of Pump Station and Control Facilities Recommendations | 6-10 |
| Table 6-9 | Short- and Medium-Term Vertical Facility CIP Projections | 6-13 |
| Table 6-10 | Seismic Improvements Phasing and Cost Summary | 6-14 |

LIST OF FIGURES

| | | |
|------------|--|-----|
| Figure 1-1 | Salem's Water System | 1-1 |
| Figure 2-1 | Resilience Triangle | 2-1 |
| Figure 3-1 | Temporary Water Distribution Point at the Oregon State Fairgrounds, June 1, 2018 | 3-3 |
| Figure 3-2 | Water System Backbone | 3-7 |
| Figure 5-1 | Range of Potential Risk Scores | 5-1 |
| Figure 6-1 | Summary of Pipeline Costs in Each Risk Category | 6-7 |

APPENDICES

| | | |
|-------------|---|-----|
| Appendix A. | Critical Social/Economic Needs | A-1 |
| Appendix B. | Seismic Geohazard Evaluation Report | B-1 |
| Appendix C. | Pump Station and Reservoir Seismic Vulnerability Assessment | C-1 |
| Appendix D. | Facility Vulnerability Assessment Summary | D-1 |
| Appendix E. | Facilities Cost Estimate Summary | E-1 |

List of Abbreviations

| | |
|----------------|---|
| 2013 ORP | 2013 Oregon Resilience Plan |
| 2016 NIST CRPG | 2016 Community Resilience Planning Guide for Buildings and Infrastructure Systems by the National Institute of Standards and Technology |
| AACE | Association for the Advancement of Cost Engineering |
| ALA | American Lifelines Alliance |
| ASCE | American Society of Civil Engineers |
| ASR | Aquifer Storage and Recovery |
| ADD | Average Daily Demand |
| CIP | Capital Improvement Plan |
| CIPP | Cured-in-Place Pipe |
| City | City of Salem |
| CMU | Concrete Masonry Unit |
| COF | Consequence of Failure |
| CSZ | Cascadia Subduction Zone |
| DIP | Ductile Iron Pipe |
| DOGAMI | Oregon Department of Geology and Mineral Industries |
| GIS | Geographic Information System |
| HDPE | High Density Polyethylene |
| LF | Linear Feet |
| LOF | Likelihood of Failure |
| LOS | Level of Service |
| MG | Million-Gallon |
| OAR | Oregon Administrative Rule |
| ODOT | Oregon Department of Transportation |
| OH&P | Overhead and Profit |
| OHA | Oregon Health Authority |
| O&M | Operations and Maintenance |
| OPCC | Opinion of Probable Construction Cost |
| PGD | Permanent Ground Deformation |
| PGV | Peak Ground Velocity |
| PVC | Polyvinyl Chloride |
| PVCO | Molecularly Oriented Polyvinyl Chloride |
| SCR | Structural Clay Research |
| SEFT | SEFT Consulting Group |
| USGS | U. S. Geological Survey |
| WTP | Water Treatment Plant |

Executive Summary

The Oregon Health Authority (OHA), under Oregon Administrative Rule (OAR) 333-061-0060(5)(a)(J), requires community water systems with greater than 300 connections to develop a seismic resiliency assessment and mitigation plan. The plan needs to be a component of the Water System Master Plan which the City of Salem (City) is concurrently preparing. This Seismic Resiliency Analysis Report (Report) is intended to satisfy this requirement.

OHA recommendations are aimed at mitigating the impacts of a potential occurrence of a Magnitude 9.0 (M9.0) Cascadia Subduction Zone (CSZ) earthquake. Following a CSZ earthquake event, the City's water system could suffer significant damage, which can cause service disruptions, public safety hazards, and impact firefighting capabilities. The primary objectives of this Report are to:

1. Establish level of service (LOS) goals to assist the City in prioritizing restoration of functionality to support the community's most vital social and economic needs;
2. Identify infrastructure (both pipelines and facilities) needed to supply water to critical customers and locations after an earthquake emergency – also called the water system backbone;
3. Assess seismic hazards, such as shaking and ground displacement, liquefaction, and lateral spreading, and their likelihood to impact critical infrastructure;
4. Assess the expected seismic performance of the backbone pipelines and selected facilities; and
5. Identify preliminary recommendations for system improvements that should be implemented to restore water service more rapidly after a major earthquake to meet social and economic needs.

The City established LOS goals which define both customers and water system functions that will need to be operational within the short term (1 to 7 days), intermediate-term (within 4 weeks), and long-term (within months) following a CSZ earthquake. LOS goals are summarized in Table ES-1. The colors and corresponding letters below signify red for minimal, yellow for functional, and green for operational. These are explained in further detail in Table 2-4,

Table ES-1 Level of Service Goals following a CSZ Earthquake for City of Salem

| Water Components | % "Operational" Scale/Scenario | Target Time Frame for Recovery | | | | | | | |
|--|--|--------------------------------|-----|-----|----------------------------------|-----|------|--------------------------|------|
| | | Phase 1: Short Term | | | Phase 2: Intermediate Term | | | Phase 3: Long Term | |
| | | Days | | | Weeks | | | Months | |
| | | 0-1 | 1-3 | 3-7 | 1-2 | 2-4 | 4-12 | 3-6 | 6-12 |
| Source | | | | | | | | | |
| Raw or source water and terminal reservoirs | % of winter average day demand (ADD) | R | Y | | G | | | | |
| Raw water conveyance (pump stations and piping to WTP) | % of winter ADD | R | Y | | G | | | | |
| Water production (flow rate) | % of winter ADD | R | Y | | G | | | | |
| Well and/or treatment operations functional (quality) | Minimum water quality objectives met | R | Y | | G | | | | |
| Transmission (including Booster Stations) | | | | | | | | | |
| Backbone transmission facilities (pipelines, pump stations, and tanks) | Supporting critical facilities and fire flow | G | | | | | | | |
| Water for fire suppression at key supply points (to promote redundancy) | % of fire flow x duration | G | | | | | | | |
| Control Systems & Instrumentation | | | | | | | | | |
| SCADA and other control systems (WTP and boosters) | % of components for normal operation | Y | G | | | | | | |
| Distribution | | | | | | | | | |
| Critical Facilities | | | | | | | | | |
| Wholesale Customer - City of Turner | % of winter ADD | Y | G | | | | | | |
| Critical City, community, and state facilities identified as having a short-term (no disruption) recovery goal in Table 2-2 | % of winter ADD | G | | | | | | | |
| Critical City, community, county, and state facilities identified as having a short term (1-3 days) recovery goal in Table 2-2 | % of winter ADD | Y | G | | | | | | |
| Emergency Housing | | | | | | | | | |
| Emergency shelters | % of water for drinking & sanitation | Y | G | | | | | | |
| Housing/Neighborhoods | | | | | | | | | |
| Potable water available at community distribution centers | % of water for drinking & sanitation | | Y | G | | | | | |
| Water for fire suppression at fire hydrants | % of hydrants | | | R | Y | G | | | |
| Community Recovery Infrastructure | | | | | | | | | |
| All other customers | % of customers | | R | Y | G | | | | |

The water system backbone was defined to more clearly lay out portions of the water system that are critical to provide short-term functionality and to define potential emergency shelters, community water distribution points, and vulnerable populations. To define the water system backbone, the City first established criticality levels for vertical facilities and distribution and transmissions system pipelines. A water system backbone map is provided in Section 3.0.

Both water system pipeline and vertical facilities were assessed for their vulnerability to earthquake damage, based on the characteristics of the facility or pipeline (such as bracing or joints) and the mapped geohazards from a 2021 Seismic Geohazard Evaluation Report completed by Shannon & Wilson. Table ES-2 summarizes the seismic hazard rankings for critical vertical facilities assessed by Shannon & Wilson.

Table ES-2 Seismic Hazard Rankings for Critical Vertical Facilities

| Site ID | Locations | Site Class ¹ | Liquefaction Settlement Hazard ² | Landslide Hazard ² | Fault Rupture Hazard ² |
|---------|---|-------------------------|---|-------------------------------|-----------------------------------|
| 1 | Salem-Keizer Intertie/Cherry Ave Booster Pump Station | D | M | L | L |
| 2 | Grice Hill Reservoir and Repeater Tower | B | L | L | L |
| 3 | Hemlock Well ³ | B | L | L | L |
| 4 | Mountain View Reservoir and Pump Station | B | L | L | L |
| 5 | EOLA 1B Reservoir ³ | B | L | M | L |
| 6 | Limelight Pump Station ³ | B | L | L | L |
| 7 | Fairmount Reservoir ³ | B | L | L | L |
| 8 | Candalaria Reservoir | B | L | L | L |
| 9 | South Salem Repeater Tower | B | L | L | L |
| 10 | Croisan Lower Pump Station ³ | C/D | M | H | L |
| 11 | Edwards S1 Pump Station ⁴ | D | H | M | L |
| 12 | ASR Wells ³ | B | L | L | L |
| 13 | Skyline Repeater Tower ³ | B | L | L | L |
| 14 | Lone Oak Reservoir | B | L | L | L |
| 15 | Creekside Pump Station ³ | B | L | L | L |
| 16 | Champion Hill Reservoir | B | M | M | L |
| 17 | Boone Road Pump Station ³ | D | L | L | L |
| 18 | Deer Park Pump Station | B | L | L | L |
| 19 | Mill Creek Reservoir | B | L | L | L |

| Site ID | Locations | Site Class ¹ | Liquefaction Settlement Hazard ² | Landslide Hazard ² | Fault Rupture Hazard ² |
|--|---|-------------------------|---|-------------------------------|-----------------------------------|
| 20 | Turner Control Facility | D | L | L | L |
| 21 | Franzen Reservoir and Repeater Tower ⁴ | B | L | H | M |
| 22 | Geren Island WTP | D | L | L | L |
| ¹ Site classified as Site Class A, B, C, D, E or F based on the site soil properties in accordance with Chapter 20 of ASCE 7. ² L = Low, M = Moderate, H = High ³ Sites did not have subsurface exploration data. Nearby well logs could not be found for these sites. Therefore, the risk assessments for these facilities are based on regional seismic hazard mapping only. ⁴ Geologic maps may not adequately capture geohazards for locations indicated. Refer to the Shannon and Wilson 2021 Seismic Geohazard Evaluation Report for more discussion on this topic. | | | | | |

Table ES-3 summarizes the pipeline failures by permanent ground deformation (PGD) and peak ground velocity (PGV) .

Table ES-3 Pipeline Failures for PGD, PGV, Total

| PGD-Related Failures | | | PGV-Related Failures | | | Total Failures (Breaks + Leaks) |
|----------------------|-------|------------------------------------|----------------------|-------|------------------------------------|------------------------------------|
| Breaks | Leaks | Total Failures (Breaks + Leaks) | Breaks | Leaks | Total Failures (Breaks + Leaks) | |
| 3360 | 840 | 4200 | 11 | 46 | 57 | 4257 |

Finally, recommended risk mitigation efforts and their associated costs were developed according to the City's LOS goals. In the **short term**, the City should focus on implementing mitigation that will help to preserve water in the system or to convey water to the backbone after an earthquake. As a priority, the City should implement the following strategies:

- Installation of seismic isolation valves installed at all reservoirs (the City already has seismic valves installed on a significant number of them) and seismic upgrades on the "very high" to "moderate" risk reservoirs and their control buildings.
- Seismic upgrades to pump stations which are appurtenant to reservoirs.

The City should also focus on conveyance of treated water to the backbone, by hardening the transmission lines from Geren Island Water Treatment Plant (WTP) to critical reservoirs, including to West Salem. The City should also implement providing alternative water supplies within this phase. Alternative local water supply development (such as drilling of new wells to access groundwater supplies) will provide additional supply reliability in the case of an emergency. The City should also complete studies to understand system vulnerability and risk at vertical facilities not assessed as part of this study, such as Franzen Reservoir. As part of the short-term phase, all "moderate" to "very high" risk facilities should be seismically improved, and all "moderate to high" to "very high" risk pipelines should be hardened.

In the **medium term**, the City should focus on hardening the rest of the backbone system so that the system will remain operational following a major earthquake. "Low to moderate" and "low" risk facilities should be seismically improved, and "moderate" and "low to moderate" risk pipelines (all remaining pipelines within the backbone system) should be hardened.

In the **long term**, the City should focus on hardening the rest of the distribution system to address the LOS goals discussed in Section 2.0. The City aims to serve a minimum of 80% of all customers within 1 to 2 weeks following a M9.0 CSZ earthquake. A limited number of breaks and leaks can be repaired by City crews in the days and weeks following an earthquake. To reduce the number of breaks and leaks down to an amount that can be quickly repaired by the City following an earthquake, and to meet the LOS goals, the City would need to replace most "low" risk pipelines.

A summary of the priorities and total costs for the short, medium, and long term are presented in Table ES-4. These costs were developed to the Class 5 (conceptual) level of accuracy, as defined by the Association for the Advancement of Cost Engineering (AACE), and expected to have an accuracy range from -30% to +50% of actual (2022) costs.

Table ES-4 Seismic Improvements Phasing and Cost Summary

| Term | Priority | Risk Level of Facilities To Be Improved | Risk Level of Pipelines To Be Improved |
|---------------------------|---|---|--|
| Short (0 – 15 Years) | 1. Preserve Water in the System 2. Convey Treated Water 3. Implement Alternative Supplies 4. Complete Studies to Refine Understanding of Expected System Performance | Very High | Very High |
| | | High | High |
| | | Moderate to High | Moderate to High |
| | | Moderate | |
| Total Cost (Short Term) | | \$8.61 – 12M | \$1.82B |
| Medium (10 – 25 Years) | 5. Harden the Rest of the Backbone | Low to Moderate | Moderate |
| | | Low | Low to Moderate |
| Total Cost (Medium Term) | | \$0.41 – 0.90M | \$0.56B |
| Long (20 – 50 years) | 6. Harden Distribution System to Reduce the Number of Repairs | - | Low |
| Total Cost (Long Term) | | \$0 | \$1.27B |

1.0 Introduction

The Oregon Health Authority (OHA), under Oregon Administrative Rule (OAR) 333-061-0060(5)(a)(J), requires community water systems with greater than 300 connections to develop a seismic resiliency assessment and mitigation plan. The plan needs to be a component of the Water System Master Plan which the City of Salem (City) is concurrently preparing. This Seismic Resiliency Analysis Report (Report) is intended to satisfy this requirement.

1.1 Water System Description

The City's water system currently consists of the City's water transmission pipelines, the Geren Island WTP, water storage reservoirs, pump stations, and distribution system pipelines. The City relies on the North Santiam River to supply water for the City's approximately 200,000 customers. Water from North Santiam River flows to Detroit Lake, which eventually feeds the Geren Island WTP raw water intake, as shown on Figure 1-1.



Figure 1-1 Salem's Water System¹

Large-diameter transmission pipelines deliver water from the Geren Island WTP to the 92-million-gallon (MG) Franzen Reservoir located in the City of Turner and, subsequently, the City's transmission and distribution system. The City's transmission and distribution system is supported by numerous pump stations and storage reservoirs within and adjacent to the City's service area. The City also operates four aquifer storage and recovery (ASR) wells in Woodmansee Park that supplement the water supply.

¹ Source: <https://online-voice.net/salemgereenisland/>, December 2022.

1.2 Project Overview

Following a Cascadia Subduction Zone (CSZ) earthquake, the City's water system could potentially suffer significant damage, which can cause service disruptions, public safety hazards, and impact firefighting capabilities. This Report serves the following primary objectives:

1. Establish LOS goals to assist the City in prioritizing restoration of functionality to support the community's most vital social and economic needs;
2. Identify infrastructure (both pipelines and facilities) needed to supply water to critical customers and locations after an earthquake emergency – also called the water system backbone;
3. Assess seismic hazards, such as shaking and ground displacement, liquefaction, and lateral spreading, and their likelihood to impact critical infrastructure;
4. Assess the expected seismic performance of the backbone pipelines and selected facilities; and
5. Identify preliminary recommendations for system improvements that should be implemented to restore water service more rapidly after a major earthquake to meet social and economic needs.

This Report analyses a subset of the following assets:

- Storage reservoirs.
- Pump stations.
- ASR wells.
- Pipelines (including pressure relief valves).
- Major control features (Turner Control Facility).

1.3 Study Limitations

The recommendations presented in this Report were developed with the standard of care commonly used for the profession. No other warranties are included, either expressed or implied, as to the professional advice included in this Report. This Report has been prepared for the City, to be used solely in its evaluation of the seismic safety of the water system components referenced. This Report has not been prepared for use by other parties and may not contain sufficient information for purposes of other parties or uses.

1.4 Background Information

The following available information was used as a part of this Report:

- 2021 Seismic Geohazard Evaluation Report completed by Shannon & Wilson.
- Geographic Information System (GIS) data including land use, tax lots, water system, etc., dated September 2020 and May 2021.
- Relevant reports pertaining to the City's water system and emergency management measures, including the 2003 Emergency Operations Plan, 1999 and 2014 Salem Emergency Management Plan, the 2020 American Water Infrastructure Act Risk and Resilience Assessment, 2004 Salem Water System Master Plan, 2019 Water Management and Conservation Plan, 2017 Natural Hazards Mitigation Plan.

- Selected record drawings of critical City water system facilities.
- Available seismic evaluations and seismic studies of the City's water system facilities.
- Maps of the City's reservoirs, pump stations, treatment, distribution systems, and upper and lower transmission maps.
- Field reconnaissance performed in 2021 by Black & Veatch and its subconsultant, SEFT Consulting Group (SEFT), at critical facilities and the Center Street and Marion Street Bridges.
- Meetings and workshops with City staff, conducted in 2021 and 2022, to discuss critical facilities, LOS, the water system backbone, geohazards, system vulnerability, and system mitigation and improvements.
- Meetings with key stakeholders, including Marion County, Polk County, the State of Oregon, and the City Fire Department.
- 2001 American Lifelines Alliance (ALA), Seismic Fragility Formulations for Water Systems (ALA, 2001), which is used widely for pipeline vulnerability assessments.
- Geohazards datasets, including Earthquake Hazard Maps of the Salem East and Salem West Quadrangles, Marion and Polk Counties, Oregon (GMS-105; Wang and Leonard, 1996); the Oregon Geologic Data Compilation Release 5; Statewide Landslide Information Database for Oregon Release 2 (Burns and others, 2011); the bedrock ground motions included in the publication provided to the Oregon Department of Geology and Mineral Industries (DOGAMI) by the U.S. Geological Survey (USGS) based on the USGS Cascadia M 9.0 scenario ShakeMap®; Seismic Hazard Maps based on the Magnitude 9.0 CSZ scenario defined in the Oregon Resilience Plan; and local geological information compiled by Shannon & Wilson.

2.0 Level of Service Goals

LOS goals establish target post-earthquake restoration timeline expectations for buildings, water system components, and customer groups based on supporting the community's social and economic needs after an earthquake. This section presents a definition of LOS goals and highlights special considerations based on City-specific circumstances.

2.1 Purpose

LOS goals, paired with a detailed understanding of the water system backbone, will be used to help identify the gaps between the system's anticipated performance and the City's desired performance during disaster recovery (NIST, 2016). Therefore, in addition to helping to establish a "triage" response to disaster recovery by assigning degrees of urgency to key system components, these LOS goals will also be used to prioritize improvements that address performance deficiencies (defined in the Risk Mitigation Plan in Section 6.0).

LOS goals establish a phased approach to restoring water system operation (in terms of both water quantity and quality) in the days, weeks, and months after a major earthquake and help the City prioritize restoration of functionality. Fifty to 60% of businesses in Oregon are small businesses that can only tolerate 2 to 4 weeks of disruption of essential services.

A system with low resilience requires a longer recovery time, resulting in more interruption in lifeline services, as shown on Figure 2-1. Pre-disaster mitigation; disaster preparedness; and a phased, prioritized approach to recovery can help to shorten recovery time and build resilience for essential services.




Figure 2-1 Resilience Triangle²

² Source: Wang, et al., 2012

2.2 Standards and References

Two key references were considered when developing City-specific LOS goals:

- The 2013 Oregon Resilience Plan (2013 ORP) developed by the Oregon Seismic Safety Policy Advisory Commission, which provides a roadmap for reducing risk and improving recovery after a CSZ earthquake. The 2013 ORP suggests performance goals for the time required to restore water services to affected communities in the aftermath of a CSZ earthquake.
- The 2016 Community Resilience Planning Guide for Buildings and Infrastructure Systems by the National Institute of Standards and Technology (2016 NIST CRPG). This document establishes a resilience planning process which involves determining a community's resilience goals and objectives. It also includes refinement for LOS categories (versus the categories included in the 2013 ORP) to more transparently cluster assets into groups based upon their functions and the degree of urgency for restoring their functions.

A phased approach to disaster recovery (shown in Table 2-1) considers those primary functions that are necessary in three key phases following the disaster: short term (days), intermediate term (weeks), and long term (months). LOS goals are defined both in terms of the estimated time for recovery as well as the target functionality of the system. Different levels of functionality are necessary at different phases of recovery to meet the customers' life-safety needs in the short term, social needs in the intermediate term, and economic recovery needs in the long term.

Table 2-1 Phased Recovery of the Built Environment (2016 NIST CRPG)

| Phase | Primary Functions | Associated Infrastructure Clusters |
|---------------------------|--|--|
| Short Term (Days) | Secure, rescue, stabilize, clear routes | Critical facilities, emergency housing, related infrastructure systems |
| Intermediate Term (Weeks) | Restore neighborhoods, meet social needs | Housing, medical, main street, schools, churches, related infrastructure systems |
| Long Term (Months) | Community social and economic recovery | Commercial businesses, industrial businesses, related infrastructure systems |

2.3 Level of Service Workshop

The project team conducted a LOS workshop with the City's Public Works staff on October 13, 2020 and continued on October 29, 2020. At this workshop, the team provided an overview of resilience planning, discussed several examples of other resilience plans, and discussed LOS goals. The objective of the workshop was to establish a mutual understanding of seismic resilience and resilience planning for water infrastructure and to set LOS goals for water system components and customer groups based on supporting the community's social and economic needs after an earthquake.

At the workshop, the following topics were discussed and defined to establish LOS goals for each asset category:

1. Categories of critical facilities that need water after an earthquake emergency;
2. Measurement of operational service performance; and
3. Emergency response coordination efforts with state, county, City fire department or other emergency services, and retail water agencies.

2.4 Community Needs Following a Major Earthquake

Table 2-2 provides a breakdown of restoration priorities for City customers that was developed jointly in collaboration with City staff and other state and county stakeholders. Table 2-2 links social/economic needs to service recovery goals.

Table 2-2 Social/Economic Needs of the Community

| Recovery Phase | Social/Economic Needs | |
|-------------------------------|--|--|
| Short Term (no disruption) | City/Community Services | <ul style="list-style-type: none"> • Water for fire suppression at key supply points • Salem Health Hospital • Dialysis centers |
| | State of Oregon Services | <ul style="list-style-type: none"> • Anderson Readiness Center • Department of Public Safety Standards and Training Campus • State Data Center • Oregon State Hospital |
| | Wholesale Customers | <ul style="list-style-type: none"> • City of Turner |
| Short Term (1-7 days) | City/Community Services | <ul style="list-style-type: none"> • City Police Department • Willamette Valley Communications Center • City Fire Stations¹ • City Hall • City Shops Complex • Salem Municipal Airport • City Main Library • Community water distribution points¹ • Emergency shelters¹ <ul style="list-style-type: none"> ○ High schools ○ Middle schools ○ Colleges • Vulnerable populations¹ <ul style="list-style-type: none"> ○ Special needs facilities ○ Rehabilitation facilities ○ Senior care facilities • Urgent care centers¹ <ul style="list-style-type: none"> ○ Salem Clinic ○ Salem Health Urgent Care ○ SwiftCare LLC ○ Urgent Care Clinic South ○ Urgent Care Kaiser Permanente North Lancaster ○ ZOOM+Care |
| | Marion County Services (exact locations should be coordinated between county and City staff) | <ul style="list-style-type: none"> • Marion County Sheriff's Office • Marion County Correctional Facility • Marion County Office Building • Marion County Health & Human Services Building |

| Recovery Phase | Social/Economic Needs | |
|--|----------------------------|---|
| Short Term (1-7 days) | State of Oregon Services | <ul style="list-style-type: none"> • Oregon National Guard Army Aviation Support Facility • Oregon Department of Aviation • Oregon State Police/Oregon State Fire Marshall • Oregon Department of Transportation (ODOT) Campus • State Motor Pool • Department of Forestry Campus • Department of Corrections <ul style="list-style-type: none"> ○ Mill Creek Correctional Facility ○ Oregon State Correctional Institute ○ Oregon State Penitentiary ○ Santiam Correctional Institute • State Buildings around Capitol Mall <ul style="list-style-type: none"> ○ State Capitol ○ State Library ○ State Supreme Court Building ○ Department of Administrative Services ○ Transportation Building (ODOT) ○ Department of Energy Building ○ Public Services Building ○ Barbara Roberts Human Service Building ○ Public Utilities Commission Building • State Fair Grounds • Treasury Building • Lottery |
| Intermediate Term (within 4 weeks) | City/County/State Services | <ul style="list-style-type: none"> • Remaining City/County/State service facilities • School district facilities |
| | Wholesale Customers | <ul style="list-style-type: none"> • Suburban East Salem Water District • Orchard Heights Water Association |
| | Retail Customers | <ul style="list-style-type: none"> • Medical office buildings • 90% of businesses, residential customers, fire hydrants |
| Long Term (months) | Retail Customers | <ul style="list-style-type: none"> • Remaining 10% of customer connections and fire hydrants |
| ¹ Critical facilities were determined by a desktop assessment performed in collaboration with City staff. Further vetting and assessment of these locations will occur following this report, to finalize the list of critical fire stations, community water distribution points, emergency shelters, vulnerable populations, and urgent care centers. | | |

The recovery phase goals in Table 2-2 have been established based on our current understanding of the community's social and economic needs, without consideration or knowledge of the current expected seismic performance of these existing community facilities. To support community social and economic needs on a similar timeline to that proposed for the water system, many of these community facilities may need to be relocated, seismically retrofitted, or replaced with new facilities that are designed with a higher structural and non-structural performance objective.

2.5 Level of Service Components

This section describes the three components of LOS goals: 1) water system functional categories, 2) target time frames for recovery, and 3) restoration levels.

2.5.1 Functional Categories

The City's water system is grouped into four functional categories, as shown in Table 2-3. The four categories are based upon the 2016 NIST CRPG: Source, Transmission, Control Systems & Instrumentation, and Distribution. Distribution is further broken down into four subcategories: Critical Facilities, Emergency Housing, Housing/Neighborhoods, and Community Recovery Infrastructure. Water system categorization helps to facilitate assigning target time frames for recovery by asset class and function, not by individual asset.

Table 2-3 Water System Functional Categories

| Functional Category | System Components | Description |
|--|---|--|
| Source | Raw or source water and terminal reservoirs | Water source itself before intake facilities |
| | Raw water conveyance | Pump stations and piping to WTP |
| | Water production | Production flow rate |
| | Well and/or treatment operations | Water quality |
| Transmission (including Booster Stations) | Backbone transmission facilities | Pipelines, pump stations, and tanks |
| | Water for fire suppression at key supply points | Reservoirs, hydrants on the backbone, temporary water sources to promote redundancy |
| Control Systems & Instrumentation | SCADA and other control systems | Server and communication facilities (WTP vs. booster stations) |
| Distribution | Critical facilities | Wholesale customers, hospitals, emergency operations centers, vulnerable populations |
| | Emergency housing | Emergency shelters |
| | Housing/Neighborhoods | Potable water available at community distribution centers; Water for fire suppression at fire hydrants |
| | Community Recovery Infrastructure | All other customers |

2.5.2 Target Time Frames for Recovery

There are three recovery phases that have target time frames for water system recovery:

- Recovery Phase 1 – Short Term (0-7 days)
- Recovery Phase 2 – Intermediate Term (1-12 weeks)
- Recovery Phase 3 – Long Term (3-12 months)

2.5.3 Restoration Levels

Descriptions of suggested LOS restoration levels (adapted from the 2013 ORP) are shown in Table 2-4.

Table 2-4 Level of Service Restoration Levels

| Restoration Stage and Description | Operational Level | Symbology |
|--|-----------------------|-----------|
| Minimal: A minimum LOS is restored, primarily for use of emergency responders, repair crews, and in support of critical health and human services. | 20-30% Operational | Red |
| Functional: Although service is not yet restored to full pre-event capacity, it is sufficient to get the economy moving again. Limits may be placed on uses that take up a lot of capacity. | 50-60% Operational | Yellow |
| Operational: A full LOS has been restored and is sufficient to allow people to use the system for non-essential activities | 80-90% Operational | Green |

2.6 Level of Service Goals

The LOS categories and their respective target time frames for recovery agreed upon in the LOS workshop are presented in Table 2-5. The City also determined the units by which the percentage (%) of operational level could be measured. These units vary by asset, or group of assets, and are summarized in Table 2-5.

Table 2-5 Level of Service Goals

| Water Components | % "Operational" Scale/Scenario | Target Time Frame for Recovery | | | | | | | |
|--|--|--------------------------------|-----|-----|----------------------------|-----|------|--------------------|------|
| | | Phase 1: Short Term | | | Phase 2: Intermediate Term | | | Phase 3: Long Term | |
| | | Days | | | Weeks | | | Months | |
| | | 0-1 | 1-3 | 3-7 | 1-2 | 2-4 | 4-12 | 3-6 | 6-12 |
| Source | | | | | | | | | |
| Raw or source water and terminal reservoirs | % of winter average day demand (ADD) | R | Y | | G | | | | |
| Raw water conveyance (pump stations and piping to WTP) | % of winter ADD | R | Y | | G | | | | |
| Water production (flow rate) | % of winter ADD | R | Y | | G | | | | |
| Well and/or treatment operations functional (quality) | Minimum water quality objectives met | R | Y | | G | | | | |
| Transmission (including Booster Stations) | | | | | | | | | |
| Backbone transmission facilities (pipelines, pump stations, and tanks) | Supporting critical facilities and fire flow | G | | | | | | | |
| Water for fire suppression at key supply points (to promote redundancy) | % of fire flow x duration | G | | | | | | | |
| Control Systems & Instrumentation | | | | | | | | | |
| SCADA and other control systems (WTP and boosters) | % of components for normal operation | Y | G | | | | | | |
| Distribution | | | | | | | | | |
| Critical Facilities | | | | | | | | | |
| Wholesale customer – City of Turner | % of winter ADD | Y | G | | | | | | |
| Critical City, community, and state facilities identified as having a short-term (no disruption) recovery goal in Table 2-2 | % of winter ADD | G | | | | | | | |
| Critical City, community, county, and state facilities identified as having a short-term (1-3 days) recovery goal in Table 2-2 | % of winter ADD | Y | G | | | | | | |
| Emergency Housing | | | | | | | | | |
| Emergency shelters | % of water for drinking & sanitation | Y | G | | | | | | |
| Housing/Neighborhoods | | | | | | | | | |
| Potable water available at community distribution centers | % of water for drinking & sanitation | | Y | G | | | | | |
| Water for fire suppression at fire hydrants | % of hydrants | | | R | Y | G | | | |
| Community Recovery Infrastructure | | | | | | | | | |
| All other customers | % of customers | | R | Y | G | | | | |

3.0 Water System Backbone Definition

This section describes the water system backbone consisting of transmission pipelines, pump stations, and storage and treatment facilities, which are needed to support fire flow and the critical social/economic needs of the community. The backbone system will support the Short-Term Recovery Phase outlined in Table 2-2 in the initial days following a CSZ earthquake.

The long-term goal for the water system backbone is that it remains operational or experiences only minor damage after a major earthquake. Because it will be challenging to implement any significant repairs to the water system backbone in the initial days after an earthquake, backbone components should be capable of remaining operational without sustaining significant damage during a CSZ earthquake event.

3.1 Water System Backbone Workshops

The project team conducted a workshop with City staff on November 5, 2020, to establish the needs for the backbone system. At this workshop, the project team provided an overview for identification and prioritization of a water system backbone. This backbone was developed following this workshop with the City through a collaborative and iterative process. The City engaged the fire department, Marion and Polk Counties, and the state in conversations about their critical facilities that need to remain operational and be staffed following a CSZ earthquake event.

3.2 Water Supply Points for Fire Suppression

A key long-term goal for the water system backbone is that it provides a reliable source for tanker trucks to obtain water for fire suppression following an earthquake. To enable this goal, the backbone must consist of a seismically-hardened system of pipelines with hydrants and key reservoir sites distributed throughout the City. The majority of the City's reservoirs have seismic shutoff valves to preserve water storage. Additionally, City fire trucks are able to draft water directly from the Willamette River.

3.3 Critical Social/Economic Needs

The process of identifying the water system backbone begins by locating critical water system customers in the Short Term Recovery Phase, which include the following:

- Hospitals
- Urgent Care Centers
- Dialysis Centers
- City of Salem Critical Services
- State of Oregon Critical Services
- Marion County Critical Services
- Correctional Facilities
- Emergency Shelters
- Community Water Distribution Points
- Vulnerable Populations

Appendix A includes a detailed list of these facilities within the City limits that are outlined in Table 2-2.

A special consideration in the above list are dialysis facilities. There are several dialysis facilities in Salem which provide specialty care. Approximately 100 gallons of water is required every 3 days per dialysis patient. The City is working with the dialysis centers in the region to identify more permanent facility locations that may potentially be connected to the backbone, along with the hospital and urgent care facilities. These facilities were not identified at the conclusion of this Report.

3.3.1 Emergency Shelters

Emergency shelters are typically located in existing dormitories or large, open buildings where temporary shelters can quickly be established. In addition to university dormitories, convention/exposition centers and school gymnasiums have the potential to serve as emergency shelters following an earthquake, provided that these buildings are constructed or retrofitted to perform well during a CSZ earthquake event.

Table 3-1 lists 23 potential emergency shelter locations identified by City staff, though there is no agreement currently in place between the City and Salem Keizer School District to operate any schools as an emergency shelter. To date, there have been concerns about the seismic performance of some of these buildings. Since resilience planning considers implementing improvements over a long time frame (approximately 50 years), it may be reasonable to assume that the seismic performance of these facilities may be improved, making them viable shelter locations in the future.

Table 3-1 Potential Emergency Shelter Locations

| Location | Address | Building Type |
|---|------------------------|--------------------------------|
| Auburn Elementary School | 4612 Auburn Rd NE | Public Elementary School |
| Battle Creek Elementary School | 1640 Waln Dr SE | Public Elementary School |
| Brush College Elementary School | 2623 Doaks Ferry Rd NW | Public Elementary School |
| Chemeketa Community College | 4000 Lancaster Dr NE | Community College |
| Corban University | 5000 Deer Park Dr SE | College / University Building |
| Crossler Middle School | 1155 Davis Rd S | Public Middle School |
| Houck Middle School | 1155 Connecticut St SE | Public Middle School |
| Judson Middle School | 4512 Jones Rd SE | Public Middle School |
| Leslie Middle School | 3850 Pringle Rd SE | Public Middle School |
| McKay High School | 2440 Lancaster Dr NE | Public High School |
| North Salem High School | 765 14th St NE | Public High School |
| Parrish Middle School | 802 Capitol St NE | Public Middle School |
| Putnam University Center | 935 Mill St SE | College / University Building |
| Robert W Straub Middle School | 1920 Wilmington Av NW | Public Middle School |
| Roberts High School-State Street Campus | 3620 State St | Public Alternative High School |
| Salem Convention Center | 200 Commercial St SE | Assembly / Exhibition Hall |
| South Salem High School | 1910 Church St SE | Public High School |
| Sprague High School | 2373 Kuebler Rd S | Public High School |
| Stephens Middle School | 4962 Hayesville Dr NE | Public Middle School |
| Tokyo International University of America | 1300 Mill St SE | College / University Building |
| Waldo Middle School | 2805 Lansing Av NE | Public Middle School |
| Walker Middle School | 1075 8th St NW | Public Middle School |
| West Salem High School | 1655 Doaks Ferry Rd NW | Public High School |

3.3.2 Community Water Distribution Points

Community water distribution points are locations throughout the service area where customers can fill their own containers during a water outage. Distribution points can be permanent locations along the water system backbone, or they can be temporary sites, as shown on Figure 3-1, where portable systems are deployed (e.g., water trucks, portable tanks, blivets, etc.).

In May 2018, the following seven temporary community water distribution points were established in the Salem water service area during a cyanotoxin water advisory:

1. Chemeketa Community College, 4000 Lancaster Drive NE, Salem
2. Oregon State Fair Grounds, 2330 17th Street NE, Salem (refer to Figure 3-1)
3. Wallace Marine Park Softball Complex, 200 Glen Creek Road NW, Salem
4. AMF Firebird Lanes, 4303 Center Street NE, Salem
5. Bush's Pasture Park, 600 Mission Street SE, Salem
6. Woodmansee Park, 4629 Sunnyside Road SE, Salem
7. Former Chevrolet Dealership, 5325 Denver Street, Turner



Photo credit: Kelly Jordan, Statesman Journal

Figure 3-1 Temporary Water Distribution Point at the Oregon State Fairgrounds, June 1, 2018

After a large regional earthquake, it will be difficult to deploy and staff temporary distribution points on a large scale, due to increased demands on City staff. Therefore, the City is planning to establish permanent community water distribution points along the water system backbone at the key sites listed in Table 3-2, including the following:

- All the emergency shelters listed in Table 3-1, which are expected to be operated by the Red Cross or other emergency relief organizations;
- All 11 of the City's fire stations, which are expected to be operated by the Salem Fire Department; and
- Eight other City water facilities and parks, which are expected to be operated by the City Public Works Department.

Table 3-2 Community Water Distribution Points

| Location | Address | Building Type |
|--|----------------------------|---------------------------|
| Emergency Shelter Locations – refer to Table 3-1 | | |
| Salem Fire Station 1 | 370 Trade St SE | Salem City Fire Station |
| Salem Fire Station 2 | 875 Madison St NE | Salem City Fire Station |
| Salem Fire Station 3 | 1884 Lansing Av NE | Salem City Fire Station |
| Salem Fire Station 4 | 200 Alice Av S | Salem City Fire Station |
| Salem Fire Station 5 | 1520 Glen Creek Rd NW | Salem City Fire Station |
| Salem Fire Station 6 | 2740 25th St SE | Salem City Fire Station |
| Salem Fire Station 7 | 1970 Orchard Heights Rd NW | Salem City Fire Station |
| Salem Fire Station 8 | 4000 Lancaster Dr NE | Salem City Fire Station |
| Salem Fire Station 9 | 5080 Battle Creek Rd SE | Salem City Fire Station |
| Salem Fire Station 10 | 3611 State St | Salem City Fire Station |
| Salem Fire Station 11 | 5021 Liberty Rd S | Salem City Fire Station |
| Cascades Gateway Park | 2100 Turner Rd SE | Developed City Park |
| Limelight Water Pump Station | 880 Van Buren Dr NW | Public Water Pump Station |
| River Road Park | 3045 River Rd N | Developed City Park |
| Salem City Shops Building 16 Water | 1440 20th St SE | Salem City Facility |
| Salem/Keiser Intertie #1 Pump Station | 4000 Block Cherry Ave NE | Public Water Pump Station |
| South River Road Water Pump Station | 3285 River Rd S | Public Water Pump Station |
| Turner Control Water Facility | 7100 3rd St SE | Public Water Facility |
| Weathers Street Park | 4188 Weathers St NE | Developed City Park |

The community water distribution points listed in the table above are also included in Appendix A.

3.3.3 Vulnerable Populations

The City's emergency planning efforts have also taken into consideration ways to serve vulnerable customers. Appendix A includes a detailed list of sizable care facilities; retirement centers where seniors receive assisted living, memory, or nursing care; and the Oregon School for the Deaf. All these facilities serve vulnerable populations that need to be supported by the water system backbone.

3.4 Water Facility Criticality Levels

In the development of the water system backbone, City staff prioritized the pumping, storage, piping, and valve facilities within the water transmission system by how important the facility is to the overall operation of the water system (and, therefore, how high the consequence of its failure is) using the priority system described in Table 3-3. Table 3-4 lists the City's water facilities in order of criticality, with the facilities listed alphabetically within each level.

Table 3-3 Water Facility Criticality/Consequence of Failure Level Definitions

| Criticality Level | Definition |
|----------------------------|---|
| 5 – Highly Critical | Paramount to the operation of the system. |
| 4 – Critical | Necessary to supply water to a significant area. |
| 3 – Semi Critical | The system could operate at reduced capacity without these facilities. |
| 2 – Local Critical | Necessary to supply water to an isolated local area. |
| 1 – Not Critical/Redundant | The system can operate without these facilities. These facilities are not considered part of the system backbone. |

Table 3-4 Storage and Pumping Facility Criticality Levels



| Criticality Level | Name | Service Level | Elevation (ft) |
|--------------------------------|----------------------------|---------------|----------------|
| Supply/Valves | | | |
| 5 – Highly Critical | Geren Island WTP | G-0 | 470 |
| 5 – Highly Critical | Turner Control Facility | G-0 | 266 |
| 4 – Critical | ASR Wells | S-2 | ~382 |
| 2 – Local Critical | Hemlock Well | G-0 | 188 |
| Reservoirs | | | |
| 5 – Highly Critical | Fairmont Reservoir | G-0 | 314 |
| | Franzen Reservoir | Franzen | 386 |
| | Mountain View Reservoir | G-0 | 313 |
| 4 – Critical | Candalaria Reservoir | S-1 | 429 |
| | Champion Hill Reservoir | S-3 | 709 |
| | Eola #1b Reservoir | W-2 | 636 |
| | Eola #2 Reservoir | W-3 | 763 |
| | Grice Hill Reservoir | W-1 | 483 |
| | Lone Oak Reservoir | S-2 | 574 |
| | Mill Creek Reservoir | MCCC S-1 | 424 |
| 3 – Semi Critical | Glen Creek Reservoir | W-1 | 483 |
| | Kurth Reservoir | S-2 | 553 |
| 2 – Local Critical | Croisan Mt Upper Reservoir | S-2 | 579 |
| 1 – Not Critical/ Redundant | Chakarun Reservoir | S-2 | 580 |
| | College Reservoir | T | 438 |
| | Mader Reservoir | S-1 | 385 |
| | Seeger Reservoir | S-2 | 553 |
| | Skyline Reservoir | S-3 | 708 |

| Criticality Level | Name | Service Level | Elevation (ft) |
|--------------------------------|---------------------------------|---------------|----------------|
| Pump Stations | | | |
| 4 – Critical | Boone Pump Station | S-2 | 235 |
| | Creekside Pump Station | S-3 | 491 |
| | Deer Park Pump Station | S-1 | 306 |
| | Edwards S1 Pump Station | S-1 | 206 |
| | Keizer Intertie Pump Station | G-0 | 130 |
| | Mountain View Pump Station | W-1 | 308 |
| 3 – Semi Critical | Lower Croisan Pump Station | S-2 | 418 |
| | South River Rd Pump Station | S-1 | 153 |
| 2 – Local Critical | Davis Road Pump Station | S-4 | 697 |
| | Eola #2 Pump Station | W-3 | 530 |
| | Limelight Pump Station | W-2 | 477 |
| | Mill Creek Pump Station | T | 349 |
| | Rock Ridge Pump Station | S-3 | 464 |
| | Skyline #4 Pump Station | S-4 | 620 |
| | Upper Croisan Pump Station | S-3 | 510 |
| | Whispering Heights Pump Station | W-2 | 426 |
| 1 – Not Critical/ Redundant | Chatnicka Pump Station | W-3 | 546 |
| | Edwards S2 Pump Station | S-2 | 206 |
| | Fairmont Pump Station | S-2 | 312 |
| | Illahe Pump Station (Private) | S-1 | 240 |
| | Jefferson Pump Station | W-1 | 240 |
| | Skyline Pump Station | S-3 | 502 |

3.5 Water System Backbone

The resulting water system backbone that is needed to connect to each of the critical water system components (supply, reservoirs, and pump stations) and the social/economic needs of the community (such as critical public agency buildings, emergency shelters, community water distribution points, and vulnerable populations) is shown on Figure 3-2. The water system backbone piping shown on Figure 3-2 connects the tax lots where critical facilities are located. Critical facilities include medical facilities (hospitals and urgent care centers), government facilities, correctional facilities, emergency shelters, community water distribution points, and vulnerable populations. Also shown on the figure are grey 0.75- and 1.0-mile radii around each community water distribution point. These radii represent reasonable walking distances, in case transportation becomes limited after a CSZ earthquake. As shown on Figure 3-2, a significant amount of the City is within 0.75 mile of a community water distribution point, and nearly all of the City is within 1 mile of a community water distribution point.

The water system backbone serves as the foundation for prioritizing seismic upgrades recommended in further sections of this Report.



Legend

Pipeline Consequence of Failure

- Highly Critical
- Critical
- Semi Critical
- Local Critical
- Labeled w/ Diameter

Pump Station (PS) Consequence of Failure

- Highly Critical
- Critical
- Semi Critical
- Local Critical

Reservoir (Res) Consequence of Failure

- Highly Critical
- Critical
- Semi Critical
- Local Critical

Valve Risk Level

- Highly Critical

Social/ Economic Needs

- Urgent Care Center
- Dialysis Center
- Hospital
- City of Salem
- State of Oregon
- Marion County
- Correctional Facility
- Emergency Shelters/ Community Water Distribution Points
- Community Water Distribution Points
- Vulnerable Population

0.75-mile Radius from Community Water Distribution Points

1.0-mile Radius from Community Water Distribution Points

Pipeline

Pump Station

Reservoir

City Limits

Urban Growth Boundary

Notes:

1. Pipelines, Pump Stations, and Reservoirs labeled as "Not Critical" are not considered part of the Water System Backbone.
2. Critical facilities were determined by a desktop assessment performed in collaboration with City staff. Further vetting and assessment of these locations will occur following this report, to finalize the list of critical Fire Stations, Community Water Distribution Points, Emergency Shelters, Vulnerable Populations, and Urgent Care Centers.

Figure 3-2:
Water System Backbone



Seismic Resiliency Analysis



3.6 Considerations and Future Coordination Efforts

Sites identified as community water distribution points require further coordination between the City's Water & Utilities and Public Works Departments and emergency services of the City and Marion and Polk Counties. All fire stations are currently designated as community water distribution points, which means that following a CSZ earthquake, the fire stations will have increased public traffic. This has a potential to interfere with fire apparatus responding to an emergency, depending upon how the public will access the fire station and water. The City Fire Department will need to consider any potential impacts to both staffing and traffic. Similarly, City staff will need to consider the implications of increased traffic and staffing at the City Shops Complex, which is also designated as a community water distribution point. Proactive coordination between the City's Water & Utilities and Public Works Departments and emergency services of the City and Marion and Polk Counties ahead of an emergency can help to effectively support the community following a crisis.

The City is also working with the dialysis centers in the region to identify more permanent facility locations that may potentially be connected to the backbone, along with the hospital and urgent care facilities. These facilities were not identified at the conclusion of this Report.

The City should also coordinate with the Salem Keizer School District with regards to operation of schools as an emergency shelter.

4.0 Water System Seismic Vulnerability Assessment

Both the pipeline system and priority facilities were evaluated to ascertain the likelihood and potential extent of damage to structures and other system infrastructure during an earthquake. Hazards associated with seismic activity that have the potential to adversely affect pipelines or water system facilities include ground rupture, liquefaction, lateral spreading, strong ground shaking, and earthquake-induced landslides. The degree to which these hazards could impact the water system is dependent upon the earthquake magnitude and distance from each pipeline or facility, the proximity to faults, the amount and type of soil displacement, and the joint systems and construction characteristics of the pipeline or facility.

4.1 Geohazards

A Seismic Geohazard Evaluation Report was completed by Shannon & Wilson in May 2021 (refer to Appendix B) to assess the potential for earthquake-induced geologic hazards and formed the basis for developing the seismic vulnerability assessment. The Seismic Geohazard Evaluation Report maps various seismic parameters within the study area based on geological information for the general area. The study area encompassed the City's major water transmission mains and facilities. Seismic hazard maps include peak ground velocity, peak ground acceleration, 0.3- and 1.0-second spectral accelerations, probability of liquefaction, liquefaction induced settlement, and landslide induced permanent ground deformation (PGD) based on the methodology developed by HAZUS. The DOGAMI publishes detailed maps showing bedrock, surficial, or engineering geology for specific regions. GMS-105, one of the DOGAMI maps which focused on the relative earthquake hazard of Marion and Polk Counties, was used as the primary source of liquefaction susceptibility within the Salem area. Permanent ground deformations from liquefaction-induced lateral spreading were calculated.

4.1.1 Pipeline Geohazards

Table 4-1 summarizes the portions of the City's water transmission and distribution system subject to liquefaction-induced lateral spreading, liquefaction-induced settlement, and peak ground velocity (PGV) based on the hazard mapping provided by Shannon & Wilson in Appendix B.

Table 4-1 Potable Water Pipelines Subject to Seismically-Induced Ground Movement

| Severity Level | Liquefaction-Induced Lateral Spreading (in.) | % Water System | Settlement (in.) | % Water System | PGV (in./s) | % Water System |
|----------------|--|----------------|------------------|----------------|---------------|----------------|
| Low to High | 0 – 0.1 | 68.6% | 0 | 43.0% | 0.00 – 2.90 | 0.0% |
| | 0.11 – 2 | 1.3% | 1 | 27.0% | 2.91 – 5.90 | 36.1% |
| | 2.1 – 6 | 4.2% | 2 | 18.4% | 5.91 – 11.90 | 61.2% |
| | 6.1 – 12 | 20.7% | 6 | 10.3% | 11.91 – 23.90 | 2.7% |
| | 12.1 – 16 | 5.1% | Other | 1.4% | > 23.91 | 0.0% |

A small portion of the City's northernmost distribution system was outside of the limits of the area assessed for earthquake-induced geologic hazards. The data set for lateral spreading was larger than the data set for settlement, and it was observed that in the northernmost portion of the City, anticipated lateral spreading was directly proportional to anticipated settlement. Therefore, when lateral spreading was known, but the settlement was unknown, settlement was assumed to follow a similar distribution as lateral spreading. In the few areas where lateral spreading and settlement were not known, it was

deemed appropriate to assign a value of 6 inches for lateral spread and 2 inches for settlement, based on settlement levels in the adjacent area.

For the pipelines, the main hazards were determined to be localized liquefaction and lateral spreading at the Sunset Park Willamette River crossing and fault rupture where the pipelines cross the Turner and Mill Creek Faults and Waldo Hills Fault. The potential for localized liquefaction is highest at the Willamette River crossings, near the City of Turner and the Geren Island WTP. Note that recent site-specific geotechnical engineering reports for Geren Island WTP indicate that the map-based liquefaction hazard shown in Appendix B may be somewhat overestimated due to the relatively high percentage of gravels underlying that site.

4.1.2 Priority Vertical Facility Geohazards

Facility geohazards were assessed using seismic hazard parameters mapped by Shannon & Wilson in the Seismic Geohazard Evaluation Report in Appendix B. These parameters included ground shaking, liquefaction-induced settlement, liquefaction-induced lateral spreading, and earthquake-induced landslide PGD.

The facilities were selected in close consultation with the City's Engineering Division based on whether the facilities are key to maintaining the integrity of the water system backbone. A total of 24 priority facilities were evaluated as part of this study, as listed in Table 4-2. A detailed structural condition assessment of the structures was not included in the scope of this project.

Table 4-2 Facilities Assessed as Part of this Study

| Facilities Assessed | |
|--|--|
| <ul style="list-style-type: none"> • ASR #1 and #2 Pump Station • ASR #4 Pump Station • ASR #5 Pump Station • Boone Road Pump Station • Candalaria Reservoir • Champion Hill Reservoir • Champion Hill Reservoir Control Building • Creekside Pump Station • Deer Park Pump Station • Edwards S1 Pump Station • Eola #1B Reservoir • Fairmount Reservoir | <ul style="list-style-type: none"> • Fairmount Reservoir Control Building • Grice Hill Reservoir Control Building • Limelight Pump Station • Lone Oak Reservoir • Lone Oak Reservoir Control Building • Mill Creek #1 Reservoir • Mill Creek #1 Reservoir Control Building • Mountain View Pump Station • Mountain View Reservoir • Salem/Keizer Intertie #1 Pump Station • Turner Control Facility |

It is recommended that the City conduct seismic evaluations of the remaining inventory of water system structures (pump stations, reservoirs, communications towers, etc.) as part of a future project. Several facilities were considered critical facilities but were excluded from this evaluation for the following reasons:

- The Geren Island WTP is a key part of the backbone, but the City requested that this facility not be included in the assessment because seismic resiliency upgrades to this facility were being implemented at the time of this study.

- Franzen Reservoir was excluded from assessment because it is an earthen facility which requires a specialized evaluation to review seismic deficiencies and potential improvements. A seismic evaluation of the Franzen Reservoir is underway under a separate scope.
- Lower Croisan Pump Station was excluded from further structural and nonstructural assessment because the Shannon & Wilson Geohazard Study recommended a full replacement of this facility.
- The Upper Transmission System (Lines 1 and 2) was evaluated by Carollo Engineers in 2016 under a separate scope. The findings indicated peak ground velocity between Geren Island and Turner is consistent and landslides and liquefaction is unlikely. The majority of anticipated damage to the Upper Transmission System will be near the Turner Control Facility.

4.1.3 Vertical Facility Hazard Rankings

The geotechnical evaluation resulted in a set of hazard rankings being assigned to the critical vertical facilities based on regional seismic mapping and review of existing information on the facilities, as shown in Table 4-3. The geotechnical evaluation found that numerous facilities were in areas where rock is mapped as the geological surface unit. The risk of PGDs at these sites were considered low.

Table 4-3 Seismic Hazard Rankings for Critical Vertical Facilities

| Site ID | Locations | Site Class ¹ | Liquefaction Settlement Hazard ² | Landslide Hazard ² | Fault Rupture Hazard ² |
|---------|---|-------------------------|---|-------------------------------|-----------------------------------|
| 1 | Salem-Keizer Intertie/Cherry Ave Booster Pump Station | D | M | L | L |
| 2 | Grice Hill Reservoir and Repeater Tower | B | L | L | L |
| 3 | Hemlock Well ³ | B | L | L | L |
| 4 | Mountain View Reservoir and Pump Station | B | L | L | L |
| 5 | EOLA 1B Reservoir ³ | B | L | M | L |
| 6 | Limelight Pump Station ³ | B | L | L | L |
| 7 | Fairmount Reservoir ³ | B | L | L | L |
| 8 | Candalaria Reservoir | B | L | L | L |
| 9 | South Salem Repeater Tower | B | L | L | L |
| 10 | Croisan Lower Pump Station ³ | C/D | M | H | L |
| 11 | Edwards S1 Pump Station ⁴ | D | H | M | L |
| 12 | ASR Wells ³ | B | L | L | L |
| 13 | Skyline Repeater Tower ³ | B | L | L | L |
| 14 | Lone Oak Reservoir | B | L | L | L |
| 15 | Creeside Pump Station ³ | B | L | L | L |
| 16 | Champion Hill Reservoir | B | M | M | L |
| 17 | Boone Road Pump Station ³ | D | L | L | L |
| 18 | Deer Park Pump Station | B | L | L | L |

| Site ID | Locations | Site Class ¹ | Liquefaction Settlement Hazard ² | Landslide Hazard ² | Fault Rupture Hazard ² |
|---|---|-------------------------|---|-------------------------------|-----------------------------------|
| 19 | Mill Creek Reservoir | B | L | L | L |
| 20 | Turner Control Facility | D | L | L | L |
| 21 | Franzen Reservoir and Repeater Tower ⁴ | B | L | H | M |
| 22 | Geren Island WTP | D | L | L | L |
| ¹ Site classified as Site Class A, B, C, D, E, or F based on the site soil properties in accordance with Chapter 20 of ASCE 7. ² L = Low, M = Moderate, H = High ³ Sites did not have subsurface exploration data. Nearby well logs could not be found for these sites. Therefore, the risk assessments for these facilities are based on regional seismic hazard mapping only. ⁴ Geologic maps may not adequately capture geohazards for locations indicated. Refer to the Shannon and Wilson 2021 Seismic Geohazard Evaluation Report for more discussion on this topic. | | | | | |

The following facilities were rated as having a moderate geologic seismic hazard:

- **EOLA 1B Reservoir:** There is a moderate landslide hazard, as the reservoir is near an existing landslide and there was lack of available site-specific subsurface information. If additional subsurface information is obtained in the future, the hazard potential for this site may be reassessed for landslide hazard.
- **Champion Hill Reservoir:** This facility was assigned a moderate to high hazard for potential liquefaction and landslides. Nearby well logs indicate that the soil is mantled by fine grained flood deposits which are more likely to experience PGD during a seismic event. The geohazard rankings may be reassessed if additional subsurface data is available in the future.

The following facilities were assigned a moderate to high geologic seismic hazard:

- **Croisan Lower Pump Station:** This facility was assigned a moderate hazard for potential liquefaction and high hazard ranking for landslides. The site is near the contact between a large existing landslide and volcanic rock, and there is a lack of available site-specific information. The geohazard rankings may be reassessed if additional subsurface data is available in the future.
- **Edwards S1 Pump Station:** Flood maps and well logs indicate presence of poor soils at the site, and the pump station may be underlain by these soils. Uncontrolled releases of water have resulted in surface settlement around the building foundations. Due to uncertainties associated with liquefaction potential and subgrade, the potential for PGD was considered moderate to high during a seismic event.
- **Franzen Reservoir and Repeater Tower:** These facilities received a moderate hazard ranking for landslide risk and high hazard for fault rupture. These ratings were based on information gathered from existing basis of design reports and understanding of past instability along the earthen embankments.

4.2 Pipeline Vulnerability Assessment

The City's water system was evaluated using the ALA (American Lifelines Analysis) Seismic Fragility Formulations for Water Systems (ALA, 2001), which is used widely for pipeline loss assessments. This method uses fragility curves that can be applied to water system components to evaluate the probability of damage from earthquake hazards. Damage estimates are expressed as pipeline repair rates for breaks and leaks. The general approach is to quantify earthquake shaking (wave propagation) intensity using PGV, quantify the amount of ground movement using PGD, and to use both PGV and PGD to estimate the damage of the system pipelines. The ALA methodology includes pipeline vulnerability functions for both PGV and PGD inputs, which vary based on pipe material.

4.2.1 Pipeline Joint Assumptions

The system includes 934.5 miles of pipe with diameters ranging from 0.75 inch to 69 inches. The pipe material, length, assumed joint type, and assumed K1 and K2 values for each are shown in Table 4-4. K1 and K2 values are constants used in the equation to represent the expected performance of the various pipe materials. K1 and K2 can have a maximum value of 1.0 each, representing the highest degree of vulnerability, which is the value used for cast iron pipe.

Table 4-4 Pipe Material, Length, Joint Type, and K1 and K2 Values

| Material | Acronym in City's Database | Length (miles) | Percent of System | Assumed Joint Type | K1 | K2 |
|--------------------------------------|----------------------------|----------------|-------------------|---------------------------------------|-----|-----|
| Ductile Iron | DI | 453.6 | 48.5% | Rubber Gasket | 0.5 | 0.5 |
| Cast Iron (pre-1950) | CI | 110.9 | 11.9% | Cement | 1.0 | 1.0 |
| Cast Iron (post-1950) | CI | 170.0 | 18.2% | Rubber Gasket | 0.8 | 0.8 |
| Steel | STEEL | 83.8 | 9.0% | Rubber Gasket | 0.7 | 0.7 |
| Asbestos Cement | AC | 36.3 | 3.9% | Rubber Gasket | 0.5 | 0.8 |
| Concrete Cylinder Pipe | CCP | 35.5 | 3.8% | Rubber Gasket | 0.8 | 0.7 |
| Unknown | UNK | 14.1 | 1.5% | Assume to Be Cast Iron Pipe | 1.0 | 1.0 |
| Polyvinyl Chloride | PVC | 10.0 | 1.1% | Rubber Gasket | 0.5 | 0.8 |
| Blank | Blank | 8.4 | 0.9% | Assume to Be Cast Iron Pipe, pre-1950 | 1.0 | 1.0 |
| Iron Pipe | IP | 5.5 | 0.6% | Threaded, no gasket | 0.5 | 0.5 |
| High Density Polyethylene | HDPE | 3.9 | 0.4% | Fused | 0.3 | 0.3 |
| Needs to Be Fixed | FIX | 1.5 | 0.2% | Assume to Be Cast Iron Pipe, pre-1950 | 1.0 | 1.0 |
| Concrete | C | 0.4 | 0.04% | Rubber Gasket | 0.5 | 0.8 |
| Unknown | OD | 0.2 | 0.02% | Assume to Be Cast Iron Pipe, pre-1950 | 1.0 | 1.0 |
| Blue Brut Polyvinyl Chloride | BB | 0.1 | 0.01% | Rubber Gasket | 0.5 | 0.8 |
| Plastic | P | 0.1 | 0.01% | Assume to Be PVC Pipe | 0.5 | 0.8 |
| Cross-Linked Polyethylene (Pex Pipe) | PEX | 0.0 | <0.01% | Fused | 0.3 | 0.3 |
| Steel | S | 0.0 | <0.01% | Rubber Gasket | 0.7 | 0.7 |
| Totals | | 934.5 | 100.0% | | | |

Black & Veatch met with City staff to discuss the assumed joint type for each pipe material based on what was typically installed in the City. In the case of cast iron pipe, the joint type was dependent upon the age of the pipe; prior to 1950, cast iron had cemented joints rather than rubber gasketed joints. If the incorrect joint types are assumed, it could result in different K1 and K2 values, increasing or decreasing the estimated number of failures. The K1 and K2 values for specific pipe materials are taken directly from the ALA document. When there are no values for some types of pipes represented in the City in the ALA document, K1 and K2 values are estimated based on similar types of pipe and pipe joints. The ALA fragility relationships assign variables to each pipe material depending on its relative performance.

There is not enough evidence to prove a diameter effect exists for all pipe materials in any given water system. However, the empirical evidence strongly indicates that some relationship does exist and that the largest pipes, those over 12 inches in diameter, have lower damage rates than common diameter distribution pipes of 4 inches to 12 inches in diameter. Therefore, it is more conservative to assume that pipe diameters are small when assigning K1 and K2 values.

In Table 4-4, the Assumed Joint Type column shows the basis for assuming the K1 and K2 values. Unknown pipe materials (FIX, OD, UNK, and materials left blank) are assumed to have the same performance attributes as cast iron pipe. Plastic pipe is assumed to have the same performance as polyvinyl chloride (PVC) pipe. These pipe materials (FIX, OD, UNK, materials left blank, and P) make up a small percentage of the system (totaling less than 2.6%) and will have a small influence on overall system performance.

4.2.2 Pipeline Failure Assessment

The number of pipe failures is calculated by multiplying the pipe repair rate (RR, repairs/1,000 feet of pipe) times the pipe length (in 1,000s of feet). The ALA fragility relationships used to calculate the RR are as follows:

- $RR = K1 \times 0.00187 \times PGV$, where PGV = Peak ground velocity in inches/sec
- $RR = K2 \times 1.06 \times PGD^{0.319}$, where PGD = Peak ground displacement in inches

RRs are calculated separately for PGD and PGV and are much lower for PGV than PGD. It was conservatively assumed that the PGD for the purposes of the ALA fragility relationships was the sum of the PGD from both liquefaction and earthquake-induced landslides.

In accordance with the 2001 ALA Guidelines, the vector sum of the liquefaction-induced lateral spreading PGD (horizontal deformation) and liquefaction-induced settlement PGD (vertical deformation) was used to calculate the total PGD associated with liquefaction, which is the distance a block of soil is expected to move during an earthquake (typically downhill or towards a free face) before remaining in that position within a few minutes after the earthquake shaking has stopped.

The breakdown of the number of leaks and breaks is dependent on the hazard environment where the pipe is located. Repairs include both leaks and breaks. The following methodology was used to segregate pipe failures:

- PGD-related failures – 80% breaks and 20% leaks
- PGV-related failures – 20% breaks and 80% leaks

Breaks are described as loss of hydraulic continuity, e.g., the loss of the ability to transmit water from Point A to Point B. "Breaks" include separation of a pipe joint by more than approximately 1 inch, or the blowout of the pipe wall. A break results in significant loss of water; a pipe break results in the pipe being nonfunctional and must be repaired before the immediate service area can be put back into service. A leak is simply a failure resulting in loss of water. A leak does not necessarily need to be restored immediately for the immediate service area to be put back into service. A leak versus a break is based on the ground deformation associated with each hazard parameter. PGD can range from inches to many feet, but PGV is typically fractions of an inch. Pipe with rigid joints such as cast iron pipe with leaded joints is particularly vulnerable to PGV, but pipe with elastomeric joints can absorb all but the very strongest PGV movements.

The results of the failure analysis are shown in Table 4-5 grouped by PGD- and PGV-related failures and leaks versus breaks.

Table 4-5 Pipeline Failures for PGD, PGV, and Total

| PGD-Related Failures | | | PGV-Related Failures | | | Total Failures (Breaks + Leaks) |
|----------------------|-------|------------------------------------|----------------------|-------|------------------------------------|------------------------------------|
| Breaks | Leaks | Total Failures (Breaks + Leaks) | Breaks | Leaks | Total Failures (Breaks + Leaks) | |
| 3360 | 840 | 4200 | 11 | 46 | 57 | 4257 |

There is no firm threshold above which pipelines need to be replaced. The highest failure rates are typically a function of vulnerable pipe materials (e.g., cast iron) and soils subject to PGD (liquefiable soils). The number of estimated failures is an approximation based on empirical data and is intended to be used for planning purposes. The number of actual failures encountered may range from twice as many as those listed to half as many as those listed in the table. Geohazards identified for pipelines are based on large-scale mapping for seismic hazards. Site-specific surveys and aerial photographs should be used to estimate the potential for loss associated with landslides or liquefaction for specific pipeline alignments prior to undertaking a capital improvement plan (CIP) project.

4.2.3 Willamette River Crossing Vulnerabilities

Pipeline crossings of the Willamette River suspended from the Center Street and Marion Street Bridges are vital water supplies to West Salem and were observed as part of this project.

4.2.3.1 Center Street Bridge

Findings of Observation: It was found that the water main under the bridge is all flanged piping with rigid Victaulic couplings in some areas. The 24-inch inner diameter DI pipe is sliplined with 22-inch HDPE. The piping is suspended under the bridge with minimal bracing. On the east side of the bridge, possible flexible joints are present, but the piping was inaccessible for assessment. It was assumed that there are no flexible joints present on any aboveground piping. The piping suspended under the bridge was determined to be vulnerable, particularly because the bridge columns are supported on piles, while the pipe is supported by soil on either side, which results in differential settlement and separation during an earthquake.

Recommendations for Improvement: The pipeline should have flexible joints at either end (where the pipe exits or enters the soil) and at each bridge expansion joint to allow for differential settlement. In addition, between flexible joints, the pipe should be properly braced to the bridge deck. The City is currently scoping the replacement of this line as part of ODOT's seismic retrofit of the Center Street Bridge.

4.2.3.2 Marion Street Bridge

Findings of Observation: A similar on-site assessment was conducted for the Marion Street Bridge. Under the bridge, there were two large diameter pipes, one assumed to be the water main. One of the pipes was observed to have welded joints and the other pipe was flanged. No flexible joints were observed. The bridge piping was determined to be vulnerable to differential settlement and separation during an earthquake since the bridge columns are supported on piles, while the pipe is supported by soil on either side.

Recommendations for Improvement: Similar to the Center Street Bridge, this pipeline should have flexible joints at either end (where the pipe exits or enters the soil) and at each bridge expansion joint to allow for differential settlement. In addition, between flexible joints, the pipe should be properly braced to the bridge deck. According to ODOT's evaluation of this bridge, the structure is not expected to survive a CSZ level event, so further investment in the waterline may not be warranted unless the bridge is first seismically retrofitted or replaced.

4.3 Vertical Facilities Vulnerability Assessment

SEFT conducted a preliminary seismic assessment based on review of design documents and site visits for a selected group of vertical facilities, which include key pump stations, reservoirs, and control buildings. The findings of this assessment are included in the Pump Station and Reservoir Seismic Vulnerability Assessment Report by SEFT, which is located in Appendix C. The main objective of the vulnerability assessment for the facilities sites was two-fold:

- To identify deficiencies in each of the facilities that affect ability to maintain service in the event of a major earthquake (M9.0 CSZ scenario); and
- To develop preliminary recommendations for mitigation measures to address the identified deficiencies.

This planning-level Report is the first step in identifying and addressing seismic resiliency needs, and the findings of this study are intended to support City planning efforts when budgeting for and prioritizing facility seismic improvements.

4.3.1 Facility Assessment Summary

The seismic structural evaluations of pump stations, control facilities, and reservoir control buildings were completed using the Tier 1 screening procedure of American Society of Civil Engineers (ASCE) 41-17, Seismic Evaluation and Retrofit of Existing Buildings. This Tier 1 procedure uses a checklist-based approach to identify potential seismic structural deficiencies that have been commonly observed in past earthquakes. It also uses quick-check calculations to identify potential deficiencies in the primary components of the seismic lateral-force resisting system.

It is important to note that the Tier 1 assessment identified structural deficiencies that were confirmed, as well as structural deficiencies that were unconfirmed and to be evaluated in future Tier 2 assessments recommended for various facilities. It was not possible to confirm certain structural deficiencies that were identified in this Tier 1 assessment, because of the following reasons:

- Engineering drawings for several of the facilities were not available for review; therefore, preliminary conclusions were drawn based on observations of readily accessible portions of the facilities.

- The visual assessment was further limited as it was not possible to observe various structural elements (such as roof to wall connections which were concealed by the ceiling and/or insulation). These structural elements need to be inspected as part of a detailed investigation. The SEFT report in Appendix C identifies specific measures needed to perform the detailed evaluation.
- Detailed structural analyses need to be performed to determine the adequacy of certain elements such as reservoir column reinforcing lap splices. These analyses are beyond the scope of this study and need to be performed as part of a Tier 2 assessments.

Seismic nonstructural evaluations were completed using the nonstructural seismic evaluation checklists presented in ASCE 41-17 supplemented by the Technical Council on Lifeline Earthquake Engineering Monograph No. 22, Seismic Screening Checklists for Water and Wastewater Facilities. Like the ASCE 41 Tier 1 structural evaluation procedure, this checklist-based evaluation approach is used to identify potential seismic nonstructural deficiencies that have been commonly observed in past earthquakes.

4.3.2 Facility Seismic Deficiencies

Table 4-6 broadly summarizes the structural and nonstructural deficiencies identified at pump stations and control buildings. Typical pump station and control building deficiencies included inadequate roof to wall in-plane connections; inadequate roof to wall out-of-place bracing; inadequate piping, valve, or pump bracing; and unanchored control cabinets or unanchored electrical transformers. Table 4-7 summarizes the structural and nonstructural deficiencies at reservoirs. Typical reservoir deficiencies included insufficient reinforcing splice length on concrete columns, overstressed walls, lack of positive connections between roofs and walls, overstressed columns, lack of dowels or seismic cables at wall connections, and lack of positive connections between pipe pedestals and reservoir floors.

Table 4-6 Pump Station and Control Facility Deficiency Summary

| Vertical Facility | Structural Deficiencies | | | | | | | | Nonstructural Deficiencies | | | | | | | | SEFT Report Table Reference (Appendix C) |
|---------------------------------------|-------------------------|-------------|--------------|----------------|-----------------|---------------------|---------------------|------------------|----------------------------|--------------|------------------|----------------------|------------------|----------------------------|-----------------------|-----------------------|---|
| | Roof Anchorage | Roof Design | Wall Bracing | Ceiling Design | Cracks in Walls | Masonry Wall Design | Liquefaction Hazard | Corrosion Damage | Pump Bracing | Pipe Bracing | Pipe Flexibility | Light Fixture Covers | Conduit Mobility | Electrical Cabinet Bracing | Misc. Element Bracing | Transformer Anchorage | |
| ASR # 1 and #2 Pump Station | ■ | ■ | ■ | | | | | | ■ | ■ | ■ | ■ | ■ | ■ | ■ | ■ | 3.1 |
| ASR #4 Pump Station | ■ | ■ | ■ | | | | | | ■ | ■ | ■ | ■ | | | ■ | ■ | 3.2 |
| ASR #5 Pump Station | | | ■ | ■ | | | | ■ | ■ | ■ | | ■ | ■ | ■ | | ■ | 3.3 |
| Boone Road Pump Station | ■ | ■ | ■ | | | | | | ■ | ■ | ■ | ■ | | | ■ | ■ | 3.4 |
| Creekside Pump Station | ■ | ■ | ■ | | | | | | ■ | ■ | ■ | | | ■ | ■ | | 3.5 |
| Deer Park Pump Station | ■ | ■ | ■ | | | | | | ■ | ■ | ■ | | | ■ | ■ | ■ | 3.6 |
| Edwards Pump Station | ■ | ■ | ■ | | ■ | ■ | | | ■ | ■ | ■ | ■ | | ■ | ■ | | 3.7 |
| Limelight Pump Station | ■ | ■ | ■ | | ■ | | | | ■ | ■ | ■ | | | ■ | ■ | ■ | 3.8 |
| Mountain View Pump Station | ■ | ■ | ■ | | | | | | ■ | ■ | ■ | ■ | | ■ | ■ | ■ | 3.9 |
| Salem/Keizer Intertie #1 Pump Station | ■ | ■ | ■ | | | | ■ | | ■ | ■ | ■ | | | ■ | ■ | ■ | 3.10 |
| Turner Control Facility | ■ | ■ | ■ | | | | ■ | | ■ | ■ | ■ | | | ■ | ■ | ■ | 3.11 |
| Champion Hill Control Building | ■ | ■ | ■ | | | | | | ■ | ■ | | | | ■ | ■ | ■ | 3.14 |
| Fairmount Control Building | | | ■ | | | | | | ■ | ■ | ■ | | ■ | ■ | ■ | ■ | 3.17 |
| Grice Hill Control Building | | ■ | ■ | | | | | | | ■ | | | | ■ | ■ | ■ | 3.19 |
| Lone Oak Control Building | | ■ | | | | ■ | | | ■ | ■ | | | | ■ | ■ | ■ | 3.21 |
| Mill Creek #1 Control Building | ■ | | ■ | | | | | | ■ | ■ | ■ | | | ■ | ■ | ■ | 3.23 |

Table 4-7 Reservoirs Deficiency Summary

| Vertical Facility | Structural Deficiencies | | | | | Nonstructural Deficiencies | | | | SEFT Report Table Reference (Appendix C) |
|-------------------------|---------------------------------|--------------------|---|-----------------------------------|------------------------|----------------------------|----------------|--------------|--------------------------------|--|
| | Reinforcement Lap Splice Length | Overstressed Walls | Roof to Wall or Wall to Foundation Connection | Concrete Cracking / Deterioration | Potential Liquefaction | Precast Vault | Cast Iron Pipe | Pipe Bracing | Miscellaneous Elements Bracing | |
| Candalaria Reservoir | ■ | | | | | ■ | ■ | ■ | ■ | 3.12 |
| Champion Hill Reservoir | ■ | | | | ■ | | | ■ | | 3.13 |
| Eola #1B Reservoir | ■ | | | ■ | | ■ | | ■ | | 3.15 |
| Fairmount Reservoir | ■ | ■ | ■ | | | | ■ | | | 3.16 |
| Grice Hill Reservoir | ■ | | | | | | | ■ | | 3.18 |
| Lone Oak Reservoir | | | | | | | | | | 3.20 |
| Mill Creek #1 Reservoir | ■ | | | | | | | ■ | ■ | 3.22 |
| Mountain View Reservoir | ■ | ■ | ■ | | | | ■ | | | 3.24 |

Table 4-8 summarizes the readiness of various facilities to meet immediate occupancy, operational, or life safety performance under a CSZ M9.0 earthquake. These performance objectives are defined as follows:

- **Immediate Occupancy:** "Immediate Occupancy" refers to the post-earthquake damage state in which only very limited structural damage has occurred. The basic vertical- and lateral-force-resisting systems of the building retain almost all their pre-earthquake strength and stiffness. The risk of life-threatening injury from structural damage is very low, and although some minor structural repairs might be appropriate, these repairs would generally not be required before re-occupancy. Continued use of the building is not limited by its structural condition but might be limited by damage or disruption to nonstructural elements of the building, furnishings, or equipment and availability of external utility services.
- **Operational:** "Operational" refers to the performance level where most nonstructural systems required for normal use of the building are functional, although minor cleanup and repair of some items might be required. Achieving the Operational nonstructural performance level requires considerations of many elements beyond those that are normally within the sole province of the structural engineer's responsibilities. For Operational nonstructural performance, in addition to ensuring that nonstructural components are properly mounted and braced within the structure, it is often necessary to provide emergency standby equipment to

provide utility services from external sources that might be disrupted. It might also be necessary to perform qualification testing to ensure that all necessary equipment will function during or after strong shaking.

- **Life Safety:** "Life Safety" refers to the post-earthquake damage state in which significant damage to the structure has occurred but some margin against either partial or total structural collapse remains. Some structural elements and components are severely damaged, but this damage has not resulted in large falling debris hazards, either inside or outside the building. Injuries might occur during the earthquake; however, the overall risk of life-threatening injury as a result of structural damage is expected to be low. It should be possible to repair the structure; however, for economic reasons, this repair might not be practical. Although the damaged structure is not an imminent collapse risk, it would be prudent to implement structural repairs or install temporary bracing before re-occupancy.

Most of the facilities do not meet the criteria for immediate occupancy, operational nonstructural performance, or life safety. Completion of the structural and nonstructural mitigation measures identified in the SEFT report will enable these facilities to meet these occupancy and safety criteria. The degree to which these facilities require mitigation (and the associated cost) vary significantly from one facility to the other as discussed later in this Report.

Table 4-8 Facility Assessment Summary

| Readiness to Meet M9.0 CSZ Earthquake | | | |
|---------------------------------------|---|--|---------------------------------------|
| Facility | Immediate Occupancy Structural Performance | Operational Nonstructural Performance | Life Safety Structural Performance |
| ASR # 1 and #2 Pump Station | No | No | No |
| ASR #4 Pump Station | No | No | No |
| ASR #5 Pump Station | No | No | No |
| Boone Road Pump Station | No | No | No |
| Creekside Pump Station | No | No | No |
| Deer Park Pump Station | No | No | No |
| Edwards Pump Station | No | No | No |
| Limelight Pump Station | No | No | No |
| Mountain View Pump Station | No | No | No |
| Salem/Keizer Intertie #1 Pump Station | No | No | No |
| Turner Control Facility | No | No | No |
| Candalaria Reservoir | No | No | N/A |
| Champion Hill Reservoir | No | No | N/A |
| Champion Hill Control Building | No | No | No |
| Eola #1B Reservoir | No | No | N/A |
| Fairmount Reservoir | No | No | N/A |

| Readiness to Meet M9.0 CSZ Earthquake | | | |
|---------------------------------------|--|---------------------------------------|------------------------------------|
| Facility | Immediate Occupancy Structural Performance | Operational Nonstructural Performance | Life Safety Structural Performance |
| Fairmount Control Building | No | No | No |
| Grice Hill Reservoir | No | No | N/A |
| Grice Hill Control Building | No | No | No |
| Lone Oak Reservoir | Yes | Yes | N/A |
| Lone Oak Control Building | No | No | No |
| Mill Creek #1 Reservoir | No | No | N/A |
| Mill Creek #1 Control Building | No | No | No |
| Mountain View Reservoir | No | No | N/A |

5.0 Water System Risk Assessment

5.1 Risk Assessment of Pipelines and Vertical Facilities

A risk assessment approach can support development and execution of a seismic rehabilitation and replacement capital improvement strategy. The risk assessment considers both the Consequence of Failure (COF) and Likelihood of Failure (LOF) of an asset to rank and prioritize that asset's overall risk. In the case of this Report, COF is a measure of the asset's criticality and LOF is a measure of the asset's vulnerability to seismic geohazards. Total risk for an asset is the LOF multiplied by the COF.

Together, the threat and vulnerability of an asset make up that asset's LOF. Assets that have a high LOF are those that have both a) physical vulnerabilities to seismic hazards and b) a high likelihood of seismic hazards. Assets that have a high COF are those that are part of the water system backbone and are critical to supporting fire flow and the critical social/economic needs of the community during the Short-Term Recovery Phase in the initial days following a CSZ earthquake. It is recommended that high risk assets are given higher priority for replacement/retrofit over lower risk assets.

An asset's risk score is calculated based by multiplying its LOF by its COF. The risk score may range from 1 to 25, as shown on Figure 5-1.

| RISK | | LIKELIHOOD | | | | |
|-------------|---|------------|----|----|----|----|
| | | 1 | 2 | 3 | 4 | 5 |
| CONSEQUENCE | 5 | 5 | 10 | 15 | 20 | 25 |
| | 4 | 4 | 8 | 12 | 16 | 20 |
| | 3 | 3 | 6 | 9 | 12 | 15 |
| | 2 | 2 | 4 | 6 | 8 | 10 |
| | 1 | 1 | 2 | 3 | 4 | 5 |

| Risk |
|----------------------------|
| Very High (25) |
| High (20) |
| Moderate to High (15 – 16) |
| Moderate (10 – 12) |
| Low to Moderate (8 – 9) |
| Low (1 – 5) |

Figure 5-1 Range of Potential Risk Scores

5.1.1 Consequence of Failure

The COF score for each asset (facility or pipeline segment) is equal to its criticality level. Criticality levels were assigned when establishing the system backbone (refer to Section 3.0, Water System Backbone Definition). COF values range from 1 to 5, as listed below:

- 5 – Highly Critical
- 4 – Critical
- 3 – Semi Critical
- 2 – Local Critical
- 1 – Not Critical/Redundant (not part of the system backbone)

A summary of COF scores for the City's backbone facilities is presented in Table 3-4 (as characterized by the numerical Criticality Level). COF values for pipelines are assigned in a GIS database. Pipeline segment COF scores were coordinated with the COF scores of vertical facilities they connect to, because these pipelines and vertical facilities are interdependent.

5.1.2 Likelihood of Failure for Pipelines

A LOF score was assigned to each pipeline segment, based upon the number of breaks per 1,000 feet within that pipe segment, as shown in Table 5-1.

Table 5-1 Likelihood of Failure Scores for Pipelines

| Likelihood of Failure | Breaks per 1,000 Feet | Percentage of Pipelines | Miles of Pipeline |
|-----------------------|-----------------------|-------------------------|-------------------|
| Low (1) | <0.1 | 29.1% | 230 |
| Low to Moderate (2) | 0.10 – 0.69 | 23.4% | 185 |
| Moderate (3) | 0.7 – 0.89 | 19.2% | 161 |
| Moderate to High (4) | 0.90 – 1.39 | 16.6% | 115 |
| High (5) | 1.40 – 3.01 | 13.2% | 99 |

5.1.3 Risk Assessment for Vertical Facilities

The LOF, COF, and risk scores for the 22 vertical facilities that were assessed in this project are summarized in Table 5-2.

Table 5-2 Risk Assessment for Vertical Facilities

| Facility | Service Level | Potential Liquefaction | Potential Landslide | LOF | COF | Risk | |
|----------------------------|---------------|------------------------|---------------------|-----|-----|------|------------------|
| Fairmount Reservoir | G-0 | | | 5 | 5 | 25 | Very High |
| Mountain View Reservoir | G-0 | | | 4 | 5 | 20 | High |
| Deer Park Pump Station | S-1 | | | 5 | 4 | 20 | High |
| Edwards Pump Station | S-1, S-2 | ■ | | 5 | 4 | 20 | High |
| Turner Control Facility | G-0 | ■ | | 4 | 5 | 20 | High |
| Lower Croisan Pump Station | S-2 | ■ | ■ | 5 | 4 | 20 | High |
| Mountain View Pump Station | W-1 | | | 4 | 4 | 16 | Moderate to High |
| ASR #1 and #2 Wells | S-2 | | | 4 | 4 | 16 | Moderate to High |
| ASR #5 Well | S-2 | | | 4 | 4 | 16 | Moderate to High |
| Salem/Keizer Intertie #1 | G-0 | ■ | | 4 | 4 | 16 | Moderate to High |

| Facility | Service Level | Potential Liquefaction | Potential Landslide | LOF | COF | Risk | |
|--|---------------|------------------------|---------------------|-----|-----|------|------------------|
| Boone Road Pump Station | S-2 | | | 4 | 4 | 16 | Moderate to High |
| Champion Hill Reservoir Control Building | S-3 | ■ | | 4 | 4 | 16 | Moderate to High |
| Grice Hill Reservoir Control Building | W-1 | | | 3 | 4 | 12 | Moderate |
| ASR #4 Well | S-2 | | | 3 | 4 | 12 | Moderate |
| Candalaria Reservoir | S-1 | | | 3 | 4 | 12 | Moderate |
| Champion Hill Reservoir | S-3 | ■ | | 3 | 4 | 12 | Moderate |
| Lone Oak Reservoir Control Building | S-2 | | | 3 | 4 | 12 | Moderate |
| Mill Creek #1 Reservoir Control Building | MCCC S-1 | | | 3 | 4 | 12 | Moderate |
| Creekside Pump Station | S-3 | | | 3 | 4 | 12 | Moderate |
| Fairmount Pump Station | S-2 | | | 5 | 1 | 5 | Low |

6.0 Water System Risk Mitigation Plan

This section describes the phasing of recommended improvements to address higher risk assets and rapidly restore water service after a major earthquake to meet social and economic needs. Improvements include replacement and hardening of pipelines and correction of deficiencies for vertical facilities which were identified through the vulnerability assessment. This risk mitigation plan leverages knowledge of pipeline and facility seismic vulnerabilities to develop a long-term plan for implementing water system seismic resilience improvements. Recommendations are provided in 15 to 30 year phases to allow the flexibility to incorporate these recommendations into the City's capital improvement plan.

6.1 Capital Program Prioritization Methodology

The project team developed priorities for the short, medium, and long-term CIP for seismic improvements in close consultation with City staff. The recommended risk mitigation efforts are informed by the City's LOS goals. This prioritization is summarized in Table 6-1.

Table 6-1 Capital Program Terms and Priorities

| Term | Priority | Risk Level of Facilities to Be Improved | Risk Level of Pipelines to Be Improved |
|---------------------------|--|---|--|
| Short (0 – 15 Years) | 1. Preserve Water in the System | Very High | Very High |
| | 2. Convey Treated Water | High | High |
| | 3. Implement Alternative Supplies | Moderate to High | Moderate to High |
| | 4. Complete Studies to Refine Understanding of Expected System Performance | Moderate | |
| Medium (10 – 25 Years) | 5. Harden the Rest of the Backbone | Low to Moderate | Moderate |
| | | Low | Low to Moderate |
| Long (20 – 50 years) | 6. Harden Distribution System to Reduce the Number of Repairs | - | Low |

In the **short term**, the City should focus on implementing mitigation that will help to preserve water in the system after an earthquake or to convey water to the backbone after an earthquake. As a priority, the City should implement the following strategies:

- Installation of seismic isolation valves installed at all reservoirs (the City already has seismic valves installed on a significant number of them) and seismic upgrades on the "very high" to "moderate" risk reservoirs and their control buildings.
- Seismic upgrades to pump stations which are appurtenant to reservoirs.

The City should also focus on conveyance of treated water to the backbone by hardening the transmission lines from Geren Island WTP to critical reservoirs, including to West Salem. The City should also implement providing alternative water supplies within this phase. Alternative local water supply development (such as drilling of new wells to access groundwater supplies) will provide additional supply reliability in the case of an emergency. The City should also complete studies to understand system hazards at vertical facilities not assessed as part of this study, such as Franzen Reservoir. As part

of the short-term phase, all "moderate" to "very high" risk facilities should be seismically improved and all "moderate to high" to "very high" risk pipelines should be hardened.

In the **medium term**, the City should focus on hardening the rest of the backbone system so that the system will remain operational following a major earthquake. "Low to moderate" and "low" risk facilities should be seismically improved and "moderate" and "low to moderate" risk pipelines (all remaining pipelines within the backbone system) should be hardened.

In the **long term**, the City should focus on hardening the rest of the distribution system to address the LOS goals discussed in Section 2.0. The City aims to serve a minimum of 80% of all customers within 1 to 2 weeks following a M9.0 CSZ earthquake. A limited number of breaks and leaks can be repaired by City crews in the days and weeks following an earthquake. To reduce the number of breaks and leaks down to an amount that can be quickly repaired by the City following an earthquake, and to meet the LOS goals, the City should need to replace most "low" risk pipelines.

6.2 Basis for Establishing Opinion of Probable Construction Costs

An Opinion of Probable Construction Cost (OPCC) was developed for each of the major vertical facilities and buried infrastructure identified in this Report. The OPCC was developed to the Class 5 (conceptual) level of accuracy, as defined by the Association for the Advancement of Cost Engineering (AACE), and expected to have an accuracy range from -30% to +50% of actual (2022) costs.

6.2.1 OPCC Assumptions for Pipelines

To develop the OPCC for pipelines, unit costs were developed using 1,000 linear feet (LF) of waterline. Three different pipe depths and sizes were used, and the costs were averaged to develop representative waterline replacement costs. The following items were included in the OPCC for pipelines:

- Mobilization.
- Insurance and bonds.
- System ties.
- Shoring for jacking pits.
- Corrosion protection.
- Cathodic protection.
- Fittings allowance.
- Pavement demolition and replacement over the top of the waterline.

Markups associated with the OPCC for pipelines varied depending on whether the pipelines were at rail, highway, waterway crossings, or not at any of these crossings, as shown in Table 6-2.

Table 6-2 Markups Associated with OPCC for Pipelines

| Cost Component | Pipelines | Rail & Highway Crossings | Waterway Crossings |
|---|-----------|--------------------------|--------------------|
| Contingencies ¹ | 40% | 40% | 40% |
| Professional Services ¹ | | | |
| Engineering | 10% | 15% | 20% |
| Construction Management and Inspection | 10% | 10% | 10% |
| Permitting | 5% | 8% | 10% |
| City Administration, Public Outreach, and Legal | 8% | 8% | 8% |

¹ Excludes right-of-way acquisition.

The following items were not included in the water pipeline OPCC:

- Fire hydrant with a gate valve and 6-inch fire service replacement, tracer wires, and butterfly valves. These are anticipated to be a minor additional cost (<\$5,000 on a 1,000 LF waterline replacement contract) to the project and generally covered by the "fittings allowance" or cost contingencies.
- Program costs (such as City staffing).
- Service line replacements – City staff noted that concurrent with replacement of the water mains, all service lines to the meter connection are also replaced. The waterline database used to develop the water pipeline OPCC had 2.5 miles of pipes that are 1.5 inches in diameter or smaller, and included pipes as small as 3/4-inch diameter. Therefore, it is possible that the service lines are already included, to a degree, in the pipeline database. Service line replacements were not explicitly included in the cost estimate to avoid any double-counting.

6.2.2 OPCC Assumptions for Vertical Facilities

The OPCC for vertical facilities is based on the detailed recommendations provided in the Technical Memorandum, Pump Station and Reservoir Seismic Vulnerability Assessment (September 6th, 2021), provided in Appendix C. As detailed engineering layouts of the proposed improvements were not available due to the conceptual nature of this study, the OPCC is largely based on parametric factoring of known costs for similar systems and analogous projects with comparable corresponding features and sizing. The OPCC for the vertical facilities sites is based the estimating allowances and contingencies noted in Table 6-3.

Table 6-3 OPCC Markups for Vertical Facilities

| Cost Component | Contingency Applied To | Vertical Facilities Contingency |
|--|--|---------------------------------|
| Contractor and subcontractor overhead and profit (OH&P), including market condition due to current labor availability and supply chain issues; mobilization, general conditions and field overhead expense | Direct construction cost (labor, materials, and equipment) | Base cost |
| Construction contingency | Direct construction cost, after OH&P | 30% |
| Professional services ¹ Engineering, construction management, and inspection | Construction cost ² | 30-40% |
| Additional contingency at Mountain View and Fairmount Reservoir, due to complexity of improvements | Construction and engineering costs | \$200,000 |

¹ Excludes right-of-way acquisition.

² Direct construction cost, after OH&P and construction contingency.

6.3 Pipeline System Prioritization and Cost Projections

6.3.1 Prioritization Approach

Pipeline work is prioritized based on risk using a combination of the LOF and COF scores. This resulted in the suggested phasing of improvements shown in Table 6-1. A summary of pipeline breaks and pipe length in miles for each LOF and COF is provided in Table 6-4, which is color-coded as follows:

- Red represents "high risk" and "very high risk" pipelines that have a COF and LOF of 5. "High risk" pipelines are those in pink that are not classified as "very high risk" and have an LOF of 4 paired with a COF of 5, or a COF of 4 paired with an LOF of 5.
- Orange represents "moderate to high risk" pipelines.
- Yellow represents "moderate risk" pipelines.
- Dark green represents "low risk" pipelines.
- Cells that are not color coded represent "very low risk" pipelines that have a COF of 1. These pipelines are not part of the system backbone.

Table 6-4 Pipeline Risk Matrix

| COF | LOF | | | | | | | | | |
|-----|--------|---------------------|--------|---------------------|--------|---------------------|--------|---------------------|--------|---------------------|
| | 1 | | 2 | | 3 | | 4 | | 5 | |
| | Breaks | Pipe Length (miles) | Breaks | Pipe Length (miles) | Breaks | Pipe Length (miles) | Breaks | Pipe Length (miles) | Breaks | Pipe Length (miles) |
| 5 | 0 | 3 | 13 | 5 | 8 | 2 | 104 | 17 | 91 | 10 |
| 4 | 0 | 18 | 52 | 22 | 57 | 13 | 101 | 17 | 69 | 8 |
| 3 | 0 | 3 | 2 | 1 | 4 | 1 | 24 | 4 | 48 | 5 |
| 2 | 0 | 5 | 12 | 5 | 8 | 2 | 16 | 3 | 11 | 1 |
| 1 | 3 | 230 | 416 | 185 | 704 | 161 | 692 | 115 | 936 | 99 |

Pipelines with an LOF of 1 do not require hardening because the number of breaks are anticipated to be almost zero due to either the low potential for seismic geohazards and/or the high anticipated resilience of that pipeline to withstand earthquake damage. Pipes that have an LOF of 1 and a COF of 1 represent 230 miles of pipeline, but are only forecasted to have three breaks, which can be repaired quickly by staff following an earthquake.

Pipelines with an LOF of 2 and a COF of 1 should be the City's lowest priority for hardening. These pipes represent 185 miles of pipeline, which equate to approximately 20% of the City's pipeline system by length. The LOS goals allow for a longer duration of time for bringing 20% of customers back into operation following a CSZ earthquake, which gives the City time to repair leaks and breaks as needed to restore system operation. Therefore, for this risk category, pipe replacement was not included in the cost projections. Twenty percent of the City's pipeline system does not equate to 20% of customers served, but length of pipe in miles was used as a surrogate until the City develops a more in-depth analysis.

Within a given risk level, the City could further prioritize replacement based upon the existing pipeline materials using the K1 and K2 values from Table 4-4 (i.e., prioritize replacement of pipeline materials with higher K1 and K2 values over pipelines materials with lower K1 and K2 values). For example, cast iron pipe has historically been highly vulnerable to both PGD and PGV/shaking, because it is brittle and susceptible to cracking. The joints are typically leaded and rigid. Even small movements will cause them to leak. Larger movements cause the pipe bells to break and/or the joints to separate.

6.3.2 Pipeline Mitigations

Pipeline joint systems and materials heavily influence a pipeline's ability to withstand the effects of earthquakes. Pipeline joints within seismically vulnerable areas should be designed to allow movement and/or deformation without joint failure when subjected to seismic forces. Pipe material should be designed to withstand shear and compression forces without local buckling. The overall system (joints and pipe material) should accommodate a certain amount of strain. Table 6-5 presents the recommended approach for selection of various pipe materials under different conditions.

Table 6-5 Pipe Replacement Material Selection

| Selection Criteria | Steel (Butt Welded) | Steel (Lap Welded) | DIP (Earthquake Resistant Joints) ⁶ | DIP (Mechanically Restrained Joints, not Wedges) | HDPE | PVCO ⁷ with Seismic Restrained Joints | PVCO ⁷ with Double Depth Bell |
|---|---------------------------|---------------------------|--|--|------|--|--|
| Cost per inch-Diameter/LF (\$) ¹ | 45 | 54 | 54 | 45 | 32 | 15 | 15 |
| Highway, creek, or rail crossing ² | ■ | ■ | ■ | ■ | ■ | ■ | ■ |
| 48" diameter or greater | ■ | | ■ | | | | |
| 24" ≤ diameter < 48" | ■ | ■ | ■ | ■ | ■ | | |
| 12" < diameter < 24" | ■ | ■ | ■ | ■ | ■ | | |
| 12" diameter or smaller ³ | ■ | ■ | ■ | ■ | ■ | ■ | ■ |
| PGD > 4" | ■ | | ■ | COF ≤ 3 | ■ | ■ | COF ≤ 3 |
| Corrosive soil conditions ⁴ | With corrosion protection | With corrosion protection | With corrosion protection | With corrosion protection | ■ | ■ | ■ |
| "Very Strong" ground shaking ⁵ | ■ | COF ≤ 3 | ■ | COF ≤ 3 | ■ | ■ | COF ≤ 3 |

¹ Does not include contingencies or engineering costs.

² Additional costs associated with trenchless construction.

³ Except service lines, which are generally constructed of copper tubing.

⁴ Steel corrosion potential is moderate or high, according to mapped corrosion of steel potential from the United States Department of Agriculture Natural Resources Conservation Service Web Soil Survey.
<https://websoilsurvey.sc.egov.usda.gov/App/HomePage.htm>

⁵ Very strong ground shaking is characteristic of areas which have PGVs higher than 24 inches per second. Pipelines in the City are not anticipated to have PGV values higher than 24 inches per second.

⁶ Earthquake resistant joints are restrained but allow longitudinal movement.

⁷ PVCO is molecularly-oriented PVC (AWWA C-909).

Empirical leak and break rates associated with modern piping alternatives, such as welded steel, earthquake-restrained ductile iron pipe (DIP), mechanically restrained ductile iron pipe, high density polyethylene (HDPE), and molecular-oriented polyvinyl chloride (PVCO) are not readily available. Much more research on leaks and breaks is available for historic piping materials such as ductile iron, cast iron, and asbestos concrete, which characterize the majority of most water distribution systems. Therefore, it is difficult to quantify the impact of replacing older pipe materials with newer pipe materials. Future research, conducted following future earthquakes in areas that have seismically hardened systems, can help to clarify break rates associated with various modern joint and material systems.

PVCO has successfully undergone extreme earthquake testing at the seismic pipe lab at Cornell University. PVC (AWWA C-900) pipe is inherently brittle and has been known for cracks to propagate the

full length of the pipe in non-earthquake conditions. PVC was installed in Christchurch, New Zealand, and subjected to the 2011 earthquake. It suffered significant damage which resulted in many utilities transitioning to use of HDPE or PVCO in liquefiable soils.

Another area of emerging research is to what degree cured-in-place pipe (CIPP) provides seismic resilience. Rehabilitating a pipe with CIPP is a cost-effective means of extending a pipeline's expected useful life. A CIPP liner converts a jointed pipe to a continuous pipeline, and more joint stability can reduce the rate of breaks and leaks, resulting in less potential for damage during an earthquake. City staff are encouraged to keep track of pipelines that are already CIPP-rehabilitated when prioritizing pipes for repair and stay on top of current research regarding CIPP and seismic performance.

6.3.3 Cost Projections

For the purposes of developing the cost projections for this Report, assumptions were made about the pipeline replacement material, as shown in Table 6-6. It is noted that PVC and HDPE do not currently meet City design standards, but they are more cost-effective than steel and ductile iron pipes. Due to the large number of pipes that would need to be replaced to support the system backbone and distribution system as a whole in the event of a CSZ earthquake, the City should consider using these materials in seismically vulnerable areas, if they are appropriate for the site conditions, to reduce costs. The actual pipeline material selected for replacement will be determined later, during design of the pipeline improvements. The costs for pipeline system improvements for the Center Street Bridges are not included in the cost projections.

Table 6-6 OPCC Assumed Replacement Materials for Pipelines

| Pipe Size | Assumed Replacement Material |
|---|------------------------------|
| Mains ($\leq 12"$) | PVC C-909 Brute Deep Bell |
| Distribution Pipelines ($> 12"$ and $\leq 42"$) | HDPE |
| Transmission Pipelines ($> 42"$) | Steel Pipe Butt Weld |

A summary of the anticipated pipeline replacement costs in each risk category (not including replacement of LOF 1 pipes, which are not anticipated to fail, and COF 1/LOF 2 pipes, which should be repaired following an earthquake) is presented on Figure 6-1.




Figure 6-1 Summary of Pipeline Costs in Each Risk Category

6.4 Vertical Facilities Prioritization and Cost Projections

6.4.1 Prioritization Approach

Vertical facilities are prioritized using their risk scores, as shown in Table 5-2. Suggested phasing of improvements to these facilities is shown in Table 6-1. In the near term (in the earlier part of the Short-Term phase of Table 6-1), it is recommended that the City implement a seismic retrofit program to address life safety seismic deficiencies for water system structures that are frequently accessed by City staff and contractors.

6.4.2 Vertical Facility Mitigations

An approximate, high-level summary of recommended vertical facility mitigations are presented in Table 6-7 and Table 6-8. Refer to Section 4.0 of Appendix C for full mitigation concepts and details.

Table 6-7 Summary of Recommended Mitigations Measures at Reservoirs

| Reservoir | Summary of Recommendations |
|---------------|--|
| Candalaria | <ul style="list-style-type: none"> Perform an ASCE 41 Tier 2 assessment on the reservoir column reinforcement. Install stainless steel plates to connect riser, base, and lid to the precast construction joints in the vault. Repair any leaking precast joints with polyurethane resin or similar method in the vault. Verify pipe materials in the reservoir. Evaluate the adequacy of the overflow pipe and valve operator rise shafts to resist seismic forces in the vault. Install lateral bracing of the overflow pipe and valve operator riser shafts in the vault. Verify pipe and pump bracing in the vault, install as required. |
| Champion Hill | <u>Reservoir</u> <ul style="list-style-type: none"> Perform a geotechnical study to evaluate liquefaction hazard. Perform an ASCE Tier 2 assessment on the reservoir column reinforcement. Anchor pipe support pedestals. |
| | <u>Control Building</u> <ul style="list-style-type: none"> Perform a geotechnical study to evaluate liquefaction hazard. Install new shaped blocking and Simpson A35 clips for masonry walls and roof truss connection. Install blocking support and boundary nailing to support roof sheathing. Install metal connector hardware to provide a vertical connection between the roof trusses and kicker brace frames. Provide pipe, pump, and additional bracing for building elements. Install flexible couplings between the pumps and connected piping. Install blocking and metal connector hardware to provide connection from ceiling to walls for seismic force transfer. |

| Reservoir | Summary of Recommendations |
|------------|--|
| Eola #1B | <ul style="list-style-type: none"> Investigate extent and impact of circumferential concrete cracks. Perform an ASCE Tier 2 assessment on the reservoir column reinforcement. Investigate concrete deterioration near the lid connection of the valve vault. Install stainless steel plates to connect riser, base, and lid to the precast construction joints in the vault. Repair any leaking precast joints with polyurethane resin or similar method in the vault. Assess pipe and valve's adequacy to resist seismic force. |
| Fairmount | <u>Reservoir</u> <ul style="list-style-type: none"> Add 6-inch layer of shotcrete at the inside face of the perimeter walls and footings. Install stainless steel connections along the roof expansion joints. Install anchors between roof slab and the walls. Investigate interaction between the Fairmont Reservoir and the Fairmont Reservoir Control Building. Perform an ASCE Tier 2 assessment on the reservoir column reinforcement. Verify pipe materials in the reservoir. |
| | <u>Control Building</u> <ul style="list-style-type: none"> Conduct detailed structural seismic assessment. Provide pipe, pump, and additional bracing for building elements. Install flexible couplings between the pumps and connected piping. Verify connection of the motor to the top of the steel motor support. Replace any cast iron pipe and fittings. Replace any piping, valves, or fittings with corrosion damage. |
| Grice Hill | <u>Reservoir</u> <ul style="list-style-type: none"> Perform an ASCE Tier 2 assessment on the reservoir column reinforcement. Install connection brackets to anchor pipe support pedestals. |
| | <u>Control Building</u> <ul style="list-style-type: none"> Install new shaped blocking and Simpson A35 clips for masonry walls and roof truss connection. Install blocking support and boundary nailing to support roof sheathing. Install metal connector hardware to provide a vertical connection between the roof trusses and kicker brace frames. Provide pipe, pump, and additional bracing for building elements. Install flexible couplings between the pumps and connected piping. |
| Lone Oak | <u>Control Building</u> <ul style="list-style-type: none"> Source design drawings and calculations and perform a follow up ASCE 41 Tier 1 evaluation. Provide pipe, pump, and additional bracing for building elements. |

| Reservoir | Summary of Recommendations |
|---|---|
| Mill Creek #1 | <u>Reservoir</u> <ul style="list-style-type: none"> Perform an ASCE Tier 2 assessment on the reservoir column reinforcement. Install connection brackets to anchor pipe support pedestals. Install diagonal bracing between stair landing support posts. |
| | <u>Control Building</u> <ul style="list-style-type: none"> Install new shaped blocking and Simpson A35 clips for masonry walls and roof truss connection. Install blocking support and boundary nailing to support roof sheathing. Source design drawings and evaluate the adequacy of the load path from the roof to the masonry walls. Provide pipe, pump, and additional bracing for building elements. Install flexible couplings between the pumps and connected piping. Install blocking and metal connector hardware to provide connection from ceiling to walls for seismic force transfer. |
| Mountain View | <ul style="list-style-type: none"> Install seismic restraint between the reservoir walls and foundation. Operate the reservoir at a lower maximum elevation to reduce hydrodynamic forces and avoid a seismic retrofit. <p>Or</p> <ul style="list-style-type: none"> Re-wrap the core wall with circumferential prestressing strands encased with shotcrete. Install fiber reinforced polymer wrapping around columns. Verify pipe material. |
| Note: This table is not fully inclusive. Refer to Section 4.0 of Appendix C for full mitigation concepts and details. | |

Table 6-8 Summary of Pump Station and Control Facilities Recommendations

| Pump Station/ Control Facility | Summary of Recommendations |
|-----------------------------------|---|
| ASR #1 and #2 | <ul style="list-style-type: none"> Verify load path at roof step between the masonry walls. Verify roof sheathing. Install vertical steel angles where the east-west concrete masonry unit (CMU) walls interface with west wall of ASR #1 structure. Install new shaped blocking and Simpson A35 clips for masonry walls and roof truss connection. Verify masonry wall vertical reinforcement. Provide pipe, pump, and additional bracing for building elements. Install flexible couplings between the pumps and connected piping. Verify concrete pillar reinforcement adequacy. |
| ASR #4 | <ul style="list-style-type: none"> Verify roof sheathing. Investigate roof diaphragm capacity to transfer seismic forces due to hatch. Install new shaped blocking and Simpson A35 clips for masonry walls and roof truss connection. Verify masonry wall vertical reinforcement. Provide pipe, pump, and additional bracing for building elements. Install flexible couplings between the pumps and connected piping. |

| Pump Station/ Control Facility | Summary of Recommendations |
|-----------------------------------|---|
| ASR #5 | <ul style="list-style-type: none"> • Install new shaped blocking and Simpson A35 clips for masonry walls and roof truss connection. • Investigate ceiling diaphragm connection to masonry walls. • Verify ceiling nail size and spacing. • Verify masonry wall vertical reinforcement. • Investigate the adequacy of free-standing masonry wall to resist seismic forces without additional bracing. • Investigate extent of corrosion damage to steel column and repair. • Provide pipe, pump, and additional bracing for building elements. • Install flexible couplings between the pumps and connected piping. |
| Boone Road | <ul style="list-style-type: none"> • Investigate gable end framing, sheathing nailing, and connection details to roof. • Install wood panel overlay to existing sheathing. • Install sub-diaphragm framing and connection hardware to repair roof and wall bracing. • Provide pipe, pump, and additional bracing for building elements. • Install flexible couplings between the pumps and connected piping. • Verify connection of the motor to the top of the steel motor support. |
| Creekside | <ul style="list-style-type: none"> • Verify existing roof sheathing to truss nailing. • Verify roof to masonry wall connection and install new shaped blocking and Simpson A35 clips for masonry walls and roof truss connection. • Install plywood, blocking, steel straps, and metal connector hardware to repair CMU wall bracing. • Verify the roof sheathing and gable end masonry wall op plate connection. • Provide pipe, pump, and additional bracing for building elements. • Install flexible couplings between the pumps and connected piping. • Verify connection of the motor to the top of the steel motor support. |
| Deer Park | <ul style="list-style-type: none"> • Verify the size and location of masonry wall reinforcement. • Replace roof and install out-of-plane bracing to perimeter and interior masonry walls. • Provide pipe, pump, and additional bracing for building elements. • Install flexible couplings between the pumps and connected piping. |
| Edwards | <ul style="list-style-type: none"> • Perform a geotechnical study to investigate liquefaction and lateral spreading. • Replace the entire structure. • Provide pipe, pump, and additional bracing for building elements. • Install flexible couplings between the pumps and connected piping. • Verify connection of the motor to the top of the steel motor support. |
| Limelight | <ul style="list-style-type: none"> • Investigate extent and impact of vertical cracks in masonry shear walls. • Verify roof sheathing and truss nailing. • Install new shaped blocking and Simpson A35 clips for masonry walls and roof truss connection. • Install plywood, blocking, steel straps, and metal connector hardware to repair CMU wall bracing. • Provide pipe, pump, and additional bracing for building elements. • Install flexible couplings between the pumps and connected piping. |

| Pump Station/ Control Facility | Summary of Recommendations |
|---|---|
| Mountain View | <ul style="list-style-type: none"> • Install plywood/sheathing, framing/blocking, and connector hardware to provide a load path between the roof and interior masonry walls. • Verify roof to masonry wall connection and install new shaped blocking and Simpson A35 clips for masonry walls and roof truss connection. • Install plywood, blocking, steel straps, and metal connector hardware to repair CMU wall bracing. • Provide pipe, pump, and additional bracing for building elements. • Install flexible couplings between the pumps and connected piping. • Verify connection of the motor to the top of the steel motor support. • Install anchorage/positive connection between the strut and masonry shear wall for seismic demands. |
| Salem/Keizer Intertie #1 | <ul style="list-style-type: none"> • Perform a geotechnical study to investigate liquefaction and lateral spreading. • Investigate the gap between the City pump station and the City of Keizer building. • Install shaped blocking and boundary nailing to correct the gap in the roof sheathing. • Install new shaped blocking and Simpson A35 clips for masonry walls and roof truss connection. • Install flexible joints where water system piping penetrates through the pump station floor. • Install flexible couplings between the pumps and connected piping. • Verify connection of the motor to the top of the steel motor support. • Install anchorage/positive connection between the strut and masonry shear wall for seismic demands. |
| Turner Control Facility | <ul style="list-style-type: none"> • Perform a geotechnical study to investigate liquefaction and lateral spreading. • Verify the roof sheathing to masonry wall top plate connections. • Install fasteners between roof sheathing and outrigger. • Perform a geotechnical study to investigate liquefaction and lateral spreading. • Install flexible couplings between the pumps and connected piping. • Verify connection of the motor to the top of the steel motor support. • Install anchorage/positive connection between the strut and masonry shear wall for seismic demands. |
| Note: This table is not fully inclusive. Refer to Section 4.0 of Appendix C for full mitigation concepts and details. | |

6.4.3 Cost Projections

For each vertical facility assessed, costs were developed for (1) addressing known issues identified through the seismic vulnerability assessment, (2) additional studies recommended by the seismic vulnerability assessment, and (3) work identified from additional studies. These costs are broken into short and medium term CIP phases in Table 6-9.

Table 6-9 Short- and Medium-Term Vertical Facility CIP Projections

| Facility | Known Issues | Additional Studies | Potential Additional Work ¹ | Total |
|--------------------------------------|--------------------|--------------------|--|---------------------|
| Short-Term CIP (Years 0-15) | | | | |
| ASR 1&2 | \$180,000 | \$49,000 | \$100,000 | \$329,000 |
| ASR 4 | \$100,000 | \$36,000 | None | \$136,000 |
| ASR 5 | \$60,000 | \$65,000 | \$170,000 | \$295,000 |
| Creekside PS | \$120,000 | \$94,000 | \$80,000 | \$294,000 |
| Deer Park PS | \$130,000 | \$62,000 | \$190,000 | \$382,000 |
| Mountain View PS | \$230,000 | \$11,000 | \$30,000 | \$271,000 |
| Salem Keiser Intertie #1 | \$140,000 | \$21,000 | \$10,000 | \$171,000 |
| Turner Control Facility | \$70,000 | \$29,000 | \$100,000 | \$199,000 |
| Candalaria Reservoir | \$10,000 | \$101,000 | \$240,000 | \$351,000 |
| Champion Hill Reservoir | \$100,000 | \$8,000 | None | \$108,000 |
| Champion Hill Reservoir Control Bldg | \$180,000 | \$6,000 | \$10,000 | \$196,000 |
| Edwards PS | \$190,000 | \$11,000 | \$810,000 | \$1,011,000 |
| Fairmount Reservoir | \$2,650,000 | \$29,000 | \$390,000 | \$2,869,000 |
| Fairmount Res. Control Bldg | \$140,000 | \$18,000 | \$30,000 | \$188,000 |
| Grice Hill Res Control Bldg | \$150,000 | None | None | \$150,000 |
| Lone Oak Res. Cntrl Bldg | \$30,000 | \$44,000 | \$10,000 | \$84,000 |
| Mill Creek Reservoir | \$40,000 | \$8,000 | \$940,000 | \$988,000 |
| Mill Creek#1 Res. Cntrl. Bldg | \$60,000 | \$44,000 | \$150,000 | \$254,000 |
| Mountain View Reservoir | \$3,790,000 | None | \$70,000 | \$3,660,000 |
| Eolia 1B Seismic Valve | \$200,000 | None | None | \$200,000 |
| Subtotal – Short-Term CIP | \$8,570,000 | \$636,000 | \$3,330,000 | \$12,136,000 |
| Medium-Term CIP (Years 20-30) | | | | |
| Boone Road PS | \$110,000 | \$25,000 | \$140,000 | \$275,000 |
| Limelight PS | \$100,000 | \$67,000 | \$310,000 | \$477,000 |
| Eolia #1B Reservoir | \$80,000 | \$8,000 | \$20,000 | \$108,000 |
| Grice Hill Reservoir | \$20,000 | None | \$20,000 | \$40,000 |
| Lone Oak Reservoir | None | None | None | None |
| Subtotal – Medium-Term CIP | \$310,000 | \$100,000 | \$490,000 | \$900,000 |
| Total CIP | \$8.88M | \$0.74M | \$3.82M | \$13.04M |

¹This includes estimated costs for remedial measures that may arise from the additional studies; these additional studies would further define the nature, extent, and cost of this remedial work.

6.5 Seismic Capital Recommendations Summary

A summary of the priorities and total costs for the short, medium, and long term are presented in Table 6-10.

Table 6-10 Seismic Improvements Phasing and Cost Summary

| Term | Priority | Risk Level of Facilities to Be Improved | Risk Level of Pipelines to Be Improved |
|---------------------------|---|---|--|
| Short (0 – 15 Years) | 1. Preserve Water in the System 2. Convey Treated Water 3. Implement Alternative Supplies 4. Complete Studies to Understand System Hazards | Very High | Very High |
| | | High | High |
| | | Moderate to High | Moderate to High |
| | | Moderate | |
| Total Cost (Short Term) | | \$8.61 - 12M | \$1.82B |
| Medium (10 – 25 Years) | 5. Harden the Rest of the Backbone | Low to Moderate | Moderate |
| | | Low | Low to Moderate |
| Total Cost (Medium Term) | | \$0.41 - 0.90M | \$0.56B |
| Long (20 – 50 years) | 6. Harden Distribution System to Reduce the Number of Repairs | - | Low |
| Total Cost (Long Term) | | \$0 | \$1.27B |

6.6 Opportunities for Further Study and System Improvements

It is recommended that the City consider the following noncapital improvements to further mitigate the risk of a CSZ earthquake:

- **Emergency Contractors.** Staffing shortages and the ability of the City to mobilize contractors can impact the City's ability to respond to an emergency. The provision of standing emergency contracts with pipeline contractors and maintaining adequate staffing levels can help to improve the City's resilience and promote a quicker response to an emergency. It is recommended that the City consider the use of emergency contracts.
- **Public Emergency Preparedness.** The public can take certain steps to mitigate the impacts of a natural disaster. For example, maintaining a 2-week water supply and understanding where to find an emergency shelter are two steps that can mitigate the impact of an earthquake. Public outreach can help to promote preparedness.
- **Funding Assessment.** It is recommended that the City conduct a funding assessment and apply for alternative financing to support seismic resiliency improvements. It is also recommended that the City analyze staffing and funding constraints to help fully develop a sustainable program.
- **Seismic Upgrade Program.** It is recommended that the City develop a program for transmission pipelines and distribution pipelines which specify replacement materials to be used to promote seismic resiliency if those pipes are at risk of damage during a CSZ earthquake. It is recommended that new subdivisions that are developed in seismically vulnerable areas use seismically resistant materials for new pipelines. It is noted that PVC and HDPE do not currently meet City design standards, but they are more cost-effective than steel and ductile iron pipes.

The City should consider revising the City standards to allow use of these materials in seismically vulnerable areas if they are appropriate for the site conditions.

- **Integrate Seismic Vulnerabilities with Water Master Plan.** The City is undertaking a Water Master Plan that will identify hydraulic and structural deficiencies. It is recommended that the pipelines and vertical facilities that are identified as high priority in this seismic resiliency study be similarly prioritized in the master plan. Furthermore, it is recommended that system outage scenarios and their impact to the City's backbone system are evaluated in the master plan or as a separate effort.

It is also recommended that the City consider the following future studies and system improvements to further mitigate the risk of a CSZ earthquake:

- **Valve Isolation Analysis.** The system can be modeled to determine: (1) valves that must be closed to isolate the backbone and (2) how to prioritize those valves considering the number of valves that can be closed each day in an emergency. The number of valves that can be closed in a day depends upon the number of field crews that are available during an emergency to perform this service. A valve isolation analysis can be used to develop a workflow and strategy for valve isolation and should consider both valve and hydrant flushing.
- **Operations & Maintenance (O&M) Inventory Assessment.** An O&M inventory assessment will enable the City to know what inventory of materials should be kept on hand in case of an emergency, such as pipe clamps, couplings, pipe materials, or chemicals. Materials stored for an emergency must also be stored safely in case they are not needed for a long time. Storage of materials can be costly, especially for large diameter pipes, but it is useful to have some materials on hand so that supply chain delays will not have large impacts on the City's disaster response. This assessment can also review the use of inflatable pipes on a temporary basis, such as to direct water across a street.
- **Center Street Bridge Improvements Design.** As a follow up to the recommendations provided in Subection 4.2.3 for the Center Street Bridge, additional design work is necessary to improve the pipeline performance during an earthquake and be able to adapt to differential settlement without pipe failure. The City is currently scoping the replacement of this line as part of ODOT's seismic retrofit of Center Street Bridge.
- **Development of Alternative Water Supplies.** It is recommended that the City consider implementation of alternative water supplies. The City currently operates four ASR wells and is considering constructing emergency well at additional locations. Wells located near the City's critical customers can offset some of the demand on the distribution system, which will not be hardened in the short term except for "very high," "high," and "moderate to high" pipeline segments. Because wells located in liquefiable soils are prone to seismic failure, it is recommended that the City site wells in areas with low liquefaction and landslide potential to safeguard the integrity of these wells during a seismic event.
- **Seismic Evaluation of Remaining Water System Structures.** It is recommended that the City conduct seismic evaluations of the remaining inventory of water system structures (pump stations, reservoirs, communications towers, etc.) as part of a future project. A key component of these evaluations is the assessment of Franzen Reservoir.

- **Hydrants and Seismic Shutoff Valves.** It is recommended that the City consider installing hydrants between the reservoirs and seismic isolation valves so that stored water can be accessed by the City staff and the City Fire Department. The majority of the City's reservoirs have seismic shutoff valves to preserve water storage. However, the reservoir sites with seismic shutoff valves seem to be lacking hydrants that are connected between the reservoir and the seismic valve. As a result, fire trucks may not currently have a way to access the water stored in the reservoirs after the seismic valves close. As part of the City's resilience implementation plan, it is recommended that a hydrant is installed between the connection between each of the reservoirs and its seismic shutoff valve.
- **Evaluate Improvement Alternatives.** It is recommended that the City evaluate improvement alternatives for the transmission main alignments and for opportunities to serve West Salem during a CSZ earthquake.

7.0 References

- American Lifelines Alliance. April 2001. Seismic Fragility Formulations for Water Systems Part 1 – Guideline. Available: https://www.americanlifelinesalliance.com/pdf/Part_1_Guideline.pdf.
- American Lifelines Alliance. April 2001. Seismic Fragility Formulations for Water Systems Part 2 – Appendices. Available: https://www.americanlifelinesalliance.com/pdf/Part_2_Appendices.pdf.
- National Institute of Standards and Technology. May 2016. Community Resilience Planning Guide for Buildings and Infrastructure Systems, Volume 1, Special Publication 1190. Available: <https://nvlpubs.nist.gov/nistpubs/SpecialPublications/NIST.SP.1190v1.pdf>. Accessed: February 11, 2021.
- Oregon Seismic Safety Policy Advisory Commission. February 2013. The Oregon Resilience Plan: Reducing Risk and Improving Recovery for the Next Cascadia Earthquake and Tsunami. Available: https://www.oregon.gov/oem/documents/oregon_resilience_plan_final.pdf. Accessed: February 11, 2021.
- SEFT Consulting Group. June 2022. Final Technical Memorandum: Pump Station and Reservoir Seismic Vulnerability Assessment.
- Shannon & Wilson. May 2021. Seismic Geohazard Evaluation Report.
- U.S. Department of Homeland Security. June 2016. National Disaster Recovery Framework, Second Edition. Available: https://www.fema.gov/sites/default/files/2020-06/national_disaster_recovery_framework_2nd.pdf. Accessed: February 11, 2021.
- Wang, Y., and Leonard, W.J., 1996, Relative Earthquake Hazard Maps of the Salem East and Salem West Quadrangles, Marion and Polk Counties, Oregon. Oregon Department of Geology and Mineral Industries, Open File Report GMS 105.
- Wang, Y. Bartlett, S.F., and Miles, S.B. Oregon Department of Geology and Mineral Industries. August 2012. Earthquake Risk Study for Oregon's Critical Energy Infrastructure Hub. Available: <https://digital.osl.state.or.us/islandora/object/osl:24734>. Accessed: February 11, 2021.

Appendix A. Critical Social/Economic Needs

Appendix A
Critical Social/Economic Needs: Name and Address List

| Parcel Description | Address | City GIS PLACE_TYPE |
|---|--|--|
| Hospitals | | |
| SALEM HOSPITAL | 1002 BELLEVUE ST SE | Health Care Clinic or Service |
| SALEM HOSPITAL | 2455 FRANZEN ST NE | Health Care Clinic or Service |
| SALEM HOSPITAL | 2561 CENTER ST NE | Health Care Clinic or Service |
| SALEM HOSPITAL | 3300 & 3310 STATE ST | Health Care Clinic or Service |
| SALEM HOSPITAL | 665 & 699 WINTER ST SE | Hospital / Health Care Complex |
| SALEM HOSPITAL | 698 12TH ST SE | Health Care Clinic or Service |
| SALEM HOSPITAL | 875, 939, & 1127 OAK ST SE | Hospital / Health Care Complex |
| SALEM HOSPITAL | 1073 OAK ST SE | Health Care Clinic or Service |
| SALEM HOSPITAL | 985 MISSION ST SE | Health Care Clinic or Service |
| SALEM HOSPITAL REGIONAL LABORATORY | 869 MEDICAL CENTER DR NE | Health Care Clinic or Service |
| Urgent Care Centers | | |
| KAISER PERMANENTE NORTH LANCASTER | 2400 LANCASTER DR NE | Health Care Clinic or Service |
| MEND CLINIC ORTHOPEDIC URGENT CARE | 2936 COMMERCIAL ST SE | Health Care Clinic or Service |
| SALEM CLINIC | 2020 CAPITOL ST NE | Health Care Clinic or Service |
| SALEM CLINIC SOUTH | 2531 BOONE RD SE | Health Care Clinic or Service |
| SALEM HEALTH MEDICAL CLINIC | 1049 EDGEWATER ST NW | Health Care Clinic or Service |
| SOUTH SALEM IMMEDIATE CARE CLINIC | 3777 COMMERCIAL ST SE | Health Care Clinic or Service |
| SWIFTCARE | 560 Wallace Rd NW Suite 140 | BV_ADDED |
| Dialysis Centers | | |
| DAVITA DIALYSIS | 1220 LIBERTY ST NE | Health Care Clinic or Service |
| DAVITA DIALYSIS | 645 9TH ST NW STE 145 | BV_ADDED |
| DAVITA DIALYSIS | 421 LANCASTER DR NE | BV_ADDED |
| DAVITA DIALYSIS | 4792 PORTLAND RD NE | BV_ADDED |
| DAVITA DIALYSIS | 3550 LIBERTY RD S STE 100 | BV_ADDED |
| FRESENIUS KIDNEY CARE | 1060 2ND ST NW | Health Care Clinic or Service |
| FRESENIUS KIDNEY CARE | 440 LANCASTER DR NE | BV_ADDED |
| City of Salem Critical Services | | |
| CITY HALL | 1320 EDGEWATER ST NW | Office Business |
| CITY OF SALEM INFORMATION TECHNOLOGY | 295 CHURCH ST SE | Multi-Use Building |
| SALEM AIRPORT TERMINAL BUILDING / SALEM AIRPORT TOWER | 2990 & 3000 25TH ST SE | Airport Terminal, Runway or Support Facility |
| SALEM CITY SHOPS COMPLEX | 1388 - 1590 20TH ST SE 1395 - 1582 22ND ST SE | Salem City Facility |
| SALEM FIRE STATION 11 | 1970 ORCHARD HEIGHTS RD NW | Salem City Fire Station |
| SALEM FIRE STATION 8 | 4000 LANCASTER DR NE | Salem City Fire Station |
| SALEM FIRE STATION 7 | 5021 LIBERTY RD S | Salem City Fire Station |
| SALEM MAIN LIBRARY | 1400 BROADWAY ST NE | Service Business |
| SALEM POLICE DEPT EMERGENCY SERVICES BUILDING | 4730 LIBERTY RD S | Salem City Facility |
| SALEM POLICE FACILITY | 333 DIVISION ST NE | Municipal Police Station |
| WILLAMETTE VALLEY COMMUNICATIONS CENTER | 595 COTTAGE ST NE | Salem City Facility |
| State of Oregon Critical Services | | |
| ANDERSON READINESS CENTER | 3225 STATE ST | State Government Facility |
| ARMY AVIATION SUPPORT FACILITY | 1921 TURNER RD SE | State Government Facility |
| CAPITOL BUILDING | 900 COURT ST NE | State Government Facility |
| DEPARTMENT OF AVIATION | 3040 25TH ST SE | State Government Facility |
| DEPT OF ADMINISTRATIVE SERVICES | 155 COTTAGE ST NE | State Government Facility |
| DEPT OF ENERGY | 550 CAPITOL ST NE | State Government Facility |
| DEPT OF FORESTRY | 2600 STATE ST 2600 LEE ST SE | State Government Facility |
| HUMAN SERVICES BUILDING | 500 SUMMER ST NE | State Government Facility |
| ODOT | 455 & 885 AIRPORT RD SE 1158 & 1178 CHEMEKETA ST NE 4040 FAIRVIEW INDUSTRIAL DR SE | State Government Facility |
| ODOT AUTO MAINTENANCE | 2480 TURNER RD SE | State Government Facility |
| ODOT MATERIALS LAB | 800 AIRPORT RD SE | State Government Facility |
| ODOT MILL CREEK BUILDING | 555 13TH ST NE | State Government Facility |
| ODOT SAFE HAVEN | 1144 CENTER ST NE | State Government Facility |
| ODOT TRAFFIC SIGNAL DIVISION | 2445 LIBERTY ST NE | State Government Facility |
| OREGON LOTTERY BUILDING | 500 AIRPORT RD SE | State Government Facility |
| OREGON PUBLIC SAFETY ACADEMY | 4190 AUMSVILLE HW SE | State Government Facility |
| OREGON STATE FAIRGROUNDS | 2330 17TH ST NE | State Government Facility |
| OREGON STATE HOSPITAL | 2600 CENTER ST NE | State Government Facility |
| OREGON STATE POLICE OFFICE | 3545 & 3565 TRELSTAD AV SE | State Police Station / Facility |
| PUBLIC SERVICE BUILDING | 255 CAPITOL ST NE | State Government Facility |
| PUBLIC UTILITY COMMISSION | 201 HIGH ST SE | Office Business |

Appendix A
Critical Social/Economic Needs: Name and Address List

| Parcel Description | Address | City GIS PLACE_TYPE |
|---|----------------------------------|---|
| State of Oregon Critical Services (Cont.) | | |
| SANTIAM CORRECTIONAL INSTITUTION | 4005 AUMSVILLE HW SE | State Government Facility |
| STATE DATA CENTER | 530 AIRPORT RD SE | State Government Facility |
| STATE LIBRARY BUILDING | 250 WINTER ST NE | Library / Research Facility |
| STATE MOTOR POOL | 1100 AIRPORT RD SE | State Government Facility |
| SUPREME COURT BUILDING | 1163 STATE ST | State Government Facility |
| TRANSPORTATION BUILDING | 355 CAPITOL ST NE | State Government Facility |
| Marion County Critical Services | | |
| MARION COUNTY COURTHOUSE | 100 HIGH ST NE | County Government Facility |
| MARION COUNTY HEALTH | 2045 SILVERTON RD NE | County Government Facility |
| MARION COUNTY HEALTH DEPT | 3180 CENTER ST NE | County Government Facility |
| MARION COUNTY OFFICE BUILDING | 555 COURT ST NE | Office Business |
| Correctional Facilities | | |
| HILLCREST YOUTH CORRECTIONAL FACILITY | 2450 STRONG RD SE | State Government Facility |
| MARION COUNTY CORRECTIONAL FACILITY | 4000 AUMSVILLE HW SE | County Government Facility |
| MARION COUNTY JUVENILE DEPT DETENTION CENTER | 2970 CENTER ST NE | County Government Facility |
| MILL CREEK CORRECTIONAL FACILITY | 5400 , 5465, & 5471 TURNER RD SE | State Government Facility |
| OREGON STATE CORRECTIONAL INSTITUTION | 3405 DEER PARK DR SE | State Government Facility |
| STATE PENITENTIARY | 2605 STATE ST | State Government Facility |
| STATE PENITENTIARY MINIMUM | 2809 STATE ST | State Government Facility |
| Emergency Shelters & Community Water Distribution Points | | |
| AUBURN ELEMENTARY SCHOOL | 4612 AUBURN RD NE | Public Elementary School |
| BATTLE CREEK ELEMENTARY SCHOOL | 1640 WALN DR SE | Public Elementary School |
| BRUSH COLLEGE ELEMENTARY SCHOOL | 2623 DOAKS FERRY RD NW | Public Elementary School |
| CHEMEKETA COMMUNITY COLLEGE | 4000 LANCASTER DR NE | Community College |
| CORBAN UNIVERSITY | 5000 DEER PARK DR SE | College / University Building |
| CROSSLER MIDDLE SCHOOL | 1155 DAVIS RD S | Public Middle School |
| HOUCK MIDDLE SCHOOL | 1155 CONNECTICUT ST SE | Public Middle School |
| JUDSON MIDDLE SCHOOL | 4512 JONES RD SE | Public Middle School |
| LESLIE MIDDLE SCHOOL | 3850 PRINGLE RD SE | Public Middle School |
| MCKAY HIGH SCHOOL | 2440 LANCASTER DR NE | Public High School |
| NORTH SALEM HIGH SCHOOL | 765 14TH ST NE | Public High School |
| PARRISH MIDDLE SCHOOL | 802 CAPITOL ST NE | Public Middle School |
| PUTNAM UNIVERSITY CENTER | 935 MILL ST SE | College / University Building |
| ROBERT W STRAUB MIDDLE SCHOOL | 1920 WILMINGTON AV NW | Public Middle School |
| ROBERTS HIGH SCHOOL-STATE STREET CAMPUS | 3620 STATE ST | Public Alternative High School |
| SALEM CONVENTION CENTER | 200 COMMERCIAL ST SE | Assembly / Exhibition Hall |
| SOUTH SALEM HIGH SCHOOL | 1910 CHURCH ST SE | Public High School |
| SPRAGUE HIGH SCHOOL | 2373 KUEBLER RD S | Public High School |
| STEPHENS MIDDLE SCHOOL | 4962 HAYESVILLE DR NE | Public Middle School |
| TOKYO INTERNATIONAL UNIVERSITY OF AMERICA | 1300 MILL ST SE | College / University Building |
| WALDO MIDDLE SCHOOL | 2805 LANSING AV NE | Public Middle School |
| WALKER MIDDLE SCHOOL | 1075 8TH ST NW | Public Middle School |
| WEST SALEM HIGH SCHOOL | 1655 DOAKS FERRY RD NW | Public High School |
| Community Water Distribution Points | | |
| CASCADES GATEWAY PARK | 2100 TURNER RD SE | Developed City, County or State Park / Area |
| LIMELIGHT WATER PUMP STATION | 880 VAN BUREN DR NW | Public Water Pump Station |
| RIVER ROAD PARK | 3045 RIVER RD N | Developed City, County or State Park / Area |
| SALEM CITY SHOPS BUILDING 16 WATER STORAGE | 1440 20TH ST SE | Salem City Facility |
| SALEM FIRE STATION 1 | 370 TRADE ST SE | Salem City Fire Station |
| SALEM FIRE STATION 2 | 875 MADISON ST NE | Salem City Fire Station |
| SALEM FIRE STATION 3 | 1884 LANSING AV NE | Salem City Fire Station |
| SALEM FIRE STATION 4 | 200 ALICE AV S | Salem City Fire Station |
| SALEM FIRE STATION 5 | 1520 GLEN CREEK RD NW | Salem City Fire Station |
| SALEM FIRE STATION 6 | 2740 25TH ST SE | Salem City Fire Station |
| SALEM FIRE STATION 7 | 1970 ORCHARD HEIGHTS RD NW | Salem City Fire Station |
| SALEM FIRE STATION 8 | 4000 LANCASTER DR NE | Salem City Fire Station |
| SALEM FIRE STATION 9 | 5080 BATTLE CREEK RD SE | Salem City Fire Station |
| SALEM FIRE STATION 10 | 3611 STATE ST | Salem City Fire Station |
| SALEM FIRE STATION 11 | 5021 LIBERTY RD S | Salem City Fire Station |
| SALEM/KEISER INTERTIE #1 (CHERRY AVE BOOSTER) | 4000 BLOCK CHERRY AVE NE | Public Water Pump Station |
| SOUTH RIVER ROAD WATER PUMP STATION | 3285 RIVER RD S | Public Water Pump Station |
| TURNER CONTROL WATER FACILITY | 7100 3RD ST SE | Public Water Facility |
| WEATHERS STREET PARK | 4188 WEATHERS ST NE | Developed City, County or State Park / Area |

Appendix A
Critical Social/Economic Needs: Name and Address List

| Parcel Description | Address | City GIS PLACE_TYPE |
|--|---------------------------|-------------------------------|
| Vulnerable Populations | | |
| ADULT CARE HOME | 1530 GABRIELA CT NE | Adult Care Home or Facility |
| AFH LICENSE #514816 | 3565 BELLE VISTA CT S | Adult Care Home or Facility |
| AVAMERE SKILLED NURSING FACILITY | 3445 BOONE RD SE | Adult Care Home or Facility |
| BATTLE CREEK MEMORY CARE | 1805 WALN DR SE | Adult Care Home or Facility |
| BERRY CARE | 1665 BERRY ST SE | Adult Care Home or Facility |
| BONAVENTURE SENIOR LIVING CENTER | 3411 BOONE RD SE | Retirement Center or Other |
| BROOKDALE SALEM ALZHEIMERS & DEMENTIA CARE(Clare Bridge) | 1355 BOONE RD SE | Retirement Center or Other |
| BROOKSTONE ALZHEIMER SPECIAL CARE CENTER | 5881 WOODSIDE DR SE | Retirement Center or Other |
| CAPITAL MANOR RETIREMENT | 368 LOWER LAVISTA CT NW | Retirement Center or Other |
| CAPITAL MANOR RETIREMENT | 1961 MANORVIEW LN NW | Retirement Center Residence |
| CAPITOL MANOR MAINTENANCE BLDG | 2071 SALEM DALLAS HW NW | Retirement Center or Other |
| DANVILLE SERVICES OF OREGON LLC | 4900 LIBERTY RD S | Adult Care Home or Facility |
| FARMINGTON SQUARE OFFICE | 920 BOONE RD SE | Retirement Center or Other |
| FORDS WESTSIDE MANOR | 1042 8TH ST NW | Retirement Center or Other |
| FOUR SEASONS RESIDENTIAL CARE FACILITY | 2850-2855 EVERGREEN AV NE | Adult Care Home or Facility |
| GIBSON CREEK ASSISTED LIVING OFFICE | 1615 BRUSH COLLEGE RD NW | Adult Care Home or Facility |
| HARMONY HOUSE | 3062 HYACINTH ST NE | Adult Care Home or Facility |
| HAWTHORNE HOUSE | 3042 HYACINTH ST NE | Adult Care Home or Facility |
| HIDDEN LAKES OFFICE | 400 MADRONA AV SE | Retirement Center or Other |
| HOME INSTEAD SENIOR CARE | 2015 25TH ST SE | Health Care Clinic or Service |
| INDEPENDENT LIVING CENTER AND DAYCARE FACILITY | 2990 BOONE RD SE | Adult Care Home or Facility |
| JASON LEE MANOR | 1551 CENTER ST NE | Retirement Center or Other |
| LANCASTER VILLAGE RETIREMENT COMMUNITY | 1496 BRENNER ST NE | Retirement Center or Other |
| LANCASTER VILLAGE RETIREMENT COMMUNITY | 4099 CYPRESS ST NE | Retirement Center or Other |
| LANCASTER VILLAGE RETIREMENT COMMUNITY | 4138 - 4156 MARKET ST NE | Retirement Center or Other |
| LANCASTER VILLAGE RETIREMENT COMMUNITY | 1492 BRENNER ST NE | Retirement Center or Other |
| MADRONA HILLS RETIREMENT APTS OFFICE | 707 MADRONA AV SE | Retirement Center or Other |
| MEADOW CREEK VILLAGE | 3988 12TH ST CUTOFF SE | Retirement Center or Other |
| MOSAIC SENIOR LIVING | 2950 BOONE RD SE | Retirement Center or Other |
| ORCHARD HEIGHTS SENIOR COMMUNITY | 695 ORCHARD HEIGHTS RD NW | Retirement Center or Other |
| OREGON SCHOOL FOR THE DEAF | 999 LOCUST ST NE | Special Purpose School |
| REDWOOD HEIGHTS ASSISTED LIVING CO | 4050 12TH ST CUTOFF SE | Retirement Center or Other |
| RODINA RETIREMENT CENTER | 4107 FISHER RD NE | Retirement Center or Other |
| SALEM MASONIC TEMPLE CARE HOME | 1601 BRUSH COLLEGE RD NW | Adult Care Home or Facility |
| SHANGRI LA CORP | 1460 VISTA AV SE | Adult Care Home or Facility |
| SOUTHERN HILLS ASSISTED LIVING COMMUNITY | 4795 SKYLINE RD S | Adult Care Home or Facility |
| SPRUCE VILLA INC SIZEMORE APTS | 1915 SIZEMORE DR NE | Adult Care Home or Facility |
| SUNNY OAKS INC | 2526 WILARK DR NW | Adult Care Home or Facility |
| SUNNY OAKS INC THE GROTTO | 4375 RICKEY ST SE | Adult Care Home or Facility |
| SUNNYSIDE CARE HOME | 4515 SUNNYSIDE RD SE | Retirement Center or Other |
| SWEET BYE N BYE ASSISTED LIVING | 2520 CORAL AV NE | Retirement Center or Other |
| SWEET BYE N BYE RCF | 2480 CORAL AV NE | Adult Care Home or Facility |
| THARSEL NURSING HOME | 2210 LANSING AV NE | Adult Care Home or Facility |
| THE RIDGE AT MADRONA HILLS CLUBHOUSE | 678 RATCLIFF DR SE | Retirement Center or Other |
| THE SPRINGS AT SUNNYVIEW RETIREMENT COMMUNITY | 1950 45TH AV NE | Retirement Center or Other |
| THE WOODS AT WILLOWCREEK | 4398 GLENCOE ST NE | Adult Care Home or Facility |
| TIERRA ROSE SENIOR LIVING COMMUNITTY | 4254 WEATHERS ST NE | Retirement Center or Other |
| TOUCH OF LOVE SENIOR CARE | 4190 SUNNYVIEW RD NE | Adult Care Home or Facility |
| WILLSON HOUSE | 1625 CENTER ST NE | Retirement Center or Other |
| WINDSONG OF EOLA HILLS | 2030 WALLACE RD NW | Adult Care Home or Facility |
| WOODLAND RESIDENCE INN OFFICE | 4710 SUNNYSIDE RD SE | Retirement Center or Other |

Appendix B. Seismic Geohazard Evaluation Report



SUBMITTED TO:
Black & Veatch
19801 SW 72nd Ave Suite 200
Tualatin, Oregon, 97602



BY:
Shannon & Wilson, Inc.
3990 SW Collins Way, Ste 100
Lake Oswego, Oregon,
97035

503-210-4750
www.shannonwilson.com

DRAFT

SEISMIC GEOHAZARD EVALUATION REPORT

City of Salem Seismic Resilience Study

SALEM, OREGON



PAGE INTENTIONALLY LEFT BLANK FOR DOUBLE-SIDED PRINTING

Submitted To: Black & Veatch
19801 SW 72nd Ave Suite 200
Tualatin, Oregon, 97602
Attn: Ho-ping Wei, PE

Subject: DRAFT SEISMIC GEOHAZARD EVALUATION REPORT, CITY OF SALEM
SEISMIC
RESILIENCE STUDY, SALEM, OREGON

Shannon & Wilson prepared this report and participated in this project as a subconsultant to Black & Veatch. Our scope of services was specified in Agreement Number 406828.12.1000 with Black & Veatch dated October 16, 2020. This report presents our Seismic Geohazard Evaluation and was prepared by the undersigned.

We appreciate the opportunity to be of service to you on this project. If you have questions concerning this report, or we may be of further service, please contact us.

Sincerely,

SHANNON & WILSON, INC.

Elliott Mecham, PE
Senior Associate

Kevin Wood, PE
Senior Engineer

DJS:KJW:ECM:WJP/las

EXECUTIVE SUMMARY

Based on our regional seismic hazard mapping and review of existing information provided to us or obtained from publicly available sources, we have assigned hazard rankings for various seismic hazards at each of the critical facilities provided to us. The hazard rankings for the various seismic hazards we considered are summarized in Exhibit ES-1. Numerous assets are located in areas where rock is mapped as the geologic surface unit. The risk of permanent ground deformation from liquefaction related hazards at rock sites is considered low and the primary seismic hazard is strong ground motions. Assets where rock is mapped and we have ranked a low risk of liquefaction and landslide include Grice Hill Reservoir, Hemlock Well, Mountain View Reservoir and Pump Station, Limelight Pump Station, Fairmount Reservoir, Candalaria Reservoir, the South Salem Repeater Tower, the ASR Wells, Skyline Repeater Tower, Lone Oak Reservoir, Creekside Pump Station, Deer Park Pump Station, and Mill Creek Reservoir.

We assigned a moderate hazard ranking to the EOLA 1B Reservoir for landslides due to the proximity of the reservoir to an existing landslide and the lack of available site-specific subsurface information. If subsurface information is provided to us for this site, we can reassess the landslide hazard and ranking at this site.

We assigned moderate and high hazard rankings to Croisan Lower Pump Station for liquefaction and landslides based on the predicted ground deformations, our site reconnaissance, and due to the site being near the contact between a large existing landslide and volcanic rock, and the lack of available site-specific subsurface information. If subsurface information is provided to us for this site, we can reassess the seismic hazards and rankings at this site.

Based solely on the geologic mapping and modeling, the potential permanent ground deformation was low at the Edwards S1 Pump Station. However, the assessment is based on the presence of coarse-grained flood deposits at the site as indicated on the geologic map and the nearest publicly available well logs indicate that site is mantled with fine-grained flood deposits. Because the predicted settlements in the mapping model are based on the assumption that the pump station is underlain by gravel as mapped which appears not to be correct based on the closest available well log, the hazard may not be adequately defined by the hazard mapping. Additionally, we understand that there have been uncontrolled releases of water at this site in the past that has resulted in the manifestation of surface settlement around the building foundations. Due to uncertainties associated with the liquefaction potential and subgrade, we consider the potential for permanent ground deformation from landslides and liquefaction to be moderate to high during a seismic event.

We assigned a moderate hazard rating to the Champion Hill Reservoir for potential liquefaction and landslides due to uncertainty in the subsurface conditions from a lack of available site-specific subsurface explorations. Based solely on the geologic mapping and the hazard modeling, the potential for geohazards was considered to be low due to rock being mapped at the site. However, the nearest publicly available well logs indicate that site is mantled with fine grained flood deposits, which are at a higher risk of permanent ground surface deformations during a seismic event. If subsurface information is provided to us for this site, we can reassess the seismic hazards and ranking at this site.

We assigned moderate and high hazard rankings to the Franzen Reservoir and Repeater Tower for potential landslides and fault rupture. The hazard rankings are based on our understanding from the existing basis of design reports provided to us and our understanding of past instability along the earthen embankments.

Exhibit ES-1: Summary of Geotechnical Seismic Hazard Rankings

| Site ID | Locations | Site Class | Liquefaction Settlement Hazard | Landslide Hazard | Fault Rupture Hazard |
|---------|---|------------|--------------------------------|------------------|----------------------|
| 1 | Salem-Keizer Intertie/Cherry Ave Booster Pump Station | D | M | L | L |
| 2 | Grice Hill Reservoir and Repeater Tower | B | L | L | L |
| 3 | Hemlock Well | B | L | L | L |
| 4 | Mountain View Reservoir and Pump Station | B | L | L | L |
| 5 | EOLA 1B Reservoir | B | L | M | L |
| 6 | Limelight Pump Station | B | L | L | L |
| 7 | Fairmount Reservoir | B | L | L | L |
| 8 | Candalaria Reservoir | B | L | L | L |
| 9 | South Salem Repeater Tower | B | L | L | L |
| 10 | Croisan Lower Pump Station | C/D | M | H | L |
| 11 | Edwards S1 Pump Station* | D | H | M | L* |
| 12 | ASR Wells | B | L | L | L |
| 13 | Skyline Repeater Tower | B | L | L | L |
| 14 | Lone Oak Reservoir | B | L | L | L |
| 15 | Creekside Pump Station | B | L | L | L |
| 16 | Champion Hill Reservoir | B | M | M | L |
| 17 | Boone Road Pump Station | D | L | L | L |
| 18 | Deer Park Pump Station | B | L | L | L |
| 19 | Mill Creek Reservoir | B | L | L | L |
| 20 | Turner Control Facility | D | L | L | L |
| 21 | Franzen Reservoir and Repeater Tower* | B | L | H | M |
| 22 | Geren Island Water Treatment Plant | D | L | L | L |

NOTE: L = Low, M = Moderate, H = High

*See discussion in main text. Geologic maps may not adequately capture geohazard.

Note that the sites highlighted in red did not have subsurface explorations available for review, and nearby well logs could not be found. Therefore, the sites highlighted in red in Exhibit ES-1 are based on the regional seismic hazard mapping only.

For the pipelines, the main hazards based on the mapping appears to be localized liquefaction, lateral spreading at the Sunset Park Willamette River crossing, and fault rupture where the pipelines cross the Turner and Mill Creek Faults and Waldo Hills Fault. Based on the mapping, the potential for localized liquefaction is highest at the Willamette River Crossings, near Turner, Oregon, and near the Geren Island Water Treatment Plant (WTP). However, existing subsurface information and Geotechnical Engineering Reports performed at Geren Island WTP show that the mapping-based liquefaction hazard may overestimate the actual hazard. This is due to the relatively high percentage of gravels underlying that site.

CONTENTS

| | | |
|-------|--|----|
| 1 | Scope of Services | 1 |
| 2 | Seismic Hazard Mapping..... | 1 |
| 2.1 | Approach..... | 1 |
| 2.2 | Existing Information Review | 2 |
| 2.2.1 | Regional Seismological Setting..... | 2 |
| 2.2.2 | Oregon Resilience Plan..... | 3 |
| 2.2.3 | Geology | 3 |
| 2.2.4 | Available Mapping..... | 4 |
| 2.3 | Shear Wave Velocity, Vs30 | 5 |
| 2.4 | Liquefaction Hazard | 6 |
| 2.5 | Landslide Susceptibility | 7 |
| 2.6 | PGA, SA1, SA0.3, and PGV..... | 7 |
| 2.7 | Probability of Liquefaction | 7 |
| 2.8 | Liquefaction-Induced PGD | 8 |
| 2.8.1 | Lateral Spreading | 8 |
| 2.8.2 | Settlement | 8 |
| 2.9 | Probability of Earthquake-Induced Landslides..... | 8 |
| 2.10 | Earthquake-Induced Landslide PGD | 8 |
| 2.11 | Surface Faulting..... | 9 |
| 2.12 | Seismic Hazards at Critical Infrastructure..... | 10 |
| 3 | Site Reconnaissance and Document Review | 10 |
| 3.1 | Site 1 - Salem-Keizer Intertie/Cherry Ave Booster Pump Station | 10 |
| 3.2 | Site 2 - Grice Hill Reservoir and Transmission Tower..... | 11 |
| 3.3 | Site 3 - Hemlock Well..... | 13 |
| 3.4 | Site 4 - Mountain View Reservoir and Pump Station | 13 |
| 3.5 | Site 5 - EOLA 1B Reservoir | 14 |
| 3.6 | Site 6 - Limelight Pump Station..... | 16 |
| 3.7 | Site 7 - Fairmont Reservoir..... | 16 |
| 3.8 | Site 8 - Candalaria Reservoir | 17 |

CONTENTS

| | | |
|------|--|----|
| 3.9 | Site 9 - South Salem Repeater Tower..... | 20 |
| 3.10 | Site 10 - Croisan Lower Pump Station..... | 20 |
| 3.11 | Site 11 - Edwards Pump Station..... | 22 |
| 3.12 | Site 12 - ASR Wells..... | 25 |
| 3.13 | Site 13 - Skyline Repeater Tower..... | 26 |
| 3.14 | Site 14 - Lone Oak Reservoir..... | 27 |
| 3.15 | Site 15 - Creekside Pump Station..... | 28 |
| 3.16 | Site 16 - Champion Hill Reservoir..... | 29 |
| 3.17 | Site 17 - Boone Road Pump Station..... | 30 |
| 3.18 | Site 18 - Deer Park Pump Station..... | 31 |
| 3.19 | Site 19 - Mill Creek Reservoir..... | 32 |
| 3.20 | Site 20 - Turner Control Facility..... | 34 |
| 3.21 | Site 21 - Franzen Reservoir and Transmission Tower..... | 34 |
| 3.22 | Site 22 - Geren Island Water Treatment Plant and Transmission Tower..... | 37 |
| 3.23 | Sites 23 and 24 - Upper and Lower Transmission Mains..... | 43 |
| 4 | Limitations..... | 45 |
| 5 | References..... | 45 |

Exhibits

| | |
|---|----|
| Exhibit ES-1: Summary of Geotechnical Seismic Hazard Rankings..... | v |
| Exhibit 2-1: USGS Fault Information for Mapped Faults Crossed by Transmission Mains..... | 9 |
| Exhibit 3-1: Photo of Salem-Keizer Intertie/Cherry Avenue Booster PS During Site Visit..... | 11 |
| Exhibit 3-2: Photo of Grice Hill Reservoir During Site Visit..... | 12 |
| Exhibit 3-3: Photo of Hemlock Well During Site Visit..... | 13 |
| Exhibit 3-4: Photo of Mountain View Reservoir and Pump Station During Site Visit..... | 14 |
| Exhibit 3-5: Photo of EOLA 1B Reservoir During Site Visit..... | 15 |
| Exhibit 3-6: Photo of Limelight Pump Station During Site Visit..... | 16 |
| Exhibit 3-7: Photo of Fairmont Reservoir During Site Visit..... | 17 |
| Exhibit 3-8: Photo of Candalaria Reservoir During Site Visit..... | 19 |
| Exhibit 3-9: Photo of Croisan Lower Pump Station During Site Visit..... | 21 |
| Exhibit 3-10: Photo of Cracking Observed in Driveway During Site Visit..... | 22 |
| Exhibit 3-11: Photo of Edwards Pump Station During Site Visit..... | 24 |

| | |
|---|----|
| Exhibit 3-12: Photo of Cracking and Settlement along Edwards Pump Station West Wall During Site Visit..... | 25 |
| Exhibit 3-13: Photo of Woodmansee Park During Site Visit..... | 26 |
| Exhibit 3-14: Photo of Lone Oak Reservoir During Site Visit..... | 28 |
| Exhibit 3-15: Photo of Creekside Pump Station During Site Visit..... | 29 |
| Exhibit 3-16: Photo of Champion Hill Reservoir During Site Visit..... | 30 |
| Exhibit 3-17: Photo of Boone Road Pump Station During Site Visit..... | 31 |
| Exhibit 3-18: Photo of Deer Park Pump Station During Site Visit | 32 |
| Exhibit 3-19: Photo of Mill Creek Reservoir During Site Visit..... | 33 |
| Exhibit 3-20: Photo of Franzen Reservoir During Site Visit..... | 36 |
| Exhibit 3-21: Photo of Slump Failure along Cut Slope of West Cell from 2008 (Photo Provided by the City of Salem) | 37 |
| Exhibit 3-22: Photo Showing Area Near New Ozone Facility | 40 |
| Exhibit 3-23: Photo Showing Middle Intake at Geren Island Water Treatment Plant | 41 |
| Exhibit 3-24: Photo Showing Geren Island Transmission Tower..... | 42 |

Tables

| | |
|----------|---|
| Table 1: | Seismic Hazards Mapped at Critical Infrastructure Locations |
|----------|---|

Figures

| | |
|------------|--|
| Figure 1: | Site Map |
| Figure 2: | Geologic Map |
| Figure 3: | Shear Wave Velocity, Vs 30 |
| Figure 4: | Liquefaction Hazard |
| Figure 5: | Landslide Susceptibility (Dry Conditions) |
| Figure 6: | Landslide Susceptibility (Wet Conditions) |
| Figure 7: | Peak Ground Acceleration, PGA |
| Figure 8: | 0.3-Second Spectral Acceleration, SA0.3 |
| Figure 9: | 1-Second Spectral Acceleration, SA1 |
| Figure 10: | Peak Ground Velocity, PGV |
| Figure 11: | Probability of Liquefaction |
| Figure 12: | Liquefaction-Induced Lateral Spreading Permanent Ground Deformation, PGD |
| Figure 13: | Liquefaction-Induced Settlement Permanent Ground Deformation, PGD |
| Figure 14: | Probability of Earthquake-Induced Landslides (Dry) |
| Figure 15: | Probability of Earthquake-Induced Landslides (Wet) |

- Figure 16: Earthquake-Induced Landslide Permanent Ground Deformation, PGD (Dry)
Figure 17: Earthquake-Induced Landslide Permanent Ground Deformation, PGD (Wet)
Figure 18: Previous Explorations on Geren Island

Appendices

- Appendix A: Existing Information Site 1 – Salem-Keizer Intertie and Cherry Avenue Booster Pump Station
Appendix B: Existing Information Site 2 - Grice Hill Reservoir
Appendix C: Existing Information Site 4 – Mountain View Reservoir
Appendix D: Existing Information Site 8 – Candalaria Reservoir
Appendix E: Existing Information Site 9 – South Salem Repeater Tower
Appendix F: Existing Information Site 10 – Edwards S1 Pump Station
Appendix G: Existing Information Site 14 – Lone Oak Reservoir
Appendix H: Existing Information Site 16 Champion Hill Reservoir
Appendix I: Existing Information Site 18 – Deer Park Pump Station
Appendix J: Existing Information Site 19 – Mill Creek Reservoir
Appendix K: Existing Information Site 20 – Turner Control Facility
Appendix L: Existing Information Site 21 – Franzen Reservoir and Repeater Tower
Appendix M: Existing Information Site 22 – Geren Island Water Treatment Plant
Appendix N: Existing Information Center Street Bridge Crossing
Important Information

1 SCOPE OF SERVICES

The purpose of the project is to provide a seismic resiliency analysis of the City of Salem (City) water treatment, transmission, and distribution system and to develop recommendations for mitigation and future infrastructure design. Shannon & Wilson's scope of work consisted of the following:

- Gather existing geologic/geotechnical and seismic data in the greater Salem area to develop a preliminary understanding of subsurface conditions and potential seismic hazards, including local and regional readily available geologic publications and maps, DOGAMI seismic hazard maps, Oregon Department of Water Resources well logs at select locations and geotechnical boring information and reports, as available.
- Evaluate existing geologic/geotechnical and seismic data in the greater Salem area to develop a thorough understanding of subsurface conditions and potential seismic hazards.
- Prepare seismic hazard maps including Seismic Hazard Maps based on the Magnitude 9.0 Cascadia Subduction Zone (CSZ) scenario defined in the Oregon Resilience Plan and local geology. The maps include peak ground velocity, peak ground acceleration, 0.3- and 1.0-second spectral accelerations, probability of liquefaction, liquefaction induced settlement, and landslide induced permanent ground deformation based on the methodology developed by HAZUS.
- Perform screening level liquefaction analyses on available geotechnical borings provided by the City using methods developed by Boulanger and Idriss (2014).
- Perform site visits to facilities identified by the City as critical.
- Evaluate the seismic geohazard rankings and assigned hazard rankings to the backbone assets identified by Black & Veatch and the City.

2 SEISMIC HAZARD MAPPING

2.1 Approach

The GIS map layers developed for this project are primarily based on published geologic maps; variations from actual site conditions should be expected. Also, the analyses, methods, and approaches applied herein were developed and used by the Oregon Department of Geology and Mineral Industries (DOGAMI) and the Federal Emergency Management Agency (FEMA) for planning purposes only. FEMA methodology referenced by DOGAMI refers to the Hazus® -MH 2.1 Technical Manual (FEMA, 2011). This manual

has since been updated, (Hazus® -MH 4.2 Technical Manual (FEMA, 2020), and these manuals were compared so that current, updated methodologies would be used where applicable. While the 2020 Hazus® manual expanded on analyses in the 2011 manual, for all of the analyses done for this regional mapping, the two manuals do not differ in their methodologies. Also, note that these types of analyses are not the same as those used for site-specific, code-based geotechnical design.

2.2 Existing Information Review

2.2.1 Regional Seismological Setting

Earthquakes in the Pacific Northwest occur largely as a result of the subduction of the Juan de Fuca plate beneath the North American plate along the Cascadia Subduction Zone (CSZ). The CSZ is located approximately parallel to the coastline from northern California to southern British Columbia. The compressional forces that exist between these two colliding plates cause the oceanic Juan de Fuca plate to descend, or subduct, beneath the continental plate at a rate of about 1.5-inches per year (DeMets and others, 1990). This process leads to volcanism in the North American plate and stresses and faulting in both plates throughout much of the western regions of southern British Columbia, Washington, Oregon, and northern California. Stress between the colliding plates is periodically relieved through great earthquakes at the CSZ plate interface.

Within the regional tectonic framework and historical seismicity, three broad earthquake sources are identified:

- Subduction Zone Interface Earthquakes originate along the CSZ, which is located 25 miles beneath the coastline. Paleoseismic evidence and historic tsunami records from Japan indicate that the most recent subduction zone interface event was in 1700 AD and was an approximately magnitude 9 earthquake that likely ruptured the full length of the CSZ.
- Deep-Focus, Intraplate Earthquakes originate from within the subducting Juan de Fuca oceanic plate as a result of the downward bending and tension in the subducted plate. These earthquakes typically occur 28 to 38 miles beneath the surface. Such events on the CSZ are estimated to be as large as magnitude 7.5. Historic earthquakes include the 1949 magnitude 7.1 Olympia earthquake, the 1965 magnitude 6.5 earthquake between Tacoma and Seattle, and the magnitude 6.8 2001 Nisqually earthquake. The highest rate of CSZ intraslab activity is beneath the Puget Sound area, with much lower rates observed beneath western Oregon.
- Shallow-Focus Crustal Earthquakes are typically located within the upper 12 miles of the earth's surface. The relative plate movements along the CSZ cause not only east-west compressive strain but dextral shear, clockwise rotation, and north-south

compression of the leading edge of the North American Plate (Wells and others, 1998), which is the cause of much of the shallow crustal seismicity of engineering significance in the region. The largest known crustal earthquake in the Pacific Northwest is the 1872 North Cascades earthquake with an estimated magnitude of about 7. Other examples include the 1993 magnitude 5.6 Scotts Mill earthquake and magnitudes 5.9 and 6.0 Klamath Falls earthquakes.

2.2.2 Oregon Resilience Plan

The Oregon Resilience Plan is a result of Oregon House Resolution 3, adopted in April 2011. The House Resolution directed the Oregon Seismic Safety Policy Advisory Commission “to lead and coordinate preparation of an Oregon Resilience Plan that reviews policy options, summarizes relevant reports and studies by state agencies, and makes recommendations on policy direction to protect lives and keep commerce flowing during and after a Cascadia earthquake and tsunami” (OSSPAC, 2013). A task group then developed a Cascadia Earthquake Scenario for use by other work groups as a basis for assessing the effects of the scenario on various sectors of society or parts of the built environment.

This assessment is for a magnitude 9.0 CSZ earthquake, as defined in the Oregon Resilience Plan. Other magnitudes of CSZ events and earthquakes from other sources are not considered. However, at the request of Black & Veatch, we have provided design ground displacements from fault rupture at the pipeline crossings of shallow Class A faults.

2.2.3 Geology

The project site lies within the Willamette Valley physiographic province (Orr and others, 1992). The local geology has been mapped by numerous authors including Tolan and others (2000) and O'Connor and others (2001). A simplified geologic map of the study area is presented in Figure 2 and is based on DOGAMI publications OGDC-6 (Smith and Row, 2015) and SLIDO 4.0 (Franczyk and others, 2019).

Today the Willamette Valley is a broad alluvial plain bounded by the Columbia River to the north, the Cascade Range to the east, and the Coast Range to the west and south. Before it was a terrestrial valley, the region was a broad continental shelf, extending westward from the proto-Cascades into the ocean (Orr and others, 1992). Around 50 million years ago, an oceanic island chain slowly collided with the coastline as the oceanic crust that carried it was subducting beneath the North American tectonic plate. This accreted island chain ultimately formed the Coast Range and shaped the present-day Willamette Valley by creating the western and southern boundary.

Structurally, the valley is a tectonic fore-arc basin created by down warping and faulting of the underlying Columbia River Basalt Group bedrock as the Coast Range and Cascades were being uplifted (Gannett and others, 1998). From the creation of the sedimentary basin to the beginning of the ice age, the valley was inundated by deposition from the surrounding uplands including Pleistocene (2.6 million to 11,700 years ago) sand and gravels, and mud and debris flows from volcanic eruptions in the Cascades (O'Conner and others, 2001). These Pleistocene sand and gravels formed large widespread sheets and alluvial fan complexes which extended into the Valley floor where major Willamette tributaries exited from the Cascade Range. In the central and southern Willamette Valley, these Pleistocene sand and gravels directly correspond to previously mapped Pleistocene alluvial deposits referred to as Linn Gravel and the Rowland Formation (O'Conner and others, 2001). Estimated thickness of the Pleistocene sand and gravel deposits from drill logs indicate near surface deposits of 40 to greater than 100 meters thick at alluvial fan apexes, and 10 to 20 meters thick in the distant areas away from the Cascades or Coast ranges (O'Conner and others, 2001).

During the late stages of the last great ice age, between about 18,000 and 15,000 years ago, a lobe of the continental ice sheet repeatedly blocked and dammed the Clark Fork River in western Montana, which then formed an immense glacial lake called Lake Missoula. The lake grew until its depth was sufficient to buoyantly lift and rupture the ice dam, which allowed the entire massive lake to empty catastrophically. Once the lake had emptied, the ice sheet again gradually dammed the Clark Fork Valley and the lake refilled, leading to 40 or more repetitive outburst floods at intervals of decades (Allen and others, 2009). During each short-lived episode, floodwaters washed across the Idaho panhandle, through the eastern Washington scablands, and through the Columbia River Gorge. When the floodwater emerged from the western end of the gorge, it spread out over the Portland Basin and up the Willamette Valley as far south as Junction City, depositing a tremendous load of sediment (O'Conner and others, 2001). In the Salem area, these deposits are mostly composed of silt and clay, and mapped as fine-grained Missoula Flood deposits by O'Connor and others (2001). These fine-grained flood deposits blanketed the earlier Pleistocene sand and gravel alluvium obscuring the underlying gravels beneath a layer of silt and clay. In more recent times, portions of the site have been cut, graded, or filled during the course of development.

2.2.4 Available Mapping

DOGAMI developed a publication based on the Oregon Resilience Plan CSZ scenario for the state of Oregon. The publication, Open-File Report O-13-06, primarily consists of GIS data of site conditions, ground motions, ground deformations, and other hazards associated with

a magnitude 9.0 event on the CSZ (Madin and Burns, 2013). Datasets of interest for this project include the following:

- Shear Wave Velocity within 30 meters of the Ground Surface (Vs30)
- Bedrock and Site Peak Ground Acceleration (PGA)
- Bedrock and Site 1-second Spectral Acceleration (SA1)
- Bedrock and Site Peak Ground Velocity (PGV)
- Liquefaction Susceptibility, Probability, and Permanent Ground Deformation (PGD)
- Earthquake-Induced Landslide Susceptibility, Probability, and PGD

The provided methodology indicates that, within the project area, the majority of these datasets were derived based on the Relative Earthquake Hazard Maps of the Salem East and Salem West Quadrangles, Marion and Polk Counties, Oregon (GMS-105; Wang and Leonard, 1996); the Oregon Geologic Data Compilation Release 5 (OGDC-5); and the Statewide Landslide Information Database for Oregon Release 2 (SLIDO-2; Burns and others, 2011). The bedrock ground motions included in the publication were provided to DOGAMI by the U. S. Geological Survey (USGS) and are based on the USGS Cascadia M 9.0 scenario ShakeMap®.

Following the publication of O-13-06, DOGAMI published the Oregon Geologic Data Compilation Release 6 (OGDC-6; Smith and Roe, 2015) and Release 4.0 of the Statewide Landslide Information Database for Oregon (SLIDO-4.0, Franczyk and others, 2019). These recent publications have not yet been incorporated into DOGAMI's CSZ scenario datasets.

Bedrock 0.3-second spectral acceleration data were downloaded from the USGS website for the Cascadia M 9.0 scenario ShakeMap® (USGS, 2017). Data for the 0.2-second spectral acceleration, as used in building codes, were not available. For preliminary planning purposes, the 0.2-second spectral acceleration can be approximated as the 0.3-second spectral acceleration.

2.3 Shear Wave Velocity, Vs30

For the study area around Salem, there are published DOGAMI maps which show both Vs (approximate weighted average shear wave velocity of the geologic unit) and Vs30 values (time-averaged shear wave velocity in the upper 30 meters of the geologic profile). However, the published Vs30 values for the study area do not incorporate shear wave velocity measurements from the Salem area. Instead, they represent averages from measurements from similar geologic units taken from across the state, primarily the Portland Metropolitan area. Therefore, we used Vs values from the DOGAMI GMS-105

publication. While Vs and Vs30 values can differ, because the data from GMS-105 represents actual values from the study area, for this project, we are assuming that Vs and Vs30 values are approximately the same. The values used for the geologic units within the study area are shown below and on Figure 3.

- Volcanic Rock: 968 m/s
- Sedimentary Rock: 920 m/s
- Landslide deposits: 360 m/s
- Terrace Deposits: 250 m/s
- Recent Alluvium: 250 m/s
- Missoula Flood Deposits: 190 m/s

2.4 Liquefaction Hazard

The liquefaction susceptibility map provided in O-13-06 is a compilation of liquefaction susceptibility maps from other DOGAMI publications. Within the Salem area, this primarily includes GMS-105 (Wang and Leonard, 1996). Explanatory text for GMS-105 indicates that susceptibility categories (0-5) were based on the available thickness of liquefiable material. Conservative groundwater levels were also used so as to not underestimate the liquefaction susceptibility.

Even though the map provided in O-13-06 indicates that the GMS-105 map was used, comparison of the original map and the one provided indicated this was not the case. Therefore, the O-13-06 map was not used. Instead, the raw data from GMS-105 was used for the area within Salem, and outside of it we used our geologic map (Figure 2), updated to include all mapped landslides, and employed the Youd and Perkins (1978) methodology, as well as knowledge of regional liquefaction susceptibility, to assign new liquefaction susceptibilities and create a unified map. To do this, we considered how Youd and Perkins would have classified a unit, and then qualitatively fit that with the Wang and Leonard (1996) susceptibility categories. During this process, the Wang and Leonard susceptibility categories 4 and 5 were merged. In areas where a susceptibility category of 5 was given, there were no apparent site-specific studies as recommended by the methodology. Furthermore, GMS-105 does not include an underlying geologic map in GIS form. Instead, it shows a generalized geologic map, which was amended based on limited site visits, aerial photograph interpretation, limited field reconnaissance, and available subsurface data. Therefore, the categories were combined to create a unified map. The resulting map is shown on Figure 4

2.5 Landslide Susceptibility

We generally followed the methodology and Geologic Group assignments as described in O-13-06, using the compiled geologic map shown on Figure 2 and discussed above, as the base map. We assigned Geologic Group C (relatively weak material) to areas mapped as Alluvium, Missoula Flood Deposits, Terrace Deposits, and Landslide Deposits. All other geologic units, including Volcanic Rock and Sedimentary Rock, were assigned Geologic Group B. We calculated a slope map from bare earth lidar data of the area to complete the landslide susceptibility map because DOGAMI's slope map was not included in O-13-06. In order to give what we believe are upper and lower limits of landslide susceptibility, maps accounting for both dry and wet conditions were generated. Dry conditions assume that the groundwater is below the level of sliding, while wet conditions assume that the groundwater level is at ground surface. The landslide susceptibility maps are shown on Figures 5 and 6.

2.6 PGA, SA1, SA0.3, and PGV

The site amplification factors in O-13-06 were calculated based on site class and the appropriate Vs30 value for each site, as determined from the Vs30 map. We calculated the PGA and SA1 site amplification factors for the Salem area from the Vs30 dataset described above using the approach referenced in O-13-06 (Boore and Atkinson, 2008) and applied them to the bedrock PGA and SA1 maps provided with O-13-06 to produce PGA, SA1, and PGV maps.

Maps of Peak Ground Acceleration, 1-Second Spectral Acceleration, and Peak Ground Velocity are shown on Figures 7, 9, and 10, respectively. The same methodology was used for the 0.3-Second Spectral Acceleration map, shown in Figure 8, using the bedrock SA0.3 map from the USGS scenario. It should be noted that current USGS & DOGAMI mapping does not include mapping for the 0.2-second spectral acceleration, but it does include spectral acceleration for a period of 0.3 seconds. For preliminary planning purposes the 0.2-second spectral acceleration can be approximated as the 0.3-second spectral acceleration.

2.7 Probability of Liquefaction

We used the refined liquefaction hazard map described above and followed the methods presented in O-13-06 to develop a map of liquefaction probability. The resulting map is shown on Figure 11.

2.8 Liquefaction-Induced PGD

2.8.1 Lateral Spreading

We used the refined liquefaction hazard map described above and followed the methods presented in O-13-06 to calculate permanent ground deformations from liquefaction-induced lateral spreading. The map of estimated PGD due to lateral spreading is included on Figure 12.

2.8.2 Settlement

DOGAMI did not include a map of predicted ground settlement associated with liquefaction in O-13-06. We calculated estimated liquefaction-induced settlements using the methodology in Chapter 4 of the Hazus® -MH 4.2 Technical Manual (FEMA, 2020), using the refined liquefaction hazard map discussed above.

The FEMA method associates each susceptibility category with a unique settlement amplitude value. Each of the values is assumed to have an uncertainty with a uniform probability distribution from one-half to two times the respective value. The map of estimated PGD due to liquefaction-induced settlement is included on Figure 13.

2.9 Probability of Earthquake-Induced Landslides

We used the refined landslide susceptibility and PGA maps described above and followed the methods presented in O-13-06 to calculate and map the probability of earthquake-induced landslides. To give what we believe are upper and lower limits of the probability of earthquake-induced landslides, we calculated probabilities in both wet and dry conditions. This was done by populating tables 4.16 and 4.17 in Chapter 4 of the Hazus® -MH 4.2 Technical Manual (FEMA, 2020). The resulting maps are shown on Figures 14 and 15.

2.10 Earthquake-Induced Landslide PGD

The earthquake-induced landslide PGD map is based on the methodology in Hazus® -MH 2 Technical Manual (FEMA, 2011), which is referenced in O-13-06. It should be noted that the Hazus methodology remains the same in the 4.2 Technical Manual (2020). We retained the acceleration term that DOGAMI chose to remove from FEMA equation 4-14 because the acceleration is in “decimal fraction of g’s,” not cm/sec², as DOGAMI indicated.

Additionally, we observed that the equation given by DOGAMI for the displacement factor did not produce a curve similar to the FEMA Figure 4.13 relationship. In examining the

DOGAMI equation, we saw that if the first constant was made negative, a curve similar to the FEMA Figure 4.13 relationship was seen. Therefore, we based our calculations on this slightly amended and corrected relationship to match the source FEMA publication. As we did for all landslide maps, we generated permanent ground deformation maps for both wet and dry conditions. These maps were based on probability inputs generated when calculating the probability of earthquake-induced landslides. Our maps of estimated earthquake-induced landslide permanent ground deformation are shown on Figures 16 and 17.

2.11 Surface Faulting

The United States Geologic Survey defines four categories of faults, Class A through D, based on evidence of tectonic movement known or presumed to be associated with large earthquakes during Quaternary time (within the last 2.6 million years). For Class A faults, geologic evidence demonstrates that a tectonic fault exists and that it has likely been active within the Quaternary period. The Lower Transmission Line crosses two Class A Faults identified in the United States Geologic Study Fault and Fold Data Base at the locations shown on Figure 2, Geologic Map. The Class A faults consist of the Turner Creek and Mill Creek Faults (the southern fault) and the Waldo Hills Fault (the northern fault).

Exhibit 2-1: USGS Fault Information for Mapped Faults Crossed by Transmission Mains

| Fault Name | USGS Fault Number | Fault Class | Approximate Length | Sense of Slip | Slip Rate Category ¹ | Time Since Last Deformation ² |
|------------------------------|-------------------|-------------|--------------------|---------------|---------------------------------|--|
| Turner and Mill Creek Faults | 871 | A | 11.2 miles | Strike Slip | < 0.2 mm/yr | < 1.6 Ma |
| Waldo Hills Fault | 872 | A | 7.5 miles | Normal | < 0.2 mm/yr | < 1.6 Ma |

NOTES:

mm = millimeters; yr = year.

Ma = "Mega-annum" or million years ago.

The American Lifelines Alliance (ALA) water pipeline seismic design guidelines specify that large diameter transmission pipelines should be designed to cross active faults with evidence of fault movement within the Holocene geologic time period (i.e. less than approximately 11,000 years). While there is currently no evidence of Holocene tectonic activity along either the Turner and Mill Creek Faults or the Waldo Hills Fault, the ALA guidelines suggest considering a hypothetical displacement of approximately 10 percent of the maximum estimated fault movement due to a surface rupture.

Using the regression equations published in Wells and Coppersmith (1994), maximum hypothetical earthquake magnitudes of 6.3 and 6.6 were determined for the Waldo Hills

Fault and Turner and Mill Creek Faults, respectively. Applying the Wells and Coppersmith (1994) magnitude-fault displacement relationship calculates a maximum displacement of approximately 19 and 21 inches for the Waldo Hills Fault and Turner and Mill Creek Faults, respectively. Thus, 10 percent of the maximum estimated fault movement along both the Waldo Hills Fault and Turner and Mill Creek Faults is approximately 2 inches.

2.12 Seismic Hazards at Critical Infrastructure

The locations of selected infrastructure have been provided by Black & Veatch. The approximate locations of the selected infrastructure are shown on Figures 1 through 17, and a summary of the GIS map results for seismic hazards at these specific locations are shown on the attached Table 1.

3 SITE RECONNAISSANCE AND DOCUMENT REVIEW

Site reconnaissance was completed in two stages, on March 30, 2021 and April 16, 2021. A Shannon & Wilson geology staff member and a senior geotechnical engineer completed the reconnaissance. Descriptions of findings are provided in the following subsections, and information related to the on-site structures is primarily from the Black & Veatch 2001 seismic resiliency study. For information regarding the seismic geohazards at each of the critical facilities, see Table 1. We present the results of our site reconnaissances in the following sections in the same order that they are listed on the figures and in Table 1.

3.1 Site 1 - Salem-Keizer Intertie/Cherry Ave Booster Pump Station

The Salem-Keizer intertie is located at the Cherry Avenue Booster in Keizer, Oregon. The pump station houses a single pump, with a capacity of approximately 5 million gallons per day. During our site reconnaissance, it was observed that the pump station is on flat ground, with no observed geologic hazards.

Existing subsurface information was not available for this pump station. Based on the geologic mapping, the site is underlain by alluvial deposits. Therefore, the regional seismic hazard mapping indicates there are seismic related hazards as an issue for this site. As the site is flat, the regional seismic hazard mapping is showing liquefaction as the main hazard for this site.

We reviewed a publicly available water well log completed for the Keizer Water District within 350 feet of the site. The water well log indicates sandy clay to 22 feet, which is underlain by sands and gravels. Cemented gravel is noted at a depth of 75 feet. The static

groundwater table based on this log is at 25 feet below the ground surface. A log of the exploration we reviewed is included in Appendix A.

If subsurface conditions underlying the pump station are similar to what was encountered in the nearby exploration, then the potential for liquefaction and associated hazards is considered to be moderate, which is consistent with the regional seismic mapping.



Exhibit 3-1: Photo of Salem-Keizer Intertie/Cherry Avenue Booster PS During Site Visit

3.2 Site 2 - Grice Hill Reservoir and Transmission Tower

Grice Hill Reservoir is a 20-foot-high reinforced concrete reservoir with a nearby Transmission Tower. The reservoir is located at the western extent of the Salem urban growth boundary and has a capacity of 2.3 million gallons. During our site visit, we observed that the reservoir is on relatively flat ground, and evidence or indicators of potential geologic hazards were not observed.

Subsurface information from the City and Black and Veatch was not available for this reservoir. Based on the geologic mapping, the site is underlain by volcanic rock. Therefore,

the regional seismic hazard mapping does not indicate seismic geohazards at this site, except for strong ground motions.

We reviewed publicly available water well logs from two nearby residences that are approximately 700 to 800 feet south of the reservoir on 27th Place NW. The water well logs indicate that approximately 55 to 60 feet of clay overlies the basalt rock. However, both water well logs indicate that groundwater is near the contact between the clay and rock. Logs of the explorations that we reviewed are included in Appendix B.

If subsurface conditions underlying the reservoir are similar to what was encountered in the nearby explorations, the potential for permanent ground deformation from liquefaction and seismic slope instability is low, which is consistent with the regional seismic geohazard mapping.



Exhibit 3-2: Photo of Grice Hill Reservoir During Site Visit

3.3 Site 3 - Hemlock Well

Hemlock well is located near 1398 Hemlock Street NW. During our site reconnaissance, we observed that the site is on relatively flat ground with no observable geologic hazards. Based on the geologic mapping, the site is underlain by volcanic rock. Therefore, the regional seismic hazard mapping does not indicate permanent ground deformations from liquefaction induced settlement or seismic slope instability.



Exhibit 3-3: Photo of Hemlock Well During Site Visit

3.4 Site 4 - Mountain View Reservoir and Pump Station

Mountain View Reservoir is a buried, circular, prestressed concrete wire-wrapped reservoir, that was constructed in 1971. The reservoir tank has a capacity of approximately 10 million gallons. Just northeast of the reservoir is Mountain View Pump Station, constructed in 1995. This pump station is built on a 6-inch-thick reinforced concrete slab.

Only approximately 6 inches of the tank are exposed. Therefore, it could not be fully observed during our site visit. During our site visit, no evidence of slope instability or other geologic hazards were observed at either the reservoir or pump station.

The borings used during design were not available for this reservoir. Based on the geologic mapping, the site is underlain by volcanic rock. We reviewed publicly available geotechnical explorations completed for 1500 Orchard Heights Rd NW, which is approximately 700 to 800 feet northwest from the reservoir. The explorations were completed in 2011 and indicate that approximately 15 feet of clay overlies weathered basalt. A water well from 1999 for 1657 Orchard Heights Rd NW, which is approximately 500 feet north of the reservoir indicates that groundwater may be relatively deep (i.e. greater than 100 feet). Logs of the explorations that we reviewed are included in Appendix C.

If the subsurface conditions underlying the reservoir are similar to what was encountered in the nearby explorations, then the potential for liquefaction and associated hazards is considered to be low, which is consistent with the regional seismic mapping and the available. Therefore, the primary geologic hazard identified at this site for the Cascadia Subduction Zone event is strong ground motions.



Exhibit 3-4: Photo of Mountain View Reservoir and Pump Station During Site Visit

3.5 Site 5 - EOLA 1B Reservoir

EOLA 1B reservoir is a partially-buried reinforced concrete tank that was constructed in 2001. The tank has a capacity of 0.77 million gallons, with approximately 1.5 to 3 feet exposed above ground.

During the site visit, we observed that the reservoir is approximately 450 feet north of the mapped headscarp of a landslide above Doaks Ferry Road. However, at the reservoir, the ground is only gently-sloping to the south, and no on-site slope instability, such as road cracking, was observed.

Subsurface information was not available for the EOLA reservoir. Based on the geologic mapping, the site is underlain by volcanic rock. Therefore, the regional seismic hazard mapping does not indicate permanent ground deformation from liquefaction induced settlement or seismic slope instability. However, because of the proximity of the reservoir to an existing landslide, we recommend site specific geotechnical data be considered to further assess the geohazards. If the City has existing as-built information or geotechnical borings at this reservoir we request that they be provided to the project team to better assess the seismic geohazards.



Exhibit 3-5: Photo of EOLA 1B Reservoir During Site Visit

3.6 Site 6 - Limelight Pump Station

Limelight Pump Station is a reinforced masonry structure with a flexible roof diaphragm located just north of Glen Creek Reservoir. Built in 1998, the structure rests on a 6-inch reinforced concrete slab. Housing three pumps, the pump station has a total capacity of 5.18 million gallons per day. During our site reconnaissance, no evidence of slope instability or other geologic hazards were observed.

Existing subsurface information was not available for this pump station. Based on the geologic mapping, the site is underlain by volcanic rock. Therefore, the regional seismic hazard mapping does not indicate permanent ground deformations from liquefaction induced settlement or seismic slope instability.



Exhibit 3-6: Photo of Limelight Pump Station During Site Visit

3.7 Site 7 - Fairmont Reservoir

Fairmont Reservoir is a partially-buried rectangular reinforced concrete reservoir, constructed in 1937, making it Salem's oldest reservoir. The reservoir tank, which has a capacity of approximately 10 million gallons, is divided into two cells. The total height of the reservoir is 22 feet.

With approximately 2 feet of the reservoir exposed above the ground surface, it could not be fully observed during our site visit. In the immediate vicinity around the reservoir, the ground is flat, and there are no signs of slope instability.

Subsurface information was not available for this reservoir. Based on the geologic mapping, the site is underlain by volcanic rock. Therefore, the regional seismic hazard mapping does not indicate permanent ground deformation from liquefaction induced settlement or seismic slope instability. The primary geologic hazard identified at this site for the Cascadia Subduction Zone event is strong ground motions.



Exhibit 3-7: Photo of Fairmont Reservoir During Site Visit

3.8 Site 8 - Candalaria Reservoir

Candalaria Reservoir is a buried rectangular reinforced concrete reservoir that was constructed in 1940. The tank is 15 feet tall and has a capacity of 0.56 million gallons. The reservoir is currently beneath a small park where the ground is typically flat but slopes to the north, just beyond of the reservoir. The Candalaria Reservoir was included in a 2004 study performed by GRI for proposed seismic improvements. We understand from this

study, that the proposed seismic improvements would likely consist of adding "seismic" valves to the reservoir. However, we do not know if the proposed improvements to the reservoir were completed.

As part of this 2004 study, a boring was completed to assess the subsurface conditions. The boring was designated B-2, and the location is shown on the site plan included in Appendix D. This boring encountered an approximately 28-foot-thick layer of hard silt with weathered basalt fragments overlying basalt. Average SPT blow counts in the silt ranged from 40 to refusal. One sample taken within the silt directly overlying the basalt had a blow count of 10. Groundwater was not indicated on the boring log, and a nearby water well installed in 1999 indicated that static groundwater was at a depth of 30 feet below the ground surface.

The tank is buried and could not be observed during the site visit. However, we observed the slopes in the immediate vicinity around the reservoir and our reconnaissance did not reveal signs of on-site slope instability nor did we observe evidence of soil creep. Based on our site visit, existing subsurface information provided to us and assumed groundwater conditions from publicly available resources, we consider the potential for seismic related permanent ground deformation due to liquefaction or seismic slope instability at this site to be low, which is consistent with the regional seismic hazard mapping. The primary geologic hazard identified at this site for the Cascadia Subduction Zone event is strong ground motions (i.e., ground shaking).



Exhibit 3-8: Photo of Candalaria Reservoir During Site Visit

3.9 Site 9 - South Salem Repeater Tower

The South Salem Repeater Tower is located at 955 Downs Street S. Based on the geologic mapping, the site is underlain by volcanic rock. Therefore, the regional seismic hazard mapping does not indicate permanent ground deformations from liquefaction induced settlement or seismic slope instability. We reviewed a publicly available geotechnical exploration completed at the site for the City of Salem. The log of the exploration indicates that the site is underlain by weathered basalt to a depth of 45 feet, which is consistent with the regional seismic hazard mapping.

3.10 Site 10 - Croisan Lower Pump Station

Croisan Lower Pump Station is a wood frame structure that sits on a 6-inch reinforced concrete slab. According to geologic mapping, this pump station sits on the headscarp of a landslide. Information from the Statewide Landslide Information Database for Oregon (SLIDO Release 4) indicates it is a deep-seated landslide with a length exceeding 1,000 feet and an estimated area of approximately 382,000 square feet. Based on our site reconnaissance, we estimate pavement cracks are typically 1/4 to 1/2 inch wide and oriented parallel and perpendicular to the roadway. The cracks were observed throughout the roadway leading to the pump station, as well as in Croisan Mountain Drive above the pump station.

Subsurface information was not available for this pump station. Based on the geologic mapping, the site is near the contact between volcanic rock and the mapped landslide. The values included in Table 1 are based on the pump station being located in landslide deposits.

If the City has existing as-built information or geotechnical borings at this pump station, we request that they be provided to the project team to better assess the seismic geohazards.



Exhibit 3-9: Photo of Croisan Lower Pump Station During Site Visit



Exhibit 3-10: Photo of Cracking Observed in Driveway During Site Visit

3.11 Site 11 - Edwards Pump Station

Edwards Pump Station was built in 1961 of non-reinforced SCR bricks. There are three pumps inside the pump station. The pump station is located within approximately 25 feet of a small creek with creek bank heights estimated to be less than 5 feet but is otherwise located on relatively level ground.

Based on our conversations with the City of Salem, we understand that past uncontrolled, pressurized water releases lifted the pavement outside the pump station above the base rock and subgrade. We observed locations where the pavement adjacent to the west side of the pump station building settled and cracks radiating around the pavement settlement formed. We also observed some cracking in the southwest corner of the pump station building. Exact measurements of the settlement areas and cracks were not performed; however, we estimate the pavement settlement adjacent to the building to be less than 6 inches and the width of the cracks to be less than 1/2 inch in width. A photo of the pump station and a

close-up photo of the cracking and settlement observed in the pavement on the west side of the pump station are included below.

Subsurface information from the City was not available for this pump station at the time of our report. Based on the geologic mapping, the site is underlain by Missoula flood deposits. The Missoula flood deposits in this area are mapped as coarse-grained deposits with a very low liquefaction hazard.

We reviewed a publicly available geotechnical exploration that was completed in 1995 for the City of Salem near the intersection of Madrona Street and Madrona Court, which is approximately 250 feet southeast of the site. The exploration indicates that a 13-foot-thick layer of clay overlies gravel to a depth of 25 feet. Groundwater conditions were not indicated on the log; however, we expect them to closely follow those in the nearby creek. A log of the exploration we reviewed is included in Appendix F.

Because the predicted settlements in the HAZUS model are based on the assumption that the pump station is underlain by gravel which appears not to be correct based on the closest available well log, the hazard may not be adequately defined by the hazard mapping. The actual potential for liquefaction and movement to the nearby creek would be a function of the plasticity of the fine-grained material above the gravel. If the fine-grained material has consistent medium or high plasticity the liquefaction potential may be low. However, if layers of saturated, low plasticity silt or loose sand are also present, a liquefaction hazard may be present. Additionally, portions of the subgrade in the pavement next to the building appear to be negatively affected by past uncontrolled water releases at the pump station. If the areas of disturbed soil or voids extend below the building foundations, then portions of the foundations may have significantly less subgrade support than at locations where undisturbed native soil is present during both seismic and static conditions. Due to uncertainties associated with the liquefaction potential and subgrade we consider the potential for permanent ground deformation to be moderate to high during a seismic event.



Exhibit 3-11: Photo of Edwards Pump Station During Site Visit



Exhibit 3-12: Photo of Cracking and Settlement along Edwards Pump Station West Wall During Site Visit

3.12 Site 12 - ASR Wells

The ASR Wells for the City of Salem are located in Woodmansee Park. At the ASR wells, of which there are five, treated water from the North Santiam River is pumped deep into the

underground aquifer so that it can be used during times of the year where usage is higher. The ASR system is currently under construction, undergoing improvements and expansions to the system. As it currently stands, the ASR capacity is 8.71 million gallons per day. Because the ASR wells are located on relatively flat ground, there were no observed geologic hazards during our site reconnaissance.

Existing subsurface information was not available for this pump station. Based on the geologic mapping, the site is underlain by volcanic rock. Therefore, the regional seismic hazard mapping does not indicate permanent ground deformations from liquefaction induced settlement or seismic slope instability.



Exhibit 3-13: Photo of Woodmansee Park During Site Visit

3.13 Site 13 - Skyline Repeater Tower

Based on the geologic mapping, the site is underlain by volcanic rock. Therefore, the regional seismic hazard mapping does not indicate permanent ground deformations from liquefaction induced settlement or seismic slope instability.

3.14 Site 14 - Lone Oak Reservoir

Lone Oak Reservoir is a partially-buried reinforced concrete reservoir. Approximately 2 to 6 feet of the reservoir, which is 25 feet high, are exposed at the surface. The tank has a total capacity of 5.64 million gallons. At the reservoir site, there is a gentle slope to the south. During our site reconnaissance, no evidence of slope instability or soil creep was observed.

Existing subsurface information was not available for this reservoir. Based on the geologic mapping, the site is underlain by volcanic rock. Therefore, the regional seismic hazard mapping does not indicate permanent ground deformations from liquefaction induced settlement or seismic slope instability.

We reviewed publicly available geotechnical exploration logs from the intersection of Lone Oak Road SE and Mildred Lane SE, which is the intersection adjacent to the reservoir and were completed for the City of Salem Public Works Department. Two explorations were completed, and both included a monitoring well. Both explorations encountered residual soil to depths of 40 feet and both did not encounter groundwater. Logs of the explorations that we reviewed are included in Appendix G.

If subsurface conditions underlying the reservoir are similar to what was encountered in the nearby explorations, then we consider the potential for liquefaction and associated hazards to be low, which is consistent with the regional seismic mapping.



Exhibit 3-14: Photo of Lone Oak Reservoir During Site Visit

3.15 Site 15 - Creekside Pump Station

Creekside Pump Station is located just south of Lone Oak Reservoir. The pump station, constructed in 1998, contains three pumps and has a capacity of approximately 6 million gallons per day. The pump station sits on relatively flat ground at the bottom of a hill. During site reconnaissance, no signs of slope instability were observed.

Existing subsurface information was not available for this pump station. Based on the geologic mapping, the site is underlain by volcanic rock. Therefore, the regional seismic hazard mapping does not indicate permanent ground deformations from liquefaction induced settlement or seismic slope instability.



Exhibit 3-15: Photo of Creekside Pump Station During Site Visit

3.16 Site 16 - Champion Hill Reservoir

Champion Hill Reservoir is a 2.3-million-gallon reinforced concrete reservoir. The reservoir is located just south of the Salem city limits and is surrounded by vineyards. In the area around the tank, the ground is gently-sloping to the south. However, no signs of slope instability or soil creep were observed during our site reconnaissance.

Existing subsurface information was not available for this reservoir. Based on the geologic mapping, the site is underlain by volcanic rock. Therefore, the regional seismic hazard mapping does not indicate seismic related hazards as an issue for this site.

We reviewed publicly available geotechnical exploration logs from a site that is approximately 800 feet north of the intersection between Hylo Road SE and Champions Hill Road SE, which would be approximately 200 feet south of the reservoir. Three explorations were completed at this site with one exploration including a monitoring well. Two of the explorations indicate that approximately 40 to 63 feet of silt overlies decomposed basalt. The third exploration was performed to 25 feet and included a monitoring well. Groundwater was not observed within the monitoring well and was not noted on the other

explorations. Water well logs that are within approximately 0.5 miles from the reservoir site indicate that groundwater is relatively deep (i.e. greater than 100 feet below the ground surface). Logs of the explorations that we reviewed are included in Appendix H.

If the reservoir is potentially founded on silty soil overlying rock and perched water was present, then the silt may be susceptible to liquefaction depending on its plasticity. However, if the static groundwater is similar to the nearby water wells, then the potential for liquefaction and associated seismic hazards is considered to be low, which is consistent with the regional seismic mapping. If the City has existing as-built information or geotechnical borings at this reservoir, we request that they be provided to the project team to better assess the seismic geohazards.



Exhibit 3-16: Photo of Champion Hill Reservoir During Site Visit

3.17 Site 17 - Boone Road Pump Station

Boone Road Pump Station was originally constructed in 1977 with modifications made in 1994 and again after 2001. Three pumps, with a total capacity of 12.96 million gallons per

day are inside two structures on site. The pump station sits on flat ground and there were no observed slope or geologic hazards observed during our site reconnaissance.

Existing subsurface information was not available for this pump station. Based on the geologic mapping, the site is underlain by terrace deposits. However, the mapped terrace deposits in this area are mapped as coarse-grained deposits with a very low liquefaction hazard.



Exhibit 3-17: Photo of Boone Road Pump Station During Site Visit

3.18 Site 18 - Deer Park Pump Station

Deer Park Pump Station sits on an 8-inch-thick reinforced concrete slab foundation. The pump station, which was built in 1982, houses three pumps with a total capacity of approximately 5 million gallons per day. The pump station is on relatively flat ground and no geologic hazards were observed during our site reconnaissance.

Existing subsurface information was not available for this pump station. Based on the geologic mapping, the site is underlain by volcanic rock. Therefore, the regional seismic

hazard mapping does not indicate permanent ground deformations from liquefaction induced settlement or seismic slope instability.

We reviewed publicly available geotechnical explorations completed in 1998 for the Oregon Department of Corrections at 5485 Turner Road SE, which is 300 to 500 feet west of the pump station site. The explorations indicated 6 to 10 feet of clay to silty clay overlying weathered basalt. Monitoring wells were also installed and indicate static groundwater ranges from 15 to 18 feet below the ground surface. Logs of the explorations we reviewed are included in Appendix I.

If subsurface conditions underlying the pump station are similar to what was encountered in the nearby exploration, then we consider the potential for liquefaction and associated hazards to be low, which is consistent with the regional seismic mapping.



Exhibit 3-18: Photo of Deer Park Pump Station During Site Visit

3.19 Site 19 - Mill Creek Reservoir

Mill Creek Reservoir is a 2.3-million-gallon reinforced concrete tank. The reservoir is adjacent to College Reservoir, near Corban University. The reservoir is near the top of a hill, where it slopes to the southwest. We did not observe indicators or evidence of slope instability around the tank.

We reviewed publicly available water well and geotechnical exploration logs completed for sites near the reservoir. We found two explorations completed for 5358 Deer Park Dr SE in 2015, which is approximately 300 to 400 feet south of the reservoir. These two explorations indicated sandy silt overlying weathered basalt. The contact with the weathered basalt varied from 9 to 18 feet below the ground surface. Neither of these explorations indicated observations of groundwater. A water well was completed for 5583 Jenniches Ln SE in 2005, which is approximately 0.5 mile southeast of the reservoir indicated groundwater was at a depth of 62 feet below the ground surface. Logs of the explorations that we reviewed is included in Appendix J.

If subsurface conditions underlying the reservoir are similar to what was encountered in the nearby explorations, the potential for permanent ground deformation from liquefaction and seismic slope instability is low, which is consistent with the regional seismic mapping. The primary hazard at the site is strong ground motions.



Exhibit 3-19: Photo of Mill Creek Reservoir During Site Visit

3.20 Site 20 - Turner Control Facility

We understand from review of a Geotechnical Engineering Report prepared by Foundation Engineering, Inc., (FEI) that the Turner Control Facility was being designed for replacement with a larger structure in 2005. The existing Turner Control Facility is on relatively flat ground.

As part of the previous Geotechnical Engineering Report, one boring, designated BH-1, was drilled near the Turner Control Building on March 10, 2005. The borehole was advanced to approximately 16.6 feet prior to encountering practical refusal. Another exploration, designated BH-12, was performed by FEI southwest of the control building on May 1, 1998 and was advanced to a maximum depth of 21.5 feet.

Subsurface conditions encountered in boring BH-1 consisted of alluvial soils that were comprised of very stiff, silty clay to a depth of approximately 5 feet, which was underlain by dense to very dense gravel to the bottom of the hole at 16.6 feet. Subsurface conditions encountered in boring BH-12 also consisted of alluvial soils that were comprised of medium stiff silt to approximately 3.5 feet, which was underlain by dense to very dense sandy gravel with cobbles to approximately 19 feet. The FEI report indicates that the gravels were underlain by dense sand from 19 to 21.5 feet.

Based on the geologic mapping, the site is underlain by terrace deposits. The regional hazard mapping indicates that the terrace deposits underlying the Turner Control Building have a low liquefaction hazard, which is consistent with the subsurface conditions encountered in the previous explorations.

3.21 Site 21 - Franzen Reservoir and Transmission Tower

Franzen Reservoir, located in the hills above Turner Oregon, was built in 1951 and has a capacity of just over 92 million gallons. A transmission tower was later constructed on the site. The reservoir consists of two cells. We reviewed the following documents provided for Franzen Reservoir:

- Squire Associates, 2001, Geotechnical Schematic Design Report Franzen Reservoir Rehabilitation Project;
- Squire Associates, 2002, Geotechnical Basis of Design Report Franzen Reservoir Rehabilitation Project; and
- City of Salem Public Works, 2008, Slump Failure at Franzen Reservoir.

The 2002 Geotechnical Basis of Design Report and study performed by Squire Associates included 22 borings, 18 test pits, 12 shallow hand augers, and four seismic refraction survey

lines. The report included an evaluation of slope stability including seismic slope stability as well as evaluation of other seismic related geologic hazards such as fault rupture and liquefaction. That study identified what they believed to be an unknown fault with indeterminate activity extending through the middle of the reservoir based on offsets in the geologic units encountered in the explorations. They concluded that this unmapped fault is unlikely to experience surface ruptures for earthquake magnitudes less than M5.6, which is what they considered to be the maximum magnitude for this unmapped fault.

This study also concluded that liquefaction was not a hazard as the site is primarily underlain by residual soil, and coarse-grained subunits contained plastic fines contents ranging between 30 to 40 percent. Seismic slope stability was also performed and concluded that slopes were generally stable under the design seismic loading condition but that the downstream slope may experience deformations of up to 6 inches. A site plan and profile drawings from this study are included in Appendix L.

According to a 2008 memorandum prepared by the City of Salem, two slump failures occurred within the cut slope of the west cell of the reservoir. Each failure was approximately halfway down the slope from the top of the reservoir. Each slumped area is about 10 feet x 10 feet in size. Based on information contained within the memorandum, the failures were discovered when the plastic liner was removed for routine maintenance. No definitive cause of failure was stated in memorandum; however, the memo indicates that the original geotechnical engineer for the 2004 upgrades of the reservoirs (Barry Meyers) visited the site and that based on the type of failure groundwater was not anticipated to be the cause. The memo also indicates that a similar failure occurred at or near the site during the first year of the reservoir's operation. We understand that the failures were repaired. During our site visit the reservoir was covered, and we did not observe evidence slope instability; however, the reservoir cut walls were covered with a plastic liner. No information was available on how the cells were repaired at the time of this report.

Based on our site visit and existing subsurface information provided to us, the potential for liquefaction induced settlement of the native soils beneath the reservoir is low, which is consistent with the regional seismic mapping. However, because the failures on the embankment wall have occurred during static conditions (i.e. no-ground motion) it is our opinion the potential for permanent ground deformation from seismic slope instability is not adequately captured in the HAZUS model. Additional slope modeling outside of the of the current scope of the seismic geohazard evaluation would be required to better quantify the hazard, but it is our qualitative assessment based on the historic slumping the potential

for seismic slope instability of the embankment may be moderate to high.



Exhibit 3-20: Photo of Franzen Reservoir During Site Visit



Exhibit 3-21: Photo of Slump Failure along Cut Slope of West Cell from 2008 (Photo Provided by the City of Salem)

3.22 Site 22 - Geren Island Water Treatment Plant and Transmission Tower

Geren Island is located in the Santiam River approximately 20 miles east of Salem near Stayton. At the Geren Island Water Treatment Plant, which was constructed in 1937, water from the North Santiam River is taken from the river and filtered through sand filters and disinfected with chlorine. The treatment plant is the main source of drinking water for the City of Salem and is also an active construction site where a new ozone treatment facility, scheduled to be finished in 2021, is being built. Over the course of several decades numerous improvements have been made to improve treated water quality, capacity and reliability. Not including the improvements currently under construction, the Geren Island Water Treatment Plant includes the following elements:

- Surface water intakes and metering facilities, including one active intake referred to as the "Middle Intake" and two intakes that have been abandoned as the depth and shape of the channel has changed over time and the intakes are no longer viable;

- Three groundwater supply wells;
- Pre-treatment facilities consisting of primary coagulant, pH adjustment and two roughing filters;
- Three slow sand filters (2-cells each);
- Post-treatment facilities consisting of primary disinfection, pH adjustment, and fluoridation; and
- Office buildings for staff, located adjacent to post treatment facilities.

The water treatment plant site is relatively flat. However, there are embankments for the side walls of the various filter facilities on-site, and there are slopes along the banks of the North Santiam River Channels. During our site visit, we did not observe signs of slope instability.

Based on the geologic map, the site is underlain by alluvial soils. Therefore, the regional seismic geohazard mapping indicates high liquefaction and other associated hazards (i.e. lateral spreading) are present at this site.

Existing explorations for Geren Island were provided to us or were found within our records. We reviewed the following geotechnical reports for Geren Island:

- Shannon & Wilson, 1987, Geotechnical Studies Geren Island Water Intake Facilities;
- Foundation Engineering, Inc., 1996, Geren Island Treatment Facility Improvements Geotechnical Investigation;
- Squire, 2004, Foundation Investigation at Geren Island Corrosion Control Facility - Soda Ash Storage Silo(s) and Equipment Building; and
- McMillen Jacobs Associates, 2019, Geren Island Water Treatment Plant Improvement Project Phase 1 - Ozone Facility.

These four reports include logs of 12 test pit explorations and 10 borings. A site plan showing the location of known previous explorations is included in Figure 18. Available logs of the explorations we reviewed are included Appendix M.

Subsurface conditions indicated on the exploration logs indicate that most of the site is primarily underlain by gravel alluvium. Standard Penetration Test samples collected within the gravel indicate that it is dense to very dense. Some of the test pits and boring logs indicate that there are localized areas of loose to medium dense silty sand overlying the gravels.

We evaluated the liquefaction potential of the soils in the borings in accordance with methods described by Boulanger and Idriss (2014) for a magnitude 9 earthquake and the peak ground acceleration shown in Table 1 (0.16 g). These analyses indicate that the factors of safety against liquefaction for a magnitude 9 CSZ event are greater than 1.0. Our analysis assumed a groundwater depth of 8 feet below the ground surface based on measured groundwater conditions in the borings, which is below the bottom of the localized areas of loose to medium dense sand noted on the test pit and boring logs. If groundwater levels are higher than assumed in our analyses, the loose to medium dense sand would show zones with factors of safety against liquefaction of less than 1.0. We also note that the subsurface conditions on the site vary from loose sand to very dense gravel, with the density and particle size of the alluvial deposits which form the island related to the energy and flow in the Santiam River during deposition. Consequently, the soil type, density, and strength characteristics can change over relatively short vertical and horizontal distances.

Liquefaction potential analysis of the available boring logs did not identify a liquefaction hazard for the Cascadia Subduction Zone ground motions considered in this study. Therefore, the seismic geohazard mapping overestimates the liquefaction induced settlement on those portions of the island where borings are available. However, in areas where there are no borings to indicate a low liquefaction hazard, we recommend that the liquefaction geohazard information indicated on the seismic geohazard maps be assumed.



Exhibit 3-22: Photo Showing Area Near New Ozone Facility



Exhibit 3-23: Photo Showing Middle Intake at Geren Island Water Treatment Plant



Exhibit 3-24: Photo Showing Geren Island Transmission Tower.

We note that the Geren Island WTP is downstream of Detroit Lake, a Lake impounded by the Detroit Dam, and the Big Cliff Reservoir, a reservoir impounded by the Big Cliff Dam. These reservoirs and dams are owned and operated by the U.S. Army Corps of Engineers (USACE). The Water Treatment Plant is also downstream of the Upper Bennett Dam and portions of Water Treatment Plant Facilities are downstream of the Lower Bennett Dam. The Lower and Upper Bennett Dams are co-owned by the Santiam Flood Control District

and the City of Salem. Our study did not include an evaluation of the Upper and Lower Bennett Dams or the dams owned by the USACE.

3.23 Sites 23 and 24 - Upper and Lower Transmission Mains

We understand that the City of Salem's water transmission backbone is separated into an upper and a lower segment. The upper and lower transmission mains are further divided into two lines. The upper transmission lines extend from the Geren Island WTP and terminate in Turner at the Turner Control Valves, which is northwest of Franzen Reservoir. Line 1 for the upper transmission main is 36 inches in diameter, and Line 2 for the upper transmission main is 54 inches in diameter. The lower transmission lines extend from the Turner Control Valves and Line 1 terminates at the Fairmont Reservoir and Line 2 terminates at the Mountain View Reservoir. Line 2 of the lower transmission main crosses under the Willamette River at Sunset Park.

Based on the geologic mapping, both lines of the upper transmission main segment are primarily within terrace deposits. Based on the regional seismic geohazard mapping, the terrace deposits in this area are characterized as coarse-grained sediments that have a low liquefaction hazard. There are portions of the upper transmission mains that are within mapped areas of alluvium, specifically near Geren Island and just south of Turner. Based on the regional seismic geohazard mapping, the alluvial soils have a high liquefaction hazard.

Based on geologic mapping, both lines of the lower transmission main segment are primarily within terrace deposits and Missoula flood deposits. The regional seismic geohazard mapping indicates that the terrace and Missoula flood deposits have a low liquefaction potential in the HAZUS model. However, there are areas in the north part of Salem where the Missoula flood deposits have a moderate liquefaction hazard, and Line 2 of the lower transmission main crosses through these regions. Line 2 of the lower transmission main also crosses through mapped alluvium as it approaches the Willamette River. This area is mapped as having a moderate to high liquefaction hazard.

The other liquefaction-related hazard for Line 2 of the lower transmission main segment is lateral spreading near the Willamette River crossing. There is also a potential for lateral spreading where the upper transmission main segment crosses the North Santiam River. Lateral spreading can occur if soil liquefaction develops during a seismic event and the ground acceleration (inertial force) surpasses the yield acceleration (shear strength) of the liquefied soil. The displacements are cumulative and permanent and can occur on mild slopes or level ground adjacent to a much steeper slope or vertical face (free face).

Existing information related to this river crossing was not provided. Also, the depth of the pipeline was unknown to Shannon & Wilson at the time of this report. Based on a paper published by Youd in 2018, if a pipeline was buried 1H below the bottom of a channel, then the shear zone generated by lateral spread is typically above and non-damaging to the pipe.

Based on the regional seismic hazard mapping, permanent ground deformations due to lateral spreading are estimated to be up to 11 inches at distances of up to 350 feet west of the Willamette River crossing and 4 inches at distances of up to 1,000 feet east of the Willamette River crossing. Permanent ground deformations due to lateral spreading are estimated to be up to 9 inches at distances of up to 1,000 feet on either side of the North Santiam River crossing.

We also understand that there are lower Willamette River crossings at Marion Street and Center Street and that the pipelines for these crossings are supported by the Marion and Center Street bridges that are owned and maintained by ODOT. Our study did not include an evaluation of the lower Willamette River bridge crossings owned by ODOT. However, Shannon & Wilson is involved with a planned seismic retrofit of the Center Street bridge for ODOT and has submitted a draft Preliminary Geotechnical Memorandum (Shannon & Wilson, 2018).

The draft Preliminary Geotechnical Memorandum prepared by Shannon & Wilson did not include subsurface explorations, and preliminary results were based on historic explorations performed for the existing bridge. Based on the Preliminary Geotechnical Memorandum, soils underlying the West Approach and River Spans are susceptible to liquefaction. Up to 8 inches of liquefaction-induced settlement is estimated for the West Approach and River Spans. At the time the Preliminary Memorandum was prepared, Shannon & Wilson determined that there was not sufficient SPT data to perform a liquefaction analysis for the East Approach. However, Shannon & Wilson did include review of one existing test hole performed for the East Approach, which showed low liquefaction susceptibility. Lateral spreading was also noted as a hazard for the west riverbank, but a low potential for the east riverbank. Existing geotechnical data for the bridge from Historic Record Drawings provide by ODOT are included in Appendix N.

We recommend that the project team communicate with ODOT to understand the expected performance of the bridges and use that information to estimate the performance of the pipelines supported by the bridges.

Also, note that based on fault mapping, the upper and lower transmission mains appear to cross two Class A faults. A discussion of the faults and potential for surface rupture are included in Section 2.11 of this report.

4 LIMITATIONS

Our interpretations, conclusions and geotechnical considerations are based on a desktop study including review of publicly available information prepared by others, and a single site visit. No explorations were performed to evaluate geotechnical site conditions and make interpretations. Should proposed development of sites within the study area occur, we recommend that appropriate explorations and site characterization testing and evaluation be done, a detailed site-specific geotechnical study be performed, and geotechnical firms with experience in both static and seismic conditions perform the work.

Within the limitations of scope, schedule, and budget, the conclusions presented in this report were prepared in accordance with generally accepted professional geotechnical engineering principles and practice in this area at the time this report was prepared. Shannon & Wilson makes no other warranty, either express or implied. These conclusions were based on Shannon & Wilson's understanding of the project as described in this report and the site conditions as observed at the time of our field reconnaissance.

This report was prepared for the exclusive use of Black & Veatch and City of Salem, Oregon. The scope of Shannon & Wilson's present work did not include environmental assessments or evaluations regarding the presence or absence of hazardous or toxic substances in the soil, surface water, groundwater, or air, on or below or around this sites, or for the evaluation or disposal of contaminated soils or groundwater should any be encountered.


Shannon & Wilson has prepared "Important Information About Your Geotechnical/Environmental Report" to assist you and others in understanding the use and limitations of our reports and is attached at the end of this report.

5 REFERENCES

- Allen, J.E., Burns, M., and Burns, S., 2009, *Cataclysms on the Columbia: The Great Missoula Floods* (2nd ed.): Portland, Oregon, Ooligan Press, 204 p.
- American Lifelines Alliance (ALA). 2005, *Seismic Guidelines for Water Pipelines*. FEMA and National Institute of Building Sciences. www.americanlifelinesalliance.org.
- Boore, D. M. and Atkinson, G. M., 2008, Ground-motion prediction equations for the average horizontal component of PGA, PGV, and 5%-damped PSA at spectral periods between 0.01 s and 10.0 s: *Earthquake Spectra*, v. 24, no. 1, p. 99-138.

- Burns, W. J.; Mickelson, K. A.; and Saint-Pierre, Evan C., 2011, Statewide landslide information database for Oregon, release 2 (SLIDO-2): Oregon Department of Geology and Mineral Industries Digital Data Series SLIDO-2, scale 1:750,000.
- Boulanger, R. W. and Idriss, I. M., 2014, CPT and SPT-based liquefaction triggering procedures: Davis, Calif., University of California Davis, Center for Geotechnical Modeling, report UCD/CGM-14/01, 134 p.
- DeMets, C., Gordon R.G.; Argus, D.F.; and Stein, S., 1990, Current plate motions: *Geophysics Journal International*, v. 101, p. 425-478.
- Federal Emergency Management Administration, 2011, HAZUS-MH Technical Manual, Release 2.0.
- Federal Emergency Management Administration, 2020, HAZUS-MH Technical Manual, Release 4.2.
- Franczyk, J.J., Burns, W.J., Calhoun, N.C., 2019, Statewide Landslide Information Database for Oregon (SLIDO), Release 4: Oregon Department of Geology and Mineral Industries, Open File Report O-20-13.
- Gannett M.W., and Caldwell, R.C., 1998, Geologic frame work of the Willamette lowland qauifer system, Oregon and Washington, U.S. Geological Survey Professional Paper 1424-A, 32p.
- Ma, L., Madin, I.P., Olson, K.V., and Watzig, R.J., 2009, Oregon Geologic Data Compilation, Release 5: Oregon Department of Geology and Mineral Industries, OGDC-5.
- Madin, I.P., and Burns, W.J., 2013, Ground Motion, Ground Deformation, Tsunami Inundation, Coseismic Subsidence, and Damage Potential Maps for the 2012 Oregon Resilience Plan for Cascadia Subduction Zone Earthquakes: Oregon Department of Geology and Mineral Industries, Open-File Report O-2013-06.
- O'Connor, J.E., Sarna-Wojcicki, A., Wozniak, K.C., Polette, D.J., and Fleck, R.J., 2001, Origin, Extent, and Thickness of Quaternary Geologic Units in the Willamette Valley, Oregon: U.S. Geological Survey Professional Paper 1620.
- Oregon Seismic Safety Policy Advisory Commission (OSSPAC), 2013, The Oregon Resilience Plan.
- Orr, E.L., Orr, W.N., and Baldwin, E.M., 1992, *Geology of Oregon* (4th ed.): Dubuque, Iowa, Kendall/Hunt Publishing Co., 254 p.
- Smith, R.L., and Roe, W.P., 2015, Oregon Geologic Data Compilation, Release 6: Oregon Department of Geology and Mineral Industries, OGDC-6.

- Tolan, T.L., and Beason, M.H., 2000, Geologic Map and Database of the Salem East and Turner 7.5 Minute Quadrangles, Marion County, United States Geologic Survey, Open File Report 00-351.
- Wang, Y., and Leonard, W.J., 1996, Relative Earthquake Hazard Maps of the Salem East and Salem West Quadrangles, Marion and Polk Counties, Oregon. Oregon Department of Geology and Mineral Industries, Open File Report GMS 105.
- Wells, R.E., Weaver, C.S., and Blakely, R.J., 1998, Fore-arc Migration in Cascadia and Its Neotectonic Significance: *Geology*, 26, p. 759-762.
- Wells, D.L., and Coppersmith, K.J., 1994, New empirical relationships among magnitude, rupture length, rupture width, rupture area, and surface displacement: *Bulletin of the Seismological Society of America*, v. 84, no. 4, p. 974-1002. Youd, T. L. and Perkins, D. M (1978) Mapping liquefaction induced ground failure potential, *J. Geotech. Eng. Div., ASCE*, 104: 433–446. Youd, T. L., 2018, Application of MLR procedure for prediction of liquefaction-induced lateral spread displacement: *Journal of Geotechnical and Geoenvironmental Engineering*, v. 144, no. 6, paper no. 04018033, 12 p.




- Critical Facilities:**
- 1. Salem-Keizer Intertie/Cherry Ave Booster
 - 2. Grice Hill Reservoir and Repeater Tower
 - 3. Hemlock Well
 - 4. Mountain View Reservoir and Pump Station
 - 5. EOLA 1B Reservoir
 - 6. Limelight Pump Station
 - 7. Fairmont Reservoir
 - 8. Candalaria Reservoir
 - 9. South Salem Repeater Tower
 - 10. Croisan Lower Pump Station
 - 11. Edwards Pump Station
 - 12. ASR Wells
 - 13. Skyline Repeater Tower
 - 14. Lone Oak Reservoir
 - 15. Creekside Pump Station
 - 16. Champion Hill Reservoir
 - 17. Boone Road Pump Station
 - 18. Deer Park Pump Station
 - 19. Mill Creek Reservoir
 - 20. Turner Control Facilities
 - 21. Franzen Reservoir and Repeater Tower
 - 22. Geren Island WTP and Repeater Tower
 - 23. Upper Transmission Mains
 - 24. Lower Transmission Mains

LEGEND

★ Critical Facilities


— City of Salem Pipeline Backbone

□ Study Area



- NOTES**
- 1. City of Salem pipelines provided by Black & Veatch.

| | |
|--|---------------|
| Salem Seismic Salem, Oregon | |
| SITE MAP | |
| May 2021 | 105679 |
| SHANNON & WILSON, INC. GEOTECHNICAL AND ENVIRONMENTAL CONSULTANTS | FIG. 1 |



- Critical Facilities:**
1. Salem-Keizer Intertie/Cherry Ave Booster
 2. Grice Hill Reservoir and Repeater Tower
 3. Hemlock Well
 4. Mountain View Reservoir and Pump Station
 5. EOLA 1B Reservoir
 6. Limelight Pump Station
 7. Fairmont Reservoir
 8. Candalaria Reservoir
 9. South Salem Repeater Tower
 10. Croisan Lower Pump Station
 11. Edwards Pump Station
 12. ASR Wells
 13. Skyline Repeater Tower
 14. Lone Oak Reservoir
 15. Creekside Pump Station
 16. Champion Hill Reservoir
 17. Boone Road Pump Station
 18. Deer Park Pump Station
 19. Mill Creek Reservoir
 20. Turner Control Facilities
 21. Franzen Reservoir and Repeater Tower
 22. Geren Island WTP and Repeater Tower
 23. Upper Transmission Mains
 24. Lower Transmission Mains

LEGEND


★ Critical Facilities

Geologic Map Unit

- Alluvial Deposits
- Missoula Flood deposits
- Terrace Deposits
- Landslide Deposits
- Sedimentary Rock
- Volcanic Rock


— City of Salem Pipeline Backbone

— Approximate Location of Quaternary Fault




- NOTES**
1. Geologic map units from DOGAMI publications OGDC-7 and SLIDO-4.0. See text for details.
 2. City of Salem pipelines provided by Black & Veatch.


| | |
|--|---------------|
| Salem Seismic Salem, Oregon | |
| GEOLOGIC MAP | |
| May 2021 | 105679 |
| SHANNON & WILSON, INC. GEOTECHNICAL AND ENVIRONMENTAL CONSULTANTS | FIG. 2 |



- Critical Facilities:**
1. Salem-Keizer Intertie/Cherry Ave Booster
 2. Grice Hill Reservoir and Repeater Tower
 3. Hemlock Well
 4. Mountain View Reservoir and Pump Station
 5. EOLA 1B Reservoir
 6. Limelight Pump Station
 7. Fairmont Reservoir
 8. Candalaria Reservoir
 9. South Salem Repeater Tower
 10. Croisan Lower Pump Station
 11. Edwards Pump Station
 12. ASR Wells
 13. Skyline Repeater Tower
 14. Lone Oak Reservoir
 15. Creekside Pump Station
 16. Champion Hill Reservoir
 17. Boone Road Pump Station
 18. Deer Park Pump Station
 19. Mill Creek Reservoir
 20. Turner Control Facilities
 21. Franzen Reservoir and Repeater Tower
 22. Geren Island WTP and Repeater Tower
 23. Upper Transmission Mains
 24. Lower Transmission Mains




— City of Salem Pipeline Backbone



- NOTES**
1. Vs30 values based on Vs values from DOGAMI publication GMS-105. See text for details.
 2. City of Salem pipelines provided by Black & Veatch.

| | |
|--|---------------|
| Salem Seismic Salem, Oregon | |
| SHEAR WAVE VELOCITY, Vs 30 | |
| May 2021 | 105679 |
| SHANNON & WILSON, INC. GEOTECHNICAL AND ENVIRONMENTAL CONSULTANTS | FIG. 3 |




- Critical Facilities:**
- 1. Salem-Keizer Intertie/Cherry Ave Booster
 - 2. Grice Hill Reservoir and Repeater Tower
 - 3. Hemlock Well
 - 4. Mountain View Reservoir and Pump Station
 - 5. EOLA 1B Reservoir
 - 6. Limelight Pump Station
 - 7. Fairmont Reservoir
 - 8. Candalaria Reservoir
 - 9. South Salem Repeater Tower
 - 10. Croisan Lower Pump Station
 - 11. Edwards Pump Station
 - 12. ASR Wells
 - 13. Skyline Repeater Tower
 - 14. Lone Oak Reservoir
 - 15. Creekside Pump Station
 - 16. Champion Hill Reservoir
 - 17. Boone Road Pump Station
 - 18. Deer Park Pump Station
 - 19. Mill Creek Reservoir
 - 20. Turner Control Facilities
 - 21. Franzen Reservoir and Repeater Tower
 - 22. Geren Island WTP and Repeater Tower
 - 23. Upper Transmission Mains
 - 24. Lower Transmission Mains

LEGEND

★ Critical Facilities


Liquefaction Hazard

- Very Low
- Low
- Moderate
- High




- NOTES**
- 1. Liquefaction hazard developed from data provided with DOGAMI publications GMS-105 and OGDC-7, the Youd and Perkins, 1978 methodology, and knowledge of regional liquefaction hazards.
 - 2. City of Salem pipelines provided by Black & Veatch.

| | |
|--|---------------|
| Salem Seismic Salem, Oregon | |
| LIQUEFACTION HAZARD | |
| May 2021 | 105679 |
| SHANNON & WILSON, INC. GEOTECHNICAL AND ENVIRONMENTAL CONSULTANTS | FIG. 4 |




- Critical Facilities:**
1. Salem-Keizer Intertie/Cherry Ave Booster
 2. Grice Hill Reservoir and Repeater Tower
 3. Hemlock Well
 4. Mountain View Reservoir and Pump Station
 5. EOLA 1B Reservoir
 6. Limelight Pump Station
 7. Fairmont Reservoir
 8. Candalaria Reservoir
 9. South Salem Repeater Tower
 10. Croisan Lower Pump Station
 11. Edwards Pump Station
 12. ASR Wells
 13. Skyline Repeater Tower
 14. Lone Oak Reservoir
 15. Creekside Pump Station
 16. Champion Hill Reservoir
 17. Boone Road Pump Station
 18. Deer Park Pump Station
 19. Mill Creek Reservoir
 20. Turner Control Facilities
 21. Franzen Reservoir and Repeater Tower
 22. Geren Island WTP and Repeater Tower
 23. Upper Transmission Mains
 24. Lower Transmission Mains

**Landslide Susceptibility in Dry Conditions
(Scale of 0-10)**



★ Critical Facilities

— City of Salem Pipeline Backbone



NOTES

1. Landslide Susceptibility calculated from data provided with DOGAMI publications SLIDO-4.0, O-12-02, OGDG-6, and LiDAR. Methodology taken from HAZUS. See text for details.
2. City of Salem pipelines provided by Black & Veatch.

Salem Seismic
Salem, Oregon


**LANDSLIDE SUSCEPTIBILITY
(DRY CONDITIONS)**

May 2021


105679

SHANNON & WILSON, INC.
GEOTECHNICAL AND ENVIRONMENTAL CONSULTANTS


FIG. 5



- Critical Facilities:**
- 1. Salem-Keizer Intertie/Cherry Ave Booster
 - 2. Grice Hill Reservoir and Repeater Tower
 - 3. Hemlock Well
 - 4. Mountain View Reservoir and Pump Station
 - 5. EOLA 1B Reservoir
 - 6. Limelight Pump Station
 - 7. Fairmont Reservoir
 - 8. Candalaria Reservoir
 - 9. South Salem Repeater Tower
 - 10. Croisan Lower Pump Station
 - 11. Edwards Pump Station
 - 12. ASR Wells
 - 13. Skyline Repeater Tower
 - 14. Lone Oak Reservoir
 - 15. Creekside Pump Station
 - 16. Champion Hill Reservoir
 - 17. Boone Road Pump Station
 - 18. Deer Park Pump Station
 - 19. Mill Creek Reservoir
 - 20. Turner Control Facilities
 - 21. Franzen Reservoir and Repeater Tower
 - 22. Geren Island WTP and Repeater Tower
 - 23. Upper Transmission Mains
 - 24. Lower Transmission Mains




- ★ Critical Facilities
- City of Salem Pipeline Backbone






- NOTES**
- 1. Landslide Susceptibility calculated from data provided with DOGAMI publications SLIDO-4.0, O-12-02, OGDC-6, and LiDAR. Methodology taken from HAZUS. See text for details.
 - 2. City of Salem pipelines provided by Black & Veatch.


| | |
|---|---------------|
| Salem Seismic Salem, Oregon | |
| LANDSLIDE SUSCEPTIBILITY (WET CONDITIONS) | |
| May 2021 | 105679 |
| SHANNON & WILSON, INC. GEOTECHNICAL AND ENVIRONMENTAL CONSULTANTS | FIG. 6 |



Sources: Esri, HERE, Garmin, Intermap, increment P Corp., GEBCO, USGS, FAO, NPS, NRCAN, GeoBase, IGN, Kadaster NL, Ordnance Survey, Esri Japan, METI, Esri China (Hong Kong), swisstopo, © OpenStreetMap contributors, and the GIS User Community




 Critical Facilities
 City of Salem Pipeline Backbone



NOTES













1. PGA map for the magnitude 9.0 Cascadia Earthquake Scenario calculated from data provided in DOGAMI publication O-13-06 and methodology in Boore and Atkinson, 2008. See text for details.
2. City of Salem pipelines provided by Black & Veatch.

| | |
|---|---------------|
| Salem Seismic Salem, Oregon | |
| PEAK GROUND ACCELERATION, PGA | |
| May 2021 | 105679 |
| SHANNON & WILSON, INC. GEOTECHNICAL AND ENVIRONMENTAL CONSULTANTS | FIG. 7 |




LEGEND

Site SA 0.3 (g)

| | | | | | |
|---|-------------|---|-------------|---|-------------|
|  | 0.21 - 0.26 |  | 0.41 - 0.46 |  | 0.61 - 0.66 |
|  | 0.26 - 0.31 |  | 0.46 - 0.51 |  | 0.66 - 0.71 |
|  | 0.31 - 0.36 |  | 0.51 - 0.56 |  | 0.71 - 0.76 |
|  | 0.36 - 0.41 |  | 0.56 - 0.61 |  | 0.76 - 0.81 |

- Critical Facilities
- City of Salem Pipeline Backbone



NOTES

1. SA0.3 map for the magnitude 9.0 Cascadia Earthquake Scenario calculated from data provided with the USGS Scenario published September 20, 2011, and DOGAMI publications O-12-02 and OGDC-6. See text for details.
2. City of Salem pipelines provided by Black & Veatch.

Salem Seismic
Salem, Oregon



**0.3-SECOND SPECTRAL
ACCELERATION, SA0.3**

May 2021

105679


SHANNON & WILSON, INC.
GEOTECHNICAL AND ENVIRONMENTAL CONSULTANTS

FIG. 8



★ Critical Facilities

— City of Salem Pipeline Backbone



NOTES

1. SA1 map for the magnitude 9.0 Cascadia Earthquake Scenario calculated from data provided in DOGAMI publications O-13-06 and OGDC-6, and methodology in Boore and Atkinson, 2008. See text for details.
2. City of Salem pipelines provided by Black & Veatch.

Salem Seismic
Salem, Oregon


**1-SECOND SPECTRAL
ACCELERATION, SA1**

May 2021

105679

SHANNON & WILSON, INC.
GEOTECHNICAL AND ENVIRONMENTAL CONSULTANTS


FIG. 9



- Critical Facilities:**
- 1. Salem-Keizer Intertie/Cherry Ave Booster
 - 2. Grice Hill Reservoir and Repeater Tower
 - 3. Hemlock Well
 - 4. Mountain View Reservoir and Pump Station
 - 5. EOLA 1B Reservoir
 - 6. Limelight Pump Station
 - 7. Fairmont Reservoir
 - 8. Candalaria Reservoir
 - 9. South Salem Repeater Tower
 - 10. Croisan Lower Pump Station
 - 11. Edwards Pump Station
 - 12. ASR Wells
 - 13. Skyline Repeater Tower
 - 14. Lone Oak Reservoir
 - 15. Creekside Pump Station
 - 16. Champion Hill Reservoir
 - 17. Boone Road Pump Station
 - 18. Deer Park Pump Station
 - 19. Mill Creek Reservoir
 - 20. Turner Control Facilities
 - 21. Franzen Reservoir and Repeater Tower
 - 22. Geren Island WTP and Repeater Tower
 - 23. Upper Transmission Mains
 - 24. Lower Transmission Mains


| LEGEND | | | | | |
|-------------------|---------|-------------|---------|-------------|---------|
| Site PGV (cm/sec) | | | | | |
| <div></div> | 9 - 11 | <div></div> | 17 - 19 | <div></div> | 25 - 27 |
| <div></div> | 11 - 13 | <div></div> | 19 - 21 | <div></div> | 27 - 29 |
| <div></div> | 13 - 15 | <div></div> | 21 - 23 | <div></div> | 29 - 31 |
| <div></div> | 15 - 17 | <div></div> | 23 - 25 | <div></div> | 31 - 33 |

- Critical Facilities
- City of Salem Pipeline Backbone




- NOTES**
- 1. PGV map for the magnitude 9.0 Cascadia Earthquake Scenario calculated from data provided in DOGAMI publications O-13-06 and OGDC-6, and methodology in Boore and Atkinson, 2008. See text for details.
 - 2. City of Salem pipelines provided by Black & Veatch.

| | |
|---|----------------|
| Salem Seismic Salem, Oregon | |
| PEAK GROUND VELOCITY, PGV | |
| May 2021 | 105679 |
| SHANNON & WILSON, INC. GEOTECHNICAL AND ENVIRONMENTAL CONSULTANTS | FIG. 10 |




Sources: Esri, HERE, Garmin, Intermap, increment P Corp., GEBCO, USGS, FAO, NPS, NRCAN, GeoBase, IGN, Kadaster NL, Ordnance Survey, Esri Japan, METI, Esri China (Hong Kong), swisstopo, © OpenStreetMap contributors, and the GIS User Community




★ Critical Facilities

— City of Salem Pipeline Backbone




- NOTES**
1. Probability of liquefaction for magnitude 9.0 Cascadia Earthquake Scenario calculated from data provided with DOGAMI publications O-12-02, GMS-105, and OGDC-6. See text for details.
 2. City of Salem pipelines provided by Black & Veatch.

| | |
|--|----------------|
| Salem Seismic Salem, Oregon | |
| PROBABILITY OF LIQUEFACTION | |
| May 2021 | 105679 |
| SHANNON & WILSON, INC. GEOTECHNICAL AND ENVIRONMENTAL CONSULTANTS | FIG. 11 |




- Critical Facilities:**
1. Salem-Keizer Intertie/Cherry Ave Booster
 2. Grice Hill Reservoir and Repeater Tower
 3. Hemlock Well
 4. Mountain View Reservoir and Pump Station
 5. EOLA 1B Reservoir
 6. Limelight Pump Station
 7. Fairmont Reservoir
 8. Candalaria Reservoir
 9. South Salem Repeater Tower
 10. Croisan Lower Pump Station
 11. Edwards Pump Station
 12. ASR Wells
 13. Skyline Repeater Tower
 14. Lone Oak Reservoir
 15. Creekside Pump Station
 16. Champion Hill Reservoir
 17. Boone Road Pump Station
 18. Deer Park Pump Station
 19. Mill Creek Reservoir
 20. Turner Control Facilities
 21. Franzen Reservoir and Repeater Tower
 22. Geren Island WTP and Repeater Tower
 23. Upper Transmission Mains
 24. Lower Transmission Mains

Sources: Esri, HERE, Garmin, Intermap, increment P Corp., GEBCO, USGS, FAO, NPS, NRCAN, GeoBase, IGN, Kadaster NL, Ordnance Survey, Esri Japan, METI, Esri China (Hong Kong), swisstopo, © OpenStreetMap contributors, and the GIS User Community




- ★ Critical Facilities
- City of Salem Pipeline Backbone




- NOTES**
1. Liquefaction-induced lateral spreading PGD for the magnitude 9.0 Cascadia Earthquake Scenario calculated from data provided with DOGAMI publications O-12-02, OGDC-6, GMS-105, and FEMA publication HAZUS 4.2 Technical Manual. See text for details.
 2. City of Salem pipelines provided by Black & Veatch.

| | |
|---|----------------|
| Salem Seismic Salem, Oregon | |
| LIQUEFACTION-INDUCED LATERAL SPREADING PERMANENT GROUND DEFORMATION, PGD | |
| May 2021 | 105679 |
| SHANNON & WILSON, INC. GEOTECHNICAL AND ENVIRONMENTAL CONSULTANTS | FIG. 12 |




- Critical Facilities:**
1. Salem-Keizer Intertie/Cherry Ave Booster
 2. Grice Hill Reservoir and Repeater Tower
 3. Hemlock Well
 4. Mountain View Reservoir and Pump Station
 5. EOLA 1B Reservoir
 6. Limelight Pump Station
 7. Fairmont Reservoir
 8. Candalaria Reservoir
 9. South Salem Repeater Tower
 10. Croisan Lower Pump Station
 11. Edwards Pump Station
 12. ASR Wells
 13. Skyline Repeater Tower
 14. Lone Oak Reservoir
 15. Creekside Pump Station
 16. Champion Hill Reservoir
 17. Boone Road Pump Station
 18. Deer Park Pump Station
 19. Mill Creek Reservoir
 20. Turner Control Facilities
 21. Franzen Reservoir and Repeater Tower
 22. Geren Island WTP and Repeater Tower
 23. Upper Transmission Mains
 24. Lower Transmission Mains




- NOTES**
1. Liquefaction-induced lateral spreading PGD for the magnitude 9.0 Cascadia Earthquake Scenario calculated from data provided with DOGAMI publications O-12-02, OGDC-6, GMS-105, and FEMA publication HAZUS 4.2 Technical Manual. See text for details.
 2. City of Salem pipelines provided by Black & Veatch.


| | |
|--|----------------|
| Salem Seismic Salem, Oregon | |
| LIQUEFACTION-INDUCED SETTLEMENT PERMANENT GROUND DEFORMATION, PGD | |
| May 2021 | 105679 |
| SHANNON & WILSON, INC. GEOTECHNICAL AND ENVIRONMENTAL CONSULTANTS | FIG. 13 |



- Critical Facilities:**
1. Salem-Keizer Intertie/Cherry Ave Booster
 2. Grice Hill Reservoir and Repeater Tower
 3. Hemlock Well
 4. Mountain View Reservoir and Pump Station
 5. EOLA 1B Reservoir
 6. Limelight Pump Station
 7. Fairmont Reservoir
 8. Candalaria Reservoir
 9. South Salem Repeater Tower
 10. Croisan Lower Pump Station
 11. Edwards Pump Station
 12. ASR Wells
 13. Skyline Repeater Tower
 14. Lone Oak Reservoir
 15. Creekside Pump Station
 16. Champion Hill Reservoir
 17. Boone Road Pump Station
 18. Deer Park Pump Station
 19. Mill Creek Reservoir
 20. Turner Control Facilities
 21. Franzen Reservoir and Repeater Tower
 22. Geren Island WTP and Repeater Tower
 23. Upper Transmission Mains
 24. Lower Transmission Mains




- ★ Critical Facilities
- City of Salem Pipeline Backbone




- NOTES**
1. Earthquake-induced landslide probability for the magnitude 9.0 Cascadia Earthquake Scenario calculated from data provided with DOGAMI publications O-12-02, OGDC-6, SLIDO-4.0 and LiDAR. See text for details.
 2. City of Salem pipelines provided by Black & Veatch.

| | |
|---|----------------|
| Salem Seismic Salem, Oregon | |
| PROBABILITY OF EARTHQUAKE-INDUCED LANDSLIDES (DRY) | |
| May 2021 | 105679 |
| SHANNON & WILSON, INC. GEOTECHNICAL AND ENVIRONMENTAL CONSULTANTS | FIG. 14 |




- Critical Facilities:**
- 1. Salem-Keizer Intertie/Cherry Ave Booster
 - 2. Grice Hill Reservoir and Repeater Tower
 - 3. Hemlock Well
 - 4. Mountain View Reservoir and Pump Station
 - 5. EOLA 1B Reservoir
 - 6. Limelight Pump Station
 - 7. Fairmont Reservoir
 - 8. Candalaria Reservoir
 - 9. South Salem Repeater Tower
 - 10. Croisan Lower Pump Station
 - 11. Edwards Pump Station
 - 12. ASR Wells
 - 13. Skyline Repeater Tower
 - 14. Lone Oak Reservoir
 - 15. Creekside Pump Station
 - 16. Champion Hill Reservoir
 - 17. Boone Road Pump Station
 - 18. Deer Park Pump Station
 - 19. Mill Creek Reservoir
 - 20. Turner Control Facilities
 - 21. Franzen Reservoir and Repeater Tower
 - 22. Geren Island WTP and Repeater Tower
 - 23. Upper Transmission Mains
 - 24. Lower Transmission Mains

Earthquake-Induced Landslide Probability in Wet Conditions (%)
(Proportion of Area Expected to Fail)




- ★ Critical Facilities
- City of Salem Pipeline Backbone



NOTES

- 1. Earthquake-induced landslide probability for the magnitude 9.0 Cascadia Earthquake Scenario calculated from data provided with DOGAMI publications O-12-02, OGDC-6, SLIDO-4.0 and LiDAR. See text for details.
- 2. City of Salem pipelines provided by Black & Veatch.

| | |
|---|----------------|
| Salem Seismic Salem, Oregon | |
| PROBABILITY OF EARTHQUAKE-INDUCED LANDSLIDES (WET) | |
| May 2021 | 105679 |
| SHANNON & WILSON, INC. GEOTECHNICAL AND ENVIRONMENTAL CONSULTANTS | FIG. 15 |



- Critical Facilities:**
1. Salem-Keizer Intertie/Cherry Ave Booster
 2. Grice Hill Reservoir and Repeater Tower
 3. Hemlock Well
 4. Mountain View Reservoir and Pump Station
 5. EOLA 1B Reservoir
 6. Limelight Pump Station
 7. Fairmont Reservoir
 8. Candalaria Reservoir
 9. South Salem Repeater Tower
 10. Croisan Lower Pump Station
 11. Edwards Pump Station
 12. ASR Wells
 13. Skyline Repeater Tower
 14. Lone Oak Reservoir
 15. Creekside Pump Station
 16. Champion Hill Reservoir
 17. Boone Road Pump Station
 18. Deer Park Pump Station
 19. Mill Creek Reservoir
 20. Turner Control Facilities
 21. Franzen Reservoir and Repeater Tower
 22. Geren Island WTP and Repeater Tower
 23. Upper Transmission Mains
 24. Lower Transmission Mains


LEGEND

Earthquake-Induced Landslide PGD (ft)

| | |
|--|------------|
| | Negligible |
| | 0 - 0.5 |
| | 0.5 - 1 |


Critical Facilities

City of Salem Pipeline Backbone



- NOTES**
1. Earthquake-induced landslide PGD for the magnitude 9.0 Cascadia Earthquake Scenario calculated from data provided with DOGAMI publications O-12-02, OGDC-6, SLIDO-4.0 and LiDAR. See text for details.
 2. City of Salem pipelines provided by Black & Veatch.

| | |
|---|----------------|
| Salem Seismic Salem, Oregon | |
| EARTHQUAKE-INDUCED LANDSLIDE PERMANENT GROUND DEFORMATION, PGD (DRY) | |
| May 2021 | 105679 |
| SHANNON & WILSON, INC. GEOTECHNICAL AND ENVIRONMENTAL CONSULTANTS | FIG. 16 |



- Critical Facilities:**
- 1. Salem-Keizer Intertie/Cherry Ave Booster
 - 2. Grice Hill Reservoir and Repeater Tower
 - 3. Hemlock Well
 - 4. Mountain View Reservoir and Pump Station
 - 5. EOLA 1B Reservoir
 - 6. Limelight Pump Station
 - 7. Fairmont Reservoir
 - 8. Candalaria Reservoir
 - 9. South Salem Repeater Tower
 - 10. Croisan Lower Pump Station
 - 11. Edwards Pump Station
 - 12. ASR Wells
 - 13. Skyline Repeater Tower
 - 14. Lone Oak Reservoir
 - 15. Creekside Pump Station
 - 16. Champion Hill Reservoir
 - 17. Boone Road Pump Station
 - 18. Deer Park Pump Station
 - 19. Mill Creek Reservoir
 - 20. Turner Control Facilities
 - 21. Franzen Reservoir and Repeater Tower
 - 22. Geren Island WTP and Repeater Tower
 - 23. Upper Transmission Mains
 - 24. Lower Transmission Mains

LEGEND

Earthquake-Induced Landslide PGD (ft)

| | |
|--|------------|
| | Negligible |
| | 0-1 |
| | 1-2 |
| | 2-3 |
| | 3-4 |

★ Critical Facilities

— City of Salem Pipeline Backbone

0 6,000 12,000 24,000

Scale in Feet

NOTES

1. Earthquake-induced landslide PGD for the magnitude 9.0 Cascadia Earthquake Scenario calculated from data provided with DOGAMI publications O-12-02, OGDC-6, SLIDO-4.0 and LiDAR. See text for details.

2. City of Salem pipelines provided by Black & Veatch.

Salem Seismic
Salem, Oregon

**EARTHQUAKE-INDUCED
LANDSLIDE PERMANENT GROUND
DEFORMATION, PGD (WET)**


May 2021 105679

SHANNON & WILSON, INC.
GEOTECHNICAL AND ENVIRONMENTAL CONSULTANTS

FIG. 17



- LEGEND**
- Approximate Location of Shannon & Wilson Test Pit, 1987
 - Approximate Location of Applied Geotechnology Borehole, 1993
 - Approximate Location of Foundation Engineering Test Pit, 1996
 - Approximate Location of Foundation Engineering Borehole, 1996
 - Approximate Location of McMillen Jacobs Borehole, 2019



| | |
|--|----------------|
| Salem Seismic, Salem, Oregon | |
| PREVIOUS EXPLORATIONS ON GEREN ISLAND | |
| May 2021 | 105679 |
| SHANNON & WILSON, INC. <small>GEOTECHNICAL AND ENVIRONMENTAL CONSULTANTS</small> | FIG. 18 |

APPENDIX A

EXISTING INFORMATION
SITE 1 - SALEIM-KEIZER INTERTIE
&
CHERRY AVE BOOSTER PUMP STATION

WELL REPORT STATE OF OREGON

RECEIVED

State Well No. 753W-2

JAN 29 1982

State Permit No.

WATER RESOURCES DEPT
SALEM, OREGON

MAR 1 1982

16771

OWNER:

Name Reiger Water Dist.
Address 64 Chemawa Rd NE
City Salem State Ore

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary Air ☐ Driven ☐
Rotary Mud ☐ Dug ☐
Cased ☒ Bored ☐

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☒
Irrigation ☐ Test Well ☐ Other ☐
Thermal: Withdrawal ☐ Reinjection ☐

(5) CASING INSTALLED:

Steel ☒ Plastic ☐
Threaded ☐ Welded ☒

12" Diam. from 71 ft. to 120 ft. Gauge 250
" Diam. from ft. to ft. Gauge

(6) LINER INSTALLED:

" Diam. from ft. to ft. Gauge

(6) PERFORATIONS:

Perforated? ☐ Yes ☒ No

Type of perforator used

Size of perforations in. by in.
..... perforations from ft. to ft.
..... perforations from ft. to ft.
..... perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☒ Yes ☐ No

Manufacturer's Name Johanson
Type 12" - 60 slot 120-140 Model No. 304
Diam. 10" Slot Size 30 Set from 170 ft. to 188 ft.
Diam. 10" Slot Size 25 Set from 188 ft. to 205 ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☒ Yes ☐ No If yes, by whom?
Dmd: 600 gal./min. with 90 ft. drawdown after 24 hrs.

Air test gal./min. with drill stem at ft. hrs.

Bailer test gal./min. with ft. drawdown after hrs.

Artesian flow g.p.m.

Temperature of water Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Special standards: Yes ☐ No ☒

Well seal—Material used Cement

Well sealed from land surface to 80 ft.

Diameter of well bore to bottom of seal 16 in.

Diameter of well bore below seal 12 in.

Number of sacks of cement used in well seal 104 sacks

How was cement grout placed? Pumped

Was pump installed? Yes Type HP Depth ft.

Was a drive shoe used? ☒ Yes ☐ No Plugs Size: location ft.

Did any strata contain unusable water? ☐ Yes ☐ No

Type of Water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel:

Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Morrow Driller's well number
1/4 1/4 Section 2 T. 7 R. 32 W.M.

Tax Lot # Lot Blk Subdivision

Address at well location: Cherry Ave

(11) WATER LEVEL: Completed well.

Depth at which water was first found 22 ft.

Static level 25 ft. below land surface. Date 1-22-82

Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 12

Depth drilled 232 ft. Depth of completed well 210 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

| MATERIAL | From | To | SWL |
|------------------------------|------|-----|-----|
| Sandy clay | 0 | 22 | |
| Small to Large Gravel | 22 | 35 | |
| Small to Large Gravel | 35 | 43 | |
| Small to Large Gravel | 43 | 66 | |
| Heavy clay | 66 | 75 | |
| Gravelled Gravel | 75 | 95 | |
| Small to Large Gravel | 95 | 115 | |
| Gravelled Gravel | 115 | 117 | |
| Small to Large Gravel & Sand | 117 | 140 | |
| Gravelled Gravel | 140 | 145 | |
| Sand & Gravel | 145 | 167 | |
| Clay & Gravel | 167 | 168 | |
| Small to Large Gravel | 168 | 189 | |
| Sand Some Small Gravel | 189 | 208 | |
| Gravel mostly Long | 208 | 212 | |
| Gravelled Gravel | 212 | 232 | |
| Red Cinder | 212 | 232 | |
| Well back filled from | 232 | | |
| 210 thru Red Cinder zone | | | |

Work started 10-16 19 82 Completed 1-22 19 82

Date well drilling machine moved off of well 1-22 19 82

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Norman H. Stenell Date 1-22, 1982

(Drilling Machine Operator)

Drilling Machine Operator's License No. 455

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name ECOLA WELL DRILLING (Type or print)

(Person, Partner or Corporation) N.W.,

SALEM, OR 97304

Address Hamlet St Bendt

[Signed] Hamlet St Bendt (Water Well Contractor)

Contractor's License No. 619 Date 1-27 19 82

NOTICE TO WATER WELL CONTRACTOR

The original and first copy of this report are to be filed with the

WATER RESOURCES DEPARTMENT,
SALEM, OREGON 97310
within 30 days from the date of well completion.

SP*12658-690

7s/3w-2
Marion

RECEIVED

JAN 29 1982

WATER RESOURCES DEPT
SALEM, OREGON

Depth in Feet
Below Surface 0'

Existing 12" I.D. .250
casing

80'

118'

120'

Fig. K
Packer

60
Slot

12" T.S.
S.S. screen

140'

12" O.D.
.250 steel
black pipe

170'

10" P.S.
S.S. screen

30
Slot

188'

25
Slot

205'

Keizer Water District
Cherry Ave. Production Well

Vertical Well Profile
12-15-81 - N.T.S.
E. Butts

OREGON HEALTH DIVISION ONLY:

Received Date:

County Well Log ID #

9/18/00

MARI 16771

**WELL IDENTIFICATION LABEL ATTACHMENT FORM
(OREGON HEALTH DIVISION)**

COMPANY /CURRENT WELL OWNER:

OWNER (S) WELL NO: #5

Name: City of Keizer

Mailing Address: P.O. Box 21000

City: Keizer State: OR Zip: 97307 Phone: (503) 390-3700

CONTACT PERSON:

NAME: Joe Edgell PHONE # (503) 390-3700

**THIS FORM IS ONLY TO BE USED FOR WELLS WITH
POSITIVELY IDENTIFIED
WATER SUPPLY WELL REPORTS.**

O.H.D. OFFICIAL USE ONLY

TOWNSHIP: 7 N / S RANGE: 3 E / W SECTION: 2 TAX-LOT: 9600

Well Identification Label : L-32102

LABEL ATTACHED BY: Tom Pattee DATE: 8/18/00
(O.H.D. OFFICIAL)

(WATER SUPPLY WELL REPORT MUST BE ATTACHED!)

Please Return Completed Form to:

Larry D. McQueen
Well Identification Program
Oregon Water Resources Department
158 12th Street NE
Salem OR 97310

LDM/WRD/OHD

APPENDIX B

EXISTING INFORMATION
SITE 2 - GRICE HILL RESERVOIR
&
REPEATER TOWER

RECEIVED
APR 5 1990

POLK 002 7S/3W/17cb
19059

STATE OF OREGON
WATER WELL REPORT
(as required by ORS 537.765)

WATER RESOURCES DEPT.

(START CARD) #

(1) OWNER:

Name James Hellyer
Address 1900 27th Place N.W.
City Salem, Oregon 97304 State _____ Zip _____

(2) TYPE OF WORK:

☒ New Well ☐ Deepen ☐ Recondition ☐ Abandon

(3) DRILL METHOD

☒ Rotary Air ☐ Rotary Mud ☐ Cable

☐ Other _____

(4) PROPOSED USE:

☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation

☐ Thermal ☐ Injection ☐ Other _____

(5) BORE HOLE CONSTRUCTION:

Special Construction approval Yes No Depth of Completed Well 220 ft.

Explosives used ☐ Yes ☒ No ☐ Type _____ Amount _____

| HOLE | | | SEAL | | | Amount sacks or pounds |
|----------|------|-----|-------------|------|-----|---------------------------|
| Diameter | From | To | Material | From | To | |
| 10 | 0 | 120 | Cement & 5% | 0 | 120 | 35+bentonite |
| 6 | 0 | 220 | | | | |

How was seal placed: Method ☐ A ☐ B ☒ C ☐ D ☐ E

☐ Other _____

Backfill placed from _____ ft. to _____ ft. Material _____

Gravel placed from _____ ft. to _____ ft. Size of gravel _____

(6) CASING/LINER:

| | Diameter | From | To | Gauge | Steel | Plastic | Welded | Threaded |
|---------|----------|------|-----|--------|-------------------------------------|--------------------------|-------------------------------------|--------------------------|
| Casing: | 6 | +18 | 120 | .25 | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> |
| | | | | | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| | | | | | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| | | | | | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| Liner: | 4 | 0 | 220 | 160PSI | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| | | | | | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |

Final location of shoe(s) 120

(7) PERFORATIONS/SCREENS:

☒ Perforations Method Skillsaw

☐ Screens Type _____ Material _____

| From | To | Slot size | Number | Diameter | Tele/pipe size | Casing | Liner |
|------|-----|--------------|--------|----------|-------------------|--------------------------|-------------------------------------|
| 160 | 220 | 1/8" | 135 | | | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
| | | X 8" | | | | <input type="checkbox"/> | <input type="checkbox"/> |
| | | | | | | <input type="checkbox"/> | <input type="checkbox"/> |
| | | | | | | <input type="checkbox"/> | <input type="checkbox"/> |
| | | | | | | <input type="checkbox"/> | <input type="checkbox"/> |
| | | | | | | <input type="checkbox"/> | <input type="checkbox"/> |

(8) WELL TESTS: Minimum testing time is 1 hour

☐ Pump ☐ Bailer ☒ Air ☐ Flowing Artesian

| Yield gal/min | Drawdown | Drill stem at | Time |
|---------------|----------|---------------|-------|
| 50 | | 220 | 1 hr. |
| | | | |
| | | | |

Temperature of water _____ Depth Artesian Flow Found _____

Was a water analysis done? ☐ Yes By whom _____

Did any strata contain water not suitable for intended use? ☐ Too little

☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other _____

Depth of strata: _____

(9) LOCATION OF WELL by legal description:

County Polk Latitude _____ Longitude _____
Township 7S Nor or S, Range 3W E or W, WM.
Section 17 NW ¼ SW ¼
Tax Lot _____ Lot _____ Block _____ Subdivision _____
Street Address of Well (or nearest address) _____
1900 27th Place N.W. Salem, OR

(10) STATIC WATER LEVEL:

55 ft. below land surface. Date 3/27/90

Artesian pressure _____ lb. per square inch. Date _____

(11) WATER BEARING ZONES:

Depth at which water was first found 84

| From | To | Estimated Flow Rate | SWL |
|------|-----|---------------------|-----|
| 84 | 91 | 10 | |
| 121 | 220 | 50 | 55 |
| 107 | 112 | 8 | |

(12) WELL LOG:

Ground elevation _____

| Material | From | To | SWL |
|--|------|-----|-----|
| Topsoil | 0 | 2 | |
| Brown Clay | 2 | 41 | |
| Brown Shale | 41 | 46 | |
| Brown Clay | 46 | 55 | |
| Broken Rock | 55 | 73 | |
| Black Basalt | 73 | 77 | |
| Broken Rock | 77 | 84 | |
| Broken Rock W.B. | 84 | 91 | |
| Broken Rock | 91 | 107 | |
| Broken Rock W.B. | 107 | 112 | |
| Broken Rock | 112 | 121 | |
| Red Sandy Shale | 121 | 129 | |
| Brown Brown Broken Rock | 129 | 149 | |
| Light Gray Clay | 149 | 156 | |
| Broken Basalt W.B. | 156 | 220 | |
| Shale Traps placed on liner at 140' and 150' | | | |
| | | | |
| | | | |
| | | | |
| | | | |

Date started 3/21/90 Completed 3/28/90

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief.

Signed Mark D. Bein WWC Number 753
Date 3/28/90

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. all work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief. WILLAMETTE DRILLING CO. WWC Number =753

Signed Mark D. Bein Date 3/28/90

RECEIVED

DEC 20 1999

STATE OF OREGON
WATER SUPPLY WELL REPORT WATER RESOURCES DEPT.
(as required by ORS 537.765) SALEM, OREGON

WELL I.D. # L 23074
START CARD # 115810

Instructions for completing this report are on the last page of this form.

(1) OWNER: Well Number _____
Name MARK ROBINSON
Address 2246 27th place
City salem State ore Zip 97304

(2) TYPE OF WORK
☒ New Well ☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment

(3) DRILL METHOD:
☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger
☐ Other _____

(4) PROPOSED USE:
☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☐ Livestock ☐ Other _____

(5) BORE HOLE CONSTRUCTION:
Special Construction approval ☐ Yes ☒ No Depth of Completed Well 204 ft.
Explosives used ☐ Yes ☒ No Type _____ Amount _____

| HOLE | | | SEAL | | | |
|----------|------|-----|-----------|------|----|-----------------|
| Diameter | From | To | Material | From | To | Sacks or pounds |
| 10 | 0 | 95 | cement | 50 | 95 | 12 bags |
| 6 | 95 | 204 | bentonite | 0 | 50 | 20 bags |

How was seal placed: Method ☐ A ☐ B ☐ C ☒ D ☐ E
☒ Other filled to top w/ dry bentonite
Backfill placed from _____ ft. to _____ ft. Material _____
Gravel placed from 24 ft. to 260 ft. Size of gravel 3/4-

(6) CASING/LINER:

| Diameter | From | To | Gauge | Steel | Plastic | Welded | Threaded |
|-----------|------|-----|-------|-------------------------------------|-------------------------------------|-------------------------------------|--------------------------|
| Casing: 6 | +1 | 95 | 250 | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> |
| Liner: 4 | 7 | 204 | 40 | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> |

Final location of shoe(s) _____

(7) PERFORATIONS/SCREENS:
☒ Perforations Method saw cut
☐ Screens Type _____ Material _____

| From | To | Slot size | Number | Diameter | Tele/pipe size | Casing | Liner |
|------|-----|-----------|--------|----------|----------------|--------------------------|--------------------------|
| 120 | 203 | 1/8 | 55 | 6 long | | <input type="checkbox"/> | <input type="checkbox"/> |

(8) WELL TESTS: Minimum testing time is 1 hour

| Yield gal/min | Drawdown | Drill stem at | Flowing Time |
|---------------|----------|---------------|--------------|
| 8 gpm | | 260 | 1 hr. |
| 20 gpm | | 195 | pump |

Temperature of water 56° Depth Artesian Flow Found _____

Was a water analysis done? ☐ Yes By whom _____

Did any strata contain water not suitable for intended use? ☐ Too little

☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other _____

Depth of strata: _____

(9) LOCATION OF WELL by legal description:

County POLK Latitude _____ Longitude _____
Township 7 S N or S Range 3 W E or W. WM.
Section 17 SW 1/4 ne 1/4
Tax Lot 1600 Lot _____ Block _____ Subdivision _____
Street Address of Well (or nearest address) same

(10) STATIC WATER LEVEL:

84' ft. below land surface. Date 11/26/99
Artesian pressure _____ lb. per square inch. Date _____

(11) WATER BEARING ZONES:

Depth at which water was first found _____

| From | To | Estimated Flow Rate | SWL |
|------|-----|---------------------|-----|
| 120 | 203 | 20 gpm | 84 |
| | | | |
| | | | |

(12) WELL LOG:

Ground Elevation _____

| Material | From | To | SWL |
|---|------|-----|-----|
| Soil | 0 | 1 | |
| brown clay | 1 | 12 | |
| red clay | 12 | 42 | |
| tan clay | 42 | 53 | |
| brown clay | 53 | 60 | |
| rock brown broken basalt | 60 | 75 | |
| rock black hard basalt | 75 | 124 | |
| rock black brown broken | 124 | 153 | |
| tan brown clay w/rock | 153 | 168 | |
| rock black broken basalt | 168 | 185 | |
| gray clay | 185 | 187 | |
| rock black broken basalt | 187 | 213 | |
| rock black brown basalt | 213 | 260 | |
| due to cavee broken rock, completed depth of well is 204' | | | |

Date started 11/14/99 Completed 11/26/99

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

FEB 03 2000 WWC Number _____

Signed _____

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed _____ WWC Number 1585 Date 11/26/99

APPENDIX C

EXISTING INFORMATION
SITE 4 - MOUNTAIN VIEW RESERVOIR
&
PUMP STATION

RECEIVED

RECEIVED

STATE OF OREGON
WATER SUPPLY WELL REPORT
(as required by ORS 537.765)

polk
51034

OCT 13 1999

NOV 19 1999

34623

WATER RESOURCES DEPT. SALEM, OREGON

WATER RESOURCES DEPT. SALEM, OREGON

127263

Instructions for completing this report are on the last page of this form.

(1) OWNER:

Name Mike Kottek Well Number 3423
Address 1657 Orchard Heights Rd NW
City Salem State OR Zip 97304

(2) TYPE OF WORK

☐ New Well ☐ Deepening ☒ Alteration (repair/recondition) ☐ Abandonment

(3) DRILL METHOD:

☐ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger

☒ Other Crane Hoist

(4) PROPOSED USE:

☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation

☐ Thermal ☐ Injection ☐ Livestock ☐ Other

(5) BORE HOLE CONSTRUCTION:

Special Construction approval ☐ Yes ☒ No Depth of Completed Well 180 ft.

Explosives used ☐ Yes ☒ No Type _____ Amount _____

HOLE

SEAL

Diameter From To Material From To Sacks or pounds

6" 41 180 Existing Well

How was seal placed: - Method ☐ A ☐ B ☐ C ☐ D ☐ E

☒ Other Existing not disturbed

Backfill placed from _____ ft. to _____ ft. Material _____

Gravel placed from _____ ft. to _____ ft. Size of gravel _____

(6) CASING/LINER:

Diameter From To Gauge Steel Plastic Welded Threaded
Casing: 6" Existing ☒ ☐ ☐ ☐

Liner: 4" 0 180 ☐ ☒ ☐ ☐
Packer placed at 130

Final location of shoe(s) Unknown

(7) PERFORATIONS/SCREENS:

☒ Perforations Method Skil saw

☐ Screens Type _____ Material _____

From To Slot size Number Diameter Tele/pipe size Casing Liner
140 180 4x6 160 ☐ ☒

(8) WELL TESTS: Minimum testing time is 1 hour

☐ Pump ☐ Bailer ☐ Air ☐ Flowing
Yield gal/min Drawdown Drill stem at Time
NA NA NA 1 hr.

Temperature of water 53 Depth Artesian Flow Found _____

Was a water analysis done? no Yes By whom _____

Did any strata contain water not suitable for intended use? no Too little

☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other

Depth of strata: _____

(9) LOCATION OF WELL by legal description:

County Polk Latitude _____ Longitude _____

Township 7S N or S Range 3W E or W. WM.

Section 16 NW 1/4 SW 1/4

Tax Lot 200 Lot _____ Block _____ Subdivision _____

Street Address of Well (or nearest address) _____

(10) STATIC WATER LEVEL:

109 ft. below land surface. Date 10/5/99

Artesian pressure _____ lb. per square inch. Date _____


(11) WATER BEARING ZONES:

Depth at which water was first found Existing 109

| From | To | Estimated Flow Rate | SWL |
|-----------------|----|---------------------|------------|
| <u>Existing</u> | | | <u>109</u> |
| | | | |
| | | | |
| | | | |

(12) WELL LOG:

Ground Elevation _____

| Material | From | To | SWL |
|--|------|----|-----|
| <u>Because of excessive rust because of age of casing at liner was placed to the bottom with a neoprene packer placed at 120 ft.</u> | | | |
| <u>No log was found for original well</u> | | | |
| Willamette Drilling Company | | | |
|  | | | |
| | | | |
| | | | |
| | | | |
| | | | |

Date started 10/5/99 Completed 10/5/99

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

Signed Richard Marshall WWC Number 1728 Date 10/11/99

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed Dallas L Davis WWC Number 561 Date 10/11/99

STATE OF OREGON
GEOTECHNICAL HOLE REPORT
 (as required by OAR 690-240-0035)

10-12-2011

(1) OWNER/PROJECT

Hole Number B-2

PROJECT NAME/NBR: BRY 100611

First Name _____ Last Name _____
 Company LINDBECK FAMILY LLC
 Address 2255 ELLIS AVE NE
 City SALEM State OR Zip 97301

(2) TYPE OF WORK ☒ New ☐ Deepening ☒ Abandonment
☐ Alteration (repair/recondition)

(3) CONSTRUCTION

☐ Rotary Air ☐ Hand Auger ☒ Hollow stem auger
☐ Rotary Mud ☐ Cable ☐ Push Probe
☐ Other _____

(4) TYPE OF HOLE:

☒ Uncased Temporary ☐ Cased Permanent
☐ Uncased Permanent ☐ Slope Stability
☐ Other
 Other: _____

(5) USE OF HOLE

GEOTECHNICAL

(6) BORE HOLE CONSTRUCTION Special Standard ☐ (Attach copy)

Depth of Completed Hole 20.00 ft.

| BORE HOLE | | | SEAL | | | | sacks/ |
|-----------|------|----|-----------|------|----|-----|--------|
| Dia | From | To | Material | From | To | Amt | lbs |
| 8 | 0 | 20 | Bentonite | 0 | 20 | 10 | S |
| | | | | | | | |
| | | | | | | | |

Backfill placed from _____ ft. to _____ ft. Material _____
 Filter pack from _____ ft. to _____ ft. Material _____ Size _____

(7) CASING/SCREEN

| Casing | Screen | Dia | + | From | To | Gauge | Stl | Plstc | Wld | Thrd |
|--------------------------|--------------------------|-----|---|------|----|-------|--------------------------|--------------------------|--------------------------|--------------------------|
| <input type="checkbox"/> | <input type="checkbox"/> | | | | | | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| <input type="checkbox"/> | <input type="checkbox"/> | | | | | | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| <input type="checkbox"/> | <input type="checkbox"/> | | | | | | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| <input type="checkbox"/> | <input type="checkbox"/> | | | | | | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| <input type="checkbox"/> | <input type="checkbox"/> | | | | | | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |

(8) WELL TESTS

☐ Pump ☐ Bailer ☐ Air ☐ Flowing Artesian
 Yield gal/min Drawdown Drill stem/Pump depth Duration(hr)

| | | | |
|--|--|--|--|
| | | | |
| | | | |

Temperature _____ °F Lab analysis ☐ Yes By _____

Supervising Geologist/Engineer _____

Water quality concerns? ☐ Yes (describe below)

| From | To | Description | Amount | Units |
|------|----|-------------|--------|-------|
| | | | | |
| | | | | |

(9) LOCATION OF HOLE (legal description)

County Polk Twp 7.00 S N/S Range 3.00 W E/W WM
 Sec 16 SW 1/4 of the SW 1/4 Tax Lot 103
 Tax Map Number _____ Lot _____
 Lat _____ " or _____ DMS or DD
 Long _____ " or _____ DMS or DD
☒ Street address of hole ☐ Nearest address

1500 ORCHARD HEIGHTS RD. NW SALEM, OREGON 97308

(10) STATIC WATER LEVEL

Date _____ SWL(psi) + SWL(ft)

| | | |
|------------------------------|--|--|
| Existing Well / Predeepening | | |
| Completed Well | | |

WATER BEARING ZONES

Flowing Artesian? ☐

Depth water was first found

| SWL Date | From | To | Est Flow | SWL(psi) | + SWL(ft) |
|----------|------|----|----------|----------|-----------|
| | | | | | 16.00 |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |

(11) SUBSURFACE LOG

Ground Elevation

| Material | From | To |
|-----------------------|------|----|
| BROWNISH REDDISH CLAY | 0 | 15 |
| WEATHERED BASALT | 15 | 20 |
| | | |
| | | |
| | | |
| | | |
| | | |

Date Started 10-06-2011 Completed 10-06-2011

(12) ABANDONMENT LOG:

| Material | From | To | Amt | sacks/ |
|-----------|------|----|-----|--------|
| Bentonite | 0 | 20 | 10 | S |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |

Date Started 10-06-2011 Completed 10-06-2011

Professional Certification (to be signed by an Oregon licensed water or monitoring well constructor, Oregon registered geologist or professional engineer).

I accept responsibility for the construction, deepening, alteration, or abandonment work performed during the construction dates reported above. All work performed during this time is in compliance with Oregon geotechnical hole construction standards. This report is true to the best of my knowledge and belief.

License/Registration Number 10626 Date _____
 Electronically Submitted
 First Name BRYAN Last Name MEAD
 Affiliation SUBSURFACE TECHNOLOGIES

STATE OF OREGON
GEOTECHNICAL HOLE REPORT
 (as required by OAR 690-240-0035)

10-12-2011

(1) OWNER/PROJECT

Hole Number B-1

PROJECT NAME/NBR: BRY 100611

First Name _____ Last Name _____
 Company LINDBECK FAMILY LLC
 Address 2255 ELLIS AVE NE
 City SALEM State OR Zip 97301

(2) TYPE OF WORK ☒ New ☐ Deepening ☒ Abandonment
☐ Alteration (repair/recondition)

(3) CONSTRUCTION

☐ Rotary Air ☐ Hand Auger ☒ Hollow stem auger
☐ Rotary Mud ☐ Cable ☐ Push Probe
☐ Other _____

(4) TYPE OF HOLE:

☒ Uncased Temporary ☐ Cased Permanent
☐ Uncased Permanent ☐ Slope Stability
☐ Other
 Other: _____

(5) USE OF HOLE

GEOTECHNICAL

(6) BORE HOLE CONSTRUCTION Special Standard ☐ (Attach copy)

Depth of Completed Hole 20.00 ft.

| BORE HOLE | | | SEAL | | | | sacks/ |
|-----------|------|----|-----------|------|----|-----|--------|
| Dia | From | To | Material | From | To | Amt | lbs |
| 8 | 0 | 20 | Bentonite | 0 | 20 | 10 | S |
| | | | | | | | |
| | | | | | | | |

Backfill placed from _____ ft. to _____ ft. Material _____
 Filter pack from _____ ft. to _____ ft. Material _____ Size _____

(7) CASING/SCREEN

| Casing | Screen | Dia | + | From | To | Gauge | Stl | Plstc | Wld | Thrd |
|--------------------------|--------------------------|-----|---|------|----|-------|--------------------------|--------------------------|--------------------------|--------------------------|
| <input type="checkbox"/> | <input type="checkbox"/> | | | | | | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| <input type="checkbox"/> | <input type="checkbox"/> | | | | | | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| <input type="checkbox"/> | <input type="checkbox"/> | | | | | | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| <input type="checkbox"/> | <input type="checkbox"/> | | | | | | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |

(8) WELL TESTS

☐ Pump ☐ Bailer ☐ Air ☐ Flowing Artesian
 Yield gal/min Drawdown Drill stem/Pump depth Duration(hr)

| | | | |
|--|--|--|--|
| | | | |
| | | | |

Temperature _____ °F Lab analysis ☐ Yes By _____

Supervising Geologist/Engineer _____

Water quality concerns? ☐ Yes (describe below)

| From | To | Description | Amount | Units |
|------|----|-------------|--------|-------|
| | | | | |
| | | | | |

(9) LOCATION OF HOLE (legal description)

County Polk Twp 7.00 S N/S Range 3.00 W E/W WM
 Sec 16 SW 1/4 of the SW 1/4 Tax Lot 103
 Tax Map Number _____ Lot _____
 Lat _____ " or _____ DMS or DD
 Long _____ " or _____ DMS or DD
☒ Street address of hole ☐ Nearest address

1500 ORCHARD HEIGHTS RD. NW SALEM, OREGON 97308

(10) STATIC WATER LEVEL

Date _____ SWL(psi) + SWL(ft)

| | | | |
|------------------------------|--|--|--|
| Existing Well / Predeepening | | | |
| Completed Well | | | |

WATER BEARING ZONES

Flowing Artesian? ☐

Depth water was first found

| SWL Date | From | To | Est Flow | SWL(psi) | + SWL(ft) |
|----------|------|----|----------|----------|-----------|
| | | | | | 16.00 |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |

(11) SUBSURFACE LOG

Ground Elevation

| Material | From | To |
|-----------------------|------|----|
| BROWNISH REDDISH CLAY | 0 | 15 |
| WEATHERED BASALT | 15 | 20 |
| | | |
| | | |
| | | |
| | | |
| | | |

Date Started 10-06-2011 Completed 10-06-2011

(12) ABANDONMENT LOG:

| Material | From | To | Amt | sacks/ |
|-----------|------|----|-----|--------|
| Bentonite | 0 | 20 | 10 | S |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |


Date Started 10-06-2011 Completed 10-06-2011

Professional Certification (to be signed by an Oregon licensed water or monitoring well constructor, Oregon registered geologist or professional engineer).

I accept responsibility for the construction, deepening, alteration, or abandonment work performed during the construction dates reported above. All work performed during this time is in compliance with Oregon geotechnical hole construction standards. This report is true to the best of my knowledge and belief.

License/Registration Number 10626 Date _____
 Electronically Submitted
 First Name BRYAN Last Name MEAD
 Affiliation SUBSURFACE TECHNOLOGIES


Map of Hole




APPENDIX D


EXISTING INFORMATION
SITE 8 - CANDALARIA RESERVOIR

DRAFT



 BORING MADE BY GRI
 (JUNE 11, 2004)

SITE PLAN FROM FILE BY WESTLAKE CONSULTANTS, INC., DATED JUNE 17, 2004




GRI BLACK & VEATCH CORPORATION
 CITY OF SALEM RESERVOIRS

SITE PLAN (CANDALARIA RESERVOIR)

JULY 2004

JOB NO. 4091

FIG. 4



- I 2-IN.-OD SPLIT-SPOON SAMPLER
- II 3-IN.-OD THIN-WALLED SAMPLER
- G GRAB SAMPLE OF DRILL CUTTINGS
- NX CORE RUN
- SLOTTED PVC PIPE
- ▼ Water Level (date)
- ◆ TORVANE SHEAR STRENGTH, TSF
- UNDRAINED SHEAR STRENGTH, TSF
- * NO RECOVERY
- Liquid Limit
- Moisture Content
- Plastic Limit

GRI

JULY 2004

BORING B-2
(CANDALARIA RESERVOIR)

JOB. NO. 4091

FIG. 2A

APPENDIX E

EXISTING INFORMATION
SITE 9 – SOUTH SALEM REPEATER TOWER

STATE OF OREGON
GEOTECHNICAL HOLE REPORT
(as required by OAR 690-240-035)

(1) OWNER/PROJECT: Hole Number **B-2**
Name **CITY OF SALEM**
Address **1580 - 20TH ST, SE #24**
City **SALEM** State **OR** Zip **97301**

(2) TYPE OF WORK
☒ New ☐ Deepening ☐ Alteration (repair/recondition) ☒ Abandonment

(3) CONSTRUCTION:
☐ Rotary Air ☐ Hand Auger ☒ Hollow Stem Auger
☐ Rotary Mud ☐ Cable Tool ☐ Push Probe ☐ Other ☐

(4) TYPE OF HOLE:
☒ Uncased Temporary ☐ Cased Permanent
☐ Uncased Permanent ☐ Slope Stability ☐ Other

(5) USE OF HOLE: **GEOTECHNICAL**

(6) BORE HOLE CONSTRUCTION:
Special Construction approval ☐ Yes ☒ No Depth of Completed Hole **45** ft.

| HOLE | | | SEAL | | | Sacks or pounds |
|----------|----------|-----------|-------------------|-----------|----------|-----------------|
| Diameter | From | To | Material | From | To | |
| 8 | 0 | 45 | BENT CHIPS | 45 | 0 | 23 SKS |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Backfill placed from _____ ft. to _____ ft. Material _____
Filter Pack placed from _____ ft. to _____ ft. Size of pack _____

(7) CASING/SCREEN:

| | Diameter | From | To | Gauge | Steel | Plastic | Welded | Threaded |
|-----------|------------|------|----|-------|--------------------------|-------------------------------------|--------------------------|--------------------------|
| Casing: | N/A | | | | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| | | | | | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| | | | | | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| | | | | | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| Screen: | | | | | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| | | | | | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| | | | | | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| Slot size | | | | | | | | |

(8) WELL TEST:
☐ Pump ☐ Bailer ☐ Air ☐ Flowing Artesian
Permeability _____ Yield _____ GPM _____
Conductivity _____ PH _____
Temperature of water **N/A** °F Depth artesian flow found _____ ft.
Was water analysis done? ☐ Yes ☒ No
By whom? _____
Depth of strata analyzed. From _____ ft. to _____ ft.
Remarks: _____

(9) LOCATION OF HOLE by legal description:
County **MARION** Latitude _____ Longitude _____
Township **8** S Range **3** W WM.
Section **4** NW 1/4 **NE** 1/4
Tax Lot **7900** Lot _____ Block _____ Subdivision _____
Street Address of Well (or nearest address) **955 DOWNS ST S**
SALEM, OR

Map with location identified must be attached

(10) STATIC WATER LEVEL:
N/A ft. below land surface. Date **06/27/2006**
Artesian pressure _____ lb. per square inch. Date _____

(11) SUBSURFACE LOG:
Ground Elevation _____

| Material Description | From | To | SWL |
|---------------------------------|----------|-----------|-----|
| REDDISH WEATHERED BASALT | 0 | 45 | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

Date Started **06/27/2006** Date Completed **06/27/2006**

(12) ABANDONMENT LOG:


| Material Description | From | To | Sacks or Pounds |
|----------------------|-----------|----------|-----------------|
| BENT CHIPS | 45 | 0 | 23 SKS |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

Date started **06/27/2006** Date Completed **06/27/2006**

Professional Certification
(to be signed by a licensed water supply or monitoring well constructor, or registered geologist or civil engineer).

I accept responsibility for the construction, alteration, or abandonment work performed on during the construction dates reported above. All work performed during this time is in compliance with Oregon geotechnical hole construction standards. This report is true to the best of my knowledge and belief.

License or Registration Number **10536**
Signed **BURTON MARSHALL** Date **7-2-06**
Affiliation **SUBSURFACE TECHNOLOGIES**



THIS REPORT MUST BE SUBMITTED TO THE WATER RESOURCES DEPARTMENT WITHIN 30 DAYS OF COMPLETION OF WORK


ORIGINAL & FIRST COPY-WATER RESOURCES DEPARTMENT SECOND COPY-CONSTRUCTOR THIRD COPY-CUSTOMER

123°05.000' W

123°04.000' W

123°03.000' W

WGS84 123°02.000' W



44°56.000' N

44°55.000' N

44°54.000' N

44°53.000' N

44°56.000' N

44°55.000' N

44°54.000' N

44°53.000' N

123°05.000' W

123°04.000' W

123°03.000' W

WGS84 123°02.000' W

TN* / MN
17°

Map created with TOPOI® ©2002 National Geographic (www.nationalgeographic.com/topoi)

RECEIVED
JUL 26 2006
WATER RESOURCES DEPT
SALEM, OREGON



Crestview

Downs St S.

OB-2

Water tower

RECEIVED

JUL 26 2006

WATER RESOURCES DEPT
SALEM, OREGON

1"=50'

APPENDIX F

EXISTING INFORMATION
SITE 10 - EDWARDS S1 PUMP STATION

DRAFT

STATE OF OREGON
GEOTECHNICAL HOLE REPORT
(as required by OAR 690-240-035)

MARI 50417

(1) OWNER/PROJECT:

Hole Number

B-3

Name City of Salem
Address 555 Liberty St. SE
City Salem State OR Zip 97301

(2) TYPE OF WORK

☒ New ☐ Deepening ☐ Alteration (repair/recondition) ☒ Abandonment

(3) CONSTRUCTION:

☐ Rotary Air ☐ Hand Auger ☐ Hollow Stem Auger
☒ Rotary Mud ☐ Cable Tool ☐ Push Probe ☐ Other

(4) TYPE OF HOLE:

☒ Uncased Temporary ☐ Cased Permanent
☐ Uncased Permanent ☐ Slope Stability ☐ Other

(5) USE OF HOLE:

Foundation

(9) LOCATION OF HOLE by legal description:

County MARION Latitude _____ Longitude _____
Township 8S N or S Range 3W E or W. WM.
Section 2 S 1/4 E 1/4
Tax Lot _____ Lot _____ Block _____ Subdivision _____
Street Address of Well (or nearest address) _____

Map with location identified must be attached

(10) STATIC WATER LEVEL:

N/A ft. below land surface. Date 9-07-95
Artesian pressure _____ lb. per square inch. Date _____

(11) SUBSURFACE LOG:

Ground Elevation _____

| Material Description | From | To | SWL |
|---------------------------------|----------|---------------|-----------|
| <u>CL Boulders & Gravel</u> | <u>0</u> | <u>13 1/2</u> | <u>25</u> |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

Date Started _____

Date Completed _____

(12) ABANDONMENT LOG:

| Material Description | From | To | Sacks or Pounds |
|----------------------|-----------|----------|-----------------|
| <u>Hole plug</u> | <u>25</u> | <u>0</u> | <u>3</u> |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

Date started 9-07-95

Date Completed 9-07-95

| HOLE | | | SEAL | | | Sacks or pounds |
|--------------|----------|-----------|------------------|-----------|----------|-----------------|
| Diameter | From | To | Material | From | To | |
| <u>4 7/8</u> | <u>0</u> | <u>25</u> | <u>Hole plug</u> | <u>25</u> | <u>0</u> | <u>3</u> |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Backfill placed from _____ ft. to _____ ft. Material _____
Filter Pack placed from _____ ft. to _____ ft. Size of pack _____

(7) CASING/SCREEN:

| | Diameter | From | To | Gauge | Steel | Plastic | Welded | Threaded |
|-----------|----------|------|----|-------|--------------------------|--------------------------|--------------------------|--------------------------|
| Casing: | | | | | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| | | | | | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| | | | | | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| | | | | | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| Screen: | | | | | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| | | | | | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| | | | | | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| Slot size | | | | | | | | |

(8) WELL TEST:

☐ Pump ☐ Bailer ☐ Air ☐ Flowing Artesian
Permeability _____ Yield _____ GPM _____
Conductivity _____ PH _____
Temperature of water _____ °F/C Depth artesian flow found _____ ft.
Was water analysis done? ☐ Yes ☐ No
By whom? _____
Depth of strata analyzed. From _____ ft. to _____ ft.
Remarks: _____

Professional Certification

(to be signed by a licensed water supply or monitoring well constructor, or registered geologist or civil engineer).

I accept responsibility for the construction, alteration, or abandonment work performed on during the construction dates reported above. All work performed during this time is in compliance with Oregon geotechnical hole construction standards. This report is true to the best of my knowledge and belief.

License or Registration Number 10076

Signed

Bradley Wickard Date 9-14-95

Affiliation _____

THIS REPORT MUST BE SUBMITTED TO THE WATER RESOURCES DEPARTMENT WITHIN 30 DAYS OF COMPLETION OF WORK

ORIGINAL & FIRST COPY-WATER RESOURCES DEPARTMENT SECOND COPY-CONSTRUCTOR THIRD COPY-CUSTOMER

1 N

SITE MAP For B-3

SALLEN

Madrona St.

B-3

Madrona Ct.

APPENDIX G

EXISTING INFORMATION
SITE 14 – LONE OAK RESERVOIR


DRAFT

(1) OWNER/PROJECT WELL NO. MW 2
 Name CITY OF SALEM PUBLIC WORKS DEPT
 Address 555 LIBERTY ST SE RM 325
 City SALEM State OR Zip 97301

☒ New construction ☐ Alteration (Repair/Recondition)
☐ Conversion ☐ Deepening ☐ Abandonment

☐ Rotary Air ☐ Rotary Mud ☐ Cable
☒ Hollow Stem Auger ☐ Other _____

Special Standards ☐ Yes ☒ No Depth of Completed Well 40 ft.



WELL TESTS:

☐ Pump ☐ Bailer ☐ Air ☐ Flowing Artesian

Permeability _____ Yield _____ GPM

Conductivity _____ PH _____

Temperature of water _____ °F/C Depth artesian flow found _____ ft.

Was water analysis done? ☐ Yes ☒ No

By whom? _____

Depth of test to be analyzed. From _____ ft. to _____ ft.

Remarks: _____

Name of supervising Geologist/Engineer

County MARION Latitude _____ Longitude _____
Township 8 (N or S) Range 3 (E or W) Section 16
SE 1/4 of SE 1/4 of above section.
Street address of well location LGNECAY & MILBURN

_____ Ft. below land surface. Date _____
 Artesian Pressure None lb/sq. in. Date _____

Depth at which water was first found _____

| From | To | Est. Flow Rate | SWL |
|------|----|----------------|-----|
| | | | |
| | | | |
| | | | |
| | | | |

Ground Elevation _____

[illegible]

Date started 10/10/01 Completed 10/10/01

(unbonded) Monitor Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

Signed *D. Fort Laster* MWC Number 10306
Date 10-13-01

(bonded) Monitor Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed Wan C MWC Number 10459 Date 10/12/01

ORIGINAL COPY – WATER RESOURCES DEPARTMENT

FIRST COPY – CONSTRUCTOR SECOND COPY – CUSTOMER


TOPO! map printed on 10/03/01 from "Oregon.tpo" and "Untitled.tpg"

123°05'00" W

123°04'00" W

123°03'00" W

WGS84 123°02'00" W



TN
MN
17 1/2°

123°05'00" W

123°04'00" W

123°03'00" W

WGS84 123°02'00" W

0 1000 FEET 0 500 1000 METERS

Printed from TOPO! ©2000 National Geographic Holdings (www.topo.com)

MONITORING WELL REPORT

(as required by ORS 537.765 & OAR 690-240-095)

Instructions for completing this report are on the last page of this form.


Well ID# L47218

Start Card # W 140864

| | |
|---|--|
| (1) OWNER/PROJECT Name <u>City of Salem Public Works Dept.</u> Address <u>555 Liberty St SE RM 325</u> City <u>Salem</u> State <u>OR</u> Zip <u>97301</u> | (2) LOCATION OF WELL By legal description: County <u>MARION</u> Latitude _____ Longitude _____ Township <u>8</u> (N or S) Range <u>3</u> (E or W) Section <u>16</u> <u>SE</u> 1/4 of <u>SE</u> 1/4 of above section. Street address of well location <u>Lowz Oak & Mildred</u> Tax lot number of well location <u>ROW</u> ATTACH MAP WITH LOCATION IDENTIFIED. Map shall include approximate scale and north arrow. |
| (2) TYPE OF WORK <input checked="" type="checkbox"/> New construction <input type="checkbox"/> Alteration (Repair/Recondition) <input type="checkbox"/> Conversion <input type="checkbox"/> Deepening <input type="checkbox"/> Abandonment | (3) DRILLING METHOD <input type="checkbox"/> Rotary Air <input type="checkbox"/> Rotary Mud <input type="checkbox"/> Cable <input checked="" type="checkbox"/> Hollow Stem Auger <input type="checkbox"/> Other _____ |
| (4) STATIC WATER LEVEL: _____ Ft. below land surface Date _____ Artesian Pressure <u>NONE</u> lb/sq. in. Date _____ | |

(4) BORE HOLE CONSTRUCTION:

Special Standards ☐ Yes ☒ No Depth of Completed Well 40 ft.



(5) WELL TESTS:

☐ Pump ☐ Bailer ☐ Air ☐ Flowing Artesian
 Permeability _____ Yield _____ GPM
 Conductivity _____ PH _____
 Temperature of water _____ °F/C Depth artesian flow found _____ ft.
 Was water analysis done ☒ Yes ☐ No
 By whom? _____
 Depth of strata to be analyzed. From _____ ft. to _____ ft.
 Remarks: _____

Name of supervising Geologist/Engineer _____

(6) LOCATION OF WELL By legal description:

County MARION Latitude _____ Longitude _____
Township 8 (N or S) Range 3 (E or W) Section 16
SE 1/4 of SE 1/4 of above section.
Street address of well location LOWE OAK &
MILOREO
Tax lot number of well location ROW
ATTACH MAP WITH LOCATION IDENTIFIED. Map shall include
approximate scale and north arrow.

(7) STATIC WATER LEVEL:

_____ Ft. below land surface Date _____
Artesian Pressure NONE lb/sq. in. Date _____

(8) WATER BEARING ZONES:

Depth at which water was first found _____

| From | To | Est. Flow Rate | SWL |
|------|----|----------------|-----|
| | | | |
| | | | |
| | | | |
| | | | |

(9) WELL LOG:

Ground Elevation _____

[illegible]

| | | | | | | | |
|--------------|----|---|----|-----------|----|---|----|
| Date started | 10 | 9 | 01 | Completed | 10 | 9 | 01 |
|--------------|----|---|----|-----------|----|---|----|

(unbonded) Monitor Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

Signed _____ MWC Number _____
Date _____

(bonded) Monitor Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed Wan Chen MWC Number 10459 Date 10/12/01

ORIGINAL COPY – WATER RESOURCES DEPARTMENT

FIRST COPY – CONSTRUCTOR SECOND COPY – CUSTOMER


TOPOI map printed on 10/03/01 from "Oregon.tpo" and "Untitled.tpg"

123°05'00" W

123°04'00" W

123°03'00" W

WGS84 123°02'00" W



TN
17°

0 1000 FEET 0 500 1000 METRES
Printed from TOPOI ©2000 National Geographic Holdings (www.topo.com)

Instructions for completing this report are on the last page of this form.


Start Card # 140889

Signed Wan Cu MWC Number 1259
Date 10/14/02
SECOND COPY-CONSTRUCTOR THIRD COPY-CUSTOMER

Name of supervising Geologist/Engineer _____
ORIGINAL & FIRST COPY-WATER RESOURCES DEPARTMENT

IMARI 56939

56938
56939



↑ N

RECEIVED

DEC 16 2004

WATER RESOURCES DEPT
SALEM, OREGON

RECEIVED

NOV - 8 2001

WATER RESOURCES DEPT.
SALEM, OREGON

STATE OF OREGON
WATER SUPPLY WELL REPORT

(as required by ORS 537.765)

WELL I.D. # L 62635
START CARD # 155923

Instructions for completing this report are on the last page of this form.

(1) LAND OWNER

Well Number _____
Name Don Company Inc.
Address 390 Holder Ln SE
City Salem State OR Zip 97306

(2) TYPE OF WORK

☒ New Well ☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment

(3) DRILL METHOD:

☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger
☐ Other _____

(4) PROPOSED USE:

☒ Domestic ☐ Community ☐ Industrial ☒ Irrigation
☐ Thermal ☐ Injection ☐ Livestock ☐ Other _____

(5) BORE HOLE CONSTRUCTION:

Special Construction approval ☐ Yes ☒ No Depth of Completed Well 314 ft.
Explosives used ☐ Yes ☒ No Type _____ Amount _____

| HOLE | | | SEAL | | | Sacks or pounds |
|----------|------|-----|----------|------|-----|-----------------|
| Diameter | From | To | Material | From | To | |
| 10 | 0 | 56 | Cement | -7 | 237 | 30 + 5% bent. |
| 8 | 56 | 237 | | | | |
| 6.5 | 237 | 304 | | | | |
| 6 | 304 | 314 | | | | |

How was seal placed: Method ☐ A ☐ B ☒ C ☒ D ☐ E
☐ Other _____

Backfill placed from _____ ft. to _____ ft. Material _____

Gravel placed from _____ ft. to _____ ft. Size of gravel _____

(6) CASING/LINER:

| | Diameter | From | To | Gauge | Steel | Plastic | Welded | Threaded |
|---------|----------|------|-----|-------|-------------------------------------|-------------------------------------|-------------------------------------|--------------------------|
| Casing: | 6 in | +1 | 237 | 25 | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> |
| | | | | | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| | | | | | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| | | | | | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| Liner: | 4 in | 0 | 314 | 7/16 | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| | | | | | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |

Drive Shoe used ☐ Inside ☐ Outside ☒ None

Final location of shoe(s) _____

(7) PERFORATIONS/SCREENS:

☒ Perforations

Method Saw

☐ Screens

Type _____

Material _____

| From | To | Slot size | Number | Diameter | Tele/pipe size | Casing | Liner |
|------|-----|-----------|--------|----------|----------------|--------------------------|-------------------------------------|
| 274 | 309 | 1/2 x 6 | 56 | | | <input type="checkbox"/> | <input checked="" type="checkbox"/> |
| | | | | | | <input type="checkbox"/> | <input type="checkbox"/> |
| | | | | | | <input type="checkbox"/> | <input type="checkbox"/> |
| | | | | | | <input type="checkbox"/> | <input type="checkbox"/> |

(8) WELL TESTS: Minimum testing time is 1 hour

☐ Pump

☐ Bailer

☒ Air

☐ Flowing
☐ Artesian

| Yield gal/min | Drawdown | Drill stem at | Time |
|---------------|----------|---------------|-------|
| 20 | | 312 | 1 hr. |
| | | | |
| | | | |

Temperature of water 53 ± Depth Artesian Flow Found _____

Was a water analysis done? ☐ Yes By whom _____

Did any strata contain water not suitable for intended use? ☐ Too little

☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other _____

Depth of strata: _____

(9) LOCATION OF WELL by legal description:

County Marion Latitude _____ Longitude _____
Township 8-S N or S Range 3-W E or W. WM.
Section 16 SE 1/4 SE 1/4
Tax Lot 400 Lot _____ Block _____ Subdivision _____
Street Address of Well (or nearest address) Same as #1

(10) STATIC WATER LEVEL:

249 ft. below land surface. Date 3-19-03
Artesian pressure _____ lb. per square inch Date _____

(11) WATER BEARING ZONES:

| From | To | Estimated Flow Rate | SWL |
|------|-----|---------------------|-----|
| 16 | 48 | | |
| 122 | 140 | 2 | 105 |
| 252 | 314 | 20 | 249 |

(12) WELL LOG:

Ground Elevation _____

| Material | From | To | SWL |
|-----------------------------|------|-----|-----|
| Red Soil | 1 | 6 | |
| Red Clay | 6 | 16 | |
| Brown Clay Soft | 16 | 48 | |
| Red Clay hard | 48 | 54 | |
| Semi-Weathered basalt | 54 | 76 | |
| Hard gray basalt | 76 | 106 | |
| Med black basalt | 106 | 122 | |
| Very Weathered brown basalt | 122 | 140 | |
| Gray basalt - hard | 140 | 240 | |
| Semi-Weathered basalt | 240 | 252 | |
| Porous black basalt | 252 | 314 | |
| caving | | | |

RECEIVED

APR 03 2003

WATER RESOURCES DEPT.
SALEM, OREGON

Date started 3-12-03 Completed 3-19-03

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

WWC Number 1629

Signed [Signature] Date 3-20-03

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

WWC Number 1273

Signed Floyd J. Suppe Date 3-20-03

APPENDIX H

EXISTING INFORMATION
SITE 16 - CHAMPION HILL RESERVOIR

DRAFT

(START CARD) # 22888

9809C 3/88

MARI
17405

8S/36/28 ac

(START CARD) # 31621

Well Number:

Name William P Long
Address 11101 Steinkamp Rd
City Burnsville State Or. Zip 97325

☒ New Well ☐ Deepen ☐ Recondition ☐ Abandon

☒ Rotary Air ☐ Rotary Mud ☐ Cable
☐ Other _____

☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☐ Other _____

Special Construction approval Yes No Depth of Completed Well 270 ft.

Explosives used ☐ Yes ☒ No Type _____ Amount _____

| HOLE | | | Material | SEAL | | Amount sacks or pounds |
|----------|------|-----|----------|------|----|---------------------------|
| Diameter | From | To | | From | To | |
| 10 | 0 | 20 | Cement | 0 | 20 | 8 |
| 8 | 20 | 75 | Cement | 20 | 75 | 10 |
| 6 | 75 | 270 | | | | |

How was seal placed: Method ☐ A ☐ B ☒ C ☐ D ☐ E
☐ Other _____

Backfill placed from _____ ft. to _____ ft. Material _____
Gravel placed from _____ ft. to _____ ft. Size of gravel _____

| | Diameter | From | To | Gauge | Steel | Plastic | Welded | Threaded |
|------------------|--------------|------------|------------|-------------------------------------|--------------------------|-------------------------------------|--------------------------|----------|
| Casing: <u>6</u> | <u>1 1/2</u> | <u>7.5</u> | <u>200</u> | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input checked="" type="checkbox"/> | <input type="checkbox"/> | |
| | | | | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | |
| | | | | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | |
| | | | | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | |
| Liner: _____ | | | | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | |
| | | | | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | |

Final location of shoe(s)

☐ Perforations Method _____

☐ Screens Type _____ Material _____

[illegible]

☐ Pump ☐ Bailer ☒ Air ☐ Flowing Artesian

| Yield gal/min | Drawdown | Drill stem at | Time |
|---------------|----------|---------------|-------|
| 30 | | 26.5' | 1 hr. |
| | | | |
| | | | |

Temperature of water 52 Depth Artesian Flow Found _____

Was a water analysis done? ☐ Yes By whom _____

Did any strata contain water not suitable for intended use? ☐ Too little

☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other

Depth of strata: _____

County Marion Latitude _____ Longitude _____
Township 8.3 N or S. Range 34 E or W. WM.
Section 28 S.W. $\frac{1}{4}$ N.E. $\frac{1}{4}$
Tax Lot _____ Lot _____ Block _____ Subdivision _____
Street Address of Well (or nearest address) 173 Hyle Rd. S.E.
Salem, Or.

1.32 ft. below land surface. Date July 24, 1997
Artesian pressure _____ lb. per square inch. Date _____

Depth at which water was first found 180'

| From | To | Estimated Flow Rate | SWL |
|------|-----|---------------------|-----|
| 180' | 270 | 30 G.P.M. | 132 |
| | | | |
| | | | |

Ground elevation

[illegible]

RECEIVED

~~AUG 05 1991~~

WATER RESOURCES DEPT
SALEM, OREGON

Date started July 18, 1991 Completed July 27, 1991

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief.

Signed _____ WWC Number _____
Date _____

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. all work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief.

belief. 2/11/92 WWC Number 75
Signed [Signature] Date: July 24 1992

85/3w/28aa
25562

WATER RESOURCES DISTRICT CARD)

25562

Depth of strata: _____

Signed George Robinson WWC Number 06115
Date 3-24-92

MONITORING WELL REPORT

(as required by ORS 537.765 & OAR 690-240-095)

Instructions for completing this report are on the last page of this form.

MARI 58542
58542

Well ID#

Start Card #

L73355
16790

(1) OWNER/PROJECT

WELL NO. P-1

Name Eclain CammackAddress 411 Hyla Road SECity SalemState ORZip 97306

(2) TYPE OF WORK

- ☒ New construction ☐ Alteration (Repair/Recondition)
☐ Conversion ☐ Deepening ☐ Abandonment

(3) DRILLING METHOD

- ☐ Rotary Air ☒ Rotary Mud ☐ Cable
☐ Hollow Stem Auger ☐ Other Piezometer

(6) LOCATION OF WELL By legal description:

County Marion Latitude _____ Longitude _____
 Township 8 (N or S) Range 3 (E or W) Section 28
SE 1/4 of NE 1/4 of above section.


Street address of well location West of Champion Hill Rd SE
1800' North of Intersection of Hyla Rd SE

Tax lot number of well location 230

ATTACH MAP WITH LOCATION IDENTIFIED. Map shall include approximate scale and north arrow.

(4) BORE HOLE CONSTRUCTION:

Special Standards Yes No ☐ ☒ Depth of Completed Well 25 ft.



(7) STATIC WATER LEVEL:

NOT OBSERVED Ft. below land surface Date _____
 Artesian Pressure _____ lb./sq. in. Date _____

(8) WATER BEARING ZONES:

| From | To | Est. Flow Rate | SWL |
|--------------|----|----------------|-----|
| NOT OBSERVED | | | |
| | | | |
| | | | |
| | | | |

(9) WELL LOG:

Ground Elevation _____

| Material | From | To | SWL |
|----------------------|------|----|-----|
| Silt | 0 | 25 | |
| RECEIVED | | | |
| DEC 02 2004 | | | |
| WATER RESOURCES DEPT | | | |
| SALEM, OREGON | | | |
| RECEIVED | | | |
| MAR 11 2005 | | | |
| WATER RESOURCES DEPT | | | |
| SALEM, OREGON | | | |

Date started 11/10/04 Completed 11/10/04

(unbonded) Monitor Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

Signed Carlos Anguiano MWC Number 10500
 Date 12/1/04

(bonded) Monitor Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed [Signature] MWC Number 10442
 Date 12/1/04

(5) WELL TESTS:

☐ Pump ☐ Bailer ☐ Air ☐ Flowing Artesian
 Permeability _____ Yield _____ GPM
 Conductivity _____ pH _____
 Temperature of water 74.0 °F Depth artesian flow found _____ ft.
 Was water analysis done? ☐ Yes ☒ OBSERVED
 By whom? _____
 Depth of strata to be analyzed. From _____ ft. to _____ ft.
 Remarks: _____

Name of supervising Geologist/Engineer _____

ORIGINAL COPY - WATER RESOURCES DEPARTMENT

FIRST COPY - CONSTRUCTOR

SECOND COPY - CUSTOMER

STATE OF OREGON
GEOTECHNICAL HOLE REPORT
(as required by OAR 690-240-035)

(1) OWNER/PROJECT: Hole Number B-3
Name Ecluin Cammack
Address 411 Hyle Road SE
City Salem State OR Zip 97301

(2) TYPE OF WORK
☒ New ☐ Deepening ☐ Alteration (repair/recondition) ☒ Abandonment

(3) CONSTRUCTION:
☐ Rotary Air ☐ Hand Auger ☐ Hollow Stem Auger
☒ Rotary Mud ☐ Cable Tool ☐ Push Probe ☐ Other

(4) TYPE OF HOLE:
☒ Uncased Temporary ☐ Cased Permanent
☐ Uncased Permanent ☐ Slope Stability ☐ Other

(5) USE OF HOLE:
Geotechnical Study

(6) BORE HOLE CONSTRUCTION:
Special Construction approval ☐ Yes ☒ No Depth of Completed Hole 65 ft.

| HOLE | | | SEAL | | | Sacks or pounds |
|----------|------|----|----------|------|----|-----------------|
| Diameter | From | To | Material | From | To | |
| 5 | 0 | 65 | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Backfill placed from _____ ft. to _____ ft. Material _____
Filter Pack placed from _____ ft. to _____ ft. Size of pack _____

(7) CASING/SCREEN:

| | Diameter | From | To | Gauge | Steel | Plastic | Welded | Threaded |
|-----------|----------|------|----|-------|-------------------------------------|--------------------------|--------------------------|--------------------------|
| Casing: | | | | | <input checked="" type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| | | | | | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| | | | | | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| Screen: | | | | | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| | | | | | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| Slot size | | | | | | | | |

(8) WELL TEST:
☐ Pump ☐ Bailor ☐ Air ☐ Flowing Artesian
Permeability _____ Yield _____ GPM _____
Conductivity _____ PH _____
Temperature of water _____ °F/C Depth artesian flow found _____ ft.
Was water analysis done? ☐ Yes ☒ No
By whom? _____
Depth of strata analyzed. From _____
Remarks: _____

RECEIVED

MAR 11 2005

WATER RESOURCES DEPT
SALEM, OREGON

(9) LOCATION OF HOLE by legal description:
County Marietta Latitude _____ Longitude _____
Township 8 N 3 Range 3 E of W. WM.
Section 28 SE 1/4 NE 1/4
Tax Lot 230 Lot _____ Block _____ Subdivision _____
Street Address of Well (or nearest address) West of Champion Hill
Rd SE 1800' North of Intersection with Hyle Rd
Map with location identified must be attached

(10) STATIC WATER LEVEL:
_____ ft. below land surface. Date _____
Artesian pressure _____ lb. per square inch. Date _____

(11) SUBSURFACE LOG:

Ground Elevation _____

| Material Description | From | To | SWL |
|--------------------------|-----------|-----------|-----|
| <u>Silt</u> | <u>0</u> | <u>63</u> | |
| <u>Decomposed Basalt</u> | <u>63</u> | <u>65</u> | |
| | | | |
| | | | |
| | | | |
| | | | |

Date Started 11/10/04 Date Completed 11/10/04

(12) ABANDONMENT LOG:

| Material Description | From | To | Sacks or Pounds |
|----------------------|----------|-----------|-----------------|
| <u>Bentonite</u> | <u>0</u> | <u>65</u> | <u>23 bags</u> |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

RECEIVED
DEC 02 2004
WATER RESOURCES DEPT
SALEM, OREGON

Date started 11/10/04 Date Completed 11/10/04

Professional Certification
(to be signed by a licensed water supply or monitoring well constructor, or Oregon registered geologist or civil engineer).
I accept responsibility for the construction, alteration, or abandonment work performed during the construction dates reported above. All work performed during this time is in compliance with Oregon's geotechnical hole construction standards. This report is true to the best of my knowledge and belief.

License or Registration Number 10500
Signed Carlos Angiano Date 12/1/04
Affiliation _____

THIS REPORT MUST BE SUBMITTED TO THE WATER RESOURCES DEPARTMENT WITHIN 30 DAYS OF COMPLETION OF WORK

ORIGINAL -- WATER RESOURCES DEPARTMENT FIRST COPY -- CONSTRUCTOR SECOND COPY -- CUSTOMER

STATE OF OREGON
GEOTECHNICAL HOLE REPORT
(as required by OAR 690-240-035)

(1) OWNER/PROJECT: Hole Number B-2
Name Eclwin Cammack
Address 411 Hyla Road SE
City Salem State OR Zip 97302
(2) TYPE OF WORK
☒ New ☐ Deepening ☐ Alteration (repair/recondition) ☒ Abandonment
(3) CONSTRUCTION:
☐ Rotary Air ☐ Hand Auger ☐ Hollow Stem Auger
☒ Rotary Mud ☐ Cable Tool ☐ Push Probe ☐ Other
(4) TYPE OF HOLE:
☒ Uncased Temporary ☐ Cased Permanent
☐ Uncased Permanent ☐ Slope Stability ☐ Other
(5) USE OF HOLE:
Geotechnical Study

(6) BORE HOLE CONSTRUCTION:
Special Construction approval ☐ Yes ☒ No Depth of Completed Hole 50 ft.

| HOLE | | | SEAL | | | Sacks or pounds |
|----------|------|----|----------|------|----|-----------------|
| Diameter | From | To | Material | From | To | |
| 5 | 0 | 50 | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Backfill placed from _____ ft. to _____ ft. Material _____
Filter Pack placed from _____ ft. to _____ ft. Size of pack _____

(7) CASING/SCREEN:

| Diameter | From | To | Gauge | Steel | Plastic | Welded | Threaded |
|----------|------|----|-------|--------------------------|--------------------------|--------------------------|--------------------------|
| Casing: | | | | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| | | | | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| | | | | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| Screen: | | | | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| | | | | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| | | | | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |

Slot size _____

(8) WELL TEST:
☐ Pump ☐ Bailer ☐ Air ☐ Flowing Artesian
Permeability _____ Yield _____ GPM _____
Conductivity _____ PH _____
Temperature of water _____ °F/C Depth artesian flow found _____ ft.
Was water analysis done? ☐ Yes ☒ No
By whom? _____
Depth of strata analyzed. From _____
Remarks: _____

(9) LOCATION OF HOLE by legal description:
County Marion Latitude _____ Longitude _____
Township 8 N 3 Range 3 E W WM.
Section 28 1/4 SE 1/4 NE 1/4
Tax Lot 230 Lot _____ Block _____ Subdivision _____
Street Address of Well (or nearest address) West of Champion Hill Rd SE 1800' North of Intersection Hyla Rd SE
Map with location identified must be attached

(10) STATIC WATER LEVEL:
_____ ft. below land surface. Date _____
Artesian pressure _____ lb. per square inch. Date _____

(11) SUBSURFACE LOG:
Ground Elevation _____

| Material Description | From | To | SWL |
|----------------------|------|----|-----|
| Sills | 0 | 40 | |
| Decomposed Basalts | 40 | 50 | |
| | | | |
| | | | |
| | | | |
| | | | |

Date Started 11/9/04 Date Completed 11/9/04

(12) ABANDONMENT LOG:

| Material Description | From | To | Sacks or Pounds |
|----------------------|------|----|-----------------|
| Ben Enik | 0 | 50 | 20 bags |
| | | | |
| | | | |
| | | | |
| | | | |

Date started 11/11/04 Date Completed 11/11/04

Professional Certification

(to be signed by a licensed water supply or monitoring well constructor, or Oregon registered geologist or civil engineer).

I accept responsibility for the construction, alteration, or abandonment work performed during the construction dates reported above. All work performed during this time is in compliance with Oregon's geotechnical hole construction standards. This report is true to the best of my knowledge and belief.


License or Registration Number 10500
Signed Carlos Angiano Date 12/1/07
Affiliation _____

WATER RESOURCES DEPT

THIS REPORT MUST BE SUBMITTED TO THE WATER RESOURCES DEPARTMENT WITHIN 30 DAYS OF COMPLETION OF WORK

ORIGINAL - WATER RESOURCES DEPARTMENT FIRST COPY - CONSTRUCTOR SECOND COPY - CUSTOMER

Oregon, United States, North America



RECEIVED
MAR 11 2005
WATER RESOURCES DEPT
SALEM, OREGON

Oregon, United States, North America

• 15.2
• 18.3

Hyla Rd SE

Champion Hill Rd SE

0 yds 50 100 150 200

DRAFT

RECEIVED

MAY - 2 2005

WATER RESOURCES DEPT
SALEM, OREGON

APPENDIX I

EXISTING INFORMATION
SITE 18 - DEER PARK
PUMP STATION

STATE OF OREGON
MONITORING WELL REPORT

MARI 53734

Received Date 01/04/1999
Well ID Tag# L 29739
Start Card # 117263

(as required by ORS 537.765 & OAR 690-240-095) Instructions for completing this report are on the last page of this form.

(1) OWNER/PROJECT

Name **OREGON DEPARTMENT OF CORRECTIONS**
Street **2575 CENTER ST NE**
City **SALEM** State **OR** Zip **97310**

Well No. **29739**
Co Job No. **2422**

(2) TYPE OF WORK

☒ New Construction ☐ Alter (Recondition) ☐ Alter (Repair)
☐ Conversion ☐ Deepening ☐ Abandonment

(3) DRILLING METHOD

☐ Rotary Air ☐ Rotary Mud ☐ Cable
☒ Hollow Stem Auger Other *****

(4) BORE HOLE CONSTRUCTION

Special Standards ☐ Depth of completed well **20** ft.

| Diameter | From | To | Material | Begin Depth | End Depth | Material Amount | Units |
|----------|------|----|-----------|-------------|-----------|-----------------|-------|
| 10.00 | 0.00 | 20 | Concrete | 0.00 | 1.00 | 2.00 | S |
| | | | Bentonite | 1.00 | 8.00 | 6.00 | S |

Vault

0 ft. Casing Diameter Liner ☐
1 TO

| Monument | Casing or Liner | Diameter | Begin Depth | End Depth | Gauge | Material | Construction Weld | Threaded | Location Of Shoe |
|----------|-----------------|----------|-------------|-----------|-------|----------|-------------------|----------|------------------|
| ft. | | 2.00 | | | | Plastic | | | |
| TO | | | | | | | | | |
| ft. | | | | | | | | | |

Seal

| TO | From | To | Material | Amount | Seal Grout Weight | Units |
|-----|------|------|-----------|--------|-------------------|-------|
| ft. | 0.00 | 1.00 | Concrete | 2.00 | | S |
| ft. | 1.00 | 8.00 | Bentonite | 6.00 | | S |

Filter Pack Screen ☐

| Diameter | From | To | Gauge | Material | Type | Slot Size |
|----------|------|----|-------|----------|------|-----------|
| 10 | 20 | | | PL | | .010 |

Filter Pack
Material SA
Size 20.00 in.

(5) WELL TEST

Permeability Yield
Conductivity PH
Temperature of water **53** °F/C Depth artesian flow found ft.

Was water analysis done? ☒

By Whom? **PBS ENVIRONMENTAL**

Depth of strata to be analyzed. From ft. to ft.

Remarks

Name of supervising Geologist/Engineer

(6) LOCATION OF WELL By legal description

County
Township **8.00 S** Range **2.00 W** Section **18**
1. **SE** 1/4 of **NE** 1/4 of above section.
Legal Desc:

2. Either Street address of well location

5485 TURNER RD SE

or Tax lot number of well location **100**

3. ATTACH MAP WITH LOCATION IDENTIFIED. Map shall include approximate scale and north arrow.

(7) STATIC WATER LEVEL

15.0 Ft. below land surface. Date **/15/1998**
Artesian Pressure lb/sq. in. Date

(8) WATER BEARING ZONES

Depth at which water was first found **15** ft.

| From | To | Est. Flow Rate | SWL |
|------|----|----------------|-----|
| 15 | 20 | | 15 |

(9) WELL LOG

Ground elevation ft.

| Material | From | To | SWL |
|------------|------|----|-----|
| SILTY CLAY | 0 | 15 | 15 |
| SANDY CLAY | 15 | 20 | |

Date started **12/10/1998** Completed **12/10/1998**

(unbonded) Monitor Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to the best knowledge and belief.

Signed By **PABLO ARMANDO**

MWC Number **10440**

Date

(bonded) Monitor Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief.

Signed By **GREG MCINNIS**

MWC Number **10011**

Date

STATE OF OREGON
MONITORING WELL REPORT

MARI 53735

Received Date 01/04/1999
Well ID Tag# L 29740
Start Card # 117264

(as required by ORS 537.765 & OAR 690-240-095)

Instructions for completing this report are on the last page of this form.

(1) OWNER/PROJECT

Well No. 29740
Co Job No. 2422

Name OREGON DEPARTMENT OF CORRECTIONS
Street 2575 CENTER ST NE
City SALEM State OR Zip 97310

(2) TYPE OF WORK

- ☒ New Construction ☐ Alter (Recondition) ☐ Alter (Repair)
☐ Conversion ☐ Deepening ☐ Abandonment

(3) DRILLING METHOD

- ☐ Rotary Air ☐ Rotary Mud ☐ Cable
☒ Hollow Stem Auger Other *****

(4) BORE HOLE CONSTRUCTION

Special Standards ☐ Depth of completed well 23 ft.

| Diameter | From | To | Material | Begin Depth | End Depth | Material Amount | Units |
|----------|------|----|-----------|-------------|-----------|-----------------|-------|
| 10.00 | 0.00 | 23 | Concrete | 0.00 | 1.00 | 2.00 | S |
| | | | Bentonite | 1.00 | 11.00 | 7.00 | S |

Vault

0 ft. Casing Diameter
1 TO

Liner ☐

| Monument | ft. | Casing or Liner | Diameter | Begin Depth | End Depth | Gauge | Material | Construction | Weld | Threaded | Location Of Shoe |
|----------|-----|-----------------|----------|-------------|-----------|-------|----------|--------------|------|----------|------------------|
| | ft. | | 2.00 | | | | Plastic | | | | |

TO
ft.

Seal

| TO | ft. | From | To | Material | Amount | Seal Grout Weight | Units |
|----|-----|------|-------|-----------|--------|-------------------|-------|
| | ft. | 0.00 | 1.00 | Concrete | 2.00 | | S |
| | | 1.00 | 11.00 | Bentonite | 7.00 | | S |

Filter Pack

Screen ☐

| TO | ft. | Diameter | From | To | Gauge | Material | Type | Slot Size |
|----|-----|----------|------|----|-------|----------|------|-----------|
| 23 | ft. | | 13 | 23 | | PL | | .010 |

Filter Pack

Material SA
Size 20.00 in.

(5) WELL TEST

Permeability Yield
Conductivity PH
Temperature of water 53 °F/C Depth artesian flow found ft.

Was water analysis done? ☒

By Whom? PBS ENVIRONMENTAL

Depth of strata to be analyzed. From ft. to ft.

Remarks

Name of supervising Geologist/Engineer

(6) LOCATION OF WELL By legal description

County
Township 8.00 S Range 2.00 W Section 18

1. SE 1/4 of NE 1/4 of above section.

Legal Desc:

2. Either Street address of well location

5485 TURNER RD SE

or Tax lot number of well location 100

3. ATTACH MAP WITH LOCATION IDENTIFIED. Map shall include approximate scale and north arrow.

(7) STATIC WATER LEVEL

18.0 Ft. below land surface. Date /10/1998
Artesian Pressure lb/sq. in. Date

(8) WATER BEARING ZONES

Depth at which water was first found 18 ft.

| From | To | Est. Flow Rate | SWL |
|------|----|----------------|-----|
| 18 | 23 | | 18 |

(9) WELL LOG

Ground elevation ft.

| Material | From | To | SWL |
|--------------|------|----|-----|
| SILTY CLOY | 0 | 16 | |
| GRAVELY CLAY | 16 | 23 | 18 |

Date started 12/10/1998 Completed 12/10/1998

(unbonded) Monitor Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to the best knowledge and belief.

MWC Number 10440

Signed By PABLO ARMANDO

Date

(bonded) Monitor Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief.

MWC Number 10011

Signed By GREG MCINNIS

Date

STATE OF OREGON
MONITORING WELL REPORT

MARI 53736

Received Date 01/04/1999
Well ID Tag# L 29741
Start Card # 117265

(as required by ORS 537.765 & OAR 690-240-095)

Instructions for completing this report are on the last page of this form.

(1) OWNER/PROJECT

Well No. 29741
Co Job No. 2422

Name OREGON DEPARTMENT OF CORRECTIONS
Street 2575 CENTER ST NE
City SALEM State OR Zip 97310

(2) TYPE OF WORK

☒ New Construction ☐ Alter (Recondition) ☐ Alter (Repair)
☐ Conversion ☐ Deepening ☐ Abandonment

(3) DRILLING METHOD

☐ Rotary Air ☐ Rotary Mud ☐ Cable
☒ Hollow Stem Auger Other *****

(4) BORE HOLE CONSTRUCTION

Special Standards ☐ Depth of completed well 16 ft.

| Diameter | From | To | Material | Begin Depth | End Depth | Material Amount | Units |
|----------|------|----|-----------|-------------|-----------|-----------------|-------|
| 10.00 | 0.00 | 16 | Concrete | 0.00 | 1.00 | 2.00 | S |
| | | | Bentonite | 1.00 | 4.00 | 3.00 | S |

Vault

0 ft.
1 TO

Casing Diameter

Liner ☐

| Monument | Casing or Liner | Diameter | Begin Depth | End Depth | Gauge | Material | Construction Weld | Location Threaded | Of Shoe |
|----------|-----------------|----------|-------------|-----------|-------|----------|-------------------|-------------------------------------|---------|
| ft. | | 2.00 | | | | Plastic | | <input checked="" type="checkbox"/> | |
| TO | | | | | | | | | |
| ft. | | | | | | | | | |

Seal

ft.
TO

| From | To | Material | Amount | Seal Grout Weight | Units |
|------|------|-----------|--------|-------------------|-------|
| 0.00 | 1.00 | Concrete | 2.00 | | S |
| 1.00 | 4.00 | Bentonite | 3.00 | | S |

Filter Pack

Screen ☐

4 ft.
TO
16 ft.

| Diameter | From | To | Gauge | Material | Type | Slot Size |
|----------|------|----|-------|----------|------|-----------|
| | 6 | 16 | | PL | | .010 |

Filter Pack

Material SA

Size 20.00 in.

(5) WELL TEST

Permeability Yield
Conductivity PH
Temperature of water 53 °F/C Depth artesian flow found ft.

Was water analysis done? ☒

By Whom? PBS ENVIRONMENTAL

Depth of strata to be analyzed. From ft. to ft.

Remarks

Name of supervising Geologist/Engineer

(6) LOCATION OF WELL By legal description

County

Township 8.00 S Range 2.00 W Section 18

1. SE 1/4 of NE 1/4 of above section.

Legal Desc:

2. Either Street address of well location

5485 TURNER RD SE

or Tax lot number of well location 100

3. ATTACH MAP WITH LOCATION IDENTIFIED. Map shall include approximate scale and north arrow.

(7) STATIC WATER LEVEL

15.0 Ft. below land surface. Date /10/1998
Artesian Pressure lb/sq. in. Date

(8) WATER BEARING ZONES

Depth at which water was first found 15 ft.

| From | To | Est. Flow Rate | SWL |
|------|----|----------------|-----|
| 15 | 16 | | 15 |

(9) WELL LOG

Ground elevation ft.

| Material | From | To | SWL |
|------------|------|----|-----|
| SILTY CLAY | 0 | 12 | |
| CLAY | 12 | 16 | 15 |

Date started 12/10/1998 Completed 12/10/1998

(unbonded) Monitor Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to the best knowledge and belief.

Signed By PABLO ARMANDO

MWC Number 10440

Date

(bonded) Monitor Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief.

Signed By GREG MCINNIS

MWC Number 10011

Date


Marion

S3734-

S3734

SITE MAP

Mill Creek
Corrections Facility



5485 Turner Rd.

Gate

Parking

Parking

117264 ⊕



117265 ⊕

Building

⊕ 117263

GEOTECHNICAL HOLE REPORT

MARI 53757

Received date 01/15/1999

(as required by OAR 690-240-035)

(1) OWNER/PROJECT

Hole No.
Co. Job No. **B-1**

Name **OREGON DEPARTMENT OF CORRECTION**

Street **2575 CENTER ST NE**

City **SALEM** State **OR** Zip **97310**

(2) TYPE OF WORK

- ☒ New ☐ Alter (Recondition) ☐ Alter (Repair)
- ☐ Deepening ☒ Abandonment

(3) CONSTRUCTION

- ☐ Rotary Air ☐ Hand Auger ☐ Hollow Stem Auger
- ☐ Rotary Mud ☐ Cable Tool ☒ Push Probe ☐ Other

(4) TYPE OF HOLE

- ☒ Uncased Temporary ☐ Cased Permanent
- ☐ Uncased Permanent ☐ Slope Stability ☐ Other

(5) USE OF HOLE

SOIL COLLECTION

(6) BORE HOLE CONSTRUCTIONSpecial Standards ☐ Depth of completed well **16** ft.

HOLE

| Diameter | From | To |
|-------------|-------------|-----------|
| 2.00 | 0.00 | 16 |

SEAL

| From | To | Material | Amount | Seal Grout Weight | Units |
|-------------|--------------|------------------|--------------|-------------------|----------|
| 0.00 | 16.00 | Bentonite | 22.00 | | P |

Backfill placed from ft. TO ft. Material

Filter pack placed from ft. TO ft. Size in.

(7) CASING/SCREENScreen ☐(8) WELL TEST

Permeability Yield GPM

Conductivity PH

Temperature of water °F/C Depth artesian flow found ft.

Was water analysis done? ☐

By Whom?

Depth of strata to be analyzed. From ft. to ft.

Remarks

Name of supervising Geologist/Engineer

(9) LOCATION OF HOLE By legal description

County **Marion** Latitude Longitude

Township **8.00 S** Range **2.00 W**

Section **18** **SE 1/4 NE 1/4**

Tax lot **100** Lot Block Subdivision

Legal desc:

Street Address of Well (or nearest address)

5485 TURNER RD SE

MAP with location identified must be attached

(10) STATIC WATER LEVEL

Ft. below land surface. Date

Artesian Pressure lb/sq. in. Date

(11) SUBSURFACE LOG

Ground Elevation ft.

| Material | From | To | SWL |
|-------------------|-----------|-----------|-----|
| SILTY CLAY | 0 | 10 | |
| BASALT | 10 | 16 | |

Date started **12/15/1998** Completed **12/15/1998**(12) ABANDONMENT LOG

Date started Completed

Professional Certification

(to be signed by a licensed water supply or monitoring well constructor, or registered geologist or civil engineer).

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon geotechnical hole construction standards. This report is true to the best of my knowledge and belief.

License or Registration Number **10402**Signed By **KEITH VIDOS**

Date

Affiliation **GEO TECH EXPLORATIONS**

GEOTECHNICAL HOLE REPORT

MARI 53758

Received date 01/15/1999

(as required by OAR 690-240-035)

(1) OWNER/PROJECTHole No.
Co. Job No. **B-2**Name **OREGON DEPARTMENT OF CORRECTIONS**
Street **2575 CENTER ST NE**
City **SALEM** State **OR** Zip **97310**(2) TYPE OF WORK

- ☒
- New
- ☐
- Alter (Recondition)
- ☐
- Alter (Repair)
-
- ☐
- Deepening
- ☒
- Abandonment

(3) CONSTRUCTION

- ☐
- Rotary Air
- ☐
- Hand Auger
- ☐
- Hollow Stem Auger
-
- ☐
- Rotary Mud
- ☐
- Cable Tool
- ☒
- Push Probe
- ☐
- Other

(4) TYPE OF HOLE

- ☒
- Uncased Temporary
- ☐
- Cased Permanent
-
- ☐
- Uncased Permanent
- ☐
- Slope Stability
- ☐
- Other

(5) USE OF HOLE

SOIL COLLECTION

(6) BORE HOLE CONSTRUCTIONSpecial Standards ☐ Depth of completed well **16** ft.

| HOLE | Diameter | | From | | To | |
|------|----------|-------|-----------|--------|-------------------|-------|
| | 2.00 | 0.00 | 0.00 | 16.00 | 16.00 | |
| SEAL | From | To | Material | Amount | Seal Grout Weight | Units |
| | 0.00 | 16.00 | Bentonite | 22.00 | | P |

Backfill placed from _____ ft. TO _____ ft. Material _____
Filter pack placed from _____ ft. TO _____ ft. Size _____ in.(7) CASING/SCREENScreen ☐(8) WELL TESTPermeability _____ Yield _____ GPM
Conductivity _____ PH _____
Temperature of water _____ °F/C Depth artesian flow found _____ ft.Was water analysis done? ☐

By Whom? _____

Depth of strata to be analyzed. From _____ ft. to _____ ft.

Remarks _____

Name of supervising Geologist/Engineer _____

(9) LOCATION OF HOLE By legal descriptionCounty **Marion** Latitude _____ Longitude _____
Township **8.00 S** Range **2.00 W**
Section **18** **SE 1/4 NE 1/4**
Tax lot **100** Lot _____ Block _____ Subdivision _____

Legal desc: _____

Street Address of Well (or nearest address)

5485 TURNER RD SE

MAP with location identified must be attached

(10) STATIC WATER LEVELFt. below land surface. _____ Date _____
Artesian Pressure _____ lb/sq. in. _____ Date _____(11) SUBSURFACE LOG

Ground Elevation _____ ft.

| Material | From | To | SWL |
|------------------|------|----|-----|
| SILTY CLAY | 0 | 6 | |
| WEATHERED BASALT | 6 | 16 | |

Date started **12/15/1998** Completed **12/15/1998**(12) ABANDONMENT LOG

Date started _____ Completed _____

Professional Certification

(to be signed by a licensed water supply or monitoring well constructor, or registered geologist or civil engineer).

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon geotechnical hole construction standards. This report is true to the best of my knowledge and belief.

License or Registration Number **10402**Signed By **KEITH VIDOS**

Date _____

Affiliation **GEO TECH EXPLORATIONS**

GEOTECHNICAL HOLE REPORT

MARI 53759

Received date 01/15/1999

(as required by OAR 690-240-035)

(1) OWNER/PROJECTHole No.
Co. Job No. **B-3**Name **OREGON DEPARTMENT OF CORRECTIONS**
Street **2575 CENTER ST NE**
City **SALEM** State **OR** Zip **97310**(2) TYPE OF WORK

- ☒
- New
- ☐
- Alter (Recondition)
- ☐
- Alter (Repair)
-
- ☐
- Deepening
- ☒
- Abandonment

(3) CONSTRUCTION

- ☐
- Rotary Air
- ☐
- Hand Auger
- ☐
- Hollow Stem Auger
-
- ☐
- Rotary Mud
- ☐
- Cable Tool
- ☒
- Push Probe Other

(4) TYPE OF HOLE

- ☒
- Uncased Temporary
- ☐
- Cased Permanent
-
- ☐
- Uncased Permanent
- ☐
- Slope Stability Other

(5) USE OF HOLE

SOIL COLLECTION

(6) BORE HOLE CONSTRUCTIONSpecial Standards ☐ Depth of completed well **14** ft.

| | | | | | | |
|------|----------|-------|-----------|--------|-------------------------|-------|
| HOLE | Diameter | From | To | | | |
| | 2.00 | 0.00 | 16 | | | |
| SEAL | From | To | Material | Amount | Seal Grout Weight | Units |
| | 0.00 | 16.00 | Bentonite | 22.00 | | P |

Backfill placed from _____ ft. TO _____ ft. Material _____
Filter pack placed from _____ ft. TO _____ ft. Size _____ in.(7) CASING/SCREENScreen ☐(8) WELL TESTPermeability _____ Yield _____ GPM
Conductivity _____ PH _____
Temperature of water _____ °F/C Depth artesian flow found _____ ft.
Was water analysis done? ☐
By Whom? _____
Depth of strata to be analyzed. From _____ ft. to _____ ft.
Remarks _____
Name of supervising Geologist/Engineer _____(9) LOCATION OF HOLE By legal descriptionCounty **Marion** Latitude _____ Longitude _____
Township **8.00 S** Range **2.00 W**
Section **18** **SE 1/4 NE 1/4**
Tax lot **100** Lot _____ Block _____ Subdivision _____
Legal desc: _____

Street Address of Well (or nearest address)

5485 TURNER RD SE

MAP with location identified must be attached

(10) STATIC WATER LEVEL

Ft. below land surface. _____ Date _____

Artesian Pressure _____ lb/sq. in. _____ Date _____

(11) SUBSURFACE LOG

Ground Elevation _____ ft.

| Material | From | To | SWL |
|------------------|------|----|-----|
| SILTY CLAY | 0 | 10 | |
| WEATHERED BASALT | 10 | 16 | |

Date started **12/15/1998** Completed **12/15/1998**(12) ABANDONMENT LOG

Date started _____ Completed _____

Professional Certification

(to be signed by a licensed water supply or monitoring well constructor, or registered geologist or civil engineer).

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon geotechnical hole construction standards. This report is true to the best of my knowledge and belief.

License or Registration Number **10402**Signed By **KEITH VIDOS**

Date _____

Affiliation **GEO TECH EXPLORATIONS**

GEOTECHNICAL HOLE REPORT

MARI 53760

Received date 01/15/1999

(as required by OAR 690-240-035)

(1) OWNER/PROJECTHole No.
Co. Job No. **B-4**Name **OREGON DEPARTMENT OF CORRECTIONS**
Street **2575 CENTER ST NE**
City **SALEM** State **OR** Zip **97310**(2) TYPE OF WORK

- ☒
- New
- ☐
- Alter (Recondition)
- ☐
- Alter (Repair)
-
- ☐
- Deepening
- ☒
- Abandonment

(3) CONSTRUCTION

- ☐
- Rotary Air
- ☐
- Hand Auger
- ☐
- Hollow Stem Auger
-
- ☐
- Rotary Mud
- ☐
- Cable Tool
- ☒
- Push Probe Other

(4) TYPE OF HOLE

- ☒
- Uncased Temporary
- ☐
- Cased Permanent
-
- ☐
- Uncased Permanent
- ☐
- Slope Stability Other

(5) USE OF HOLE

SOIL COLLECTION

(6) BORE HOLE CONSTRUCTIONSpecial Standards ☐ Depth of completed well **16** ft.

| HOLE | Diameter | | From | | To | |
|------|----------|-------|-----------|--------|-------------------|-------|
| | 2.00 | 0.00 | 0.00 | 16 | | |
| SEAL | From | To | Material | Amount | Seal Grout Weight | Units |
| | 0.00 | 16.00 | Bentonite | 22.00 | | P |

Backfill placed from _____ ft. TO _____ ft. Material _____
Filter pack placed from _____ ft. TO _____ ft. Size _____ in.(7) CASING/SCREENScreen ☐(8) WELL TESTPermeability _____ Yield _____ GPM
Conductivity _____ PH _____
Temperature of water _____ °F/C Depth artesian flow found _____ ft.
Was water analysis done? ☐
By Whom? _____
Depth of strata to be analyzed. From _____ ft. to _____ ft.
Remarks _____
Name of supervising Geologist/Engineer _____(9) LOCATION OF HOLE By legal descriptionCounty **Marion** Latitude _____ Longitude _____
Township **8.00 S** Range **2.00 W**
Section **18** **SE 1/4 NE 1/4**
Tax lot _____ Lot _____ Block _____ Subdivision _____
Legal desc: _____

Street Address of Well (or nearest address)

5485 TURNER RD SE

MAP with location identified must be attached

(10) STATIC WATER LEVELFt. below land surface. _____ Date _____
Artesian Pressure _____ lb/sq. in. _____ Date _____(11) SUBSURFACE LOG

Ground Elevation _____ ft.

| Material | From | To | SWL |
|------------------|------|----|-----|
| SILTY CLAY | 0 | 6 | |
| WEATHERED BASALT | 6 | 16 | |

Date started **12/15/1998** Completed **12/16/1998**(12) ABANDONMENT LOG

Date started _____ Completed _____

Professional Certification

(to be signed by a licensed water supply or monitoring well constructor, or registered geologist or civil engineer).

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon geotechnical hole construction standards. This report is true to the best of my knowledge and belief.

License or Registration Number **10402**Signed By **KEITH VIDOS**

Date _____

Affiliation **GEO TECH EXPLORATIONS**

Marion
53757-
53760


SITE MAP

N
not to scale

Machine
shop



Turner Road



APPENDIX J

EXISTING INFORMATION
SITE 19 - MILL CREEK RESERVOIR

DRAFT

STATE OF OREGON
GEOTECHNICAL HOLE REPORT
 (as required by OAR 690-240-0035)

3/31/2015

(1) OWNER/PROJECT Hole Number B1PROJECT NAME/NBR: 7-184/ODOT-162-01

First Name _____ Last Name _____
 Company OREGON STATE CORRECTIONS DEPARTMENT
 Address 2575 CENTER ST.
 City SALEM State OR Zip 97301-4667

(2) TYPE OF WORK ☒ New ☐ Deepening ☒ Abandonment
☐ Alteration (repair/recondition)

(3) CONSTRUCTION

☐ Rotary Air ☐ Hand Auger ☐ Hollow stem auger
☒ Rotary Mud ☐ Cable ☐ Push Probe
☐ Other _____

(4) TYPE OF HOLE:

☒ Uncased Temporary ☐ Cased Permanent
☐ Uncased Permanent ☐ Slope Stability
☐ Other _____
 Other: _____

(5) USE OF HOLE

GEOTECHNICAL

(6) BORE HOLE CONSTRUCTION Special Standard ☐ (Attach copy)Depth of Completed Hole 45.00 ft.

| BORE HOLE | | | SEAL | | | sacks/ | |
|-----------|------|----|-----------------|------|----|--------|-----|
| Dia | From | To | Material | From | To | Amt | lbs |
| 4 | 0 | 45 | Bentonite Chips | 0 | 45 | 6 | S |
| | | | | | | | |
| | | | | | | | |

Backfill placed from _____ ft. to _____ ft. Material _____
 Filter pack from _____ ft. to _____ ft. Material _____ Size _____

(7) CASING/SCREEN

| Casing | Screen | Dia | + | From | To | Gauge | Stl | Plstc | Wld | Thrd |
|--------------------------|--------------------------|-----|---|------|----|-------|--------------------------|--------------------------|--------------------------|--------------------------|
| <input type="checkbox"/> | <input type="checkbox"/> | | | | | | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| <input type="checkbox"/> | <input type="checkbox"/> | | | | | | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| <input type="checkbox"/> | <input type="checkbox"/> | | | | | | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| <input type="checkbox"/> | <input type="checkbox"/> | | | | | | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |

(8) WELL TESTS

☐ Pump ☐ Bailer ☐ Air ☐ Flowing Artesian
 Yield gal/min Drawdown Drill stem/Pump depth Duration(hr)

| | | | |
|--|--|--|--|
| | | | |
| | | | |

Temperature _____ °F Lab analysis ☐ Yes By _____

Supervising Geologist/Engineer _____

Water quality concerns? ☐ Yes (describe below) TDS amount _____
 From To Description Amount Units

| | | | | |
|--|--|--|--|--|
| | | | | |
| | | | | |

(9) LOCATION OF HOLE (legal description)

County MARION Twp 8.00 S N/S Range 2.00 W E/W WM
 Sec 17 SW 1/4 of the NW 1/4 Tax Lot 100
 Tax Map Number _____ Lot _____
 Lat _____ " or 44.87861111 DMS or DD
 Long _____ " or -122.96397222 DMS or DD
☐ Street address of hole ☒ Nearest address
5358 DEER PARK DR SE SALEM, OR

(10) STATIC WATER LEVEL

Date _____ SWL(psi) + SWL(ft)
 Existing Well / Predeepening _____
 Completed Well _____

WATER BEARING ZONES

Flowing Artesian? ☐

Depth water was first found _____

| SWL Date | From | To | Est Flow | SWL(psi) | + SWL(ft) |
|----------|------|----|----------|----------|-----------|
| | | | | | |
| | | | | | |
| | | | | | |

(11) SUBSURFACE LOG

Ground Elevation _____

| Material | From | To |
|------------------|------|----|
| Sandy Silt | 0 | 18 |
| Weathered Basalt | 18 | 45 |
| | | |
| | | |
| | | |
| | | |

Date Started 3/30/2015 Completed 3/30/2015**(12) ABANDONMENT LOG:**

| Material | From | To | Amt | sacks/ |
|-----------------|------|----|-----|--------|
| Bentonite Chips | 0 | 45 | 6 | S |
| | | | | |
| | | | | |
| | | | | |
| | | | | |

Date Started 3/30/2015 Completed 3/30/2015

Professional Certification (to be signed by an Oregon licensed water or monitoring well constructor, Oregon registered geologist or professional engineer).

I accept responsibility for the construction, deepening, alteration, or abandonment work performed during the construction dates reported above. All work performed during this time is in compliance with Oregon geotechnical hole construction standards. This report is true to the best of my knowledge and belief.

License/Registration Number 10591 Date 3/31/2015

First Name JEFF Last Name CRISMAN
 Affiliation WESTERN STATES SOIL CONSERVATION, INC.

ORIGINAL - WATER RESOURCES DEPARTMENT

THIS REPORT MUST BE SUBMITTED TO THE WATER RESOURCES DEPARTMENT WITHIN 30 DAYS OF COMPLETION OF WORK

Form Version:

STATE OF OREGON
GEOTECHNICAL HOLE REPORT
 (as required by OAR 690-240-0035)

3/31/2015

(1) OWNER/PROJECT Hole Number B2PROJECT NAME/NBR: 7-184/ODOT-162-01

First Name _____ Last Name _____
 Company OREGON STATE CORRECTIONS DEPARTMENT
 Address 2575 CENTER ST.
 City SALEM State OR Zip 97301-4667

(2) TYPE OF WORK ☒ New ☐ Deepening ☒ Abandonment
☐ Alteration (repair/recondition)

(3) CONSTRUCTION

☐ Rotary Air ☐ Hand Auger ☐ Hollow stem auger
☒ Rotary Mud ☐ Cable ☐ Push Probe
☒ Other HQ CORE

(4) TYPE OF HOLE:

☒ Uncased Temporary ☐ Cased Permanent
☐ Uncased Permanent ☐ Slope Stability
☐ Other
 Other: _____

(5) USE OF HOLE

GEOTECHNICAL

(6) BORE HOLE CONSTRUCTION Special Standard ☐ (Attach copy)Depth of Completed Hole 38.00 ft.

| BORE HOLE | | | SEAL | | | sacks/ |
|-----------|------|----|-----------------|------|----|---------|
| Dia | From | To | Material | From | To | Amt lbs |
| 5 | 0 | 33 | Bentonite Chips | 0 | 38 | 7 S |
| 4 | 33 | 38 | | | | |
| | | | | | | |
| | | | | | | |

Backfill placed from _____ ft. to _____ ft. Material _____
 Filter pack from _____ ft. to _____ ft. Material _____ Size _____

(7) CASING/SCREEN

| Casing | Screen | Dia | + | From | To | Gauge | Stl | Plstc | Wld | Thrd |
|--------------------------|--------------------------|-----|---|------|----|-------|--------------------------|--------------------------|--------------------------|--------------------------|
| <input type="checkbox"/> | <input type="checkbox"/> | | | | | | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| <input type="checkbox"/> | <input type="checkbox"/> | | | | | | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| <input type="checkbox"/> | <input type="checkbox"/> | | | | | | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| <input type="checkbox"/> | <input type="checkbox"/> | | | | | | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| <input type="checkbox"/> | <input type="checkbox"/> | | | | | | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |

(8) WELL TESTS

☐ Pump ☐ Bailer ☐ Air ☐ Flowing Artesian
 Yield gal/min Drawdown Drill stem/Pump depth Duration(hr)

| | | | |
|--|--|--|--|
| | | | |
| | | | |
| | | | |

Temperature _____ °F Lab analysis ☐ Yes By _____

Supervising Geologist/Engineer _____

Water quality concerns? ☐ Yes (describe below) TDS amount _____
 From To Description Amount Units

| | | | | |
|--|--|--|--|--|
| | | | | |
| | | | | |
| | | | | |

(9) LOCATION OF HOLE (legal description)

County MARION Twp 8.00 S N/S Range 2.00 W E/W WM
 Sec 17 SW 1/4 of the NW 1/4 Tax Lot 100
 Tax Map Number _____ Lot _____
 Lat _____ " or 44.87680556 DMS or DD
 Long _____ " or -122.96461111 DMS or DD
☐ Street address of hole ☒ Nearest address
5358 DEER PARK DR SE SALEM, OR

(10) STATIC WATER LEVEL

Date _____ SWL(psi) + SWL(ft)
 Existing Well / Predeepening _____
 Completed Well _____

WATER BEARING ZONES

Flowing Artesian? ☐

Depth water was first found _____

| SWL Date | From | To | Est Flow | SWL(psi) | + SWL(ft) |
|----------|------|----|----------|----------|-----------|
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |

(11) SUBSURFACE LOG

Ground Elevation _____

| Material | From | To |
|------------------|------|----|
| Sandy Silt | 0 | 9 |
| Weathered Basalt | 9 | 27 |
| Basalt | 27 | 38 |
| | | |
| | | |
| | | |
| | | |
| | | |

Date Started 3/30/2015 Completed 3/30/2015**(12) ABANDONMENT LOG:**

| Material | From | To | Amt | sacks/ |
|-----------------|------|----|-----|--------|
| Bentonite Chips | 0 | 38 | 7 | S |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |

Date Started 3/30/2015 Completed 3/30/2015

Professional Certification (to be signed by an Oregon licensed water or monitoring well constructor, Oregon registered geologist or professional engineer).

I accept responsibility for the construction, deepening, alteration, or abandonment work performed during the construction dates reported above. All work performed during this time is in compliance with Oregon geotechnical hole construction standards. This report is true to the best of my knowledge and belief.

License/Registration Number 10591 Date 3/31/2015

First Name JEFF Last Name CRISMAN
 Affiliation WESTERN STATES SOIL CONSERVATION, INC.

ORIGINAL - WATER RESOURCES DEPARTMENT

THIS REPORT MUST BE SUBMITTED TO THE WATER RESOURCES DEPARTMENT WITHIN 30 DAYS OF COMPLETION OF WORK

Form Version:

GEOTECHNICAL HOLE REPORT - Map with location identified must be attached and shall include an approximate scale and north arrow

MARI 65658

3/31/2015


Map of Hole



APPENDIX K

EXISTING INFORMATION
SITE 20 – TURNER CONTROL FACILITY

DRAFT



NOTES:

1. BORING LOCATIONS WERE ESTABLISHED BY PACING AND ARE APPROXIMATE ONLY.
2. SEE MEMORANDUM FOR A DISCUSSION OF SUBSURFACE CONDITIONS.
3. BASE MAP WAS PROVIDED BY BLACK & VEATCH CORPORATION.

DATE APR 2005
 DWN. DLR
 APPR. _____
 REVIS. _____
 PROJECT NO.
 2051029



FOUNDATION ENGINEERING INC.
 PROFESSIONAL GEOTECHNICAL SERVICES

820 NW CORNELL AVENUE
 CORVALLIS, OR 97330-4517
 BUS. (541) 757-7645 FAX (541) 757-7650

SITE LAYOUT AND BORING LOCATIONS
TURNER CONTROL STATION
 75 MGD TRANSMISSION CONDUIT - PHASE 2
 TURNER, OREGON

FIGURE NO.

1A

DISTINCTION BETWEEN FIELD LOGS AND FINAL LOGS

A field log is prepared for each boring or test pit by our field representative. The log contains information concerning sampling depths and the presence of various materials such as gravel, cobbles, and fill, and observations of ground water. It also contains our interpretation of the soil conditions between samples. The final logs presented in this report represent our interpretation of the contents of the field logs and the results of the laboratory examinations and tests. Our recommendations are based on the contents of the final logs and the information contained therein and not on the field logs.


VARIATION IN SOILS BETWEEN TEST PITS AND BORINGS

The final log and related information depict subsurface conditions only at the specific location and on the date indicated. Those using the information contained herein should be aware that soil conditions at other locations or on other dates may differ. Actual foundation or subgrade conditions should be confirmed by us during construction.

TRANSITION BETWEEN SOIL OR ROCK TYPES

The lines designating the interface between soil, fill or rock on the final logs and on subsurface profiles presented in the report are determined by interpolation and are therefore approximate. The transition between the materials may be abrupt or gradual. Only at boring or test pit locations should profiles be considered as reasonably accurate and then only to the degree implied by the notes thereon.

SAMPLE OR TEST SYMBOLS



- S - Grab Samples
- SS - Standard Penetration Test Sample (split-spoon)
- SH - Thin-walled Shelby Tube Sample
- C - Core Sample
- CS - Continuous Sample

- ▲ Standard Penetration Test Resistance equals the number of blows a 140 lb. weight falling 30 in. is required to drive a standard split-spoon sampler 1 ft. Practical refusal is equal to 50 or more blows per 6 in. of sampler penetration.
- Water Content (%).


UNIFIED SOIL CLASSIFICATION SYMBOLS

- | | |
|------------|---------------------|
| G - Gravel | W - Well Graded |
| S - Sand | P - Poorly Graded |
| M - Silt | L - Low Plasticity |
| C - Clay | H - High Plasticity |
| Pt - Peat | O - Organic |

FIELD SHEAR STRENGTH TEST

Shear strength measurements on test pit side walls, blocks of soil or Shelby tube samples are typically made with Torvane or pocket penetrometer devices.

TYPICAL SOIL/ROCK SYMBOLS



WATER TABLE

- Water Table Location
- (1/31/00) Date of Measurement
- Piezometer Tip Location (if used)



FOUNDATION ENGINEERING INC.
PROFESSIONAL GEOTECHNICAL SERVICES

820 NW CORNELL AVE
CORVALLIS, OR 97330-4517
BUS. (541) 757-7845 FAX (541) 757-7850

SYMBOL KEY

BORING AND TEST PIT LOGS

Explanation of Common Terms Used in Soil Descriptions

| Field Identification | Cohesive Soils | | | Granular Soils | |
|--|----------------|---------------|---------------------|----------------|--------------|
| | SPT | S_u^* (tsf) | Term | SPT | Term |
| Easily penetrated several inches by fist. | 0 - 1 | < 0.125 | Very Soft | 0 - 4 | Very Loose |
| Easily penetrated several inches by thumb. | 2 - 4 | 0.125-0.25 | Soft | 5 - 10 | Loose |
| Can be penetrated several inches by thumb with moderate effort. | 5 - 8 | 0.25 - 0.50 | Medium Stiff (Firm) | 11 - 30 | Medium Dense |
| Readily indented by thumb but penetrated only with great effort. | 9 - 15 | 0.50 - 1.0 | Stiff | 31 - 50 | Dense |
| Readily indented by thumbnail. | 16 - 30 | 1.0 - 2.0 | Very Stiff | > 50 | Very Dense |
| Indented with difficulty by thumbnail. | 31 - 60 | > 2.0 | Hard | | |

* Undrained shear strength

| Term | Soil Moisture Field Description |
|-------|---|
| Dry | Absence of moisture. Dusty. Dry to the touch. |
| Damp | Soil has moisture. Cohesive soils are below plastic limit and usually moldable. |
| Moist | Grains appear darkened, but no visible water. Silt/clay will clump. Sand will bulk. Soils are often at or near plastic limit. |
| Wet | Visible water on larger grain surfaces. Sand and cohesionless silt exhibit dilatancy. Cohesive silt/clay can be readily remolded. Soil leaves wetness on the hand when squeezed. "Wet" indicates that the soil is wetter than the optimum moisture content and above the plastic limit. |

| Term | PI | Plasticity Field Test |
|-------------------|---------|---|
| Nonplastic | 0 - 3 | Cannot be rolled into a thread. |
| Low Plasticity | 3 - 15 | Can be rolled into a thread with some difficulty. |
| Medium Plasticity | 15 - 30 | Easily rolled into thread. |
| High Plasticity | > 30 | Easily rolled and rerolled into thread. |

| Term | Soil Structure Criteria |
|--------------|--|
| Stratified | Alternating layers at least 1 inch thick - describe variation. |
| Laminated | Alternating layers of less than 1 inch thick - describe variation. |
| Fissured | Contains shears and partings along planes of weakness. |
| Slickensides | Partings appear glossy or striated. |
| Blocky | Breaks into lumps - crumbly. |
| Lensed | Contains pockets of different soils - describe variation. |


| Term | Soil Cementation Criteria |
|----------|--------------------------------------|
| Weak | Breaks under light finger pressure. |
| Moderate | Breaks under hard finger pressure. |
| Strong | Will not break with finger pressure. |



FOUNDATION ENGINEERING INC.
PROFESSIONAL GEOTECHNICAL SERVICES

820 NW CORNELL AVE.
CORVALLIS, OR 97330-4517
BUS. (541) 757-7645 FAX (541) 757-7650

COMMON TERMS
SOIL DESCRIPTIONS



Project No.: 2051029

Surface Elevation: N/A (Approx.)

Date of Boring: March 10, 2005


Boring Log: BH- 1

75 MGD Transmission Conduit - Phase 2

Turner, Oregon



Foundation Engineering, Inc.



Project No.: 97100135

Surface Elevation: N/A

Date of Boring: May 1, 1998


Boring Log: BH-12

75 MGD Potable Water Transmission Conduit

Salem, Oregon



Foundation Engineering, Inc.



NOTES:

1. BORING LOCATIONS WERE ESTABLISHED BY PACING AND ARE APPROXIMATE ONLY.
2. SEE MEMORANDUM FOR A DISCUSSION OF SUBSURFACE CONDITIONS.
3. BASE MAP WAS PROVIDED BY BLACK & VEATCH CORPORATION.

DATE APR 2005
 DWN. DLR
 APPR. _____
 REVIS. _____
 PROJECT NO.
 2051029



FOUNDATION ENGINEERING INC.
 PROFESSIONAL GEOTECHNICAL SERVICES
 820 NW CORNELL AVENUE
 CORVALLIS, OR 97330-4517
 BUS. (541) 757-7645 FAX (541) 757-7650

SITE LAYOUT AND BORING LOCATIONS
TURNER CONTROL STATION
 75 MGD TRANSMISSION CONDUIT - PHASE 2
 TURNER, OREGON

FIGURE NO.

1A

DISTINCTION BETWEEN FIELD LOGS AND FINAL LOGS

A field log is prepared for each boring or test pit by our field representative. The log contains information concerning sampling depths and the presence of various materials such as gravel, cobbles, and fill, and observations of ground water. It also contains our interpretation of the soil conditions between samples. The final logs presented in this report represent our interpretation of the contents of the field logs and the results of the laboratory examinations and tests. Our recommendations are based on the contents of the final logs and the information contained therein and not on the field logs.


VARIATION IN SOILS BETWEEN TEST PITS AND BORINGS

The final log and related information depict subsurface conditions only at the specific location and on the date indicated. Those using the information contained herein should be aware that soil conditions at other locations or on other dates may differ. Actual foundation or subgrade conditions should be confirmed by us during construction.

TRANSITION BETWEEN SOIL OR ROCK TYPES

The lines designating the interface between soil, fill or rock on the final logs and on subsurface profiles presented in the report are determined by interpolation and are therefore approximate. The transition between the materials may be abrupt or gradual. Only at boring or test pit locations should profiles be considered as reasonably accurate and then only to the degree implied by the notes thereon.

SAMPLE OR TEST SYMBOLS



- S - Grab Samples
- SS - Standard Penetration Test Sample (split-spoon)
- SH - Thin-walled Shelby Tube Sample
- C - Core Sample
- CS - Continuous Sample

- ▲ Standard Penetration Test Resistance equals the number of blows a 140 lb. weight falling 30 in. is required to drive a standard split-spoon sampler 1 ft. Practical refusal is equal to 50 or more blows per 6 in. of sampler penetration.
- Water Content (%).


UNIFIED SOIL CLASSIFICATION SYMBOLS

- | | |
|------------|---------------------|
| G - Gravel | W - Well Graded |
| S - Sand | P - Poorly Graded |
| M - Silt | L - Low Plasticity |
| C - Clay | H - High Plasticity |
| Pt - Peat | O - Organic |

FIELD SHEAR STRENGTH TEST

Shear strength measurements on test pit side walls, blocks of soil or Shelby tube samples are typically made with Torvane or pocket penetrometer devices.

TYPICAL SOIL/ROCK SYMBOLS



WATER TABLE

- Water Table Location
- (1/31/00) Date of Measurement
- Piezometer Tip Location (if used)



FOUNDATION ENGINEERING INC.
PROFESSIONAL GEOTECHNICAL SERVICES

820 NW CORNELL AVE
CORVALLIS, OR 97330-4517
BUS. (541) 757-7845 FAX (541) 757-7850

SYMBOL KEY

BORING AND TEST PIT LOGS

Explanation of Common Terms Used in Soil Descriptions

| Field Identification | Cohesive Soils | | | Granular Soils | |
|--|----------------|---------------|---------------------|----------------|--------------|
| | SPT | S_u^* (tsf) | Term | SPT | Term |
| Easily penetrated several inches by fist. | 0 - 1 | < 0.125 | Very Soft | 0 - 4 | Very Loose |
| Easily penetrated several inches by thumb. | 2 - 4 | 0.125-0.25 | Soft | 5 - 10 | Loose |
| Can be penetrated several inches by thumb with moderate effort. | 5 - 8 | 0.25 - 0.50 | Medium Stiff (Firm) | 11 - 30 | Medium Dense |
| Readily indented by thumb but penetrated only with great effort. | 9 - 15 | 0.50 - 1.0 | Stiff | 31 - 50 | Dense |
| Readily indented by thumbnail. | 16 - 30 | 1.0 - 2.0 | Very Stiff | > 50 | Very Dense |
| Indented with difficulty by thumbnail. | 31 - 60 | > 2.0 | Hard | | |

* Undrained shear strength

| Term | Soil Moisture Field Description |
|-------|---|
| Dry | Absence of moisture. Dusty. Dry to the touch. |
| Damp | Soil has moisture. Cohesive soils are below plastic limit and usually moldable. |
| Moist | Grains appear darkened, but no visible water. Silt/clay will clump. Sand will bulk. Soils are often at or near plastic limit. |
| Wet | Visible water on larger grain surfaces. Sand and cohesionless silt exhibit dilatancy. Cohesive silt/clay can be readily remolded. Soil leaves wetness on the hand when squeezed. "Wet" indicates that the soil is wetter than the optimum moisture content and above the plastic limit. |

| Term | PI | Plasticity Field Test |
|-------------------|---------|---|
| Nonplastic | 0 - 3 | Cannot be rolled into a thread. |
| Low Plasticity | 3 - 15 | Can be rolled into a thread with some difficulty. |
| Medium Plasticity | 15 - 30 | Easily rolled into thread. |
| High Plasticity | > 30 | Easily rolled and rerolled into thread. |

| Term | Soil Structure Criteria |
|--------------|--|
| Stratified | Alternating layers at least 1 inch thick - describe variation. |
| Laminated | Alternating layers of less than 1 inch thick - describe variation. |
| Fissured | Contains shears and partings along planes of weakness. |
| Slickensides | Partings appear glossy or striated. |
| Blocky | Breaks into lumps - crumbly. |
| Lensed | Contains pockets of different soils - describe variation. |


| Term | Soil Cementation Criteria |
|----------|--------------------------------------|
| Weak | Breaks under light finger pressure. |
| Moderate | Breaks under hard finger pressure. |
| Strong | Will not break with finger pressure. |



FOUNDATION ENGINEERING INC.
PROFESSIONAL GEOTECHNICAL SERVICES

820 NW CORNELL AVE.
CORVALLIS, OR 97330-4517
BUS. (541) 757-7645 FAX (541) 757-7650

COMMON TERMS
SOIL DESCRIPTIONS



Project No.: 2051029

Surface Elevation: N/A (Approx.)

Date of Boring: March 10, 2005


Boring Log: BH- 1

75 MGD Transmission Conduit - Phase 2

Turner, Oregon



Foundation Engineering, Inc.



Project No.: 97100135

Surface Elevation: N/A

Date of Boring: May 1, 1998

Boring Log: BH-12

75 MGD Potable Water Transmission Conduit


Salem, Oregon



Foundation Engineering, Inc.

APPENDIX L

EXISTING INFORMATION
SITE 21 - FRANZEN RESERVOIR
&
REPEATER TOWER





- BH-14 Boring
 PZ-12 Boring with dual standpipe piezometer installation
 TP-4 Test pit
 HA-2 Asphalt coring with hand auger hole
 SPT-1 Seepage observation point
 6" steel well casing above surface 1.5'
 A A' Interpretive subsurface profile location
 Seismic refraction line
 Fault - dashed where concealed, ball on down dropped side
 S1 S2 Cross-section for seepage and stability analyses

FRANZEN RESERVOIR
TURNER, OREGON

SITE PLAN


 SQUIER ASSOCIATES
 FIGURE 1







LEGEND

- Minor fill
- Fine-grained soil embankment fill
- Coarse-grained soil embankment fill
- Medium stiff to stiff fine-grained Columbia River Basalt residual soil
- Very stiff to hard fine-grained Columbia River Basalt residual soil
- Coarse-grained Columbia River Basalt residual soil
- Columbia River Basalt rock
- Fine-grained alluvium
- Coarse-grained alluvium
- Fine-grained Marine Sediment unit
- Coarse-grained Marine Sediment unit
- Piezometer water level measured on 4/13/01
- Water level at time of drilling
- - - - - Interpreted geologic boundary
- - - - - Interpreted soil/rock boundary
- Piezometer screen zone
- 43 SPT blow counts
- Fault with relative movement

SCALE
Horizontal: 1 inch = 80 feet
Vertical: 1 inch = 40 feet



- TES:
- Features shown are for illustrative purposes only and are approximate.
 - Contacts between units are interpretive and may represent a gradual transition. Conditions may vary between borings.



NOTES:

1. Features shown are for illustrative purposes only and are approximate.
2. Contacts between units are interpretive and may represent a gradual transition. Conditions may vary between borings.

SCALE

Horizontal: 1 inch = 40 feet
Vertical: 1 inch = 20 feet


FRANZEN RESERVOIR
TURNER, OREGON

**SUBSURFACE
STRATIGRAPHY SECTIONS**

**SQUIER ASSOCIATES
FIGURE 4**

APPENDIX M

EXISTING INFORMATION
SITE 22 - GEREN ISLAND
WATER TREATMENT PLANT

| Comments | Depth, Feet | Sample # | Location | Class Symbol | Water Table | C, TSF | Symbol | Soil and Rock Description |
|-------------------------------------|-------------|----------|----------|--------------|-------------|--------|---|---|
| No base rock observed. | 1- | | | | | |  | ASPHALT (4.0 TO 4.5 inches thick). |
| | 2- | | | | | | | Grey-brown, 6-inch minus, moist, dense to very dense, sandy, cobbly GRAVEL with trace silt. |
| No ground water infiltration noted. | 3- | | | | | | | |
| | 4- | | | | | | | BOTTOM OF TEST PIT |
| | 5- | | | | | | | |
| | 6- | | | | | | | |
| | 7- | | | | | | | |
| | 8- | | | | | | | |
| | 9- | | | | | | | |
| | 10- | | | | | | | |

Project No.: 96100011




Surface Elevation: 470 feet (Approx.)

Date of Test Pit: July 24, 1996

Test Pit Log: TP-1

Geren Island Treatment Facility

Improvements, Marion County, Oregon

| Comments | Depth, Feet | Sample # | Location | Class Symbol | Water Table | C, YSF | Symbol | Soil and Rock Description |
|-------------------------------------|-------------|----------|----------|--------------|-------------|--------|---|---|
| Roots extend to 5 feet. | 1- | S-2-1 | | | | |  | Brown, moist, medium stiff, sandy SILT. |
| | 2- | S-2-2 | | | | |  | Grey-brown, slightly moist to moist, medium grained, medium dense SAND. |
| | 3- | S-2-3 | | | | |  | Grey-brown, slightly moist to moist, dense to very dense, coarse, sandy, cobbly GRAVEL. |
| No ground water infiltration noted. | 4- | | | | | | | |
| | 5- | | | | | | | |
| | 6- | | | | | | | |
| | 7- | | | | | | | |
| | 8- | | | | | | | |
| | 9- | | | | | | | |
| | 10- | | | | | | | |
| | | | | | | | | BOTTOM OF TEST PIT |

Project No.:

96100011

Surface Elevation:

481 feet (Approx.)

Date of Test Pit:

July 24, 1996

Test Pit Log: TP-2

Geren Island Treatment Facility

Improvements, Marion County, Oregon




[illegible]

Project No.: 96100011

Surface Elevation: 480 feet (Approx.)

Date of Test Pit: July 24, 1996

Test Pit Log: TP-3
Geren Island Treatment Facility
Improvements, Marion County, Oregon

| Comments | Depth, Feet | Sample # | Location | Class Symbol | Water Table | C. TSF | Symbol | Soil and Rock Description |
|-------------------------------------|-------------|----------|----------|--------------|-------------|--------|--|---------------------------|
| No ground water infiltration noted. | 1- | | | | | |  ASPHALT (3.25 inches thick).  Grey, moist, dense, sandy, crushed GRAVEL with some silt (base rock).  Grey-brown, moist, dense to very dense, gravelly COBBLES. | |
| | 2- | | | | | | | |
| | 3- | | | | | | | |
| | 4- | | | | | | | BOTTOM OF TEST PIT |
| | 5- | | | | | | | |
| | 6- | | | | | | | |
| | 7- | | | | | | | |
| | 8- | | | | | | | |
| | 9- | | | | | | | |
| | 10- | | | | | | | |

Project No.: 96100011

Surface Elevation: 464 feet (Approx.)

Date of Test Pit: July 24, 1996

Test Pit Log: TP-4
Geren Island Treatment Facility
Improvements, Marion County, Oregon

| Comments | Depth, Feet | Sample # | Location | Class Symbol | Water Table | C, TSF | Symbol | Soil and Rock Description |
|---|-------------|----------|----------|--------------|-------------|--------|--------|---|
| Piezometer pipe extends above ground about 2 feet. | 1- | | | | | | | Grey-brown, dense, non-cemented, well-rounded COBBLES and GRAVEL with some medium to coarse sand. |
| Repeated caving from the ground surface to the bottom of the excavation. | 2- | | | | | | | Roots from about 0 to 2.5 feet. |
| | 3- | | | | | | | |
| | 4- | | | | | | | |
| | 5- | | | | | | | Cobbles to about 8 inches in diameter, most from 4 to 5 inches in diameter. |
| Piezometer consists of 1.5-inch PVC pipe. The bottom 5 feet is slotted and wrapped in geotextile. | 6- | | | | | | | |
| | 7- | | | | | | | Moisture increases with depth. |
| | 8- | | | | | | | |
| | 9- | | | | | | | |
| | 10- | | | | | | | BOTTOM OF TEST PIT |

Project No.:

96100011

Surface Elevation:

462 feet (Approx.)


Date of Test Pit:

August 9, 1996

Test Pit Log: TP-7

Geren Island Treatment Facility

Improvements, Marion County, Oregon



Project No.: 96100011

Surface Elevation: 486 feet (Approx.)

Date of Boring: July 25, 1996




Foundation Engineering, Inc.

Boring Log: BH-1

Geren Island Treatment Facility

Improvements, Marion County, Oregon



Project No.: 96100011

Surface Elevation: 480 feet (Approx.)

Date of Boring: July 25, 1996




Foundation Engineering, Inc.

Boring Log: BH-2

Geren Island Treatment Facility

Improvements, Marion County, Oregon



Project No.: 96100011

Surface Elevation: 480 feet (Approx.)

Date of Boring: July 26, 1996




Foundation Engineering, Inc.

Boring Log: BH-3

Geren Island Treatment Facility

Improvements, Marion County, Oregon



Project No.: 96100011

Surface Elevation: 478 feet (Approx.)

Date of Boring: July 26, 1996




Foundation Engineering, Inc.

Boring Log: BH-4

Geren Island Treatment Facility

Improvements, Marion County, Oregon



Project No.: 96100011

Surface Elevation: 479 feet (Approx.)

Date of Boring: July 29, 1996


Boring Log: BH-5

Geren Island Treatment Facility

Improvements, Marion County, Oregon



Foundation Engineering, Inc.



Project No.: 96100011

Surface Elevation: 461 feet (Approx.)

Date of Boring: July 29, 1996




Foundation Engineering, Inc.

Boring Log: BH-6

Geren Island Treatment Facility

Improvements, Marion County, Oregon



Project No.: 96100011

Surface Elevation: 464 feet (Approx.)

Date of Boring: July 30, 1996




Foundation Engineering, Inc.

Boring Log: BH-7

Geren Island Treatment Facility


Improvements, Marion County, Oregon



Project No.: 96100011

Surface Elevation: 462 feet (Approx.)

Date of Boring: July 30, 1996




Boring Log: BH-8

Geren Island Treatment Facility

Improvements, Marion County, Oregon

| | | | | | | | | | |
|--|--|--|--|--|--|----------------------------|--|--|--|
| Project: Geren Island Water Treatment Facility Project Location: 2700 E. Santiam St. Stayton, Oregon 97203 Project Number: 5966.0 | | | | | | Log of Boring B-01 | | | |
| Date(s) Drilled 04/08/2019 - 04/09/2019 | | Geotechnical Consultant McMillen Jacobs Associates | | Logged By J. Fissel | | Checked By J. Quinn | | | |
| Drilling Method/Rig Type Sonic Drilling/TSi 150CC Track-Mounted Drill Rig | | Drilling Contractor Holt Services Inc. | | Total Depth of Borehole 75.0 ft | | | | | |
| Hole Diameter 6.00 in | | Hammer Weight/Drop (lb/in.)/Type 140 lb / 30 in / Automatic | | Ground Surface Elevation/Datum 485.0 ft (approximate) | | | | | |
| Location Near SW corner of Filter #3 West | | Coordinates | | Elevation Source 30% Submittal Drawings, Aug 2019 | | | | | |

| ELEV. (FT) | WATER LEVEL | DEPTH (FT) | SAMPLE TYPE | RECOVERY (%) | BLOW COUNTS | SAMPLE NUMBER | <input type="checkbox"/> PENETRATION RESISTANCE BLOWS/FT 10 20 30 40 <input type="checkbox"/> WATER CONTENT (MC) 20 40 60 80 <input type="checkbox"/> ATTERBERG LL/PL | | USCS GRAPHIC | USCS | MATERIAL DESCRIPTION | REMARKS AND TESTS | BACKFILL/INSTALL. |
|------------|-------------|------------|-------------|--------------|----------------------|---------------|---|--|--------------|-------|--|-------------------|-------------------|
| | | | | | | | | | | | | | |
| | | | | | | | | | | ML | Brown, Sandy SILT (ML); rootlets. [Topsoil] | | |
| 480 | | 5 | | 100 | | R-1 | | | | GW | Medium dense, moist, gray, Well-graded GRAVEL (GW); well-graded, subrounded, fine to coarse gravel, fine to coarse sand. [Fill] <i>Gravel coarsening upward</i> | | |
| | | | | 67 | 8-16-16 (N=32) | SPT_1 | | | | GW-GM | Dense, moist, gray, Well-graded GRAVEL with silt and sand (GW-GM); low plasticity fines, well-graded, subangular, fine to coarse gravel, fine to coarse sand. [Fill] <i>Gravel coarsening upward</i> | | |
| | | | | 100 | | R-2 | | | | | | | |
| 475 | | 10 | | 45 | 13-16-21 (N=37) | SPT_2 | | | | GW | Dense, moist, gray, Well-graded GRAVEL with sand (GW); well-graded, angular, fine gravel, fine to coarse sand, trace silt. [Fill] | | |
| | | | | 75 | | R-3 | | | | GW-GM | Dense, moist, gray, Well-graded GRAVEL with silt and sand (GW-GM); low plasticity fines, well-graded, angular, fine to coarse gravel, fine to coarse sand. [Fill] <i>Moist grading to wet</i> | | |
| 470 | | 15 | | 73 | 9-50/5" (Refusal) | SPT_3 | | | | | | | |
| | | | | 60 | | R-4 | | | | | | | |
| 465 | | 20 | | 45 | 6-20-22 (N=42) | SPT_4 | | | | GW-GM | Dense, wet, gray, Well-graded GRAVEL with silt and sand (GW-GM); low plasticity fines, well-graded, subrounded to rounded, fine to coarse gravel, fine to coarse sand. [Alluvial Deposits] | | |
| | | | | 100 | | R-5 | | | | | | | |
| 460 | | 25 | | 106 | 3-10-50/5" (Refusal) | SPT_5 | | | | | | | |
| | | | | 100 | | R-6 | | | | | Very dense, wet, brown, Silty GRAVEL with sand, cobbles, and boulders (GM); low plasticity fines, trace boulders, trace subrounded to rounded cobbles, subrounded to rounded gravel, fine to | | |



Boring B-01
 Sheet 1 of 3

Project: Geren Island Water Treatment Facility
Project Location: 2700 E. Santiam St. Stayton, Oregon 97203
Project Number: 5966.0

Log of Boring B-02

| | | | |
|---|---|---|-------------------------------|
| Date(s) Drilled 04/09/2019 | Geotechnical Consultant McMillen Jacobs Associates | Logged By J. Fissel | Checked By J. Quinn |
| Drilling Method/ Rig Type Sonic Drilling/TSi 150CC Track-Mounted Drill Rig | Drilling Contractor Holt Services Inc. | Total Depth of Borehole 40.9 ft | |
| Hole Diameter 6.00 in | Hammer Weight/Drop (lb/in.)/Type 140 lb / 30 in / Automatic | Ground Surface Elevation/Datum 485.0 ft (approximate) | |
| Location West-Central Perimeter of Filter #3 West | Coordinates | Elevation Source 30% Submittal Drawings, Aug 2019 | |

| ELEV. (FT) | WATER LEVEL | DEPTH (FT) | SAMPLE TYPE | RECOVERY (%) | BLOW COUNTS | SAMPLE NUMBER | <div> <input type="checkbox"/> PENETRATION RESISTANCE BLOWS/FT 10 20 30 40 <input type="checkbox"/> WATER CONTENT (MC) <input type="checkbox"/> ATTERBERG LL/PL 20 40 60 80 </div> | USCS GRAPHIC | USCS | MATERIAL DESCRIPTION | REMARKS AND TESTS | BACKFILL/INSTALL. |
|------------|-------------|------------|-------------|--------------|-----------------------|---------------|--|--------------|-------|--|--|-------------------|
| 480 | | 5 | | 0 | 1-1-1 (N=2) | SPT_1 | <input type="checkbox"/> | | ML | Dark brown, Sandy SILT (ML); roots. [Topsoil] | | |
| | | | | 70 | | R-1 | | | SM | Loose, moist, brown, Silty SAND with cobbles (SM); trace subrounded to rounded cobbles, trace subrounded, fine to coarse gravel, trace roots. [Fill] | | |
| | | | | | | | | | GW | | | |
| | | | | | | | | | GM | Medium dense, moist, gray, Well-graded GRAVEL with sand (GW); well-graded, angular gravel, fine to coarse sand. [Fill] | | |
| | | | | 100 | | G-2 | <input type="checkbox"/> | | ML | Medium dense, moist, brown, Silty GRAVEL with sand (GM); subrounded, fine to coarse gravel, fine to coarse sand. [Fill] | 57% Fines per ASTM D1140 | |
| | | | | 100 | | R-2 | | | | | | |
| 475 | | 10 | | 77 | 17-29-30/1" (N=30/1") | SPT_2 | | | GW | Soft, moist, brown, Sandy SILT (ML); low plasticity, fine to medium sand. [Fill] | | |
| | | | | | | | | | | <i>Below 7 feet, color changes from brown to gray.</i> | | |
| | | | | 100 | | R-3 | | | GM | Very dense, moist, gray, Well-graded GRAVEL with sand (GW); well-graded, subangular, gravel, fine to coarse sand. [Fill] | | |
| 470 | | 15 | | 79 | 50/5" (Refusal) | SPT_3 | | | | | | |
| | | | | | | | | | | Very dense, moist, brown and gray, Silty GRAVEL with sand and cobbles (GM); trace subrounded to rounded cobbles, subangular, fine to coarse gravel, fine to coarse sand. [Fill] | Water level inside borehole after drilling was 16.25 feet bgs. | |
| | | | | 70 | | R-4 | | | GW-GM | Very dense, wet, gray, Well-graded GRAVEL with silt, sand, and cobbles (GW-GM); low plasticity fines, trace subrounded to rounded cobbles, well-graded, subangular gravel, with fine to coarse sand. [Fill] | | |
| 465 | | 20 | | 100 | 5-8-19 (N=27) | SPT_4 | <input type="checkbox"/> | | | <i>Color is entirely gray from 19 to 20 feet (possible cobble).</i> | 5% cobbles, 56% Gravel, 29% Sand, 10% fines | |
| | | | | 100 | | G-2 | | | | | | |
| | | | | 100 | | R-5 | | | | | | |
| 460 | | 25 | | 50 | 30-25-30 (N=55) | SPT_5 | | | | Very dense, wet, gray, Silty GRAVEL with sand, boulders, and cobbles (GM); low plasticity fines, trace boulders, trace subrounded to rounded cobbles, subangular coarse gravel, medium to coarse sand. [Alluvial Deposits] | | |
| | | | | 100 | | R-6 | | | | | | |

Log of Boring B-02

| ELEV. (FT) | WATER LEVEL | DEPTH (FT) | SAMPLE TYPE | RECOVERY (%) | BLOW COUNTS | SAMPLE NUMBER | <div> <div> <div> <div> <div>10</div> <div>20</div> <div>30</div> <div>40</div> </div> <div> <div>10</div> <div>20</div> <div>30</div> <div>40</div> </div> </div> <div> <div> <div>□</div> <div> PENETRATION RESISTANCE BLOWS/FT </div> </div> <div> <div>○</div> <div> WATER CONTENT (MC) </div> </div> <div> <div>▬</div> <div> ATTERBERG LL/PL </div> </div> </div> <div> <div>20</div> <div>40</div> <div>60</div> <div>80</div> </div> </div> </div> | USCS GRAPHIC | USCS | MATERIAL DESCRIPTION | REMARKS AND TESTS | BACKFILL/INSTALL. |
|------------|-------------|------------|-------------|--------------|--------------------|---------------|--|--------------|------|---|-------------------|-------------------|
| 450 | | 35 | | 7 | 50/15" (Refusal) | SPT_6 | | | | Very dense, wet, gray, Silty GRAVEL with sand, boulders, and cobbles (GM); low plasticity fines, trace boulders, trace subrounded to rounded cobbles, subangular coarse gravel, medium to coarse sand. [Alluvial Deposits] | | |
| | | | | 100 | | R-7 | | | | | | |
| | | | | 79 | 50/5" (Refusal) | SPT_7 | | GM | | | | |
| | | | | 100 | | R-8 | | | | | | |
| 445 | | 40 | | 54 | 43-50/5" (Refusal) | SPT_8 | | | | Below 35.5 feet, cobble percentage increases. | | |
| 440 | | 45 | | | | | | | | Borehole completed at 40.92 feet below ground surface (bgs). | | |
| | | | | | | | | | | | | |
| 435 | | 50 | | | | | | | | | | |
| 430 | | 55 | | | | | | | | | | |

Project: Geren Island Water Treatment Facility
Project Location: 2700 E. Santiam St. Stayton, Oregon 97203
Project Number: 5966.0

Log of Boring B-03

| | | | |
|---|---|---|-------------------------------|
| Date(s) Drilled 04/10/2019 | Geotechnical Consultant McMillen Jacobs Associates | Logged By J. Fissel | Checked By J. Quinn |
| Drilling Method/ Rig Type Sonic Drilling/TSi 150CC Track-Mounted Drill Rig | Drilling Contractor Holt Services Inc. | Total Depth of Borehole 40.8 ft | |
| Hole Diameter 6.00 in | Hammer Weight/Drop (lb/in.)/Type 140 lb / 30 in / Automatic | Ground Surface Elevation/Datum 485.0 ft (approximate) | |
| Location South-Central Perimeter of Filter #3 West | Coordinates | Elevation Source 30% Submittal Drawings, Aug 2019 | |

| ELEV. (FT) | WATER LEVEL | DEPTH (FT) | SAMPLE TYPE | RECOVERY (%) | BLOW COUNTS | SAMPLE NUMBER | <input type="checkbox"/> PENETRATION RESISTANCE BLOWS/FT 10 20 30 40 <input type="checkbox"/> WATER CONTENT (MC) <input type="checkbox"/> ATTERBERG LL/PL 20 40 60 80 | USCS GRAPHIC | USCS | MATERIAL DESCRIPTION | REMARKS AND TESTS | BACKFILL/INSTALL. |
|------------|-------------|------------|-------------|--------------|-----------------------|---------------|---|--------------|-------|--|---|-------------------|
| 480 | | 5 | | 100 | | R-1 | | | ML | Dark brown, Sandy SILT (ML); trace fine gravel, roots. [Fill] | | |
| | | | | | | | | | ML | | | |
| | | | | 100 | | R-2 | | | GM | Soft, brown, Sandy SILT with gravel (ML); low plasticity, subrounded, coarse gravel, fine to coarse sand. [Fill] | | |
| | | | | 50 | 5-40-20 (N=60) | SPT_1 | | | GM | Very dense, moist, brown, Silty GRAVEL with sand and cobbles (GM); low plasticity fines, trace subrounded to rounded cobbles, subrounded, coarse gravel, fine to coarse sand. | | |
| | | | | 100 | | R-2 | | | GP | [Fill] | | |
| | | | | | | | | | GP | Dense, moist, gray, Poorly graded GRAVEL with sand (GP); poorly graded, subrounded, coarse gravel, fine to coarse sand. [Fill] | | |
| 475 | | 10 | | 50 | 6-15-34 (N=49) | SPT_2 | | | GW-GM | Dense, moist, brown, Well-graded GRAVEL with silt, sand, and cobbles (GW-GM); low plasticity fines, subrounded to rounded cobbles, subrounded gravel, fine to coarse sand, weakly cemented. [Fill] | 9% Cobbles, 56% Gravel, 27% Sand, 8% Fines | |
| | | | | 100 | | G-1 | | | GW-GM | | | |
| | | | | 100 | | R-3 | | | GW-GM | | | |
| 470 | | 15 | | 36 | 22-50/5" (Refusal) | SPT_3 | | | | Becomes wet at 15 feet. | | |
| | | | | 100 | | R-4 | | | | | Water Level inside borehole at 16.3 feet bgs after drilling | |
| | | | | | | | | | | | | |
| 465 | | 20 | | 67 | 26-15-20 (N=35) | SPT_4 | | | GP | Dense, wet, gray, Poorly graded GRAVEL with sand and cobbles (GP); low plasticity fines, trace subrounded to rounded cobbles, poorly graded, subrounded, coarse gravel, fine to coarse sand, trace silt, weakly cemented. [Alluvial Deposits] | | |
| | | | | 75 | | R-5 | | | | | | |
| | | | | | | | | | | Very dense, wet, brown, Silty GRAVEL with sand (GM); low plasticity fines, subrounded, coarse gravel, trace gray gravel, medium to coarse sand, weakly cemented. [Alluvial Deposits] | | |
| 460 | | 25 | | 50 | 41-49-50/4" (Refusal) | SPT_5 | | | | | | |
| | | | | 100 | | R-6 | | | | At 29 feet encountered some red-brown fine, angular gravel | | |
| | | | | | | | | | | | | |

Project: Geren Island Water Treatment Facility
Project Location: 2700 E. Santiam St. Stayton, Oregon 97203
Project Number: 5966.0

Log of Boring B-03

| | | | |
|--|--|--|------------------------|
| Date(s) Drilled 04/10/2019 | Geotechnical Consultant McMillen Jacobs Associates | Logged By J. Fissel | Checked By J. Quinn |
| Drilling Method/ Rig Type Sonic Drilling/TSi 150CC Track-Mounted Drill Rig | Drilling Contractor Holt Services Inc. | Total Depth of Borehole 40.8 ft | |
| Hole Diameter 6.00 in | Hammer Weight/Drop (lb/in.)/Type 140 lb / 30 in / Automatic | Ground Surface Elevation/Datum 485.0 ft (approximate) | |
| Location South-Central Perimeter of Filter #3 West | Coordinates | Elevation Source 30% Submittal Drawings, Aug 2019 | |

| ELEV. (FT) | WATER LEVEL | DEPTH (FT) | SAMPLE TYPE | RECOVERY (%) | BLOW COUNTS | SAMPLE NUMBER | <div> <input type="checkbox"/> PENETRATION RESISTANCE BLOWS/FT 10 20 30 40 <input type="checkbox"/> WATER CONTENT (MC) <input type="checkbox"/> ATTERBERG LL/PL 20 40 60 80 </div> | USCS GRAPHIC | USCS | MATERIAL DESCRIPTION | REMARKS AND TESTS | BACKFILL/INSTALL. |
|------------|-------------|------------|-------------|--------------|--------------------|---------------|--|--------------|------|--|--|-------------------|
| 450 | 35 | | | 100 | 50/4" (Refusal) | SPT_6 | | | | Very dense, wet, brown, Silty GRAVEL with sand (GM); low plasticity fines, subrounded, coarse gravel, trace gray gravel, medium to coarse sand, weakly cemented. [Alluvial Deposits] | | |
| | | | | 100 | | R-7 | | | | | | |
| | | | | 75 | 38-50/2" (Refusal) | SPT_7 | | | GM | | | |
| | | | | 100 | | R-8 | | | | | | |
| 445 | 40 | | | 60 | 8-50/4" (Refusal) | SPT_8 | | | | | | |
| 440 | 45 | | | | | | | | | | Borehole completed at 40.83 feet below ground surface (bgs). | |
| 435 | 50 | | | | | | | | | | | |
| 430 | 55 | | | | | | | | | | | |

JOB NO. 0-1854-01 DATE 7/8/86

LOCATION See Fig. 1

PROJECT Geren Island Water Intake Facilities

INSPECTOR D. Hilts

WEATHER Sunny, warm

FIELD LOG OF TEST PIT 1

| SOIL DESCRIPTION & REMARKS | GROUND WATER | SAMPLES | DEPTH IN FEET | SKETCH OF S PIT SIDE | |
|--|--------------|---------|---------------|-----------------------------|-------------------|
| | | | | HORIZONTAL DISTANCE IN FEET | SURFACE ELEVATION |
| Silty SAND - Dense, brown, fine to medium. | None | | | 2 4 6 8 10 12 | 479.8 ft. |
| Sandy GRAVEL - Fine to coarse. | 1.6 | | | | |
| Sandy GRAVEL - Dense, brown, coarse, subround gravel with occasional cobbles. Sand fraction fine to medium, trace of silt. | 2.0 | | | | |
| Sandy GRAVEL - Silty, fine, subround. | 4.0 | | | | |
| Sandy GRAVEL - Same as 2-4 ft. | 4.3 | | | | |
| Silty SAND - Dense, brown and gray-brown, fine, occasional fine gravel. | 4.7 | | | | |
| Bottom of test pit | 6.0 | | | | |

Silty SAND

Sandy GRAVEL

Sandy GRAVEL - Dense, brown, coarse, subround gravel with occasional cobbles. Sand fraction fine to medium, trace of silt.

Sandy GRAVEL - Silty, fine, subround.

Sandy GRAVEL - Same as 2-4 ft.

Silty SAND - Dense, brown and gray-brown, fine, occasional fine gravel.

Bottom of test pit

Silty SAND

Sandy GRAVEL

Sandy GRAVEL

Sandy GRAVEL

Sandy GRAVEL

Silty SAND

Top of dike

Ground surface at toe of dike

SHANNON & WILSON, INC.
GEOTECHNICAL CONSULTANTS

FIELD LOG OF TEST PIT 2

JOB NO. 0-1854-01

DATE 7/8/86

LOCATION See Fig. 1

PROJECT Geren Island Water Intake Facilities

INSPECTOR D. Hilts

WEATHER Sunny, warm

| SOIL DESCRIPTION & REMARKS | GROUND WATER | SAMPLES | DEPTH IN FEET | SKETCH OF N PIT SIDE | HORIZONTAL DISTANCE IN FEET | SURFACE ELEVATION |
|--|---------------------------------------|---------|---------------|----------------------|-----------------------------|-------------------|
| Sandy GRAVEL - Dense, brown, fine to coarse, subround gravel and fine to medium sand. Trace of silt. Many cobbles, occasional voids. Many roots in upper 2 ft. | None | 1 | 2 | | 0 | 479.9 ft. |
| | SAND & GRAVEL - Gray, fine to coarse. | 2.5 | 2 | | 4 | 12 |
| SAND - Dense, brown, fine to medium with some coarse, slightly silty. Occasional pieces of fine to coarse gravel. | 3.1 | | | | | |
| Bottom of test pit | 7.5 | | | | | |

FIG. 3

JOB NO. 0-1854-01 DATE 7/8/86 LOCATION See Fig. 1
PROJECT Geren Island Water Intake Facilities
INSPECTOR D. Hilts WEATHER Sunny, warm

FIELD LOG OF TEST PIT 3


| SOIL DESCRIPTION & REMARKS | GROUND WATER | SAMPLES | DEPTH IN FEET | SKETCH OF <u>W</u> PIT SIDE | | SURFACE ELEVATION <u>480.0</u> ft. |
|---|--------------|---------|---------------|---|--|------------------------------------|
| | | | | HORIZONTAL DISTANCE IN FEET | | |
| Silty SAND - Loose to medium dense, brown, fine, trace of gravel, occasional roots. | None | | |  | | |
| Silty SAND - Dense, gray with brown mottling, fine to medium, occasional pieces of wood. | 1.5 | | 2 | | | |
| Silty SAND - Medium dense to dense, dark gray, fine to medium with some coarse. Occasional coarse gravel and cobbles. | 2.5 | | 4 | | | |
| | | | 6 | | | |
| | | | 8 | | | |
| | | | 10 | | | |
| | | | 12 | | | |
| Bottom of test pit | 7.5 | Bag | | | | |
| Note: Test pit located in area that reportedly washed out during flooding in 1965. | | | | | | |

FIG. 4

JOB NO. 0-1854-01 DATE 7/8/86 LOCATION See Fig. 1
PROJECT Geren Island Water Intake Facilities
INSPECTOR D. Hilts WEATHER Sunny, warm

FIELD LOG OF TEST PIT 4

| SOIL DESCRIPTION & REMARKS | GROUND WATER | SAMPLES | DEPTH IN FEET | SKETCH OF E PIT SIDE SURFACE ELEVATION 478.8 ft. HORIZONTAL DISTANCE IN FEET |
|---|--------------|---------|---------------|--|
| Sandy GRAVEL - Loose to medium dense, brown, coarse, subrounded gravel and fine to medium sand, slightly silty. | 5.6 | | | |
| Bottom of test pit | | | | |


FIG. 5

JOB NO. 0-1854-01 DATE 7/8/86 LOCATION See Fig. 1
PROJECT Geren Island Water Intake Facilities
INSPECTOR D. Hilts WEATHER Sunny, warm

FIELD LOG OF TEST PIT 5

| SOIL DESCRIPTION & REMARKS | GROUND WATER | SAMPLES | DEPTH IN FEET | SKETCH OF W PIT SIDE | | SURFACE ELEVATION |
|--|--------------|---------|---------------|-----------------------------|---------------------------|-------------------|
| | | | | HORIZONTAL DISTANCE IN FEET | VERTICAL DISTANCE IN FEET | |
| <p>Sandy GRAVEL - Medium dense, brown, fine to coarse, subround gravel and fine to coarse sand, trace of silt. Abundant cobbles and occasional boulders to 16 ins.</p> | <p>5.0</p> | | | 2 | 2 | 480.0 ft. |
| | | | | 4 | 4 | |
| <p>Bottom of test pit</p> <p>Note: Pit located at south abutment of new intake structure; north abutment was inaccessible.</p> | | | | 6 | 6 | |
| | | | | 8 | 8 | |
| | | | | 10 | 10 | |
| | | | | 12 | 12 | |
| | | | | 14 | 14 | |
| | | | | 16 | 16 | |
| | | | | 18 | 18 | |
| | | | | 20 | 20 | |
| | | | | 22 | 22 | |
| | | | | 24 | 24 | |

FIG. 6



Site Plan Provided By:



Black & Veatch

- TP-NO. OR BH-NO. TEST PIT OR BOREHOLE LOCATION CONDUCTED BY FOUNDATION ENGINEERING, INC. JULY 1996
- SWTP-NO. TEST PIT FROM SHANNON & WILSON STUDY IN 1986.
- AGBH-NO. BOREHOLE LOCATION FROM APPLIED GEOTECHNOLOGY STUDY IN 1993.
- MJB-NO. APPROXIMATE BOREHOLE LOCATION FROM MCMILLEN JACOBS STUDY IN 2019.

FIGURE 1. SITE PLAN (LOCATIONS OF TEST PITS AND BORINGS).




GEREN ISLAND TREATMENT FACILITY IMPROVEMENTS

MARION COUNTY, OREGON



APPENDIX N

EXISTING INFORMATION
CENTER STREET BRIDGE
CROSSING

DRAFT



GENERAL NOTES:
 Bridge designed for H20-S16-44 loading.
 All concrete shall be Class "A" and shall have a breaking strength of 3300 lbs. per square inch in 28 days ($f_c = 1320$ p.s.i.)
 All reinforcing steel shall be intermediate grade deformed bars conforming with A.S.T.M. specification A305-50T. All splices shall be 20 diameters unless shown or noted otherwise, except $\frac{1}{2}$ " bars which shall be applied 35 diameters.
 All piling except at bents 22, 23 & 24 shall be treated timber piling. At bents 22, 23 & 24 the piling shall be 12" BP 53" steel piling. For handrail posts use alternate post cap.



FOR INFORMATION ONLY

Approved: *[Signature]*
 Bridge Engineer











3-11-69 Rev. Span Nos.

OREGON
 STATE HIGHWAY COMMISSION
CENTER ST. BRIDGE
 OVER
 WILLAMETTE RIVER
 AT SALEM - MARION & POLK CO.

SCALES NOTED
 OCTOBER 15, 1951
 CALC. BK. 254 & 275 CHECKED BY
 ACCOMPANIED BY DRWGS. NO. 10087 TO 10108 INCL.,
 2050 & 9233.

DRAWN BY T.C.R.
 TRACED BY C.Q.F.

SHEET 1 OF 25
 BRIDGE NO. 1234
 DRAWING NO. 10086




FOR INFORMATION ONLY



Approved:

Bridge Engineer

OREGON
STATE HIGHWAY COMMISSION
CENTER STREET BRIDGE
EAST APPROACH
RETAINING WALLS

| | | |
|----------------|------------------|-------------------|
| SCALE AS NOTED | DRAWN BY T.C.R. | SHEET 2 OF 25 |
| MAY 18, 1951 | TRACED BY E.H.W. | BRIDGE NO. 123-A |
| CHECKED BY | | DRAWING NO. 10087 |









OREGON
STATE HIGHWAY COMMISSION
**CENTER STREET BRIDGE
WEST APPROACH**
PIER NO. 8 - BENTS NO. 11, 12 & 13
SCALE AS NOTED
SEPTEMBER 26, 1952
CHECKED BY

DRAWN BY T.C.R.
TRACED BY W.D.G.


SHEET 14 OF 25
BRIDGE NO. 123A
DRAWING NO. 10099




PLAN OF SPANS No. 20-21-22-23 & 24
Scale 1/8"=1'-0"




ELEVATION SPANS No. 23 & 24
Scale 1/8"=1'-0"



SECTION C-C BENT No. 24
Scale 1/4"=1'-0"







LONGITUDINAL SECTION OF SPANS No. 23 & 24
Scale 1/4"=1'-0"




FOR INFORMATION ONLY


Approved:
[Signature]
Bridge Engineer


OREGON
STATE HIGHWAY COMMISSION
CENTER STREET BRIDGE
WEST APPROACH
SPANS 20, 21, 22, 23 & 24
SCALE AS NOTED
APRIL 4, 1952
CHECKED BY
DRAWN BY T.C.R.
TRACED BY C.O.F.
SHEET 16 OF 25
BRIDGE NO. 123A
DRAWING NO. 10101



Approved: 
Bridge Engineer

| | | |
|----------------|------------------|-------------------|
| SCALE AS NOTED | DRAWN BY T.C.R. | SHEET 18 OF 25 |
| APRIL 28, 1952 | TRACED BY C.O.F. | BRIDGE NO. 123A |
| CHECKED BY | | DRAWING NO. 10103 |





GENERAL NOTES

All material and workmanship shall conform to Standard Specifications for Highway Construction of the Oregon State Highway Division.

Bridge designed for HS20-44 loading with an allowance of 15 psf for future wearing surface.

Concrete box girder spans designed by Load Factor Design Method. Concrete strengths shall be as shown in adjoining table.

All structural steel shall conform to ASTM Specifications in accordance with detail plans. All bolts at structural connections shall be 7/8" dia. high strength bolts conforming to ASTM Specifications A325.

All reinforcing steel shall conform to ASTM Specification A615. Bars no. 3 thru no. 5 shall be grade 40 ($f_s = 20,000$ psi). Bars no. 6 thru 11 shall be grade 60 ($f_s = 24,000$ psi). The following splice lengths shall be used unless shown otherwise. Bars no. 3 thru no. 5 shall be lapped 24 diameter or a minimum of 1'-0", bars no. 6 and 7 shall be lapped 38 dia. bars no. 8 and 9 shall be lapped 48 dia. bars no. 10 and 11 shall be lapped 60 dia. at all splices unless noted or shown otherwise. All bars shall be placed 2" clear of nearest face of concrete unless shown or noted otherwise. The top bends of stirrups extending from beam stems into the top slab may be shop or field bent, unless shown or noted otherwise.

Reinforcing steel for columns and walls shall not be fabricated until final footing elevations have been determined in the field.


Required footing bearings:
Bent 1: 1.2 ton/ft²
Bents 2 thru 5: 6.0 ton/ft²
Pier 1: 3.4 ton/ft²

| CONCRETE STRENGTHS | |
|---------------------------|---------------------------------|
| Box Stems and Bottom Slab | 3300-1" |
| Deck | 4000-1 1/2" |
| All Other Concrete | 3300-1 1/2" ($f_c = 1320$ psi) |

AS CONSTRUCTED
8-30-77








* Accompanied by dwg. no's.
29878, 30743 thru 30757, 2070, 22970, 23836, 2127, 27155, 2126 & 2126A
Drawing Numbers 10086, 10090, 10091, 10094, 10095 & 10096 of existing structure to accompany this set of plans, for information only.

| | | | |
|---|--|---|--|
| APPROVED: <i>Walter J. Bunt</i> BRIDGE ENGINEER | | OREGON STATE HIGHWAY DIVISION BRIDGE SECTION | |
| DESIGNED: W.M.T. CHECKED: WRP DRAWN: J.H. | | CENTER TO FRONT SO. BOUND OFF RAMP CENTER ST. BRIDGE (FRONT ST. OFF RAMP) SEC. WILLAMINA - SALEM HWY. MARION. Co. | |
| DATE: June 1975 ACCOMPANIED BY DWGS. * See above | | PLAN AND ELEVATION SHEET 1 OF 24 DRAWING NO. 30742 | |



| | | | |
|---|--|---|--|
| APPROVED: <i>Wally Plant</i> BRIDGE ENGINEER | | OREGON STATE HIGHWAY DIVISION BRIDGE SECTION | |
| DESIGNED: M. Thompson DRAWN: C.R. Poole CHECKED: W.R. Pease REVIEWED: J.M. Tindall 11/1/75 REVIEWED: L.L. Waller 11/1/75 CALC. BOOK No. 1588 | | CENTER TO FRONT SB OFF RAMP | |
| DATE _____ REVISION _____ | | FOOTING PLAN | |
| DATE June 1975 | | SHEET 3 OF 24 | |
| BRIDGE NO. 123 G | | DRAWING NO. 30743 | |



AS CONSTRUCTED
8-30-77



PERSPECTIVE - AT VIEW - EE

AS CONSTRUCTED
8-30-77

| | | | |
|---|--|---|--|
| APPROVED: <i>Walter J. Wadant</i> BRIDGE ENGINEER | | OREGON STATE HIGHWAY DIVISION BRIDGE SECTION | |
| DESIGNED: W. M. Thompson DRAWN: W. M. Thompson CHECKED: W. R. Pease REVIEWED: J. M. Tindall CALC. BOOK No. 1588 | | CENTER TO FRONT SB OFF RAMP | |
| DATE | | BENT-1 DETAILS | |
| REVISION | | DATE June 1975 | |
| | | BRIDGE NO. 123G | |
| | | SHEET 12 OF 24 | |
| | | DRAWING NO. 30752 | |









BAR LENGTHS

| a | b | c | d | e | f | g | h | j | k | m |
|--------|--------|---------|--------|--------|--------|--------|--------|---------|--------|--------|
| 27'-4" | 27'-7" | 27'-10" | 28'-1" | 28'-4" | 28'-7" | 24'-4" | 24'-7" | 24'-10" | 25'-1" | 25'-4" |

See bar arrangement above

COLUMN STEEL

32-#9 Vertical column bars with a standard 90° hook at bottom. Stop bars 8" from top of deck.
#4 Hoops & ties as noted.



APPROVED: *Walter Plant*
BRIDGE ENGINEER

DESIGNED: *M. Thompson*
DRAWN: *C.R. Poole*
CHECKED: *W.R. Pease*
REVIEWED: *M. Tisdall*
CALC BOOK: *No. 1588*

| DATE | REVISION |
|------|----------|
| | |
| | |
| | |
| | |

OREGON STATE HIGHWAY DIVISION
BRIDGE SECTION

CENTER TO FRONT SB OFF RAMP

DETAILS BENT-5

DATE: August, 1975
BRIDGE NO. 123 G

SHEET 15 OF 24
DRAWING NO. 30755

BRIDGE

DRAWING NUMBER


EAST APPROACH ----- 37002 - 37040

RIVER SPANS ----- 37041 - 37070

RIVER SPANS (STEEL ALTERNATE) ----- 37071 - 37082

WEST APPROACH ----- 37083 - 37129

DETOUR STRUCTURE ----- 37138 - 37142

ACCOMPANIED BY DRAWINGS ----- 2070, 2105, 2117, 2127,
27155, 30937, 30938,
30939, 30940, 31117, 31275
31600, 31724, 31825, 34880
34903, 34949, 34959, 35010
37143, 37144DRAWINGS FOR INFORMATION ONLY ----- 459-463, 10086-10108
9233, 30031-30039,
30742-30757
35968, 35969, 35972

GENERAL NOTES

All material and workmanship shall conform to the Standard Specifications for Highway Construction of the Oregon State Highway Division.

The river spans and bridge widening are designed for HS25 loading with an allowance of 25 psf for present and 25 psf for future wearing surface.

Concrete members, except prestressed members, designed by Load Factor Design Method.

Prestressing steel shall be in accordance with detail plans.

All other reinforcing steel shall conform to ASTM Specification A615(S1) Grade 60. The following splice lengths shall be used unless shown otherwise:

| BAR SIZE | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 14 & 18 |
|---------------|-------|-------|-------|-------|-------|-------|-------|-------|-------|---------------|
| SPLICE LENGTH | 1'-0" | 1'-4" | 1'-8" | 2'-0" | 2'-9" | 3'-7" | 4'-7" | 5'-9" | 7'-1" | Not Permitted |

All bars shall be placed 2" clear of the nearest face of concrete, unless shown otherwise. The top bends of stirrups extending from beam stems into the top slab may be shop or field bent.

All reinforcing steel in the upper portion of the deck shall be epoxy coated. This includes all top longitudinal bars, all top transverse bars, all transverse bent bars, all bars extending from the deck into the parapet or curb, and all other bars noted on the detail plans. Bike W Spans 12 thru 19 shall have no epoxy coated reinforcing.

Reinforcing steel for columns and walls shall not be fabricated until final footing elevations have been determined in the field.

All structural steel shall conform to ASTM Specifications in accordance with detail plans. In place of ASTM A588, ASTM A572 grade 50 may be used for plates 2 inches thick and under.

All bolts at structural connections shall be 7/8" dia. high strength bolts conforming to ASTM Specification A325, unless shown otherwise.

Concrete in the post-tensioned box girder superstructure of Spans 2R-5R shall be as shown on the detail plans.

Concrete in the deck, except Spans 2R-5R conc. alternate, shall be Class 4500-3/4".

Concrete in crossbeams of bents 2 thru 10 and 11 thru 25 shall be Class 4000-3/4".

Concrete in columns of bents 2 thru 10 and 11 thru 25 shall be Class 4000-1-1/2".

Concrete in the bottom slab and stems of box girders of Spans 2 thru 10 and Span 1R, and the stems of Spans 11 thru 26 shall be Class 3300-3/4".

All other concrete shall be Class 3300-1 1/2".

Piling shall be as noted on the detail plans, in the Special Provisions and as called out below.

RIVER SPANS

All piling in Piers 2 thru 6 shall be HP14x73 steel piling driven to a minimum bearing of 110 tons per pile. An acceptable alternate is HP12x74 steel piling.

All piling at Piers 5 and 6 shall have reinforced tips.

WEST APPROACH

All piling in Bents 11 thru 25 shall be one of the following three options A, B, or C and shall be driven to the minimum bearing specified on the detail plans.


- A. 12" nom. steel shells for cast in place concrete piling.
- B. 12" square prestressed concrete piling, see dwg. 31825.
- C. 14" octagonal prestressed concrete piling, see dwg. 31825.

Gradelines and elevations shown on these plans were determined from "As Constructed" plans of the existing bridge and are to be verified in the field.

Where the new bridge construction is dependent on existing bridge dimensions shown on these plans, the contractor shall verify their accuracy before starting construction or fabrication of materials.

For general notes relative to the Detour Structure, see dwg. no. 37138.

| | |
|--|---|
| APPROVED <i>Nathaniel</i> STRUCTURAL DESIGN ENGINEER P.E. DESIGNED DRAWN <i>J. Hardin</i> CHECKED REVIEWED <i>J.M. Trudell 7/6/82</i> REVIEWED <i>L.B. Waller 7/6/82</i> CALC. BOOK | OREGON DEPARTMENT OF TRANSPORTATION STRUCTURAL DESIGN SECTION WILLAMETTE RIV. CENTER ST. BRIDGE WILLAMETTE RIV. (CENTER ST) BRIDGE SEC. WILLAMINA-SALEM HIGHWAY POLK AND MARION COUNTIES |
| INDEX | |
| ACCOMPANIED BY DWGS. See above | |
| DATE May, 1982 BRIDGE NO. 123K | SHEET 1 OF 155 DRAWING NO. 37001 |



APPROVED: *Walter Hunt*
STRUCTURAL DESIGN ENGINEER

550-1-53 *Shike*

DESIGNED Stike
DRAWN Hardin

DRAWN 12/1/81
CHECKED _____

REVIEWED: J.M. Tindall 7/1/11

REVIEWED L.L. Wallace 7/6/88

CALC BOOK

| DATE | REVISION |
|------|----------|
|------|----------|

| DATE | REVISION |
|------|----------|
| | |

[illegible]

| | |
|--|--|
| | |
| | |

| | |
|--|--|
| | |
| | |

| | |
|--|--|
| | |
|--|--|

| | |
|--|--|
| | |
| | |

| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|-----|
| 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16 | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 | 32 | 33 | 34 | 35 | 36 | 37 | 38 | 39 | 40 | 41 | 42 | 43 | 44 | 45 | 46 | 47 | 48 | 49 | 50 | 51 | 52 | 53 | 54 | 55 | 56 | 57 | 58 | 59 | 60 | 61 | 62 | 63 | 64 | 65 | 66 | 67 | 68 | 69 | 70 | 71 | 72 | 73 | 74 | 75 | 76 | 77 | 78 | 79 | 80 | 81 | 82 | 83 | 84 | 85 | 86 | 87 | 88 | 89 | 90 | 91 | 92 | 93 | 94 | 95 | 96 | 97 | 98 | 99 | 100 |
|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|-----|

10

1

OREGON DEPARTMENT OF TRANSPORTATION
STRUCTURAL DESIGN SECTION

WILLAMETTE RIVER
CENTER STREET BRIDGE SECTION
WILLAMINA SALEM HWY.
POLK & MARION COUNTIES.



PLAN

| | |
|------------------------|------------------------------|
| DATE <u>May, 1982</u> | SHEET <u>2</u> OF <u>155</u> |
| BRIDGE NO. <u>123K</u> | DRAWING NO. <u>37002</u> |

END OF TEST _____




17-1

—




* NOTE:
Existing Bent 4 to be eliminated
and existing Spans 3, 4, & 5 to
be replaced with 2 spans (3 & 5).

FOR INFORMATION
ONLY



| | | | |
|---|--|--|--|
| APPROVED: <i>Walter J. Silbernagel</i> STRUCTURAL DESIGN ENGINEER | | OREGON DEPARTMENT OF TRANSPORTATION STRUCTURAL DESIGN SECTION | |
| DESIGNED: W.M. Thompson DRAWN: J. Silbernagel CHECKED: R. Page REVIEWED: J. H. Tisdall CALC. BOOK: 1832 | | WILLAMETTE RIVER (CENTER STREET) BRIDGE | |
| DATE: 9-7-82 REVISION: 9-7-82 Min. Vert. Clear. | | PLAN & ELEVATION - EAST APPROACH | |
| DATE: May, 1982 BRIDGE NO.: 123K | | SHEET: 3 OF 155 DRAWING NO.: 37003 | |



NOTE:



Scale: $\frac{1}{4}" = 1'-0"$

Bottom Mat
23'-7bars x 9'-0" @ 6" ctrs.
10'-7bars x 11'-0" @ 12" ctrs



Scale: $\frac{1}{4}'' = 1'-0''$

APPROVED: Walter H. Hantke
STRUCTURAL DESIGN ENGINEER
DESIGNED W.M. Thompson
DRAWN J. Silbernagel
CHECKED Page
REVIEWED J.M. Tindall 7/6/87
REVIEWED L.L. Walling 7/6/87
CALC BOOK 1832


OREGON DEPARTMENT OF TRANSPORTATION
STRUCTURAL DESIGN SECTION

(CENTER STREET) BRIDGE




DATE May, 1982
BRIDGE NO. 123K

SHEET 25 OF 155
DRAWING NO. 37025









| APPROVED: <i>Walter Hunt</i> STRUCTURAL DESIGN ENGINEER | OREGON DEPARTMENT OF TRANSPORTATION STRUCTURAL DESIGN SECTION | | | | | | | | | | | | | | | |
|--|--|----------|--|--|--|--|--|--|--|--|--|--|--|--|----------------|--|
| DESIGNED <i>W. M. Thompson</i> DRAWN <i>J. Silbernagel</i> CHECKED <i>Page</i> REVIEWED <i>J. M. Todall 7/6/82</i> REVIEWED <i>J. C. Wall 9/21/82</i> CALC. BOOK <i>1832</i> | WILLAMETTE RIVER (CENTER STREET) BRIDGE | | | | | | | | | | | | | | | |
| <table border="1"> <thead> <tr> <th>DATE</th> <th>REVISION</th> </tr> </thead> <tbody> <tr><td> </td><td> </td></tr> <tr><td> </td><td> </td></tr> <tr><td> </td><td> </td></tr> <tr><td> </td><td> </td></tr> <tr><td> </td><td> </td></tr> <tr><td> </td><td> </td></tr> </tbody> </table> | DATE | REVISION | | | | | | | | | | | | | BENT-5 DETAILS | |
| DATE | REVISION | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | |
| DATE <i>May, 1982</i> BRIDGE NO. <i>123K</i> | SHEET <i>27</i> OF <i>155</i> DRAWING NO. <i>37027</i> | | | | | | | | | | | | | | | |




NOTES:


Support existing beams on falsework with a minimum capacity of:
20 tons per beam (Bent 6)



NOTE:
See dwg. # 37028⁷⁶ For location
of Sections A-A, B-B, & C-C.









| | | |
|---|--|--|
| APPROVED: <i>Walter J. Blunt</i> STRUCTURAL DESIGN ENGINEER | OREGON DEPARTMENT OF TRANSPORTATION STRUCTURAL DESIGN SECTION | |
| DESIGNED <i>W. M. Thompson</i> DRAWN <i>J. Silbernagel</i> CHECKED <i>Page</i> REVIEWED <i>M. Fordall</i> REVIEWED <i>J. Wallace 7/6/82</i> CALC. BOOK <i>1832</i> | WILLAMETTE RIVER (CENTER STREET) BRIDGE | |
| DATE _____ REVISION _____ _____ _____ _____ _____ _____ _____ _____ _____ _____ | BENT 6 DETAILS | |
| DATE <i>May, 1982</i> BRIDGE NO. <i>123K</i> | SHEET <i>29</i> OF <i>155</i> DRAWING NO. <i>37029</i> | |






FOR INFORMATION
ONLY

| | | | |
|---|--|--|--|
| APPROVED: <i>Walter M. Thompson</i> STRUCTURAL DESIGN ENGINEER | | OREGON DEPARTMENT OF TRANSPORTATION STRUCTURAL DESIGN SECTION | |
| DESIGNED: W.M. Thompson DRAWN: J. Silbernagel CHECKED: Edge REVIEWED: W.M. Tipton 7/6/82 REVIEWED: L.L. Wallace 7/6/82 CALC. BOOK 1832 | | WILLAMETTE RIVER (CENTER STREET) BRIDGE | |
| DATE REVISION 4-26-83 Stress Rds removed 4-26-83 Cal. & Eng. added | | ELEVATION - BENT 10 | |
| DATE May, 1982 BRIDGE NO. 123K | | SHEET 34 OF 155 DRAWING NO. 37034 | |




NOTE - A:
Cut 6" ϕ holes in existing deck ea. end ea bay. Pour beam widening to bottom of deck. After concrete has taken initial set revibrate and finish pour to top of deck.

NOTE - B:
Drill 1" ϕ holes for #4 bars @ 12" ctrs. btwn. beams, ctr. Use non-impact type drill.



FOR INFORMATION ONLY
SECTION Y-Y


| | | | |
|---|--|--|--|
| APPROVED: STRUCTURAL DESIGN ENGINEER | | OREGON DEPARTMENT OF TRANSPORTATION STRUCTURAL DESIGN SECTION | |
| DESIGNED: W.M. Thompson DRAWN: J. Silbernagel CHECKED: Page REVIEWED: J. Silbernagel 7/6/82 CALC. BOOK: 1832 | | WILLAMETTE RIVER (CENTER STREET) BRIDGE | |
| DATE: 4-26-83 REVISION: Added Far Lr. col. & fig. | | BENT 7, 8, 9, & 10 DETAILS | |
| DATE: May, 1982 BRIDGE NO.: 123K | | SHEET 35 OF 155 DRAWING NO. 37035 | |



NOTE:
Looking back on Station.
Box girder, Reinf. conc. end
panel omitted.

PLAN - BENT "CF"-1


Scale: 1/4"=1'-0"




ELEVATION - BENT "CF"-1

Scale: 1/4"=1'-0"
(Looking back on Station)

NOTE:
See "Cap Detail" dwg.
#37021 for details.




VIEW A-A




VIEW B-B

NOTE:
See Sections C-C thru E-E
dwg. #37039.




TYPICAL SECTION - WINGWALL

Scale: 1/2"=1'-0"




DETAIL - "A"



WINGWALL - BENT "CF"-1

Scale: 3/8"=1'-0"



X-BEAM - BENT "CF"-1

Scale: 1/2"=1'-0"

APPROVED:
Walter J. Want
STRUCTURAL DESIGN ENGINEER
DESIGNED: M. Thompson
DRAWN: J. Silbernagel
CHECKED: Page
REVIEWED: J. M. Tidwell 7/6/82
CALC. BOOK: 1832

OREGON DEPARTMENT OF TRANSPORTATION
STRUCTURAL DESIGN SECTION

WILLAMETTE RIVER
(CENTER STREET) BRIDGE


PLAN & ELEVATION - BENT "CF"-1

DATE: May, 1982
BRIDGE NO. 123K

SHEET 36 OF 155
DRAWING NO. 37036


HYDRAULIC DATA

| | Design Flood | Intermediate Regional Flood | Max. Regulated Flood Year (1964) |
|---------------------------------|--------------|-----------------------------|----------------------------------|
| Discharge - $\frac{cfs}{m^3/s}$ | 244,000 | 279,000 | 308,000 |
| Frequency - Years | 50 | 100 | 100 + |
| HW Elevation ft. | 140.4 | 142.8 | 143.9 |
| Natural Channel m | | | |




PLAN RIVER SPANS

Scale: 1"=50'




ELEVATION - RIVER SPANS

Scale: 1"=50'-0"



GRADELINE - RIVER SPANS

No Scale



APPROVED: *Walter J. Shike*
STRUCTURAL DESIGN ENGINEER
DESIGNED: T. Shike
DRAWN: J. Silbernagel
CHECKED: P. Rabb
REVIEWED: L. M. Tindall
CALC. BOOK: 1832



OREGON DEPARTMENT OF TRANSPORTATION
STRUCTURAL DESIGN SECTION

WILLAMETTE RIVER (CENTER STREET) BRIDGE

PLAN AND ELEVATION - RIVER SPANS

DATE: May, 1982
BRIDGE NO.: 123K

SHEET 41 OF 155
DRAWING NO. 37041



| CORE | RECOVERY |
|------|----------|
| C-1 | 80% |
| C-2 | 20% |
| C-3 | 17% |
| C-4 | 0 |


Foundation data shown on this drawing, in some instances, is a consolidation of and a revision in terminology from the original field drilling logs. The original field drilling logs are available for review in the office of the Bridge Engineer in Salem.


Elevations of bottom of existing piers shown are approximate only.


LEGEND OF MATERIALS




- | | | | | | | |
|----------------------------------|----------|---------------------------------------|---------------------------------------|--|---------------|---|
| 1 Gravels, cobbles and boulders. | 3 Silts. | 5 Silty gravels, gravel-silt mixture. | 7 Clayey gravel, gravel-clay mixture. | 9 Silty clay. | 11 Sandstone. | 13 Basalt rock, broken, solid, weathered, lava. |
| 2 Sand. | 4 Clays. | 6 Silty sand, sand-silt mixture. | 8 Clayey sand, sand-clay mixture. | 10 Sand-silt-clay mixture, near equal proportions. | 12 Shale. | 14 |

| | | | |
|--|--|---|--|
| APPROVED <i>Walter Plant</i> BRIDGE ENGINEER | | OREGON STATE HIGHWAY DIVISION BRIDGE SECTION | |
| DESIGNED DRAWN CHECKED REVIEWED CALC. BOOK | | WILLAMETTE RIVER (CENTER STREET) BRIDGE | |
| DATE | | REVISION | |
| DATE 12-4-80 | | SHEET 42 OF 155 | |
| BRIDGE NO. 123K | | DRAWING NO. 37042 | |












| DATE | REVISION |
|------|----------|
| | |
| | |
| | |
| | |
| | |
| | |

WILLAMETTE RIVER
(CENTER STREET) BRIDGE
STEEL ALTERNATE




DATE MAY 1982
BRIDGE NO. 123K

SHEET 71 OF 155
DRAWING NO. 37071



COLUMN STEEL

Column steel, columns & footings are same as piers 2 & 6 see dwg. nos. 37056 & 37059 for details.



NOTE
Section AA & BB are the same as those shown on dwg. no. 3707B except note the difference in stirrup & bar sizes for piers 2 & 6

| | | |
|---|---|--|
| APPROVED: <i>Walter J. Hunt</i> BRIDGE ENGINEER | OREGON DEPARTMENT OF TRANSPORTATION BRIDGE DESIGN SECTION | |
| DESIGNED <i>R. L. Malcom</i> DRAWN <i>J. Hardin</i> CHECKED <i>P. Rabb</i> REVIEWED <i>M. J. ...</i> REVIEWED <i>L. A. Wallace 7/6/82</i> CALC. BOOK <i>1832</i> | WILLAMETTE RIVER (CENTER STREET) BRIDGE STEEL ALTERNATE | |
| DATE | REVISION | PIER 2 OR 6 DETAILS |
| | | |
| | | |
| | | |
| | | |
| DATE <i>May, 1982</i> BRIDGE NO. <i>123K</i> | | SHEET <i>76 OF 155</i> DRAWING NO. <i>37076</i> |

COLUMN STEEL

84-no. 11 vertical column bars
with 3 std. 90° hook footing end.

54-no. 11 vertical column
dowels with a std. 90° hook
footing end. Place dowels
as inner row in flat faces
of column $5\frac{1}{2}$ " from vert.
column bars. Dowel lengths
are as follows:

| | |
|-------------|--------------------------------|
| 4 x 20'-9" | } Stopped with column verts |
| 4 x 33'-6" | |
| 4 x 46'-3" | |
| 42 x 60'-0" | |

Stop no. 11 column bars
and dowels as shown.

no. 5 hoops at 4" or 12" ctrs
as shown.

no. 5 tie bars at 12" ctrs.
See Section C-C, dwg. no.
37078 for details.

12'-9"

4 col. bars
4 col. dowels

12'-9"

Stop 4 col. bars
Stop 4 col. dowels

-17-no. 11 col. bars to match
col. batter typ. ea. side

Elev. 88.0

Elev. 78.0 =

ELEVATION PIERS 3,4,5

An approved mechanical splice

The diagram shows a horizontal line with a vertical tick mark in the center. To the left of the center, there are two more tick marks, and to the right, there are two more. This divides the line into four equal segments. The first segment on the left is labeled $3'-0''$, and the first segment on the right is also labeled $3'-0''$.

Mid-height \pm (Minimum el. 125.0)

no. 5 hoops and ties at 12" max. ctrs
stop steel 1'-0" from top of cross beam

✓ mid height of col. \pm

43-Spc's at 4" = 14'-4"
no. 5 hoops
no. 5 ties at 12" ct

NOTE
For sections A-A, B-B & C-C see dwg. no. 37078.

| | | |
|--------|--------|--------|
| 7'-1" | 7'-1" | 7'-1" |
| Splice | Splice | Splice |

Use 4" hoop spacing for lap splice.

Min. Elev. 115.0

APPROVED: *Walter Blank* R-2
BRIDGE ENGINEER
DESIGNED *R. L. Malcom*
DRAWN *J. Hardin*
CHECKED *P. Rabb*
REVIEWED *L. M. Tye* *all 7/1/78*
REVIEWED *L. L. Wolfe* *7/6/78*
CALC. BOOK *1832*

OREGON DEPARTMENT OF TRANSPORTATION
BRIDGE DESIGN SECTION




WILLAMETTE RIVER
(CENTER STREET) BRIDGE

STEEL ALTERNATE

PIER 3, 4 & 5 DETAILS

DATE May, 1982
BRIDGE NO. 123K






SHEET 77 OF 155
DRAWING NO. 37077



Note
For sections A-A, B-B & C-C locations, see dwg. no. 37077


no. 5 at about 12" ctrs ea. way
no. 5 U-bars w/1'-0" legs at 12" ctrs all around footing


56-HPI 4 x 73 or HPI 12 x 74 (All with reinforced tips, see dwg. 37058)




NOTE
For sign bridge details see dwg. no. 37136, 30937, 30938, 30939 & 30940.


| | | | |
|---|--|--|--|
| APPROVED: <i>Walt Plant</i> BRIDGE ENGINEER | | OREGON DEPARTMENT OF TRANSPORTATION BRIDGE DESIGN SECTION | |
| DESIGNED: R. L. Malcom | | WILLAMETTE RIVER (CENTER STREET) BRIDGE | |
| DRAWN: J. Hardin | | STEEL ALTERNATE | |
| CHECKED: P. Rabb | | PIER 3, 4 & 5 DETAILS | |
| REVIEWED: M. Tindall | | DATE: May, 1982 | |
| CALC. BOOK: 1832 | | BRIDGE NO. 123 K | |
| DATE: 7-21-83 | | SHEET 78 OF 155 | |
| REVISION: Correct tie no. 7-21-83 Inc. tie length | | DRAWING NO. 37078 | |








| | | | |
|---|--|--|--|
| APPROVED: <i>Walter A. Plant</i> STRUCTURAL DESIGN ENGINEER | | OREGON DEPARTMENT OF TRANSPORTATION STRUCTURAL DESIGN SECTION | |
| DESIGNED: <i>JD</i> | | WILLAMETTE RIVER | |
| DRAWN: <i>JD</i> | | (CENTER STREET) BRIDGE | |
| CHECKED: _____ | | FOUNDATION DATA | |
| REVIEWED: _____ | | DATE Jan. 1981 | |
| CALC. BOOK: _____ | | BRIDGE NO. 123K | |
| DATE _____ | | SHEET 85 OF 155 | |
| REVISION _____ | | DRAWING NO. 37085 | |













| | | | |
|---------------------------------|----------|-------------------------------------|--|
| APPROVED: <i>Walter H. Hant</i> | | OREGON DEPARTMENT OF TRANSPORTATION | |
| STRUCTURAL DESIGN ENGINEER | | STRUCTURAL DESIGN SECTION | |
| DESIGNED: G. Bellin | | WILLAMETTE RIVER | |
| DRAWN: J. Hardin | | (CENTER STREET) BRIDGE | |
| CHECKED: W. M. Thompson | | BENT BIKEY-13 DETAILS | |
| REVIEWED: J. M. Tisdall 7/1/82 | | DATE: May, 1982 | |
| REVIEWED: L. L. Walters 7/1/82 | | BRIDGE NO. 123K | |
| CALC. BOOK: 1832 | | SHEET 110 OF 155 | |
| DATE | REVISION | DRAWING NO. 37110 | |
| | | | |
| | | | |
| | | | |
| | | | |

BRUNING 44.131 38525




FOOTING PLAN BENTS-11 & 12
Scale: $\frac{1}{4}'' = 1'-0''$




FOOTING PLAN BENT-13
Scale: $\frac{1}{4}'' = 1'-0''$

NOTE-X
Provide $\frac{1}{2}''$ raised shear keys with an area about $\frac{1}{3}$ the area of the column cross section at all column construction joints.




SECTION C-C
Typical for columns (A) bents 11, 12 & 13





SECTION A-A
Scale: $\frac{3}{8}'' = 1'-0''$


See dwg. no. 37107, bent-11 & dwg. no. 37108, bent-12 for typ. wall section A-A & dwg. no. 37109, bent-13.





SECTION F-F Scale: $\frac{1}{2}'' = 1'-0''$
Taken at X-beam bent-11 see dwg. no. 37107


| | | | |
|---|--|--|--|
| APPROVED:  STRUCTURAL DESIGN ENGINEER | | OREGON DEPARTMENT OF TRANSPORTATION STRUCTURAL DESIGN SECTION | |
| DESIGNED <u>G. Bellin</u> DRAWN <u>J. Hardin</u> CHECKED <u>W. M. Thompson</u> REVIEWED <u>J. M. Tindall 7/1/82</u> REVIEWED <u>L. Wallace 7/6/82</u> CALC. BOOK <u>1832</u> | | WILLAMETTE RIVER (CENTER STREET) BRIDGE | |
| DATE < | | | |
















ELEVATION BENT-19
Scale: 1/4" = 1'-0"




BEARING PLAN BENT WC-16
Scale: 1/4" = 1'-0"



COLUMN STEEL

22-no. 8 vertical column bars with a std. 90° hook ftg. end. Stop bars 1'-6" from top of deck.
no. 4 hoops at 4" or 12" ctrs as shown
no. 4 ties at 12" vertical ctrs



FOOTING PLAN
Scale: 1/4" = 1'-0"


CONSTRUCTION SEQUENCE BENT 19


1. Support existing longitudinal beams for 45 ton capacity each side of existing Beam 19.
2. Cut columns and beam pedestals and remove existing Beam 19.
3. Remove Stage II portion of existing longitudinal and end beams and construct all of new Beam 19.
4. Construct Stage II portion of new longitudinal and end beams.
5. Complete Stage III portion of longitudinal and end beams after East bound traffic has been rerouted to new Center St. structure.

NOTE
For sections B-B, F-F, J-J & existing cross beam removal for bent WC-19 see dwg. no. 37122. See dwg. no. 37005 for detail reference numbers.


| | | | |
|--|--|--|--|
| APPROVED: <i>Walter H. Hent</i> STRUCTURAL DESIGN ENGINEER | | OREGON DEPARTMENT OF TRANSPORTATION STRUCTURAL DESIGN SECTION | |
| DESIGNED: G. Bellin DRAWN: J. Hardin CHECKED: W. M. Thompson REVIEWED: J. M. Indall 7/4/82 CALC. BOOK 1832 | | WILLAMETTE RIVER (CENTER STREET) BRIDGE | |
| DATE: 8-11-82 REVISION: Add const. sequence | | BENT-19 DETAILS | |
| BRIDGE NO. 123K | | SHEET 119 OF 155 DRAWING NO. 37119 | |





BRUNING 44-131 30925





| | | | |
|--|-----------|--|-------------------|
| APPROVED: <i>W. H. H. H.</i> STRUCTURAL DESIGN ENGINEER | | OREGON DEPARTMENT OF TRANSPORTATION STRUCTURAL DESIGN SECTION | |
| DESIGNED: G. Bellin | | WILLAMETTE RIVER | |
| DRAWN: J. Herdin | | (CENTER STREET) BRIDGE | |
| CHECKED: W. M. Thompson | | BENT-22 DETAILS | |
| REVIEWED: J. M. Tindall 1/16/82 | | DATE: May, 1982 | SHEET 125 OF 155 |
| REVIEWED: L. C. Wallace 7/6/82 | | BRIDGE NO. 123K | DRAWING NO. 37125 |
| CALC. BOOK: 1832 | | | |
| DATE: | REVISION: | | |





| APPROVED: <i>Walter Belmont</i> STRUCTURAL DESIGN ENGINEER | OREGON DEPARTMENT OF TRANSPORTATION STRUCTURAL DESIGN SECTION | | | | | | | | | | | | | | |
|--|---|----------|--|--|--|--|--|--|--|--|--|--|--|--|---|
| DESIGNED: <i>G.H. Bellin</i> DRAWN: <i>M.C. Young</i> CHECKED: <i>W.M. Thompson</i> REVIEWED: <i>J.M. Tindall 7/4/82</i> REVIEWED: <i>E.L. Wallgren 7/6/82</i> CALC. BOOK: <i>1032</i> | <h2 style="margin: 0;">WILLAMETTE RIVER</h2> <h2 style="margin: 0;">(CENTER STREET) BRIDGE</h2> | | | | | | | | | | | | | | |
| <table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="width: 20%;">DATE</th> <th style="width: 80%;">REVISION</th> </tr> </thead> <tbody> <tr><td> </td><td> </td></tr> <tr><td> </td><td> </td></tr> <tr><td> </td><td> </td></tr> <tr><td> </td><td> </td></tr> <tr><td> </td><td> </td></tr> <tr><td> </td><td> </td></tr> </tbody> </table> | DATE | REVISION | | | | | | | | | | | | | <h2 style="margin: 0;">BENT B24&25 DETAILS</h2> |
| DATE | REVISION | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | |
| DATE <i>May, 1982</i> BRIDGE NO. <i>123 K</i> | SHEET <i>127</i> OF <i>155</i> DRAWING NO. <i>37127</i> | | | | | | | | | | | | | | |

IMPORTANT INFORMATION

Important Information

About Your Geotechnical Report

DRAFT

Important Information About Your Geotechnical/Environmental Report

CONSULTING SERVICES ARE PERFORMED FOR SPECIFIC PURPOSES AND FOR SPECIFIC CLIENTS.

Consultants prepare reports to meet the specific needs of specific individuals. A report prepared for a civil engineer may not be adequate for a construction contractor or even another civil engineer. Unless indicated otherwise, your consultant prepared your report expressly for you and expressly for the purposes you indicated. No one other than you should apply this report for its intended purpose without first conferring with the consultant. No party should apply this report for any purpose other than that originally contemplated without first conferring with the consultant.

THE CONSULTANT'S REPORT IS BASED ON PROJECT-SPECIFIC FACTORS.

A geotechnical/environmental report is based on a subsurface exploration plan designed to consider a unique set of project-specific factors. Depending on the project, these may include the general nature of the structure and property involved; its size and configuration; its historical use and practice; the location of the structure on the site and its orientation; other improvements such as access roads, parking lots, and underground utilities; and the additional risk created by scope-of-service limitations imposed by the client. To help avoid costly problems, ask the consultant to evaluate how any factors that change subsequent to the date of the report may affect the recommendations. Unless your consultant indicates otherwise, your report should not be used (1) when the nature of the proposed project is changed (for example, if an office building will be erected instead of a parking garage, or if a refrigerated warehouse will be built instead of an unrefrigerated one, or chemicals are discovered on or near the site); (2) when the size, elevation, or configuration of the proposed project is altered; (3) when the location or orientation of the proposed project is modified; (4) when there is a change of ownership; or (5) for application to an adjacent site. Consultants cannot accept responsibility for problems that may occur if they are not consulted after factors that were considered in the development of the report have changed.

SUBSURFACE CONDITIONS CAN CHANGE.

Subsurface conditions may be affected as a result of natural processes or human activity. Because a geotechnical/environmental report is based on conditions that existed at the time of subsurface exploration, construction decisions should not be based on a report whose adequacy may have been affected by time. Ask the consultant to advise if additional tests are desirable before construction starts; for example, groundwater conditions commonly vary seasonally.

Construction operations at or adjacent to the site and natural events such as floods, earthquakes, or groundwater fluctuations may also affect subsurface conditions and, thus, the continuing adequacy of a geotechnical/environmental report. The consultant should be kept apprised of any such events and should be consulted to determine if additional tests are necessary.

MOST RECOMMENDATIONS ARE PROFESSIONAL JUDGMENTS.

Site exploration and testing identifies actual surface and subsurface conditions only at those points where samples are taken. The data were extrapolated by your consultant, who then applied judgment to render an opinion about overall subsurface conditions. The actual interface between materials may be far more gradual or abrupt than your report indicates. Actual conditions in areas not sampled may differ from those predicted in your report. While nothing can be done to prevent such situations, you and your consultant can work together to help reduce their impacts. Retaining your consultant to observe subsurface construction operations can be particularly beneficial in this respect.

A REPORT'S CONCLUSIONS ARE PRELIMINARY.

The conclusions contained in your consultant's report are preliminary, because they must be based on the assumption that conditions revealed through selective exploratory sampling are indicative of actual conditions throughout a site. Actual subsurface conditions can be discerned only during earthwork; therefore, you should retain your consultant to observe actual conditions and to provide conclusions. Only the consultant who prepared the report is fully familiar with the background information needed to determine whether or not the report's recommendations based on those conclusions are valid and whether or not the contractor is abiding by applicable recommendations. The consultant who developed your report cannot assume responsibility or liability for the adequacy of the report's recommendations if another party is retained to observe construction.

THE CONSULTANT'S REPORT IS SUBJECT TO MISINTERPRETATION.

Costly problems can occur when other design professionals develop their plans based on misinterpretation of a geotechnical/environmental report. To help avoid these problems, the consultant should be retained to work with other project design professionals to explain relevant geotechnical, geological, hydrogeological, and environmental findings, and to review the adequacy of their plans and specifications relative to these issues.

BORING LOGS AND/OR MONITORING WELL DATA SHOULD NOT BE SEPARATED FROM THE REPORT.

Final boring logs developed by the consultant are based upon interpretation of field logs (assembled by site personnel), field test results, and laboratory and/or office evaluation of field samples and data. Only final boring logs and data are customarily included in geotechnical/environmental reports. These final logs should not, under any circumstances, be redrawn for inclusion in architectural or other design drawings, because drafters may commit errors or omissions in the transfer process.

To reduce the likelihood of boring log or monitoring well misinterpretation, contractors should be given ready access to the complete geotechnical engineering/environmental report prepared or authorized for their use. If access is provided only to the report prepared for you, you should advise contractors of the report's limitations, assuming that a contractor was not one of the specific persons for whom the report was prepared, and that developing construction cost estimates was not one of the specific purposes for which it was prepared. While a contractor may gain important knowledge from a report prepared for another party, the contractor should discuss the report with your consultant and perform the additional or alternative work believed necessary to obtain the data specifically appropriate for construction cost estimating purposes. Some clients hold the mistaken impression that simply disclaiming responsibility for the accuracy of subsurface information always insulates them from attendant liability. Providing the best available information to contractors helps prevent costly construction problems and the adversarial attitudes that aggravate them to a disproportionate scale.

READ RESPONSIBILITY CLAUSES CLOSELY.

Because geotechnical/environmental engineering is based extensively on judgment and opinion, it is far less exact than other design disciplines. This situation has resulted in wholly unwarranted claims being lodged against consultants. To help prevent this problem, consultants have developed a number of clauses for use in their contracts, reports, and other documents. These responsibility clauses are not exculpatory clauses designed to transfer the consultant's liabilities to other parties; rather, they are definitive clauses that identify where the consultant's responsibilities begin and end. Their use helps all parties involved recognize their individual responsibilities and take appropriate action. Some of these definitive clauses are likely to appear in your report, and you are encouraged to read them closely. Your consultant will be pleased to give full and frank answers to your questions.

The preceding paragraphs are based on information provided by the ASFE/Association of Engineering Firms Practicing in the Geosciences, Silver Spring, Maryland

Appendix C. Pump Station and Reservoir Seismic Vulnerability Assessment

WATER SYSTEM SEISMIC RESILIENCE STUDY

**CITY OF SALEM PUBLIC WORKS DEPARTMENT
SALEM, OREGON**

Final Technical Memorandum: Pump Station and Reservoir Seismic Vulnerability Assessment

January 6th, 2023

SEFT Project Number: B20028.00



Table of Contents

| | |
|--|------------|
| List of Figures | iii |
| List of Tables..... | xi |
| 1.0 Introduction and Background | 1 |
| 1.1 City of Salem Water System Description | 1 |
| 1.2 Seismic Resilience Study | 1 |
| 2.0 Evaluation Methodology and Seismic Performance Objectives | 8 |
| 2.1 Seismic Hazard | 8 |
| 2.2 Seismic Performance Objectives | 8 |
| 2.2.1 Structural Performance Objective | 8 |
| 2.2.2 Nonstructural Performance Objectives..... | 9 |
| 2.3 Water System Evaluation Methodology | 9 |
| 2.3.1 Pump Stations, Control Facilities, and Control Buildings | 9 |
| 2.3.2 Reservoirs | 10 |
| 3.0 Expected Seismic Structural and Nonstructural Performance | 13 |
| 3.1 Pump Stations and Control Facilities | 13 |
| 3.1.1 ASR #1 and #2 Pump Station | 13 |
| 3.1.2 ASR #4 Pump Station | 22 |
| 3.1.3 ASR #5 Pump Station | 28 |
| 3.1.4 Boone Road Pump Station..... | 36 |
| 3.1.5 Creekside Pump Station | 44 |
| 3.1.6 Deer Park Pump Station | 51 |
| 3.1.7 Edwards Pump Station..... | 59 |
| 3.1.8 Limelight Pump Station | 70 |
| 3.1.9 Mountain View Pump Station | 78 |
| 3.1.10 Salem/Keizer Intertie #1 Pump Station | 91 |
| 3.1.11 Turner Control Facility | 98 |
| 3.2 Reservoirs and Reservoir Control Buildings..... | 109 |
| 3.2.1 Candalaria Reservoir | 109 |
| 3.2.2 Champion Hill Reservoir and Control Building | 112 |
| 3.2.3 Eola #1B Reservoir | 124 |
| 3.2.4 Fairmount Reservoir and Control Building | 128 |
| 3.2.5 Grice Hill Reservoir and Control Building | 141 |
| 3.2.6 Lone Oak Reservoir and Control Building | 151 |
| 3.2.7 Mill Creek #1 Reservoir and Control Building..... | 160 |
| 3.2.8 Mountain View Reservoir | 172 |
| 4.0 Preliminary Seismic Structural and Nonstructural Mitigation Concepts..... | 174 |
| 4.1 Pump Stations and Control Facilities | 174 |
| 4.1.1 ASR #1 and #2 Pump Station | 174 |

| | | |
|------------|---|------------|
| 4.1.2 | ASR #4 Pump Station | 177 |
| 4.1.3 | ASR #5 Pump Station | 179 |
| 4.1.4 | Boone Road Pump Station..... | 182 |
| 4.1.5 | Creekside Pump Station | 184 |
| 4.1.6 | Deer Park Pump Station | 187 |
| 4.1.7 | Edwards Pump Station..... | 188 |
| 4.1.8 | Limelight Pump Station | 190 |
| 4.1.9 | Mountain View Pump Station | 192 |
| 4.1.10 | Salem/Keizer Intertie #1 Pump Station | 195 |
| 4.1.11 | Turner Control Facility | 197 |
| 4.2 | Reservoirs and Reservoir Control Buildings..... | 200 |
| 4.2.1 | Candalaria Reservoir | 200 |
| 4.2.2 | Champion Hill Reservoir | 202 |
| 4.2.3 | Eola #1B Reservoir | 204 |
| 4.2.4 | Fairmount Reservoir..... | 205 |
| 4.2.5 | Grice Hill Reservoir | 207 |
| 4.2.6 | Lone Oak Reservoir | 209 |
| 4.2.7 | Mill Creek #1 Reservoir..... | 211 |
| 4.2.8 | Mountain View Reservoir | 213 |
| 5.0 | Next Steps..... | 214 |
| 6.0 | Limitations | 216 |
| 7.0 | References..... | 217 |

List of Figures

| | |
|---|----|
| Figure 1.1 City of Salem Water System General Location Map | 7 |
| Figure 3.1 ASR #1 and #2 Pump Station | 16 |
| Figure 3.2 Inadequate Connection between Blocking and Masonry Wall Top Plate..... | 16 |
| Figure 3.3 Roof Truss to Masonry Wall Top Plate Connection | 17 |
| Figure 3.4 Unbraced Piping, Valves, and Air Relief Valve | 17 |
| Figure 3.5 Unbraced Pump Motor..... | 18 |
| Figure 3.6 Light Fixtures without Lens Covers | 18 |
| Figure 3.7 Conduit Top Connection to Electrical Panels without Flexible Connection..... | 19 |
| Figure 3.8 SCADA Antenna | 19 |
| Figure 3.9 Unknow Masonry Veneer Ties to Backup Masonry Wall | 20 |
| Figure 3.10 Architectural Concrete Pillar | 20 |
| Figure 3.11 Unanchored Electrical Transformer | 21 |
| Figure 3.12 ASR #4 Pump Station | 24 |
| Figure 3.13 Inadequate Connection between Blocking and Masonry Wall Top Plate..... | 24 |
| Figure 3.14 Roof Truss to Masonry Wall Top Plate Connection | 25 |
| Figure 3.15 Unbraced Piping, Valves, and Air Relief Valve | 25 |
| Figure 3.16 Unbraced Pump Motor..... | 26 |
| Figure 3.17 Unanchored Control Cabinet | 26 |
| Figure 3.18 Light Fixtures without Lens Covers..... | 27 |
| Figure 3.19 Unanchored Electrical Transformer | 27 |
| Figure 3.20 ASR #5 Pump Station | 30 |
| Figure 3.21 Inadequate Blocking and Masonry Wall Out-of-Plane Anchorage ... | 31 |
| Figure 3.22 Free-Standing Masonry Wall without Bracing | 31 |
| Figure 3.23 Corrosion Damage at Northern-Most Pavilion Steel Column | 32 |
| Figure 3.24 Unbraced Piping, Valves, and Air Relief Valve | 32 |
| Figure 3.25 Unbraced Air Relief Valve..... | 33 |
| Figure 3.26 Unbraced Pump Motor..... | 33 |

| | |
|---|----|
| Figure 3.27 Conduit Top Connection to Motor Control Center without Flexible Connection..... | 34 |
| Figure 3.28 Unanchored Control Cabinet | 34 |
| Figure 3.29 Light Fixtures without Lens Covers | 35 |
| Figure 3.30 Unanchored Electrical Transformer | 35 |
| Figure 3.31 Boone Road Pump Station (right) and Electrical Building (left) | 38 |
| Figure 3.32 Boone Road Pump Station | 38 |
| Figure 3.33 Unbraced Piping and Valves..... | 39 |
| Figure 3.34 Unbraced Pump Motor | 39 |
| Figure 3.35 Cable Tray Lacks Longitudinal Bracing..... | 40 |
| Figure 3.36 Cable Tray Transverse Brace with Anchor Installed in Masonry Head Joint | 41 |
| Figure 3.37 Light Fixtures without Lens Covers | 42 |
| Figure 3.38 Grating without Clip Connection to Supporting Steel Framing | 42 |
| Figure 3.39 SCADA Antenna | 43 |
| Figure 3.40 Creekside Pump Station | 46 |
| Figure 3.41 Inadequate Wall Out-of-Plane Anchorage Connection | 46 |
| Figure 3.42 Unbraced Piping and Valves..... | 47 |
| Figure 3.43 Unbraced Air Relief Valves | 47 |
| Figure 3.44 Unbraced Pump Motor | 48 |
| Figure 3.45 Unanchored Emergency Generator Air Intake Support Frame | 48 |
| Figure 3.46 Unbraced Emergency Generator Muffler | 49 |
| Figure 3.47 Unbraced Emergency Generator Exhaust Pipe | 49 |
| Figure 3.48 Unanchored Electrical Transformer | 50 |
| Figure 3.49 Deer Park Pump Station | 54 |
| Figure 3.50 Sheathing Not Connected to Top Plate of Interior Masonry Wall | 54 |
| Figure 3.51 Inadequate Connection between Blocking and Masonry Wall Top Plate..... | 55 |
| Figure 3.52 Inadequate Connection between Truss Chord and Masonry Wall Top Plate..... | 55 |
| Figure 3.53 Unbraced Piping and Valves..... | 56 |
| Figure 3.54 Pipe Support Stanchion Missing Anchors into Floor Slab | 56 |

| | |
|--|----|
| Figure 3.55 Electrical Cabinet with Unknown Anchorage Details | 57 |
| Figure 3.56 Emergency Generator Starter Battery Restraint Bracket Observed in Pump Station | 57 |
| Figure 3.57 SCADA Antenna | 58 |
| Figure 3.58 Edwards Pump Station | 62 |
| Figure 3.59 Cracking of Masonry Wall..... | 62 |
| Figure 3.60 Masonry Pilaster Supporting Roof Framing | 63 |
| Figure 3.61 Unbraced Piping and Valves..... | 63 |
| Figure 3.62 Unbraced Pump Motor | 64 |
| Figure 3.63 Electrical Cabinets with Unknown Anchorage Details..... | 65 |
| Figure 3.64 Conduits Connecting to Electrical Cabinets without Flexible Connections..... | 65 |
| Figure 3.65 Pendant Lights without Lens Covers | 66 |
| Figure 3.66 SCADA Antenna | 66 |
| Figure 3.67 Unanchored HVAC Condenser Unit | 67 |
| Figure 3.68 Grating without Clip Connection to Supporting Steel Framing | 67 |
| Figure 3.69 Unrestrained Overhead Bridge Crane..... | 68 |
| Figure 3.70 Unrestrained Ladder and Rolling Lift..... | 68 |
| Figure 3.71 Pole-Mounted Electrical Transformers..... | 69 |
| Figure 3.72 Limelight Pump Station | 72 |
| Figure 3.73 Masonry Wall Cracking | 72 |
| Figure 3.74 Sheathing and Framing Deterioration | 73 |
| Figure 3.75 Sloped Blocking Between Wood Trusses | 73 |
| Figure 3.76 Inadequate Wall Out-of-Plane Anchorage Connection | 74 |
| Figure 3.77 Unbraced Piping and Valves..... | 74 |
| Figure 3.78 Unbraced Air Relief Valve..... | 75 |
| Figure 3.79 Unbraced Pump Motor | 75 |
| Figure 3.80 Electrical Cabinets with Unknown Anchorage Details..... | 76 |
| Figure 3.81 SCADA Antenna | 76 |
| Figure 3.82 Unanchored Electrical Transformer | 77 |
| Figure 3.83 Mountain View Pump Station..... | 80 |

| | |
|---|-----|
| Figure 3.84 Incomplete Load Path at North Wall | 81 |
| Figure 3.85 Inadequate East and West Wall Out-of-Plane Anchorage | 82 |
| Figure 3.86 Unbraced Piping and Valves..... | 82 |
| Figure 3.87 Unbraced Air Relief Valve..... | 83 |
| Figure 3.88 Unbraced Pump Motor..... | 83 |
| Figure 3.89 Pipe Support Stanchion Missing Anchors into Floor Slab | 84 |
| Figure 3.90 Chlorine System without Adequate Anchorage..... | 84 |
| Figure 3.91 Deteriorated Concrete Curb..... | 85 |
| Figure 3.92 Inadequate Lag Screw and Spacer Strut Connection to Wall | 85 |
| Figure 3.93 Unbraced Elevated Electrical Transformer | 86 |
| Figure 3.94 Electrical Cabinet with Single Anchor Bracket at Top of Cabinet | 86 |
| Figure 3.95 Conduits Connecting to Electrical Cabinets without Flexible Connections..... | 87 |
| Figure 3.96 Unrestrained Emergency Generator Starter Batteries | 87 |
| Figure 3.97 Unbraced Emergency Generator Muffler | 88 |
| Figure 3.98 Light Fixtures without Lens Covers | 88 |
| Figure 3.99 SCADA Antenna | 89 |
| Figure 3.100 Unrestrained Chain Hoist and Ladder..... | 89 |
| Figure 3.101 Unanchored Electrical Transformer | 90 |
| Figure 3.102 Salem/Keizer Intertie #1 Pump Station | 93 |
| Figure 3.103 Roof Sheathing not Continuous to Ridge Line | 93 |
| Figure 3.104 Incomplete Load Path | 94 |
| Figure 3.105 Ceiling Level Blocking not Continuous..... | 94 |
| Figure 3.106 Unbraced Piping and Valves..... | 95 |
| Figure 3.107 Unbraced Overflow Pipe on South Side of Pump Station | 95 |
| Figure 3.108 Unanchored Chlorination Skid | 96 |
| Figure 3.109 Anchorage at Electrical Cabinet with Bent Strut | 96 |
| Figure 3.110 SCADA Antenna | 97 |
| Figure 3.111 Unanchored Electrical Transformer | 97 |
| Figure 3.112 Turner Control Facility..... | 100 |
| Figure 3.113 Incomplete Load Path at Gable End Walls | 100 |

| | |
|---|-----|
| Figure 3.114 Unbraced Pipe | 101 |
| Figure 3.115 Unbraced Valve | 101 |
| Figure 3.116 Unbraced Valve Actuator | 102 |
| Figure 3.117 Unanchored Control Cabinet | 103 |
| Figure 3.118 Electrical Transformer Missing Anchors into Floor Slab..... | 104 |
| Figure 3.119 Unrestrained Backup Batteries in Battery Cabinet..... | 104 |
| Figure 3.120 Unrestrained Pendant Light Fixtures | 105 |
| Figure 3.121 Light Fixtures without Lens Covers | 105 |
| Figure 3.122 SCADA Antenna | 106 |
| Figure 3.123 Unbraced Inline Fan Unit | 106 |
| Figure 3.124 Unanchored HVAC Condenser Unit | 107 |
| Figure 3.125 Unanchored Shelf | 107 |
| Figure 3.126 Unrestrained Fire Extinguisher | 108 |
| Figure 3.127 Candalaria Reservoir | 111 |
| Figure 3.128 Overflow Pipe and Valve Operator Risers Not Adequately Braced | 111 |
| Figure 3.129 Champion Hill Reservoir | 115 |
| Figure 3.130 Champion Hill Reservoir Control Building | 115 |
| Figure 3.131 Reservoir Pipe Support Detail..... | 116 |
| Figure 3.132 Inadequate Connection between Blocking and Masonry Wall Top Plate..... | 116 |
| Figure 3.133 Inadequate Connection between Sheathing and Masonry Wall Top Plate..... | 117 |
| Figure 3.134 Inadequate Connection between Blocking and Roof Truss | 117 |
| Figure 3.135 Rigid Pipe Connection Through Wall | 118 |
| Figure 3.136 Unbraced Piping and Valves..... | 118 |
| Figure 3.137 Unbraced Seismic Valve..... | 119 |
| Figure 3.138 Unanchored Recirculation Pump Motor | 119 |
| Figure 3.139 Irrigation Pressure Tank Missing Anchor | 120 |
| Figure 3.140 Unrestrained Backup Batteries | 120 |
| Figure 3.141 SCADA Antenna | 121 |
| Figure 3.142 Chlorine Room Ceiling Framing | 122 |

| | |
|---|-----|
| Figure 3.143 Temporarily Stored Electrical Cabinets..... | 122 |
| Figure 3.144 Pole-mounted Electrical Transformer..... | 123 |
| Figure 3.145 Eola #1B Reservoir | 125 |
| Figure 3.146 Concrete Deterioration at Lid to Wall Connection of South Valve Vault..... | 126 |
| Figure 3.147 Reservoir Inlet Pipe Support Detail | 127 |
| Figure 3.148 Fairmount Reservoir | 131 |
| Figure 3.149 Fairmount Reservoir Control Building | 132 |
| Figure 3.150 Fairmount Reservoir Roof Expansion Joints..... | 132 |
| Figure 3.151 Sliding Joint Between Wall and Roof | 133 |
| Figure 3.152 Reservoir Adjacent to Control Building/Pump Station | 133 |
| Figure 3.153 Inadequate Shear Wall to Diaphragm Connection | 134 |
| Figure 3.154 Inadequate Shear Wall to Foundation Connection | 134 |
| Figure 3.155 Unbraced Piping and Valves..... | 135 |
| Figure 3.156 Unbraced Valve | 135 |
| Figure 3.157 Unbraced Pump Bells and Valve Operator Riser Shafts..... | 136 |
| Figure 3.158 Cast Iron Valve | 136 |
| Figure 3.159 Corroded Bolts and Pipe..... | 137 |
| Figure 3.160 Unanchored Pump | 137 |
| Figure 3.161 Unbraced Vent Pipe..... | 138 |
| Figure 3.162 Electrical Cabinets with Unknown Anchorage Details..... | 138 |
| Figure 3.163 Conduits Connecting to Electrical Cabinets without Flexible Connections..... | 139 |
| Figure 3.164 SCADA Antenna | 139 |
| Figure 3.165 Pole-mounted Electrical Transformers..... | 140 |
| Figure 3.166 Grice Hill Reservoir | 143 |
| Figure 3.167 Grice Hill Reservoir Control Building..... | 143 |
| Figure 3.168 SCADA Antenna Supported by Lattice Tower | 144 |
| Figure 3.169 Reservoir Pipe Support Detail..... | 144 |
| Figure 3.170 Inadequate Connection between Blocking and Masonry Wall Top Plate..... | 145 |
| Figure 3.171 Inadequate Connection between Blocking and Roof Truss | 145 |

| | |
|---|-----|
| Figure 3.172 Unbraced Piping and Valves..... | 146 |
| Figure 3.173 Unbraced Seismic Valve..... | 146 |
| Figure 3.174 Note about Inoperable Seismic Valve | 147 |
| Figure 3.175 Unanchored Irrigation Pressure Tank | 147 |
| Figure 3.176 Backup Batteries without Adequate Restraint..... | 148 |
| Figure 3.177 Chlorine Room Ceiling Framing | 148 |
| Figure 3.178 Temporarily Stored Electrical Cabinet..... | 149 |
| Figure 3.179 Unrestrained Ladder | 149 |
| Figure 3.180 Unanchored Electrical Transformer | 150 |
| Figure 3.181 Lone Oak Reservoir | 153 |
| Figure 3.182 Lone Oak Reservoir Control Building..... | 154 |
| Figure 3.183 Design of Lone Oak Reservoir Control Building was a Deferred Submittal..... | 154 |
| Figure 3.184 Unbraced Piping and Valves..... | 155 |
| Figure 3.185 Unbraced Seismic Valve..... | 155 |
| Figure 3.186 Unanchored Pressure Tank | 156 |
| Figure 3.187 Control Cabinet with Unknown Anchorage Details | 156 |
| Figure 3.188 SCADA Antenna | 157 |
| Figure 3.189 Suspended HVAC Unit | 157 |
| Figure 3.190 Inadequate Overturning Anchorage of Water Heater..... | 158 |
| Figure 3.191 Chlorine Room Ceiling Framing | 158 |
| Figure 3.192 Unrestrained Step Ladder | 159 |
| Figure 3.193 Unanchored Electrical Transformer | 159 |
| Figure 3.194 Mill Creek #1 Reservoir..... | 163 |
| Figure 3.195 Mill Creek #1 Reservoir Control Building | 163 |
| Figure 3.196 Reservoir Pipe Support Detail..... | 164 |
| Figure 3.197 Mill Creek #1 Reservoir Roof Access Stair | 164 |
| Figure 3.198 Inadequate Connection between Blocking and Masonry Wall Top Plate..... | 165 |
| Figure 3.199 Inadequate Transfer Length between Blocking and Ceiling Diaphragm | 165 |
| Figure 3.200 Unbraced Piping and Valves..... | 166 |

| | |
|---|-----|
| Figure 3.201 Unbraced Seismic Valves | 166 |
| Figure 3.202 Unanchored Pressure Tank | 167 |
| Figure 3.203 Unanchored Pump Motor | 167 |
| Figure 3.204 SCADA Antenna | 168 |
| Figure 3.205 Chlorine Room Ceiling Framing | 169 |
| Figure 3.206 Unbraced Partial Height CMU Walls in Electrical Room | 170 |
| Figure 3.207 Unrestrained Ladders | 170 |
| Figure 3.208 Unanchored Electrical Transformer | 171 |
| Figure 3.209 Mountain View Reservoir | 173 |
| Figure 3.210 Base of Wall to Foundation Connection without Dowels or Seismic Cables..... | 173 |
| Figure 4.1 Sub-diaphragm Retrofit Concept | 176 |
| Figure 4.2 Sub-diaphragm Retrofit Concept | 178 |
| Figure 4.3 Sub-diaphragm Retrofit Concept | 181 |
| Figure 4.4 Sub-diaphragm Retrofit Concept | 183 |
| Figure 4.5 Sub-diaphragm Retrofit Concept | 186 |
| Figure 4.6 Sub-diaphragm Retrofit Concept | 194 |
| Figure 4.7 Sub-diaphragm Retrofit Concept | 199 |

List of Tables

| | |
|--|-----|
| Table 1.1 Summary of Evaluated Pump Stations and Control Facilities | 2 |
| Table 1.2 Summary of Evaluated Reservoirs..... | 3 |
| Table 1.3 Summary of Evaluated Reservoir Control Buildings | 4 |
| Table 1.4 Available Pump Station and Control Facility Documents | 5 |
| Table 1.5 Available Reservoir and Reservoir Control Building Documents..... | 6 |
| Table 2.1 Summary of Mapped Seismic Hazards at Pump Stations and Control Facilities | 11 |
| Table 2.2 Summary of Mapped Seismic Hazards at Reservoirs and Reservoir Control Buildings..... | 12 |
| Table 3.1 ASR #1 and #2 Pump Station Evaluation Summary | 14 |
| Table 3.2 ASR #4 Pump Station Evaluation Summary | 23 |
| Table 3.3 ASR #5 Pump Station Evaluation Summary | 29 |
| Table 3.4 Boone Road Pump Station Evaluation Summary..... | 37 |
| Table 3.5 Creekside Pump Station Evaluation Summary | 44 |
| Table 3.6 Deer Park Pump Station Evaluation Summary | 52 |
| Table 3.7 Edwards Pump Station Evaluation Summary..... | 59 |
| Table 3.8 Limelight Pump Station Evaluation Summary | 70 |
| Table 3.9 Mountain View Pump Station Evaluation Summary | 78 |
| Table 3.10 Salem/Keizer Intertie #1 Pump Station Evaluation Summary | 91 |
| Table 3.11 Turner Control Facility Evaluation Summary | 98 |
| Table 3.12 Candalaria Reservoir Evaluation Summary | 110 |
| Table 3.13 Champion Hill Reservoir Evaluation Summary | 112 |
| Table 3.14 Champion Hill Reservoir Control Building Evaluation Summary | 113 |
| Table 3.15 Eola #1B Reservoir Evaluation Summary | 124 |
| Table 3.16 Fairmount Reservoir Evaluation Summary..... | 129 |
| Table 3.17 Fairmount Reservoir Control Building Seismic Evaluation Summary..... | 130 |
| Table 3.18 Grice Hill Reservoir Evaluation Summary | 141 |
| Table 3.19 Grice Hill Reservoir Control Building Seismic Evaluation Summary..... | 142 |
| Table 3.20 Lone Oak Reservoir Evaluation Summary | 151 |
| Table 3.21 Lone Oak Reservoir Control Building Evaluation Summary | 152 |

| | |
|---|-----|
| Table 3.22 Mill Creek #1 Reservoir Evaluation Summary | 160 |
| Table 3.23 Mill Creek #1 Reservoir Control Building Evaluation Summary..... | 161 |
| Table 3.24 Mountain View Reservoir Evaluation Summary | 172 |
| Table 4.1 ASR #1 and #2 Pump Station Preliminary Mitigation Concepts | 174 |
| Table 4.2 ASR #4 Pump Station Preliminary Mitigation Concepts | 177 |
| Table 4.3 ASR #5 Pump Station Preliminary Mitigation Concepts | 179 |
| Table 4.4 Boone Road Pump Station Preliminary Mitigation Concepts | 182 |
| Table 4.5 Creekside Pump Station Preliminary Mitigation Concepts | 184 |
| Table 4.6 Deer Park Pump Station Preliminary Mitigation Concepts | 187 |
| Table 4.7 Edwards Pump Station Preliminary Mitigation Concepts | 188 |
| Table 4.8 Limelight Pump Station Preliminary Mitigation Concepts | 190 |
| Table 4.9 Mountain View Pump Station Preliminary Mitigation Concepts..... | 192 |
| Table 4.10 Salem/Keizer Intertie #1 Pump Station Preliminary Mitigation Concepts..... | 195 |
| Table 4.11 Turner Control Facility Preliminary Mitigation Concepts..... | 197 |
| Table 4.12 Candalaria Reservoir Preliminary Mitigation Concepts | 200 |
| Table 4.13 Champion Hill Reservoir Preliminary Mitigation Concepts | 202 |
| Table 4.14 Champion Hill Reservoir Control Building Preliminary Mitigation Concepts..... | 202 |
| Table 4.15 Eola #1B Reservoir Preliminary Mitigation Concepts..... | 204 |
| Table 4.16 Fairmount Reservoir Preliminary Mitigation Concepts | 205 |
| Table 4.17 Fairmount Reservoir Control Building/Pump Station Preliminary Mitigation Concepts | 206 |
| Table 4.18 Grice Hill Reservoir Preliminary Mitigation Concepts..... | 207 |
| Table 4.19 Grice Hill Reservoir Control Building Preliminary Mitigation Concepts | 207 |
| Table 4.20 Lone Oak Reservoir Preliminary Mitigation Concepts | 209 |
| Table 4.21 Lone Oak Reservoir Control Building Preliminary Mitigation Concepts | 209 |
| Table 4.22 Mill Creek #1 Reservoir Preliminary Mitigation Concepts..... | 211 |
| Table 4.23 Mill Creek #1 Reservoir Control Building Preliminary Mitigation Concepts..... | 211 |
| Table 4.24 Mountain View Reservoir Preliminary Mitigation Concepts | 213 |

1.0 Introduction and Background

1.1 City of Salem Water System Description

The City of Salem relies on the North Santiam River Watershed (including the North Santiam River and Detroit Lake) to supply water for the City’s approximately 170,000 residents and commercial customers. Water flows down the North Santiam River to the raw water intake at the Geren Island Water Treatment Facility near Stayton. Large diameter transmission mains deliver water from Geren Island to the 100-million-gallon Franzen Reservoir located in Turner and/or the City’s transmission and distribution system that is supported by numerous pump stations and storage reservoirs within and adjacent to the City of Salem service area. The City also operates four aquifer storage and recovery (ASR) wells in Woodmansee Park.

1.2 Seismic Resilience Study

Based on Oregon Health Authority requirements, the City of Salem has retained a team, led by Black & Veatch, to perform a water system seismic resilience study. This study has established post-earthquake level of service goals for the City’s water system following a Magnitude 9.0 (M9.0) Cascadia Subduction Zone (CSZ) earthquake, identified a water system backbone, evaluated the expected performance of selected City water system components following an M9.0 CSZ earthquake, and identified preliminary recommendations for improvements that should be implemented to enable the City to more rapidly restore water service after a major earthquake, and to meet community social and economic needs.

This Technical Memorandum (TM) presents SEFT’s observations, findings, and recommendations related to a preliminary structural and nonstructural seismic assessment of selected City of Salem water system facilities (10 pump stations, Turner Control Facility, 8 reservoirs, and 5 reservoir control buildings). The components of the water system that have been evaluated by SEFT as part of this effort are summarized in Table 1.1 (pump stations and control facilities), Table 1.2 (reservoirs), and Table 1.3 (reservoir control buildings). The locations of these components are illustrated in Figure 1.1. To complete this scope of work, SEFT utilized the available original design drawings, seismic retrofit drawings, and previous reports indicated in Table 1.4 (pump stations and control facilities) and Table 1.5 (reservoirs and reservoir control buildings), that were provided to the Black & Veatch team by the City.

Table 1.1 Summary of Evaluated Pump Stations and Control Facilities

| Pump Station or Control Building | Construction Type | Year of Original Construction | Year(s) of Modification or Retrofit |
|---|--|--------------------------------------|--|
| ASR #1 and #2 | Reinforced Masonry Shear Wall | 1995 | 1998 |
| ASR #4 | Reinforced Masonry Shear Wall | 1998 | -- |
| ASR #5 | Reinforced Masonry Shear Wall with Octagonal Steel Framed Pavilion | 1998 | -- |
| Boone Road (original) | Reinforced Masonry Shear Wall | 1976 | 2018 |
| Creekside | Reinforced Masonry Shear Wall | 1998 | -- |
| Deer Park | Reinforced Masonry Shear Wall | Unknown | Unknown ⁽¹⁾ & 2013 |
| Edwards | Masonry Shear Wall and Steel Frame | | -- |
| Limelight | Reinforced Masonry Shear Wall | 1998 | -- |
| Mountain View | Reinforced Masonry Shear Wall | 1994 | -- |
| Salem/Keizer Intertie #1 | Reinforced Masonry Shear Wall | 2012 | -- |
| Turner Control Facility | Reinforced Masonry Shear Wall (above-grade) and Reinforced Concrete Shear Wall (below-grade) | 2007 ⁽²⁾ | -- |

⁽¹⁾ An electrical room addition was constructed abutting to the south side of the original Deer Park Pump Station at an unknown date. This addition approximately doubled the size of the pump station.

⁽²⁾ The original Turner Control Facility was substantially replaced by the 2007 construction. However, a small subgrade portion of the original Turner Control Facility was integrated into the new structure.

Table 1.2 Summary of Evaluated Reservoirs

| Reservoir | Construction Type | Year of Original Construction | Year(s) of Modification or Retrofit |
|--------------------|---|--------------------------------------|--|
| Candalaria | 0.5 MG ⁽¹⁾ Rectangular Reinforced Concrete | 1940 | 2006 |
| Champion Hill | 2.2 MG Strand-Wound Circular Prestressed Concrete | 2005 | -- |
| Eola Reservoir #1B | 0.86 MG Circular Reinforced Concrete | 1999 | -- |
| Fairmount | 10 MG Rectangular Reinforced Concrete | 1936 | -- |
| Grice Hill | 2.2 MG Strand-Wound Circular Prestressed Concrete | 2001 | -- |
| Lone Oak | 5.6 MG Strand-Wound Circular Prestressed Concrete | 2003 | -- |
| Mill Creek #1 | 2.2 MG Strand-Wound Circular Prestressed Concrete | 2013 | -- |
| Mountain View | 10 MG Strand-Wound Circular Prestressed Concrete | 1971 | -- |

⁽¹⁾ million gallon (MG)

Table 1.3 Summary of Evaluated Reservoir Control Buildings

| Reservoir Control Building | Construction Type | Year of Original Construction | Year(s) of Modification or Retrofit |
|-----------------------------------|--|--------------------------------------|--|
| Champion Hill | Reinforced Masonry Shear Wall (above-grade) and Reinforced Concrete Shear Wall (below-grade) | 2005 | -- |
| Fairmount | Reinforced Concrete Shear Wall | 1936 | -- |
| Grice Hill | Reinforced Masonry Shear Wall | 2001 | -- |
| Lone Oak | Reinforced Masonry Shear Wall (above-grade) and Reinforced Concrete Shear Wall (below-grade) | 2003 | -- |
| Mill Creek #1 | Reinforced Masonry Shear Wall (above-grade) and Reinforced Concrete Shear Wall (below-grade) | 2013 | -- |

Table 1.4 Available Pump Station and Control Facility Documents

| Pump Station or Control Building | Design Drawing, As-Built Drawing or Evaluation Report | Date |
|---|--|----------------|
| ASR #1 and #2 | “Aquifer Storage & Recovery Project” by Stettler Company | April 1995 |
| | “Aquifer Storage & Recovery Well No. 2” by Stettler Company | November 1997 |
| ASR #4 | “Aquifer Storage & Recovery Well No. 4” by Stettler Company | February 1998 |
| ASR #5 | “Aquifer Storage & Recovery Well No. 5” by Stettler Company | November 1997 |
| Boone Road | “Boone Road Pump Station” by C & G Engineering | August 1976 |
| | “Boone Road Water Pump Station Upgrades” by Murraysmith | September 2018 |
| Creekside | “Creekside S-3 Pump Station” by Multi/Tech Consultants | September 1997 |
| Deer Park | “Deer Park Pump Station Improvements” by Landis Consulting | January 2013 |
| Edwards | “Intermediate Level Booster Pumps and Piping Edwards Pump Station” by Clark & Groff Engineers Inc. | January 1966 |
| Limelight | “Limelight Pump Station” by Multi/Tech Consultants | March 1997 |
| Mountain View | “Mt. View Pump Station for the City of Salem” by KMC, Inc. | January 1994 |
| Salem/Keizer Intertie #1 | “Keizer Intertie (Cherry Ave. N) Water Booster Pump Station” by Westech Engineering, Inc. | June 2012 |
| Turner Control Facility | “75 MGD Transmission Conduit Phase 2 Delaney Road to Turner Control” by Black & Veatch Corporation | October 2007 |

Table 1.5 Available Reservoir and Reservoir Control Building Documents

| Reservoir | Design Drawing, As-Built Drawing or Evaluation Report | Date |
|--------------------|---|---------------|
| Candalaria | “Proposed Candalaria Reservoir” by R.D. Cooper | May 1940 |
| | “Salem Concrete Reservoirs (Candalaria, Chacarun, Glen Creek and Skyline) Seismic Retrofit Project” by Black & Veatch Corporation | January 2006 |
| | “City of Salem’s 0.5 Million Gallon Candalaria Reservoir Evaluation” by Murray, Smith & Associates, Inc. | August 2011 |
| Champion Hill | “2.2 Million Gallon Champion Hill Reservoir” by Westech Engineering | August 2005 |
| Eola Reservoir #1B | “Eola 1B Water Reservoir” by Multi/Tech Consultants | May 1999 |
| Fairmount | “Fairmount Reservoir” by Stevens & Koon | April 1936 |
| | “Fairmount Reservoir Seismic Evaluation” by Black & Veatch Corporation | April 2007 |
| | “Fairmount Reservoir Structural Evaluation” by Carollo Engineers | April 2018 |
| Grice Hill | “Grice Hill Reservoir & Waterline Extension” by Westech Engineering | May 2001 |
| Lone Oak | “5.6 Million Gallon Lone Oak Reservoir” by CH2M Hill | July 2003 |
| Mill Creek #1 | “Mill Creek Reservoir As-Built Drawings” by Westech Engineering | December 2014 |
| Mountain View | “Mountain View Reservoir” by Stevens, Thomsen & Runyan Inc. | May 1971 |




Figure 1.1 City of Salem Water System General Location Map

2.0 Evaluation Methodology and Seismic Performance Objectives

2.1 Seismic Hazard

This evaluation considered a single seismic hazard level associated with a Magnitude 9.0 (M9.0) scenario earthquake originating on the Cascadia Subduction Zone (CSZ). As part of this project, Shannon and Wilson, Inc. conducted a geotechnical seismic hazard assessment (Shannon & Wilson, 2021). In their report, Shannon & Wilson provided estimates of the spectral acceleration and permanent ground deformation (PGD) for liquefaction-induced settlement, liquefaction-induced lateral spreading, and earthquake-induced landslide associated with the M9.0 CSZ scenario earthquake. The geotechnical data that was used as the basis for SEFT's structural evaluation is summarized in Table 2.1 (pump stations and control facilities) and Table 2.2 (reservoirs and reservoir control buildings).

2.2 Seismic Performance Objectives

In the initial phase of this project, the Black & Veatch/SEFT team worked with the City of Salem to establish proposed level of service (LOS) goals for the City of Salem water system following a major earthquake as described in Black & Veatch (2021). The structural and nonstructural performance objectives used for evaluation of water system components for the M9.0 CSZ scenario earthquake were based on the post-earthquake performance of facilities that will be required to achieve these LOS goals (i.e., Immediate Occupancy structural performance and Operational nonstructural performance) and are described in Sections 2.2.1 and 2.2.2. Additionally, this evaluation identified several structures that are not currently expected to achieve Life Safety structural performance (see Section 2.2.1 for definition) for the M9.0 CSZ scenario earthquake and represent a potential safety hazard to City staff and contractors.

2.2.1 Structural Performance Objective

Immediate Occupancy: "Immediate Occupancy" refers to the post-earthquake damage state in which only very limited structural damage has occurred. The basic vertical- and lateral-force-resisting systems of the building retain almost all their pre-earthquake strength and stiffness. The risk of life-threatening injury from structural damage is very low, and although some minor structural repairs might be appropriate, these repairs would generally not be required before re-occupancy. Continued use of the building is not limited by its structural condition but might be limited by damage or disruption to nonstructural elements of the building, furnishings, or equipment and availability of external utility services.

Life Safety: “Life Safety” refers to the post-earthquake damage state in which significant damage to the structure has occurred but some margin against either partial or total structural collapse remains. Some structural elements and components are severely damaged, but this damage has not resulted in large falling debris hazards, either inside or outside the building. Injuries might occur during the earthquake, however, the overall risk of life-threatening injury as a result of structural damage is expected to be low. It should be possible to repair the structure; however, for economic reasons, this repair might not be practical. Although the damaged structure is not an imminent collapse risk, it would be prudent to implement structural repairs or install temporary bracing before re-occupancy.

2.2.2 Nonstructural Performance Objectives

Operational: “Operational” refers to the performance level where most nonstructural systems required for normal use of the building are functional, although minor cleanup and repair of some items might be required. Achieving the Operational nonstructural performance level requires considerations of many elements beyond those that are normally within the sole province of the structural engineer’s responsibilities. For Operational nonstructural performance, in addition to ensuring that nonstructural components are properly mounted and braced within the structure, it is often necessary to provide emergency standby equipment to provide utility services from external sources that might be disrupted. It might also be necessary to perform qualification testing to ensure that all necessary equipment will function during or after strong shaking.

2.3 Water System Evaluation Methodology

2.3.1 Pump Stations, Control Facilities, and Control Buildings

The seismic structural evaluations of pump stations, control facilities and reservoir control buildings were completed using the Tier 1 screening procedure of the standard by the American Society of Civil Engineers (ASCE), ASCE 41-17 *Seismic Evaluation and Retrofit of Existing Buildings*. This Tier 1 procedure uses a checklist-based approach to identify potential seismic structural deficiencies that have been commonly observed in past earthquakes. The Tier 1 procedure also uses quick-check calculations to identify potential deficiencies in the primary components of the seismic lateral-force-resisting system.

The seismic nonstructural evaluation of pump stations, control facilities, and reservoir control buildings was completed using the nonstructural seismic evaluation checklists presented in ASCE 41-17 supplemented by the Technical Council on Lifeline Earthquake Engineering (TCLEE) Monograph No. 22 *Seismic Screening Checklists for Water and Wastewater Facilities*. Similar to the ASCE 41 Tier 1 structural evaluation procedure,

this checklist-based evaluation approach is used to identify potential seismic nonstructural deficiencies that have been commonly observed in past earthquakes.

2.3.2 Reservoirs

The seismic evaluation approach for the conventionally reinforced concrete reservoirs (Candalaria and Eola #1B Reservoirs) has been adapted from an American Society of Civil Engineering (ASCE) seismic evaluation and retrofit standard, ASCE 41-17 *Seismic Evaluation and Retrofit of Existing Buildings*. This standard provides a tool for identifying potential structural and nonstructural seismic deficiencies. The ASCE 41 Tier 1 screening process uses a quick-check calculation approach with unreduced (no response modification factor, R) and non-amplified (no importance factor, I) seismic forces. The demand-capacity ratio for seismic force resisting system elements is compared to ASCE 41 specified component modification factors (m -factors) to evaluate the acceptability of components of the structure for the Immediate Occupancy structural performance objective. Earthquake-induced hydrodynamic forces were calculated using the procedure outlined in American Concrete Institute (ACI) standard ACI 350.3-06 *Seismic Design of Liquid-Containing Concrete Structures and Commentary* (for Candalaria, Fairmount and Eola #1B Reservoirs), as modified by ASCE 7-16 *Minimum Design Loads and Associated Criteria for Buildings and Other Structures*. However, R and I -factors were set equal to 1.0 for consistency with the ASCE 41 evaluation approach. Consistent with ACI 350.3, soil loads were neglected where they act to decrease the demand on buried portions of reservoir concrete walls.

The approach used for the seismic evaluation of the Fairmount Reservoir was to complete a desktop review of the reservoir structural evaluation performed by Carollo Engineers in 2018 and our observations in the field.

For the five strand-wound, circular, prestressed concrete reservoirs (Champion Hill, Grice Hill, Lone Oak, Mill Creek #1, and Mountain View Reservoirs), a different evaluation approach was used because ASCE 41-17 does not include quick-check evaluations and acceptance criteria that are applicable to this type of reservoir. American Water Works Association (AWWA) standard design checks were performed to evaluate primary components of the seismic load path (roof to wall connection, circumferential strand, and seismic cables connecting the wall to foundation). Earthquake-induced hydrodynamic forces were calculated using the procedure outlined in AWWA D110-13 *Wire- and Strand-Wound, Circular, Prestressed Concrete Water Tanks*, as modified by ASCE 7-16 *Minimum Design Loads and Associated Criteria for Buildings and Other Structures*. Consistent with AWWA D110, soil loads were neglected where they act to decrease the demand on buried portions of reservoir concrete walls.

The Mill Creek #1 Reservoir, also a strand-wound, circular, prestressed concrete reservoir, was built in 2013. Since this reservoir is relatively new and was designed per

the latest seismic standards, the seismic assessment of this reservoir was conducted based on a desktop review of the reservoir drawings and our observations in the field.

Freeboard calculations were completed based on both the applicable AWWA or ACI design standard, and ASCE 7-16. The conclusions and recommendations of this study have been based on the more conservative of the freeboard estimates calculated using these standards.

The seismic nonstructural evaluation of reservoir components was completed using the nonstructural seismic evaluation checklists presented in ASCE 41-17, supplemented by TCLEE Monograph No. 22. Similar to the ASCE 41 Tier 1 structural evaluation procedure, this checklist-based evaluation approach is used to identify potential seismic nonstructural deficiencies that have been commonly observed in past earthquakes.

Table 2.1 Summary of Mapped Seismic Hazards at Pump Stations and Control Facilities
(Source: Shannon & Wilson, 2021)

| Pump Station or Control Building | Short Period Spectral Accel. (g) | One-Second Spectral Accel. (g) | Liquefaction-Induced Settlement (inches) | Liquefaction-Induced Lateral Spreading (inches) | Earthquake-Induced Landslide PGD (feet) |
|----------------------------------|----------------------------------|--------------------------------|--|---|---|
| ASR #1 and #2 | 0.28 | 0.12 | NA | NA | NA |
| ASR #4 | 0.28 | 0.12 | NA | NA | NA |
| ASR #5 | 0.28 | 0.12 | NA | NA | NA |
| Boone Road | 0.53 | 0.29 | NA | NA | NA |
| Creekside | 0.27 | 0.12 | NA | NA | NA |
| Deer Park | 0.35 | 0.12 | NA | NA | NA |
| Edwards | 0.68 | 0.32 | NA ⁽¹⁾ | NA ⁽¹⁾ | NA ⁽¹⁾ |
| Limelight | 0.33 | 0.13 | NA | NA | NA |
| Mountain View | 0.39 | 0.12 | NA | NA | NA |
| Salem/Keizer Intertie #1 | 0.74 | 0.29 | 1 | NA | NA |
| Turner Control Facility | 0.64 | 0.28 | 1 | NA | NA |

⁽¹⁾ Geologic maps may not adequately capture geohazard, see Shannon & Wilson (2021) for additional information.

Table 2.2 Summary of Mapped Seismic Hazards at Reservoirs and Reservoir Control Buildings

(Source: Shannon & Wilson, 2021)

| Reservoir and Control Building | Short Period Spectral Accel. (g) | One-Second Spectral Accel. (g) | Liquefaction-Induced Settlement (inches) | Liquefaction-Induced Lateral Spreading (inches) | Earthquake-Induced Landslide PGD (feet) |
|---------------------------------------|---|---------------------------------------|---|--|--|
| Candalaria | 0.43 | 0.12 | NA | NA | NA |
| Champion Hill | 0.27 | 0.12 | NA ⁽¹⁾ | NA ⁽¹⁾ | NA ⁽¹⁾ |
| Eola Reservoir #1B | 0.30 | 0.13 | NA | NA | NA |
| Fairmount | 0.46 | 0.12 | NA | NA | NA |
| Grice Hill | 0.30 | 0.13 | NA | NA | NA |
| Lone Oak | 0.27 | 0.12 | NA | NA | NA |
| Mill Creek #1 | 0.27 | 0.12 | NA | NA | NA |
| Mountain View | 0.39 | 0.12 | NA | NA | NA |

⁽¹⁾ Geologic maps may not adequately capture geohazard, see Shannon & Wilson (2021) for additional information.

3.0 Expected Seismic Structural and Nonstructural Performance

3.1 Pump Stations and Control Facilities

The expected structural and nonstructural seismic performance of selected City water pump stations and control facilities (i.e., Turner Control Facility) has been evaluated for a M9.0 CSZ scenario earthquake. The following sections provide a short narrative description of each pump station or control building evaluated, followed by tables that summarize the potential seismic structural and nonstructural deficiencies identified by the seismic evaluation using the ASCE 41-17 Tier 1 and TCLEE Monograph No. 22 checklist-based procedures. For each pump station or control building, selected images from the design drawings and/or site visit photos are provided to help illustrate the identified potential structural and nonstructural deficiencies.

Site visits to these pump stations and control facilities were conducted by SEFT on May 11th, 14th, 18th, and 25th, 2021. Site observation was limited to those areas readily accessible to view, and did not include any areas concealed by existing finishes, such as ceilings, soffits, etc. Site observation did not include entry into any permit required confined spaces. A detailed structural condition assessment of these structures was not included in the scope of this project.

3.1.1 ASR #1 and #2 Pump Station

The ASR #1 Pump Station structure was built in 1995 at 4635 Sunnyside Road SE. The ASR #2 structure was constructed in 1998 as an addition to the original ASR #1 Pump Station. The ASR #1 and #2 Pump Station structure (see Figure 3.1) is an above-grade, single-story, reinforced masonry shear wall structure with a plywood sheathed wood framed roof. The building is rectangular in plan, with approximate dimensions of 12 feet in the north-south direction by 54 feet in the east-west direction.

This pump station supports Wells #1 and #2 of the City's aquifer storage and recover (ASR) system. Water is drawn from the ASR system during the higher water demand summer season and the aquifer is recharged during the wintertime. One pump supports each of the wells and primarily serve the S2 pressure zone. A chlorination station is currently located within the pump station but will soon be relocated to a new common treatment building (chlorination, de-chlorination, pH adjustment, and corrosion control) that will support all the ASR wells on the site and is currently being constructed adjacent to the ASR #4 Pump Station. Therefore, the chlorination station nonstructural components within the ASR #1 and #2 Pump Station were not included in the scope of this seismic assessment.

This pump station does not have an emergency generator and does not have a pre-wired connection to hook-up a portable generator. The SCADA antenna for the ASR #1 and #2 Pump Station also supports the ASR #5 Pump Station and transmits to the antenna at the ASR #4 Pump Station that functions as a repeater to send information off this ASR site.

Table 3.1 presents a summary of potential seismic structural and nonstructural deficiencies identified by this evaluation. Based on the potential deficiencies identified in Table 3.1, the ASR #1 and #2 Pump Station is not expected to achieve Immediate Occupancy structural performance or Operational nonstructural performance for a M9.0 CSZ earthquake. Similarly, based on the structural deficiencies identified, the ASR #1 and #2 Pump Station is not currently expected to achieve Life Safety structural performance and represents a potential safety hazard to City staff and contractors.

Table 3.1 ASR #1 and #2 Pump Station Evaluation Summary

| Potential Deficiencies | Description |
|------------------------|---|
| Structural | <ul style="list-style-type: none"> • The original design drawings do not indicate how the masonry walls of the ASR #2 addition were connected to the walls of the original ASR #1 structure. • There is a step in the roof elevation between the ASR#1 and ASR #2 portions of the structure. Based on the original drawings, the load path to transfer seismic forces at this step from the roof diaphragm to the west masonry wall of the original ASR #1 structure is unclear (as it is concealed behind gypsum board). • The roof plywood sheathing to truss nailing schedule was not provided in the available original design drawings. • A positive connection does not appear to be provided between the sloped truss blocking and masonry wall top plate. Therefore, the load path is incomplete to transfer in-plane shear forces from the roof diaphragm to the masonry walls (see Figure 3.2). Additionally, blocking in approximately every third bay has a long vent slot that limits its capacity to transfer seismic forces from the roof diaphragm to the masonry wall. • Out-of-plane bracing for the perimeter and interior masonry walls is not adequate. The roof trusses are attached to the top plate of the perimeter masonry walls with hurricane ties, which are intended to provide capacity to primarily resist uplift, not to resist wall out-of-plane demands (see Figure 3.3). • Adequate cross ties between diaphragm chords are not provided in both directions. • No trim reinforcing is indicated at the sides of door and other openings in the original design drawings. |

Table 3.1 ASR #1 and #2 Pump Station Evaluation Summary (cont.)

| Potential Deficiencies | Description |
|------------------------|---|
| Nonstructural | <ul style="list-style-type: none"> • Water system piping within the pump station is not braced (see Figure 3.4) • Valves in line with the water system piping are not braced (see Figure 3.4). • The air relief valve is not braced and is only supported by rigid small diameter piping (see Figure 3.4). • Vertical pump motors are not braced above the center of gravity of the motor (see Figure 3.5). • There does not appear to be adequate flexibility in the piping that is attached to the pumps to accommodate potential relative movement between the piping and the pump, and to prevent the piping from adding additional load to the pump anchorage. • Electrical cabinets do not appear to be anchored or braced to the wall near the top of the cabinets to prevent them from tipping over during an earthquake. • Light fixtures in the pump station do not include lens covers (see Figure 3.6). • Electrical conduits, hung from the roof and connected to the top of wall-mounted electrical panels, may not have adequate flexibility to account for differential movement between the floor and the pump station roof (see Figure 3.7). • The horizontal arm of the SCADA antenna may not be adequately connected to the supporting pole to prevent the antenna from being misaligned or damaged after an earthquake (see Figure 3.8). • A 4-inch split-face CMU veneer was added to the original ASR #1 structure as part of construction of the ASR #2 addition. Original design drawings do not indicate the use of veneer ties and it was not clear if veneer ties were installed based on field observations of the gap between the original 8-inch CMU walls and 4-inch CMU veneer (see Figure 3.9). • The six architectural concrete pillars around the perimeter of the pump station may not have adequate capacity to resist seismic forces (see Figure 3.10). The number of vertical reinforcing bars is unclear in the original design drawings and no tie reinforcing is indicated. • No anchorage was observed between the electrical transformer and concrete support pad (see Figure 3.11). |



Figure 3.1 ASR #1 and #2 Pump Station



Figure 3.2 Inadequate Connection between Blocking and Masonry Wall Top Plate



Figure 3.3 Roof Truss to Masonry Wall Top Plate Connection



Figure 3.4 Unbraced Piping, Valves, and Air Relief Valve



Figure 3.5 Unbraced Pump Motor



Figure 3.6 Light Fixtures without Lens Covers



Figure 3.7 Conduit Top Connection to Electrical Panels without Flexible Connection



Figure 3.8 SCADA Antenna



Figure 3.9 Unknown Masonry Veneer Ties to Backup Masonry Wall



Figure 3.10 Architectural Concrete Pillar



Figure 3.11 Unanchored Electrical Transformer

3.1.2 ASR #4 Pump Station

The ASR #4 Pump Station structure (see Figure 3.12) was built in 1998 at 4535 Sunnyside Road SE. This structure is an above-grade, single-story, reinforced masonry shear wall structure with a plywood sheathed wood framed roof. The building is rectangular in plan, with approximate dimensions of 12 feet in the north-south direction by 30 feet in the east-west direction. Note that the interior masonry wall between the storage room and chlorination room (as shown on the original design drawings) has been previously removed.

This pump station supports Well #4 of the City's ASR system. Water is drawn from the ASR system during the higher water demand summer season and the aquifer is recharged during the wintertime. One pump supports the well and primarily serve the S2 pressure zone. A chlorination station is currently located within the pump station but will soon be relocated to a new common treatment building (chlorination, de-chlorination, pH adjustment, and corrosion control) that will support all the ASR wells on the site and is currently being constructed adjacent to the ASR #4 Pump Station. Therefore, the chlorination station nonstructural components within the ASR #4 Pump Station were not included in the scope of this seismic assessment.

This pump station does not have an emergency generator or a pre-wired connection to hook-up a portable generator. The SCADA antenna for the ASR #4 Pump Station also functions as a repeater for the ASR # 1 and #2 Pump Station and ASR #5 Pump Station to send information off this ASR site.

Table 3.2 presents a summary of potential seismic structural and nonstructural deficiencies identified by this evaluation. Based on the potential deficiencies identified in Table 3.2, the ASR #4 Pump Station is not expected to achieve Immediate Occupancy structural performance or Operational nonstructural performance for a M9.0 CSZ earthquake. Similarly, based on the structural deficiencies identified, the ASR #4 Pump Station is not currently expected to achieve Life Safety structural performance and represents a potential safety hazard to City staff and contractors.

Table 3.2 ASR #4 Pump Station Evaluation Summary

| Potential Deficiencies | Description |
|------------------------|--|
| Structural | <ul style="list-style-type: none"> • The roof plywood sheathing nailing schedule was not provided in the available original design drawings. • A positive connection does not appear to be provided between the sloped truss blocking and masonry wall top plate. Therefore, the load path is incomplete to transfer in-plane shear forces from the roof diaphragm to the masonry walls (see Figure 3.13). • The roof access hatch (for pump motor replacement) immediately adjacent to the east masonry wall creates a large opening in the diaphragm near a shear wall. This opening reduces the capacity of the diaphragm to transfer seismic forces to the shear wall below. • Out-of-plane bracing for the perimeter and interior masonry walls is not adequate. The roof trusses are attached to the top plate of the perimeter masonry walls with hurricane ties, which are intended to provide capacity to primarily resist uplift, not to resist wall out-of-plane demands (see Figure 3.14). Additionally, blocking in approximately every third bay has a long vent slot that limits its capacity to transfer seismic forces from the roof diaphragm to the masonry wall. • Adequate cross ties between diaphragm chords are not provided in both directions. • No trim reinforcing is indicated at the sides of door and other openings in the original design drawings. |
| Nonstructural | <ul style="list-style-type: none"> • Water system piping within the pump station is not braced (see Figure 3.15). • Valves in line with the water system piping are not braced (see Figure 3.15). • The air relief valve is not braced and is only supported by rigid small diameter piping (see Figure 3.15). • The vertical pump motor is not braced above the center of gravity of the motor (see Figure 3.16). • There does not appear to be adequate flexibility in the piping that is attached to the pump to accommodate potential relative movement between the piping and the pump, and to prevent the piping from adding additional load to the pump anchorage. • The pump station control cabinet does not appear to be anchored to the floor or wall (see Figure 3.17). • Light fixtures in the pump station do not include lens covers (see Figure 3.18). • No anchorage was observed between the electrical transformer and concrete support pad (see Figure 3.19). |



Figure 3.12 ASR #4 Pump Station



Figure 3.13 Inadequate Connection between Blocking and Masonry Wall Top Plate



Figure 3.14 Roof Truss to Masonry Wall Top Plate Connection



Figure 3.15 Unbraced Piping, Valves, and Air Relief Valve



Figure 3.16 Unbraced Pump Motor



Figure 3.17 Unanchored Control Cabinet



Figure 3.18 Light Fixtures without Lens Covers



Figure 3.19 Unanchored Electrical Transformer

3.1.3 ASR #5 Pump Station

The ASR #5 Pump Station structure (see Figure 3.20) was built in 1998 at 4615 Sunnyside Road SE. The pump station equipment is housed in an above-grade, single-story, reinforced masonry shear wall structure with a plywood ceiling diaphragm. This pump station structure is trapezoidal in plan, with approximate overall dimensions of 40 feet in north-south direction and 12 feet in east-west direction. This masonry shear wall structure is integrated with a premanufactured, hexagonal steel framed pavilion that is used by visitors to Woodmansee Park. The City of Salem Parks Department uses the room at the south end of the pump station structure for storage. This room was not accessible during SEFT's site visit.

This pump station supports Well #5 of the City's aquifer storage and recover (ASR) system. Water is drawn from the ASR system during the higher water demand summer season and the aquifer is recharged during the wintertime. One pump supports the well and primarily serve the S2 pressure zone. A chlorination station is currently located within the pump station but will soon be relocated to a new common treatment building (chlorination, de-chlorination, pH adjustment, and corrosion control) that will support all the ASR wells on the site and is currently being constructed adjacent to the ASR #4 Pump Station. Therefore, the chlorination station nonstructural components within the ASR #5 Pump Station were not included in the scope of this seismic assessment.

This pump station does not have an emergency generator or a pre-wired connection to hook-up a portable generator. SCADA data from the ASR #5 Pump Station is transmitted by buried cable to the ASR #1 and #2 Pump Station which then transmits to the antenna at the ASR #4 Pump Station that functions as a repeater to send information off this ASR site.

Table 3.3 presents a summary of potential seismic structural and nonstructural deficiencies identified by this evaluation. Based on the potential deficiencies identified in Table 3.3, the ASR #5 Pump Station is not expected to achieve Immediate Occupancy structural performance or Operational nonstructural performance for a M9.0 CSZ earthquake. Similarly, based on the structural deficiencies identified, the ASR #5 Pump Station is not currently expected to achieve Life Safety structural performance and represents a potential safety hazard to City staff and contractors. Note that the ASCE 41-17 Tier 1 procedure does not include checklists for the unique steel frames pavilion portion of the ASR #5 Pump Station structure. The interaction of the steel framed pavilion with the masonry shear wall structure below should be further investigated as part of a future detailed evaluation and seismic retrofit project.

Table 3.3 ASR #5 Pump Station Evaluation Summary

| Potential Deficiencies | Description |
|------------------------|--|
| Structural | <ul style="list-style-type: none"> • There does not appear to be either an adequate load path to transfer the seismic forces generated by the steel framed pavilion to the masonry shear wall structure or an adequate seismic separation to prevent unintended interaction between the steel framed pavilion and masonry shear wall structure. • The horizontal span for the ceiling diaphragm in the north-south direction is greater than the ASCE 41-17 Tier 1 limit for unblocked wood structural panel diaphragms if the interior masonry walls are not engaged as part of the seismic force resisting system. • The ceiling plywood sheathing nailing schedule was not provided in the available original design drawings. • Based on the original design drawings, it is unclear if blocking is provided between the ceiling sheathing and masonry wall top plate (see Figure 3.21). Therefore, the load path is potentially incomplete to transfer in-plane shear forces from the ceiling diaphragm to the masonry walls. • Out-of-plane bracing for the perimeter and interior masonry walls is not adequate. The ceiling joists are attached to the top plate of the perimeter masonry walls with hurricane ties, which are intended to provide capacity to primarily resist uplift, not resist wall out-of-plane demands (see Figure 3.21). • Adequate cross ties between diaphragm chords are not provided in both directions. • No vertical trim reinforcing is indicated at the sides of door and other openings in the original design drawings. • The free-standing masonry wall to the north of the pump station is not braced (see Figure 3.22). • Corrosion damage was observed at the base of the northern-most steel tube section columns of the pavilion (see Figure 3.23). If this corrosion damage is not adequately addressed, the seismic performance of the steel framed pavilion may be compromised. |

Table 3.3 ASR #5 Pump Station Evaluation Summary (cont.)

| Potential Deficiencies | Description |
|------------------------|--|
| Nonstructural | <ul style="list-style-type: none"> • Water system piping within the pump station is not braced (see Figure 3.24) • Valves in line with the water system piping are not braced (see Figure 3.24). • The air relief valve is not braced and is only supported by rigid small diameter piping (see Figure 3.25). • The vertical pump motor is not braced above the center of gravity of the motor (see Figure 3.26). • There does not appear to be adequate flexibility in the piping that is attached to the pump to accommodate potential relative movement between the piping and the pump, and to prevent the piping from adding additional load to the pump anchorage. • Electrical conduits, hung from the roof and connected to the top of floor- and wall-mounted electrical panels and cabinets, may not have adequate flexibility to account for differential movement between the floor and the pump station roof (see Figure 3.27). • The pump station controls cabinet does not appear to be anchored to the floor or wall (see Figure 3.28). • Light fixtures in the pump station do not include lens covers (see Figure 3.29). • No anchorage was observed between the electrical transformer and concrete support pad (see Figure 3.30). |



Figure 3.20 ASR #5 Pump Station




Figure 3.21 Inadequate Blocking and Masonry Wall Out-of-Plane Anchorage
(Source: Detail 5 on Sheet A3 of 1997 design drawings by Stettler Company)



Figure 3.22 Free-Standing Masonry Wall without Bracing



Figure 3.23 Corrosion Damage at Northern-Most Pavilion Steel Column



Figure 3.24 Unbraced Piping, Valves, and Air Relief Valve



Figure 3.25 Unbraced Air Relief Valve



Figure 3.26 Unbraced Pump Motor



Figure 3.27 Conduit Top Connection to Motor Control Center without Flexible Connection



Figure 3.28 Unanchored Control Cabinet



Figure 3.29 Light Fixtures without Lens Covers



Figure 3.30 Unanchored Electrical Transformer

3.1.4 Boone Road Pump Station

The original Boone Road Pump Station structure (see Figure 3.31 and Figure 3.32) was built in 1977 at 3351 Boone Rd SE. This structure is an above-grade, single-story, reinforced masonry shear wall structure with a straight-sheathed wood framed roof. The building is rectangular in plan, with approximate dimensions of 34 feet in the north-south direction by 36 feet in the east-west direction. The north and south gable end walls are offset from the masonry shear walls below, creating a step in the roof diaphragm. As part of a recent expansion project at the Boone Road Pump Station site, the original Boone Road Pump Station structure underwent a partial seismic retrofit. The roof to wall connections were strengthened with a combination of steel brackets installed between the straight-sheathed roof decking and masonry wall, and screws were added between the roof decking and masonry wall top plate.

A new electrical building that serves the pump station was recently constructed to the west of the original Boone Road Pump Station (see Figure 3.31). This recently constructed electrical building and the recently installed emergency generator, fuel tank, surge tank, and electrical utility owned transformer were excluded from the scope of this seismic assessment.

The Boone Road Pump Station currently houses three pumps that deliver water from the G0 Level to the S2 Level. Both the pump station and electrical building have capacity to support a future expansion to deliver water to the S1 Level. Note that the S2 Level pumps at Edwards Pump Station serve to supplement the Boone Road Pump Station.

Table 3.4 presents a summary of potential seismic structural and nonstructural deficiencies identified by this evaluation. Based on the potential deficiencies identified in Table 3.4, the Boone Road Pump Station is not expected to achieve Immediate Occupancy structural performance or Operational nonstructural performance for a M9.0 CSZ earthquake. Similarly, based on the structural deficiencies identified, the Boone Road Pump Station is not currently expected to achieve Life Safety structural performance and represents a potential safety hazard to City staff and contractors.

Table 3.4 Boone Road Pump Station Evaluation Summary

| Potential Deficiencies | Description |
|------------------------|---|
| Structural | <ul style="list-style-type: none"> • The roof configuration results in a partial height gable end that is offset from the masonry shear walls on the north and south sides of the building. These gable ends consist of plywood sheathing over the end glulam trusses, but the exact framing details and sheathing nail schedule are not clear in the available original design drawings. The load path may not be adequate to deliver seismic forces from the upper roof through these gable end walls and into the lower roof. • The roof diaphragm span and aspect ratio exceed the ASCE 41-17 Tier 1 limits for straight-sheathed diaphragms. • Adequate cross ties between diaphragm chords are not provided in both directions. The tension rod cross ties between diaphragm chords in the east-west direction do not provide adequate capacity to resist compressive cross tie forces. |
| Nonstructural | <ul style="list-style-type: none"> • Water system piping within the pump station is not braced (see Figure 3.33) • Valves in line with the water system piping are not braced (see Figure 3.33). • Vertical pump motors are not braced above the center of gravity of the motor (see Figure 3.34). • There does not appear to be adequate flexibility in the piping that is attached to the pumps to accommodate potential relative movement between the piping and the pump, and to prevent the piping from adding additional load to the pump anchorage. • The cable tray does not appear to have adequate longitudinal bracing (see Figure 3.35). In some locations the anchors for the transverse bracing appear to be improperly installed in a masonry head joint (see Figure 3.36). • Light fixtures in the pump station do not include lens covers (see Figure 3.37). • Metal floor grating lacks clip connecting the grating to the steel support framing (see Figure 3.38). • The horizontal arm of the SCADA antenna may not be adequately connected to the supporting pole to prevent the antenna from being misaligned or damaged after an earthquake (see Figure 3.39). |



Figure 3.31 Boone Road Pump Station (right) and Electrical Building (left)



Figure 3.32 Boone Road Pump Station




Figure 3.33 Unbraced Piping and Valves



Figure 3.34 Unbraced Pump Motor



Figure 3.35 Cable Tray Lacks Longitudinal Bracing



(a) Overall View



(b) Close-up View

Figure 3.36 Cable Tray Transverse Brace with Anchor Installed in Masonry Head Joint




Figure 3.37 Light Fixtures without Lens Covers



Figure 3.38 Grating without Clip Connection to Supporting Steel Framing



Figure 3.39 SCADA Antenna

3.1.5 Creekside Pump Station

The Creekside Pump Station structure (see Figure 3.40) was built in 1998 at 6025 Lone Oak Road SE. This structure is an above-grade, single-story, reinforced masonry shear wall structure with a plywood sheathed wood framed roof. The building is rectangular in plan, with approximate dimensions of 20 feet in the north-south direction by 47 feet in the east-west direction.

The Creekside Pump Station houses three pumps that deliver water from the S2 Level to the Champion Hill Reservoir (S3 Level). There is a terraced retaining wall to the north of the pump station that was excluded from the scope of this seismic assessment.

Table 3.5 presents a summary of potential seismic structural and nonstructural deficiencies identified by this evaluation. Based on the potential deficiencies identified in Table 3.5, the Creekside Pump Station is not expected to achieve Immediate Occupancy structural performance or Operational nonstructural performance for a M9.0 CSZ earthquake. Similarly, based on the structural deficiencies identified, the Creekside Pump Station is not currently expected to achieve Life Safety structural performance and represents a potential safety hazard to City staff and contractors.

Table 3.5 Creekside Pump Station Evaluation Summary

| Potential Deficiencies | Description |
|------------------------|--|
| Structural | <ul style="list-style-type: none"> • The roof plywood sheathing nailing schedule was not provided in the available original design drawings. • The roof diaphragm span for east-west oriented seismic forces exceeds the ASCE 41-17 Tier 1 limit for unblocked wood structural panel diaphragms. • The available original design drawings do not indicate that blocking was installed between the roof sheathing and masonry wall top plate in the bays between wood trusses. During the site visit, this area was blocked from view by soffit panels from the exterior and insulation in the attic space. Even if there is blocking installed, based on observation of similar construction, it is likely that blocking connections to the sheathing or masonry wall top plate are deficient. Therefore, the load path is likely inadequate to transfer in-plane shear forces from the roof diaphragm to the masonry walls. • The available original design drawings do not indicate how the roof diaphragm is connected to the gable end masonry walls. Therefore, the load path is potentially incomplete to transfer in-plane shear forces from the roof diaphragm to the masonry walls. |

Table 3.5 Creekside Pump Station Evaluation Summary (cont.)

| Potential Deficiencies | Description |
|---------------------------|--|
| Structural (cont.) | <ul style="list-style-type: none"> • Out-of-plane bracing of perimeter and interior masonry walls is not adequate. The roof trusses do not appear to be attached to the top plate of the perimeter masonry walls with any connection hardware intended to resist wall out-of-plane demands (see Figure 3.41). • Adequate cross ties between diaphragm chords are not provided in both directions. |
| Nonstructural | <ul style="list-style-type: none"> • Water system piping within the pump station is not braced (see Figure 3.42). • Valves in line with the water system piping are not braced (see Figure 3.42). • Air relief valves are not braced and are only supported by rigid small diameter piping (see Figure 3.43). • Vertical pump motors are not braced above the center of gravity of the motor (see Figure 3.44). • There does not appear to be adequate flexibility in the piping that is attached to the pumps to accommodate potential relative movement between the piping and the pump, and to prevent the piping from adding additional load to the pump anchorage. • Anchorage of electrical cabinets to the housekeeping pads was not visible from the outside of the cabinets and may not be adequate. Details for how the housekeeping pad is reinforced and connected to the slab on grade are not provided in the available original design drawings and may not be adequate. Additionally, electrical cabinets do not appear to be anchored or braced to the wall near the top of the cabinets to prevent them from tipping over during an earthquake. • The emergency generator air intake support frame, muffler, and exhaust pipe do not appear to be adequately anchored/braced (see Figure 3.45, Figure 3.46, and Figure 3.47). • No anchorage was observed between the electrical transformer and concrete support pad (see Figure 3.48). |



Figure 3.40 Creekside Pump Station




Figure 3.41 Inadequate Wall Out-of-Plane Anchorage Connection
(Source: Section A-A on Sheet A 2.3 of 1997 design drawings by Multi/Tech Consultants)



Figure 3.42 Unbraced Piping and Valves



Figure 3.43 Unbraced Air Relief Valves



Figure 3.44 Unbraced Pump Motor



Figure 3.45 Unanchored Emergency Generator Air Intake Support Frame



Figure 3.46 Unbraced Emergency Generator Muffler



Figure 3.47 Unbraced Emergency Generator Exhaust Pipe



Figure 3.48 Unanchored Electrical Transformer

3.1.6 Deer Park Pump Station

The Deer Park Pump Station structure (see Figure 3.49) was built in 1982 at 5475 Turner Rd SE, with an electrical room addition built between 2008 and 2010 immediately to the south of the original pump station structure. Roll-up door installation and associated modifications were constructed in 2013. The design drawings for the original pump station building and the electrical room addition were not available for review as part of this assessment. Based on site visit observations and the 2013 modification drawings, this structure is an above-grade, single-story, reinforced masonry shear wall structure with a plywood sheathed wood framed roof. The building is rectangular in plan, with approximate dimensions of 44 feet in the north-south direction by 20 feet in the east-west direction.

The Deer Park Pump Station houses three pumps that deliver water from the City's main transmission line (G0 Level) to the Mill Creek Reservoir (S1 Level). Note that the S1 Level pumps at Edwards Pump Station server as a backup to Deer Park Pump Station.

Table 3.6 presents a summary of potential seismic structural and nonstructural deficiencies identified by this evaluation. Based on the potential deficiencies identified in Table 3.6, the Deer Park Pump Station is not expected to achieve Immediate Occupancy structural performance or Operational nonstructural performance for a M9.0 CSZ earthquake. Similarly, based on the structural deficiencies identified, the Deer Park Pump Station is not currently expected to achieve Life Safety structural performance and represents a potential safety hazard to City staff and contractors.

Table 3.6 Deer Park Pump Station Evaluation Summary

| Potential Deficiencies | Description |
|------------------------|---|
| Structural | <ul style="list-style-type: none"> • No design drawings were available for the original construction of the pump station or the electrical room addition. The size, spacing, and detailing of the steel reinforcing for the masonry walls is unknown. Additionally, it is unknown how the masonry walls from the electrical room addition are connected to the walls of the original pump station. • The roof plywood sheathing to truss nail size and spacing are unknown. • The original south wall of the pump station (now an interior wall between the pump and electrical rooms) is not adequately engaged to resist seismic forces from the roof diaphragm (see Figure 3.50). Without engaging this interior wall, the roof diaphragm span for east-west oriented seismic forces exceeds the ASCE 41-17 Tier 1 limit for unblocked wood structural panel diaphragms. • A positive connection does not appear to be provided between the sloped truss blocking and masonry wall top plate in the original pump station (see Figure 3.51). In the electrical room addition, the view of the area where blocking would be installed was obstructed by insulation. Even if there is blocking installed, based on observation of similar construction, it is likely that blocking connections to the sheathing or masonry wall top plate are deficient. Therefore, the load path is likely inadequate to transfer in-plane shear forces from the roof diaphragm to the masonry walls. • The details of how the roof diaphragm is connected to the south gable end masonry wall are unknown. Therefore, the load path is potentially not adequate to transfer in-plane shear forces from the roof diaphragm to the masonry walls. • Out-of-plane bracing of perimeter and interior masonry walls is not adequate. The roof trusses are not attached to the top plate of the perimeter masonry walls with any metal connector hardware that is designed to resist wall out-of-plane demands (see Figure 3.52). • Adequate cross ties between diaphragm chords are not provided in both directions. |

Table 3.6 Deer Park Pump Station Evaluation Summary (cont.)

| Potential Deficiencies | Description |
|------------------------|---|
| Nonstructural | <ul style="list-style-type: none"> • Water system piping within the pump station is not braced (see Figure 3.53) • Valves in line with the water system piping are not braced (see Figure 3.53). • It is unknown if adequate dowels are provided between the pump support concrete pedestal and the floor slab to resist the expected shear and overturning demands. • There does not appear to be adequate flexibility in the piping that is attached to the pumps to accommodate potential relative movement between the piping and the pump, and to prevent the piping from adding additional load to the pump anchorage. • The pipe support stanchion base plates are missing anchors into the concrete slab (see Figure 3.54). • Anchorage of electrical cabinets to the concrete slab on grade was not visible from the outside of the cabinets and may not be adequate. Additionally, electrical cabinets do not appear to be anchored or braced to the wall near the top of the cabinets to prevent them from tipping over during an earthquake (see Figure 3.55). • The emergency generator starter batteries may not be adequately restrained. A restrainer bracket (similar to the one that would be expected to be installed for the emergency generator starter batteries) was observed inside the pump station (see Figure 3.56). • The horizontal arm of the SCADA antenna may not be adequately connected to the supporting pole to prevent the antenna from being misaligned or damaged after an earthquake (see Figure 3.57). • The wood pole and anchorage of the pole-mounted transformer to the pole may not be adequately designed to resist the seismic forces generated by the transformer |



Figure 3.49 Deer Park Pump Station



Figure 3.50 Sheathing Not Connected to Top Plate of Interior Masonry Wall



Figure 3.51 Inadequate Connection between Blocking and Masonry Wall Top Plate



Figure 3.52 Inadequate Connection between Truss Chord and Masonry Wall Top Plate



Figure 3.53 Unbraced Piping and Valves



Figure 3.54 Pipe Support Stanchion Missing Anchors into Floor Slab



Figure 3.55 Electrical Cabinet with Unknown Anchorage Details



Figure 3.56 Emergency Generator Starter Battery Restraint Bracket Observed in Pump Station



Figure 3.57 SCADA Antenna

3.1.7 Edwards Pump Station

The Edwards Pump Station structure (see Figure 3.58) was built in 1961 at Edward Dr SE, with intermediate level pump and piping modification completed in 1966. The design drawings for the original pump station building (i.e., 1961 construction) were not available for review as part of this assessment. Based on site observations and the 1966 modification drawings, this structure is an above-grade, single-story structure with a straight-sheathed wood framed roof. The lateral-force-resisting-system consists of Structural Clay Research (SCR) brick shear walls at the perimeter of the building and built-up steel frames in the east-west direction in the main (S2 Level) pump room area. Roof straight-sheathing is supported by a combination of steel frames, wood framing, and masonry walls. The building is L-shaped in plan, with approximate overall dimensions of 51 feet in the north-south direction by 39 feet in the east-west direction.

The Edwards Pump Station houses three pumps that deliver water from the City’s main transmission line (G0 Level) to the S1 Level and three additional pumps that deliver water to the S2 Level. Note that the S1 Level pumps at Edwards Pump Station serve as a backup to Deer Park Pump Station and the S2 Level pumps at Edwards Pump Station serve to supplement the Boone Road Pump Station.

Table 3.7 presents a summary of potential seismic structural and nonstructural deficiencies identified by this evaluation. Based on the potential deficiencies identified in Table 3.7, the Edwards Pump Station is not expected to achieve Immediate Occupancy structural performance or Operational nonstructural performance for a M9.0 CSZ earthquake. Similarly, based on the structural deficiencies identified, the Edwards Pump Station is not currently expected to achieve Life Safety structural performance and represents a potential safety hazard to City staff and contractors.

Table 3.7 Edwards Pump Station Evaluation Summary

| Potential Deficiencies | Description |
|------------------------|---|
| Structural | <ul style="list-style-type: none"> Per the Technical Memorandum “Seismic Geohazard Evaluation Report, City of Salem Seismic Resilience Study” by Shannon & Wilson, Inc., there is evidence of soil settlement resulting from past uncontrolled water releases at the pump stations and uncertainty associated with the liquefaction potential of the soil in the area around the pump station. Cracking of the masonry wall was observed at the southwest corner of the building near the base of the wall (see Figure 3.59). |

Table 3.7 Edwards Pump Station Evaluation Summary (cont.)

| Potential Deficiencies | Description |
|---------------------------|---|
| Structural (cont.) | <ul style="list-style-type: none"> • No design drawings were available for the original construction of the pump station. It has been assumed that the SCR brick walls are unreinforced. Additionally, member sizes and connection details are unknown for the roof straight-sheathing, wood framing, and steel frames in the main pump room. The load path may be incomplete or inadequate to transfer seismic forces from the roof diaphragm to the masonry walls and/or steel frames. • The shear stress in the masonry walls exceeds the ASCE 41-17 Tier 1 limit for unreinforced masonry. • The height-to-thickness ratio for the masonry walls exceeds the ASCE 41-17 Tier 1 limit for unreinforced masonry. • The flexural stress in the steel moment frame beams exceeds the ASCE 41-17 Tier 1 limit. • The story drift ratio for the steel moment frames exceeds the ASCE 41-17 Tier 1 limit. • The roof diaphragm spans and aspect ratios exceed the ASCE 41-17 Tier 1 limit for straight-sheathed diaphragms. • Adequate cross ties between diaphragm chords are not provided in both directions. • Independent secondary columns are not provided for all roof framing that is supported by unreinforced masonry walls/pilasters (see Figure 3.60). |
| Nonstructural | <ul style="list-style-type: none"> • Water system piping that penetrates through the pump station floor may not have adequate flexibility to accommodate the potential differential movement between the pump station and the surrounding soil at the pipe penetration. • Water system piping within the pump station is not braced (see Figure 3.61) • Valves in line with the water system piping are not braced (see Figure 3.61). • Vertical pump motors are not braced above the center of gravity of the motor (see Figure 3.62). • It is unknown if adequate dowels are provided between the pump support concrete pedestal and the floor slab to resist the expected shear and overturning demands. • There does not appear to be adequate flexibility in the piping that is attached to the pumps to accommodate potential relative movement between the piping and the pump, and to prevent the piping from adding additional load to the pump anchorage. |

Table 3.7 Edwards Pump Station Evaluation Summary (cont.)

| Potential Deficiencies | Description |
|------------------------------|--|
| Nonstructural (cont.) | <ul style="list-style-type: none"> • Anchorage of electrical cabinets to the housekeeping pads was not visible from the outside of the cabinets and may not be adequate. Details for how the housekeeping pad is reinforced and connected to the slab on grade are not provided in the available original design drawings and may not be adequate. Additionally, electrical cabinets do not appear to be anchored or braced to the wall near the top of the cabinets to prevent them from tipping over during an earthquake (see Figure 3.63). • Electrical conduits, hung from the roof and connected to the top of floor- and wall-mounted electrical panels and cabinets, may not have adequate flexibility to account for differential movement between the floor and the pump station roof (see Figure 3.64). • The emergency generator starter batteries may not be adequately restrained. • Pendant lights in the pump station do not include lens covers (see Figure 3.65). • The antenna may not be adequately braced to prevent the antenna from being misaligned or damaged after an earthquake (see Figure 3.66). • The HVAC condenser unit is not anchored to the concrete pad (see Figure 3.67). • Metal floor grating lacks clip connecting the grating to the steel support framing (see Figure 3.68). • The overhead bridge crane is not laterally braced and may damage other equipment during an earthquake (see Figure 3.69). • The rolling lifts are unrestrained and may potentially damage the piping and valves during an earthquake (see Figure 3.70). • The ladders are unrestrained and may topple into and potentially damage the piping and valves during an earthquake (see Figure 3.70). • The wood pole and anchorage of the pole-mounted transformer to the pole may not be adequately designed to resist the seismic forces generated by the transformer (see Figure 3.71). |



Figure 3.58 Edwards Pump Station



Figure 3.59 Cracking of Masonry Wall




Figure 3.60 Masonry Pilaster Supporting Roof Framing



Figure 3.61 Unbraced Piping and Valves



(a) S1 Level Pumps



(b) S2 Level Pumps

Figure 3.62 Unbraced Pump Motor



Figure 3.63 Electrical Cabinets with Unknown Anchorage Details



Figure 3.64 Conduits Connecting to Electrical Cabinets without Flexible Connections



Figure 3.65 Pendant Lights without Lens Covers



Figure 3.66 SCADA Antenna



Figure 3.67 Unanchored HVAC Condenser Unit



Figure 3.68 Grating without Clip Connection to Supporting Steel Framing



Figure 3.69 Unrestrained Overhead Bridge Crane



Figure 3.70 Unrestrained Ladder and Rolling Lift



Figure 3.71 Pole-Mounted Electrical Transformers

3.1.8 Limelight Pump Station

The Limelight Pump Station structure (see Figure 3.72) was built in 1998 at NW Van Buren Dr. This structure is an above-grade, single-story, reinforced masonry shear wall structure with a plywood sheathed wood framed roof. The building is rectangular in plan, with approximate dimensions of 20 feet in the east-west direction by 41 feet in the north-south direction.

The Limelight Pump Station houses three pumps that deliver water from the Glen Creek Reservoir to approximately 1,000 nearby homes.

Table 3.8 presents a summary of potential seismic structural and nonstructural deficiencies identified by this evaluation. Based on the potential deficiencies identified in Table 3.8 the Limelight Pump Station is not expected to achieve Immediate Occupancy structural performance or Operational nonstructural performance for a M9.0 CSZ earthquake. Similarly, based on the structural deficiencies identified, the Limelight Pump Station is not currently expected to achieve Life Safety structural performance and represents a potential safety hazard to City staff and contractors.

Table 3.8 Limelight Pump Station Evaluation Summary

| Potential Deficiencies | Description |
|------------------------|--|
| Structural | <ul style="list-style-type: none"> • Several vertical cracks were observed in all four exterior masonry walls of the pump station (see Figure 3.73). Also, deterioration of the plywood sheathing and support framing was observed adjacent to the pump station entrances (see Figure 3.74). • The roof plywood sheathing nailing schedule was not provided in the available original design drawings. • The roof diaphragm span for east-west oriented seismic forces exceeds the ASCE 41-17 Tier 1 limit for unblocked wood structural panel diaphragms. • A positive connection does not appear to be provided between the sloped truss blocking and masonry wall top plate. Therefore, the load path is incomplete to transfer in-plane shear forces from the roof diaphragm to the masonry walls. Additionally, blocking in approximately every other bay has a long vent slot that limits its capacity to transfer seismic forces from the roof diaphragm to the masonry wall (see Figure 3.75). |

Table 3.8 Limelight Pump Station Evaluation Summary (cont.)

| Potential Deficiencies | Description |
|---------------------------|--|
| Structural (cont.) | <ul style="list-style-type: none"> • The available original design drawings do not indicate how the roof diaphragm is connected to the gable end triangular portion wood framed walls and masonry walls below, and do not provide any details for these wood framed walls. Therefore, the load path is potentially inadequate to transfer in-plane shear forces from the roof diaphragm to the masonry shear walls below. • Out-of-plane bracing of perimeter and interior masonry walls is not adequate. The roof trusses do not appear to be attached to the top plate of the perimeter masonry walls with any connection hardware intended to resist wall out-of-plane demands (see Figure 3.76). • Adequate cross ties between diaphragm chords are not provided in both directions. |
| Nonstructural | <ul style="list-style-type: none"> • Water system piping within the pump station is not braced (see Figure 3.77). • Valves in line with the water system piping are not braced (see Figure 3.77). • Air relief valves are not braced and are only supported by rigid small diameter piping (see Figure 3.78). • Vertical pump motors are not braced above the center of gravity of the motor (see Figure 3.79). • There does not appear to be adequate flexibility in the piping that is attached to the pumps to accommodate potential relative movement between the piping and the pump, and to prevent the piping from adding additional load to the pump anchorage. • Anchorage of electrical cabinets to the housekeeping pads was not visible from the outside of the cabinets and may not be adequate. Details for how the housekeeping pad is reinforced and connected to the slab on grade are not provided in the available original design drawings and may not be adequate. Additionally, electrical cabinets do not appear to be anchored or braced to the wall near the top of the cabinets to prevent them from tipping over during an earthquake (see Figure 3.80). • The horizontal arm of the SCADA antenna may not be adequately connected to the supporting pole to prevent the antenna from being misaligned or damaged after an earthquake (see Figure 3.81). • No anchorage was observed between the electrical transformer and concrete support pad (see Figure 3.82). |



Figure 3.72 Limelight Pump Station



Figure 3.73 Masonry Wall Cracking



Figure 3.74 Sheathing and Framing Deterioration



Figure 3.75 Sloped Blocking Between Wood Trusses




Figure 3.76 Inadequate Wall Out-of-Plane Anchorage Connection
(Source: Typical Building Section on Sheet A 2.2 of 1997 design drawings by Multi/Tech Consultants)



Figure 3.77 Unbraced Piping and Valves



Figure 3.78 Unbraced Air Relief Valve



Figure 3.79 Unbraced Pump Motor



Figure 3.80 Electrical Cabinets with Unknown Anchorage Details



Figure 3.81 SCADA Antenna



Figure 3.82 Unanchored Electrical Transformer

3.1.9 Mountain View Pump Station

The Mountain View Pump Station structure (see Figure 3.83) was built in 1994 at 1616 Schoolhouse Ct NW. This structure is an above-grade, single-story, reinforced masonry shear wall structure with a plywood sheathed wood framed roof. The building is rectangular in plan, with approximate dimensions of 29 feet in the north-south direction by 62 feet in the east-west direction. A significant length of the north wall of the building is inset by approximately four feet. Roof framing at the north edge of the building is supported by a CMU beam that is then supported by three CMU square columns.

The Mountain View Pump Station houses four pumps that deliver water from the G0 Level to the Grice Hill Reservoir (W2 Level). There is a site/retaining wall to the south and west of the pump station that was excluded from the scope of this seismic assessment.

Table 3.9 presents a summary of potential seismic structural and nonstructural deficiencies identified by this evaluation. Based on the potential deficiencies identified in Table 3.9 the Mountain View Pump Station is not expected to achieve Immediate Occupancy structural performance or Operational nonstructural performance for a M9.0 CSZ earthquake. Similarly, based on the structural deficiencies identified, the Mountain View Pump Station is not currently expected to achieve Life Safety structural performance and represents a potential safety hazard to City staff and contractors.

Table 3.9 Mountain View Pump Station Evaluation Summary

| Potential Deficiencies | Description |
|------------------------|--|
| Structural | <ul style="list-style-type: none"> The load path is incomplete to deliver seismic forces from the roof diaphragm to the north masonry shear wall. Note that the observed as-built framing configuration is different than shown in the original design drawings (see Figure 3.84). Out-of-plane bracing of perimeter and interior masonry walls is not adequate. The roof trusses do not appear to be attached to the top plate of the perimeter masonry walls with metal connector hardware specifically designed to resist out-of-plane seismic forces. In the direction perpendicular to the roof trusses, the roof sheathing is used to provide out-of-plane bracing for the masonry walls (see Figure 3.85). Adequate cross ties between diaphragm chords are not provided in both directions. |

Table 3.9 Mountain View Pump Station Evaluation Summary (cont.)


| Potential Deficiencies | Description |
|------------------------|--|
| Nonstructural | <ul style="list-style-type: none"> • Water system piping within the pump station is not braced (see Figure 3.86) • Valves in line with the water system piping are not braced (see Figure 3.86). • Air relief valves are not braced and are only supported by rigid small diameter piping (see Figure 3.87). • Vertical pump motors are not braced above the center of gravity of the motor (see Figure 3.88). • There does not appear to be adequate flexibility in the piping that is attached to the pumps to accommodate potential relative movement between the piping and the pump, and to prevent the piping from adding additional load to the pump anchorage. • The piping gravity support stanchions are not anchored to the slab (see Figure 3.89). • The chlorination equipment is not adequately anchored, and the supporting concrete curb is severely damaged (see Figure 3.90 and Figure 3.91). • The fuse protection soft starter cabinets are restrained at the top by a wall mounted strut and spacers. The lag screw expansion shield anchors used to attach the strut to masonry wall are likely not seismically rated and may not provide adequate capacity (see Figure 3.92). Also, the short strut section spacers are not positively connected to the main strut. • The electrical transformer hung from the roof is not adequately braced (see Figure 3.93). • Anchorage of electrical cabinets to the concrete slab was not visible from the outside of the cabinets and may not be adequate. Additionally, electrical cabinets have only one clip angle bracket per cabinet that attaches between the top of the cabinet to the wall, which may not be adequate to prevent them from tipping over during an earthquake (see Figure 3.94). • Electrical conduits, hung from the roof and connected to the top of floor- and wall-mounted electrical panels and cabinets, may not have adequate flexibility to account for differential movement between the floor and the pump station roof (see Figure 3.95). • The emergency generator starter batteries are not adequately restrained, and the battery bins are not anchored (see Figure 3.96). • The emergency generator muffler is not adequately braced (see Figure 3.97). |

Table 3.9 Mountain View Pump Station Evaluation Summary (cont.)

| Potential Deficiencies | Description |
|------------------------------|--|
| Nonstructural (cont.) | <ul style="list-style-type: none"> • Light fixtures in the pump station do not include lens covers (see Figure 3.98). • The horizontal arm of the SCADA antenna may not be adequately connected to the supporting pole to prevent the antenna from being misaligned or damaged after an earthquake (see Figure 3.99). • The overhead trolley chain hoist is not laterally braced and may damage other equipment during an earthquake (see Figure 3.100). • A ladder is unrestrained and may topple into and potentially damage the piping and valves during an earthquake (see Figure 3.100). • No anchorage was observed between the electrical transformer and concrete support pad (see Figure 3.101). |



Figure 3.83 Mountain View Pump Station



(a) Detail from Original Design Drawings
(Source: Detail 2 on Sheet S4 of 1994 design drawings by KMC, Inc.)



(b) As-built Framing Configuration Different than Shown on Original Design Drawings

Figure 3.84 Incomplete Load Path at North Wall




Figure 3.85 Inadequate East and West Wall Out-of-Plane Anchorage
(Source: Detail 3 on Sheet S4 of 1994 design drawings by KMC, Inc.)



Figure 3.86 Unbraced Piping and Valves



Figure 3.87 Unbraced Air Relief Valve



Figure 3.88 Unbraced Pump Motor



Figure 3.89 Pipe Support Stanchion Missing Anchors into Floor Slab



Figure 3.90 Chlorine System without Adequate Anchorage



Figure 3.91 Deteriorated Concrete Curb



Figure 3.92 Inadequate Lag Screw and Spacer Strut Connection to Wall



Figure 3.93 Unbraced Elevated Electrical Transformer



Figure 3.94 Electrical Cabinet with Single Anchor Bracket at Top of Cabinet



Figure 3.95 Conduits Connecting to Electrical Cabinets without Flexible Connections



Figure 3.96 Unrestrained Emergency Generator Starter Batteries



Figure 3.97 Unbraced Emergency Generator Muffler



Figure 3.98 Light Fixtures without Lens Covers



Figure 3.99 SCADA Antenna




Figure 3.100 Unrestrained Chain Hoist and Ladder



Figure 3.101 Unanchored Electrical Transformer

3.1.10 Salem/Keizer Intertie #1 Pump Station

The Salem/Keizer Intertie #1 Pump Station structure (see Figure 3.102) was built in 2013 at 4110 Cherry Ave NE. This structure is an above-grade, single-story, reinforced masonry shear wall structure with a plywood sheathed wood framed roof. The building is rectangular in plan, with approximate dimensions of 26 feet in the north-south direction by 22 feet in the east-west direction. The pump station is separated from a City of Keizer well building immediately to the east of the pump station by a half-inch gap.

The Salem/Keizer Intertie #1 Pump Station houses one pump and chlorination equipment that can be used as an emergency source to deliver water from the City of Keizer to the City of Salem system. The pump and piping have a capacity of approximately 10 million gallons per day (MGD). However, the City of Keizer is only able to deliver approximately 4 to 5 MGD to the City of Salem at this intertie.

Table 3.10 presents a summary of potential seismic structural and nonstructural deficiencies identified by this evaluation. Based on the potential deficiencies identified in Table 3.10 the Salem/Keizer Intertie #1 Pump Station is not expected to achieve Immediate Occupancy structural performance or Operational nonstructural performance for a M9.0 CSZ earthquake. Similarly, based on the structural deficiencies identified, the Salem/Keizer Intertie #1 Pump Station is not currently expected to achieve Life Safety structural performance and represents a potential safety hazard to City staff and contractors.

Table 3.10 Salem/Keizer Intertie #1 Pump Station Evaluation Summary

| Potential Deficiencies | Description |
|------------------------|---|
| Structural | <ul style="list-style-type: none"> Per the Technical Memorandum “Seismic Geohazard Evaluation Report, City of Salem Seismic Resilience Study” by Shannon & Wilson, Inc., there is a potential liquefaction hazard at the site. Liquefaction-induced permanent ground deformation may result in damage to the building structure. The City of Salem pump station and the adjacent City of Keizer building are only separated by a half-inch seismic joint. This small separation may not be adequate to prevent damage resulting from earthquake shaking-induced pounding between the two buildings. Roof sheathing is not continuous to the roof ridge line (see Figure 3.103). A positive connection does not appear to be provided between the truss blocking and masonry wall top plate. Therefore, the load path is incomplete to transfer in-plane shear forces from the roof diaphragm to the masonry walls (see Figure 3.104). |

Table 3.10 Salem/Keizer Intertie #1 Pump Station Evaluation Summary (cont.)

| Potential Deficiencies | Description |
|---------------------------|---|
| Structural (cont.) | <ul style="list-style-type: none"> In the east-west direction, continuous cross ties are not provided between diaphragm chords. Blocking and metal connector straps are provided at 2 feet on center in all but two of the bays between trusses (see Figure 3.105). |
| Nonstructural | <ul style="list-style-type: none"> Water system piping that penetrates through the pump station floor may not have adequate flexibility to accommodate the potential differential movement between the pump station and the surrounding soil at the pipe penetration. Water system piping within the pump station is not braced (see Figure 3.106). Also, the overflow pipe on the south side of the pump station is not braced (Figure 3.107). Valves in line with the water system piping are not braced (see Figure 3.106). There does not appear to be adequate flexibility in the piping that is attached to the pumps to accommodate potential relative movement between the piping and the pump, and to prevent the piping from adding additional load to the pump anchorage. The chlorination skid is not adequately restrained (see Figure 3.108). Also, the tank is bolted to the floor grid of the chlorination skid, but the floor grid is not positively connected to the skid itself. Anchorage of electrical cabinets to the concrete housekeeping pads was not visible from the outside of the cabinets and may not be adequate. The top of the electrical cabinet is restrained with an L-shaped bracket that was fabricated by cutting the flanges of a short section of strut and bending about the web of the strut. The web of the strut may be susceptible to fracture during an earthquake based on how it was fabricated. Also, the vertical position of the anchor bolt between the bracket and wall results in a large eccentricity that will cause additional prying action demand on the anchor (see Figure 3.109). The horizontal arm of the SCADA antenna may not be adequately connected to the supporting pole to prevent the antenna from being misaligned or damaged after an earthquake (see Figure 3.110). No anchorage was observed between the electrical transformer and concrete support pad (see Figure 3.111). |



Figure 3.102 Salem/Keizer Intertie #1 Pump Station



Figure 3.103 Roof Sheathing not Continuous to Ridge Line




Figure 3.104 Incomplete Load Path
(Source: Detail 3 on Sheet S-06 of 2012 design drawings by Westech Engineering)




Figure 3.105 Ceiling Level Blocking not Continuous
(Source: Section B on Sheet S-03 of 2012 design drawings by Westech Engineering)



Figure 3.106 Unbraced Piping and Valves



Figure 3.107 Unbraced Overflow Pipe on South Side of Pump Station



Figure 3.108 Unanchored Chlorination Skid



Figure 3.109 Anchorage at Electrical Cabinet with Bent Strut



Figure 3.110 SCADA Antenna



Figure 3.111 Unanchored Electrical Transformer

3.1.11 Turner Control Facility

The original Turner Control Facility at 7100 3rd Street SE in Turner was substantially replaced in 2007. However, a small subgrade portion of the original Turner Control Facility was integrated into the new structure. The Turner Control Facility (see Figure 3.112) is a single-story, above grade reinforced masonry shear wall structure with a plywood sheathed light-gauge metal framed roof. The building is constructed over two sections of concrete basement, where the three water transmission lines and associated valves are located. The building is rectangular in plan, with approximate wall dimensions of 36 feet in the northwest-southeast direction by 52 feet in the northeast-southwest direction.

The Turner Control Facility houses valves that are used to control the flow of water to the G0 Level system from Franzen Reservoir and Geren Island Water Treatment Facility.

Table 3.11 presents a summary of potential seismic structural and nonstructural deficiencies identified by this evaluation. Based on the potential deficiencies identified in Table 3.11, the Turner Control Facility is not expected to achieve Immediate Occupancy structural performance or Operational nonstructural performance for a M9.0 CSZ earthquake. Similarly, based on the structural deficiencies identified, the Turner Control Facility is not currently expected to achieve Life Safety structural performance and represents a potential safety hazard to City staff and contractors.

Table 3.11 Turner Control Facility Evaluation Summary

| Potential Deficiencies | Description |
|------------------------|--|
| Structural | <ul style="list-style-type: none"> • Per the Technical Memorandum “Seismic Geohazard Evaluation Report, City of Salem Seismic Resilience Study” by Shannon & Wilson, Inc., there is a potential liquefaction hazard at the site. Liquefaction-induced permanent ground deformation may result in damage to the building structure. • The roof diaphragm spans in both directions exceed the ASCE 41-17 Tier 1 limit for unblocked wood structural panel diaphragms. • At the gable end walls, the roof sheathing to blocking and blocking to masonry wall top plate fastener detailing are unclear. The load path may not be adequate to transfer in-plane shear forces from the roof diaphragm to the masonry walls (see Figure 3.113). • At the gable end walls, the outrigger to roof diaphragm connection may not have adequate capacity to resist the expected out-of-plane seismic forces from the masonry walls. • There are no cross ties provided between diaphragm chords in the direction perpendicular to the roof trusses. |

Table 3.11 Turner Control Facility Evaluation Summary (cont.)

| Potential Deficiencies | Description |
|------------------------|--|
| Nonstructural | <ul style="list-style-type: none"> • Water system piping that penetrates through the control facility walls may not have adequate flexibility to accommodate the potential differential movement between the control facility and the surrounding soil at the pipe penetration. • Water system piping within the control facility does not appear to be adequately braced (see Figure 3.114) • Valves in line with the water system piping are not braced (see Figure 3.115). • The valve actuators are not braced (see Figure 3.116). • The control cabinet did not appear to be anchored to the housekeeping pad or wall (see Figure 3.117). • The electrical transformer is only anchored with two anchors at the front of the unit. It is missing two anchors into the concrete slab at the back of the unit (see Figure 3.118). • Backup batteries in the battery cabinet are not adequately restrained (see Figure 3.119). • Pendant lights are not restrained to prevent them from hitting the wall (see Figure 3.120). • Light fixtures in the control facility do not include lens covers (see Figure 3.121). • The horizontal arm of the SCADA antenna may not be adequately connected to the supporting pole to prevent the antenna from being misaligned or damaged after an earthquake (see Figure 3.122). • The ceiling hung inline HVAC fan is not laterally braced (see Figure 3.123). • No anchorage was observed between the HVAC condenser unit and concrete support pad (see Figure 3.124). • Two storage shelving units are not anchored to the floor and/or the wall (see Figure 3.125). • The fire extinguisher is not adequately restrained in its cabinet (see Figure 3.126). |



Figure 3.112 Turner Control Facility




Figure 3.113 Incomplete Load Path at Gable End Walls
(Source: Detail 2 on Sheet S11 of 2007 design drawings by Black & Veatch)



Figure 3.114 Unbraced Pipe




Figure 3.115 Unbraced Valve



Figure 3.116 Unbraced Valve Actuator



(a) Exterior View



(b) Interior View

Figure 3.117 Unanchored Control Cabinet



Figure 3.118 Electrical Transformer Missing Anchors into Floor Slab



Figure 3.119 Unrestrained Backup Batteries in Battery Cabinet



Figure 3.120 Unrestrained Pendant Light Fixtures



Figure 3.121 Light Fixtures without Lens Covers



Figure 3.122 SCADA Antenna



Figure 3.123 Unbraced Inline Fan Unit



Figure 3.124 Unanchored HVAC Condenser Unit



Figure 3.125 Unanchored Shelf



Figure 3.126 Unrestrained Fire Extinguisher

3.2 Reservoirs and Reservoir Control Buildings

The expected structural and nonstructural seismic performance for selected City water reservoirs and associated reservoir control buildings has been evaluated for a M9.0 CSZ scenario earthquake. The following sections provide a short narrative description of each reservoir and associated reservoir control building (where applicable), followed by tables that summarize the potential seismic structural and nonstructural deficiencies identified by the seismic evaluations conducted using the procedures described in Section 2.3. For each reservoir and reservoir control building, selected images from the design drawings and/or site visit photos are provided to help illustrate the identified potential structural and nonstructural deficiencies.

Site visits to these reservoirs and reservoir control buildings were conducted by SEFT on May 11th, 14th, 18th, and 25th, 2021. Site observation was limited to those areas readily accessible to view, and did not include any areas concealed by existing finishes, such as ceilings, soffits, etc. Site observation did not include entry into any permit required confined spaces and did not include any entry or observation inside the reservoirs. A detailed structural condition assessment of these structures was not included in the scope of this project.

3.2.1 Candalaria Reservoir

The Candalaria Reservoir (see Figure 3.127) is located at Candalaria Park, to the north of Candalaria Blvd S. The 0.5-million-gallon (MG) reservoir was originally constructed in 1940. This reservoir is a completely buried rectangular reinforced concrete reservoir with approximate dimensions of 123 feet in the north-south direction by 50 feet in the east-west direction, and a maximum height of retained water of 15 feet. The Candalaria Reservoir serves the City's S1 Level. The City has future plans to construct additional water storage capacity on this site, with a new reservoir located to the south of the existing reservoir.

In 2006 the reservoir was seismically retrofit. The scope of this retrofit included the addition of anchors to connect the roof of the reservoir to the walls. The 2006 retrofit also included the installation of a seismic shutoff valve in a new vault located on the north side of the reservoir. Note that SEFT did not have access to the interior of this valve vault during our site visit. In 2011, Murray, Smith & Associates conducted a condition assessment of Candalaria Reservoir. SEFT reviewed the report associated with the 2011 condition assessment to help inform our seismic assessment.

Table 3.12 presents a summary of potential seismic structural and nonstructural deficiencies identified by this evaluation. Based on the potential deficiencies identified in Table 3.12, the Candalaria Reservoir is not expected to achieve Immediate Occupancy

structural performance or Operational nonstructural performance for a M9.0 CSZ earthquake.

Table 3.12 Candalaria Reservoir Evaluation Summary

| Potential Deficiencies | Description |
|------------------------|--|
| Structural | <p><u>Reservoir</u></p> <ul style="list-style-type: none"> The column vertical reinforcing lap splice length is less than the ASCE 41-17 Tier 1 specified minimum length for Immediate Occupancy structural performance (i.e., 50 bar diameters). <p><u>Valve Vault</u></p> <ul style="list-style-type: none"> Per the 2006 design drawings, the valve vault was specified to be cast-in-place concrete or precast concrete, at the contractor's option. If the valve vault was constructed from precast concrete, riser joints of stacked precast components may separate and shift due to seismic lateral earth pressures of the face of the valve vault. Sand, silt, or groundwater may infiltrate and leak into the valve vault at the precast concrete construction joints. |
| Nonstructural | <p><u>Reservoir</u></p> <ul style="list-style-type: none"> Some piping and fittings within the reservoir may be cast-iron, which is a brittle material that may crack when subjected to earthquake shaking-induced forces and/or ground deformation. The overflow pipe and valve operator riser shafts may not be adequately braced to resist seismic forces (see Figure 3.128). Note that the 2011 condition assessment also indicated that these elements were observed to have significant corrosion deterioration. <p><u>Valve Vault</u></p> <ul style="list-style-type: none"> Per the 2006 design drawings, the piping and valve inside the valve vault are not independently braced. Backup batteries in the battery cabinet (for operation of the seismic valve) may not be adequately restrained. |



Figure 3.127 Candalaria Reservoir



Figure 3.128 Overflow Pipe and Valve Operator Risers Not Adequately Braced
(Source: 2011 Reservoir Condition Assessment by Murray, Smith & Associates)

3.2.2 Champion Hill Reservoir and Control Building

The Champion Hill Reservoir (see Figure 3.129) is a 2.2 MG tank built in 2005 at the Champion Hill site off Reservoir Road SE. This reservoir is a strand-wound, circular, prestressed concrete reservoir with a nearly flat roof, an approximate diameter of 140 feet and a maximum height of retained water of 20 feet. The Champion Hill Reservoir serves the City’s S3 Level and is supplied by the Creekside Pump Station.

The Champion Hill Reservoir Control Building (see Figure 3.130) is located to the north of the reservoir. The control building is a single-story structure, with reinforced concrete walls below grade, reinforced masonry walls above grade, and a plywood sheathed wood truss roof. The building is rectangular in plan, with approximate dimensions of 38 feet in north-south direction by 46 feet in east-west direction. The building houses piping and valves (including seismic shutoff valves) that support the operation of the reservoir. The original design of the control building included a chlorination room and associated equipment, but the chlorination system is not currently used. Therefore, the chlorination system has not been included in the scope of the nonstructural assessment.

Table 3.13 and Table 3.14 present a summary of potential seismic structural and nonstructural deficiencies identified by this evaluation. Based on the potential deficiencies identified in Table 3.13, the Champion Hill Reservoir is not expected to achieve Immediate Occupancy structural performance or Operational nonstructural performance for a M9.0 CSZ earthquake. Based on potential deficiencies identified in Table 3.14, the Champion Hill Reservoir Control Building is not expected to achieve Immediate Occupancy structural performance or Operational nonstructural performance for the M9.0 CSZ earthquake. Similarly, based on the structural deficiencies identified, the Champion Hill Reservoir Control Building is not currently expected to achieve Life Safety structural performance and represents a potential safety hazard to City staff and contractors.

Table 3.13 Champion Hill Reservoir Evaluation Summary

| Potential Deficiencies | Description |
|------------------------|---|
| Structural | <ul style="list-style-type: none"> Per the Technical Memorandum “Seismic Geohazard Evaluation Report, City of Salem Seismic Resilience Study” by Shannon & Wilson, Inc., the reservoir site is potentially founded on silty soil that may be susceptible to liquefaction depending on the groundwater level. The column vertical reinforcing lap splice length is less than the ASCE 41-17 Tier 1 specified minimum length for Immediate Occupancy structural performance (i.e., 50 bar diameters). |

Table 3.13 Champion Hill Reservoir Evaluation Summary (cont.)

| Potential Deficiencies | Description |
|------------------------|---|
| Nonstructural | <ul style="list-style-type: none"> The pipe support concrete pedestals within the reservoir do not appear to be positively connected to the reservoir floor. Original design drawings show that the vertical reinforcing at the corners of the pedestal terminates at the top of the reservoir floor (see Figure 3.131). |

Table 3.14 Champion Hill Reservoir Control Building Evaluation Summary

| Potential Deficiencies | Description |
|------------------------|---|
| Structural | <ul style="list-style-type: none"> Per the Technical Memorandum “Seismic Geohazard Evaluation Report, City of Salem Seismic Resilience Study” by Shannon & Wilson, Inc., the reservoir site is potentially founded on silty soil that may be susceptible to liquefaction depending on the groundwater level. The roof diaphragm spans in both directions exceed the ASCE 41-17 Tier 1 limit for unblocked wood structural panel diaphragms. A positive connection does not appear to be provided between the sloped truss blocking and masonry wall top plate (see Figure 3.132). Therefore, the load path is incomplete to transfer in-plane shear forces from the roof diaphragm to the masonry walls. A positive connection does not appear to be provided between the gable end wall sheathing and the masonry wall top plate (see Figure 3.133). Instead of the sheathing being edge nailed to the masonry wall top plate, drawings indicate edge nailing to the end truss bottom chord. However, no positive connection is indicated between the end truss bottom chord and masonry wall top plate. Therefore, the load path is incomplete to transfer in-plane shear forces from the roof diaphragm to the masonry walls. Out-of-plane bracing of the east and west gable end masonry walls is not adequate. Kicker braces are provided between the top of the masonry walls and roof diaphragm (see Figure 3.134). However, no positive connection is indicated between the blocking that the kicker brace frames into and the roof trusses. Therefore, the load path is incomplete to resist the vertical component of the kicker brace force associated with providing out-of-plane bracing for the gable end masonry walls. |

Table 3.14 Champion Hill Reservoir Control Building Evaluation Summary (cont.)

| Potential Deficiencies | Description |
|------------------------|--|
| Nonstructural | <ul style="list-style-type: none"> • Water system piping that penetrates through the control building walls may not have adequate flexibility to accommodate the potential differential movement between the control facility and the surrounding soil at the pipe penetration (see Figure 3.135). • Water system piping within the control building is not adequately seismically braced (see Figure 3.136). • Valves in line with the water system piping are not braced (see Figure 3.137). • The motor for the reservoir recirculation pump is not anchored at the base (see Figure 3.138) and the associated piping is not braced. • The pressure tank for the irrigation system appears to be missing an anchor at the base (see Figure 3.139). • Backup batteries in the battery cabinet (for operation of the seismic valves) are not adequately restrained (see Figure 3.140). • The horizontal arm of the SCADA antenna may not be adequately connected to the supporting pole to prevent the antenna from being misaligned or damaged after an earthquake (see Figure 3.141). • The ceiling framing of the chlorine room inside the control building does not appear to provide adequate connections to transfer seismic forces from the ceiling to the masonry walls below. Also, the wood ledger attachment to the masonry wall is not detailed to avoid cross-grain bending (see Figure 3.142). • The temporarily stored electrical cabinets are not anchored and may tip over during an earthquake and potentially damage valves or other components (see Figure 3.143). • The wood pole and anchorage of the pole-mounted transformer to the pole may not be adequately designed to resist the seismic forces generated by the transformer (see Figure 3.144). |



Figure 3.129 Champion Hill Reservoir



Figure 3.130 Champion Hill Reservoir Control Building




Figure 3.131 Reservoir Pipe Support Detail
(Source: Detail 10 on Sheet S5 of 2005 design drawings by Westech Engineering)




Figure 3.132 Inadequate Connection between Blocking and Masonry Wall Top Plate
(Source: Detail 6 on Sheet S13 of 2005 design drawings by Westech Engineering)




Figure 3.133 Inadequate Connection between Sheathing and Masonry Wall Top Plate
(Source: Detail 4 on Sheet S13 of 2005 design drawings by Westech Engineering)




Figure 3.134 Inadequate Connection between Blocking and Roof Truss
(Source: Detail 4 on Sheet S13 of 2005 design drawings by Westech Engineering)



Figure 3.135 Rigid Pipe Connection Through Wall



Figure 3.136 Unbraced Piping and Valves



Figure 3.137 Unbraced Seismic Valve



Figure 3.138 Unanchored Recirculation Pump Motor



Figure 3.139 Irrigation Pressure Tank Missing Anchor



Figure 3.140 Unrestrained Backup Batteries



Figure 3.141 SCADA Antenna





Figure 3.144 Pole-mounted Electrical Transformer

3.2.3 Eola #1B Reservoir

The Eola #1B Reservoir (see Figure 3.145) is a 0.86 million-gallon (MG) reservoir constructed in 1999, at a site west of 35th Avenue NW and north of Eola Drive NW. This reservoir is a circular-shaped reinforced concrete reservoir with an approximate diameter of 92 feet, and a maximum height of retained water of 17 feet. The west side of the reservoir is completely buried and the east side of the reservoir is partially exposed (with a maximum exposed height of approximately 3 feet). The Eola #1B Reservoir serves the City's W3 Level and is supplied by the Gibson Woods Pump Station.

Two, approximately 8-foot diameter, precast concrete valve vaults are located to the southeast of the reservoir. These vaults house piping and valves that support the operation of the reservoir. Note that SEFT did not have access to the interior of these valve vaults during our site visit.

Table 3.15 presents a summary of potential seismic structural and nonstructural deficiencies identified by this evaluation. Based on the potential deficiencies identified in Table 3.15, the Eola Reservoir #1 is not expected to achieve Immediate Occupancy structural performance or Operational nonstructural performance for a M9.0 CSZ earthquake.

Table 3.15 Eola #1B Reservoir Evaluation Summary

| Potential Deficiencies | Description |
|------------------------|--|
| Structural | <u>Reservoir</u> <ul style="list-style-type: none"> • Circumferential concrete cracking was observed near the roof to wall interface. The cracking was observed on the east side of the reservoir with a combined length of approximately one-eighth the circumference of the reservoir. • The column vertical reinforcing lap splice length is less than the ASCE 41-17 Tier 1 specified minimum length for Immediate Occupancy structural performance (i.e., 50 bar diameters). |
| | <u>Valve Vaults</u> <ul style="list-style-type: none"> • Concrete deterioration was observed near the top of South Valve Vault wall to lid interface (see Figure 3.146) that may impact the seismic performance of the valve vault. • Valve vaults are constructed from precast concrete components. The riser joints of stacked precast components may separate and shift due to seismic lateral earth pressures of the face of the valve vault. • Sand, silt, or groundwater may infiltrate and leak into the valve vaults at the precast concrete construction joints. |

Table 3.15 Eola #1B Reservoir Evaluation Summary (cont.)

| Potential Deficiencies | Description |
|------------------------|---|
| Nonstructural | <u>Reservoir</u> <ul style="list-style-type: none"> The vertical section of inlet pipe may not be adequately braced as the bracing detail relies on cantilever bending of a relatively small angle section (see Figure 3.147). |
| | <u>Valve Vaults</u> <ul style="list-style-type: none"> Per the 1999 design drawings, the piping and valves inside the valve vault may not be independently braced. |



Figure 3.145 Eola #1B Reservoir



Figure 3.146 Concrete Deterioration at Lid to Wall Connection of South Valve Vault




Figure 3.147 Reservoir Inlet Pipe Support Detail
(Source: Sheet 6 of 1999 design drawings by Multi/Tech Consultants)

3.2.4 Fairmount Reservoir and Control Building

The Fairmount Reservoir (see Figure 3.148), is a 10 MG reservoir constructed in 1936, at the Fairmount City Park near the intersection of Rural Avenue S and John Street S. This rectangular-shaped reinforced concrete reservoir is divided into two cells, each with a 5 MG capacity, and has approximate overall dimensions of 384 feet in the east-west direction by 192 feet in the north-south direction, and a maximum height of retained water of 21 feet. The reservoir is partially buried with approximately the top four feet exposed above grade. The Fairmount Reservoir serves the City's G0 Level and is hydraulically connected to both Franzen and Mountain View Reservoirs.

The Fairmount Reservoir Control Building/Pump Station (see Figure 3.149) is located on the south side of the reservoir and adjacent to the division between the two cells. The control building is a single-story above grade with a basement, constructed with reinforced concrete walls, and a reinforced concrete floor and roof. Two walls of the control building were constructed integrally with the Fairmount Reservoir. The building is square in plan, with approximate dimensions of 21 feet by 21 feet. During SEFT's site visit, the City noted that the pumps in this building are very rarely used.

In 2007, Black & Veatch conducted a condition assessment and seismic study of the Fairmount Reservoir and, in 2008, completed a follow-up structural evaluation of the roof. In 2018, Carollo Engineers conducted a seismic study of the Fairmount Reservoir and developed preliminary seismic retrofit concepts, and also developed repair concepts to address observed leaking of roof joints. SEFT reviewed the reports associated with these previous studies as part of our desktop evaluation of the Fairmount Reservoir. It should be noted that these previous studies were preliminary in nature and did not include consideration of the potential interaction between the reservoir and adjacent control building/pump station. The City plans to implement a future seismic retrofit of the Fairmount reservoir based on the recommendations of the 2018 Carollo seismic study.

Table 3.16 presents a summary of the seismic structural deficiencies for the Fairmount Reservoir that were identified in the 2018 reservoir seismic study conducted by Carollo Engineers and additional potential structural and nonstructural deficiencies identified by SEFT as part of this project. Note that based on our desktop evaluation and considering the M9.0 CSZ scenario earthquake seismic hazard parameter data provided by Shannon & Wilson as part of this project, SEFT concurs with the structural seismic deficiencies identified by Carollo.

Table 3.17 presents a summary of potential seismic structural and nonstructural deficiencies for the Fairmount Reservoir Control Building/Pump Station that were identified by this evaluation.

Based on the potential deficiencies identified in Table 3.16, the Fairmount Reservoir is not expected to achieve Immediate Occupancy structural performance or Operational nonstructural performance for a M9.0 CSZ earthquake. Based on the potential deficiencies identified in Table 3.17, the Fairmount Reservoir Control Building/Pump Station is not expected to achieve Immediate Occupancy structural performance or Operational nonstructural performance for a M9.0 CSZ earthquake. Similarly, based on the structural deficiencies identified, the Fairmount Reservoir Control Building/Pump Station is not currently expected to achieve Life Safety structural performance and represents a potential safety hazard to City staff and contractors.

Table 3.16 Fairmount Reservoir Evaluation Summary

| Potential Deficiencies | Description |
|--|--|
| Structural (based on 2018 seismic study by Carollo Engineers) | <ul style="list-style-type: none"> The perimeter walls and footings are overstressed due the tension loads imposed by the bending moment loads caused by hydrodynamic forces. There is no load path provided to transfer seismic forces from the reservoir roof to the walls. The roof expansion joints (see Figure 3.150) cannot transfer shear forces between adjacent roof panels. Additionally, there is not positive connections between the reservoir roof and walls (see Figure 3.151). This results in reservoir columns being overstressed. |
| Additional Structural (based on SEFT desktop assessment) | <ul style="list-style-type: none"> The 2018 Carollo study considered the BSE-1E seismic hazard level as defined by ASCE 41-13. Chapter 34 of the 2019 Oregon Structural Specialty Code (OSSC) indicates that the BSE-1E hazard level should not be taken as less than 75% of the BSE-1N seismic hazard level as defined by ASCE 41, much higher than what was considered in the 2018 Carollo study. Previous studies were preliminary in nature and did not include consideration of the potential interaction between the Fairmount Reservoir and adjacent Fairmount Reservoir Control Building/Pump Station. The column vertical reinforcing lap splice length is less than the ASCE 41-17 Tier 1 specified minimum length for Immediate Occupancy structural performance (i.e., 50 bar diameters). |
| Nonstructural | <ul style="list-style-type: none"> Per the original drawings, some piping and fittings within the reservoir may be cast-iron, which is a brittle material that may crack when subjected to earthquake shaking-induced forces and/or ground deformation. |

Table 3.17 Fairmount Reservoir Control Building Seismic Evaluation Summary

| Potential Deficiencies | Description |
|------------------------|--|
| Structural | <ul style="list-style-type: none"> • The northeast and northwest walls of the control building/pump station were constructed integrally with the reservoir (see Figure 3.152). Evaluation of the potential interaction between these two structures is beyond the scope of this preliminary ASCE 41 Tier 1 check-list based assessment, but should be considered as part of a future detailed seismic evaluation and retrofit design. • Several potential deficiencies are likely associated with detailing requirements for reinforcing steel [reinforcement ratio, maximum spacing limits, reinforcing around openings, reinforcing hooks at slab to wall connections (see Figure 3.153) and foundation dowels (see Figure 3.154)]. • At the operating floor level, large stair openings are located adjacent to three of the four shear walls, limiting the connection length to transfer seismic forces from the floor slab to the concrete walls. |
| Nonstructural | <ul style="list-style-type: none"> • Water system piping within the control building is not seismically braced (see Figure 3.155). • Valves and valve actuators in line with the water system piping are not braced (see Figure 3.156). • The vertical pump bells and valve operator riser shafts are not braced (see Figure 3.157). • Per the original drawings and site visit observations, piping and valves within the control building are cast-iron (see Figure 3.158), which is a brittle material that may crack when subjected to earthquake shaking-induced forces and/or ground deformation. • Significant corrosion-induced deterioration was observed for some piping, valves, and pipe connection bolts in the control building (see Figure 3.159). • Pumps do not appear to be anchored at the base (see Figure 3.160). • Vertical pump motors are not braced above the center of gravity of the motor (see Figure 3.160). • There does not appear to be adequate flexibility in the piping that is attached to the pumps to accommodate potential relative movement between the piping and the pump, and to prevent the piping from adding additional load to the pump anchorage. • The air vent vertical pipe adjacent to the east reservoir access stair does not appear to be braced (see Figure 3.161). |

Table 3.17 Fairmount Reservoir Control Building Evaluation Summary (cont.)

| Potential Deficiencies | Description |
|------------------------------|---|
| Nonstructural (cont.) | <ul style="list-style-type: none"> • Anchorage of electrical cabinets to the concrete slab was not visible from the outside of the cabinets and may not be adequate. Additionally, electrical cabinets do not appear to be anchored or braced to the wall near the top of the cabinets to prevent them from tipping over during an earthquake (see Figure 3.162) • Electrical conduits, hung from the roof, penetrating the wall and connected to the top of floor-mounted electrical cabinets, may not have adequate flexibility to account for differential movement between the floor, walls, and roof (see Figure 3.163). • The horizontal arm of the SCADA antenna may not be adequately connected to the supporting pole to prevent the antenna from being misaligned or damaged after an earthquake (see Figure 3.164). • The wood pole and anchorage of the pole-mounted transformer to the pole may not be adequately designed to resist the seismic forces generated by the transformer (see Figure 3.165). |



Figure 3.148 Fairmount Reservoir



Figure 3.149 Fairmount Reservoir Control Building



Figure 3.150 Fairmount Reservoir Roof Expansion Joints




Figure 3.151 Sliding Joint Between Wall and Roof
(Source: Section L-L on Sheet 8 of 1936 design drawings by Stevens & Koon)




Figure 3.152 Reservoir Adjacent to Control Building/Pump Station
(Source: Section H-H on Sheet 11 of 1936 design drawings by Stevens & Koon)




Figure 3.153 Inadequate Shear Wall to Diaphragm Connection
(Source: Section a-a on Sheet 16 of 1936 design drawings by Stevens & Koon)




Figure 3.154 Inadequate Shear Wall to Foundation Connection
(Source: Section J-J on Sheet 12 of 1936 design drawings by Stevens & Koon)



Figure 3.155 Unbraced Piping and Valves



Figure 3.156 Unbraced Valve



Figure 3.157 Unbraced Pump Bells and Valve Operator Riser Shafts



Figure 3.158 Cast Iron Valve



Figure 3.159 Corroded Bolts and Pipe



Figure 3.160 Unanchored Pump



Figure 3.161 Unbraced Vent Pipe



Figure 3.162 Electrical Cabinets with Unknown Anchorage Details



Figure 3.163 Conduits Connecting to Electrical Cabinets without Flexible Connections



Figure 3.164 SCADA Antenna



Figure 3.165 Pole-mounted Electrical Transformers

3.2.5 Grice Hill Reservoir and Control Building

The Grice Hill Reservoir (see Figure 3.166) is a 2.2 MG tank built in 2001 at the Grice Hill site off 27th Place NW. This reservoir is a strand-wound, circular, prestressed concrete reservoir with a nearly flat roof, an approximate diameter of 140 feet and a maximum height of retained water of 20 feet. The Grice Hill Reservoir serves the City's W2 Level and is supplied by the Mountain View Pump Station.

The Grice Hill Reservoir Control Building (see Figure 3.167) is located west of the reservoir. The control building is an above-grade, single-story structure, with reinforced masonry shear walls and a plywood sheathed wood truss roof. The building is rectangular in plan, with approximate dimensions of 45 feet in north-south direction by 37 feet in east-west direction. The building houses piping and valves (including seismic shutoff valves) that support the operation of the reservoir. The original design of the control building included a chlorination room and associated equipment, but the chlorination system is not currently used. Therefore, the chlorination system has not been included in the scope of this nonstructural assessment. The SCADA antenna at the Grice Hill Reservoir site is supported by a tall lattice tower (see Figure 3.168) and has not been included in the scope of the nonstructural assessment.

Table 3.18 and Table 3.19 present a summary of potential seismic structural and nonstructural deficiencies identified by this evaluation. Based on the potential deficiencies identified in Table 3.18, the Grice Hill Reservoir is not expected to achieve Immediate Occupancy structural performance or Operational nonstructural performance for a M9.0 CSZ earthquake. Based on the potential deficiencies identified in Table 3.19, the Grice Hill Reservoir Control Building is not expected to achieve Immediate Occupancy structural performance or Operational nonstructural performance for a M9.0 CSZ earthquake. Similarly, based on the structural deficiencies identified, the Grice Hill Reservoir Control Building is not currently expected to achieve Life Safety structural performance and represents a potential safety hazard to City staff and contractors.

Table 3.18 Grice Hill Reservoir Evaluation Summary

| Potential Deficiencies | Description |
|------------------------|---|
| Structural | <ul style="list-style-type: none"> The column vertical reinforcing lap splice length is less than the ASCE 41-17 Tier 1 specified minimum length for Immediate Occupancy structural performance (i.e., 50 bar diameters). |
| Nonstructural | <ul style="list-style-type: none"> The pipe support concrete pedestals within the reservoir do not appear to be positively connected to the reservoir floor. Original design drawings show that the vertical reinforcing at the corners of the pedestal terminates at the top of the reservoir floor (see Figure 3.169). |

Table 3.19 Grice Hill Reservoir Control Building Seismic Evaluation Summary

| Potential Deficiencies | Description |
|------------------------|---|
| Structural | <ul style="list-style-type: none"> • The roof diaphragm spans in both directions exceed the ASCE 41-17 Tier 1 limit for unblocked wood structural panel diaphragms. • The configuration of the toenail connection provided between the sloped truss blocking and masonry wall top plate (see Figure 3.170) may have resulted in splitting of the blocking, corner of the top plate, or both. Therefore, the load path may not be adequate to transfer in-plane shear forces from the roof diaphragm to the masonry walls. • Out-of-plane bracing of the north and south gable end masonry walls is not adequate. Kicker braces are provided between the top of the masonry walls and roof diaphragm (see Figure 3.171). However, no positive connection is indicated between the blocking that the kicker braces frames into and the roof trusses. Therefore, the load path is incomplete to resist the vertical component of the kicker brace force associated with providing out-of-plane bracing for the gable end masonry walls. |
| Nonstructural | <ul style="list-style-type: none"> • Water system piping within the control building is not adequately seismically braced (see Figure 3.172). • Valves in line with the water system piping are not braced (see Figure 3.173). • One of the seismic valves has a note attached indicating that the valve is out of service (see Figure 3.174). • The pressure tank for the irrigation system is not anchored at the base (see Figure 3.175). • Backup batteries in the battery cabinet (for operation of the seismic valves) are not adequately restrained (see Figure 3.176). • The ceiling framing of the chlorine room inside the control building does not appear to provide adequate connections to transfer seismic forces from the ceiling to the masonry walls below (see Figure 3.177). • The temporarily stored electrical cabinet (see Figure 3.178), emergency generator, etc. may tip over or slide during an earthquake and potentially damage valves or other components. • A ladder is unrestrained (see Figure 3.179) and may topple into and potentially damage valves or other components during an earthquake. • No anchorage was observed between the electrical transformer and concrete support pad (see Figure 3.180). |



Figure 3.166 Grice Hill Reservoir



Figure 3.167 Grice Hill Reservoir Control Building



Figure 3.168 SCADA Antenna Supported by Lattice Tower




Figure 3.169 Reservoir Pipe Support Detail
(Source: Detail 10 on Sheet S6 of 2001 design drawings by Westech Engineering)




Figure 3.170 Inadequate Connection between Blocking and Masonry Wall Top Plate
(Source: Detail 6 on Sheet B-5 of 2001 design drawings by Westech Engineering)




Figure 3.171 Inadequate Connection between Blocking and Roof Truss
(Source: Detail 4 on Sheet B-5 of 2001 design drawings by Westech Engineering)



Figure 3.172 Unbraced Piping and Valves



Figure 3.173 Unbraced Seismic Valve




Figure 3.174 Note about Inoperable Seismic Valve



Figure 3.175 Unanchored Irrigation Pressure Tank



Figure 3.176 Backup Batteries without Adequate Restraint




Figure 3.177 Chlorine Room Ceiling Framing
(Source: Detail 1 on Sheet B-5 of 2001 design drawings by Westech Engineering)



Figure 3.178 Temporarily Stored Electrical Cabinet



Figure 3.179 Unrestrained Ladder



Figure 3.180 Unanchored Electrical Transformer

3.2.6 Lone Oak Reservoir and Control Building

The Lone Oak Reservoir (see Figure 3.181) is a 5.6 MG tank built in 2003 near the intersection of Lone Oak Road SE and Midred Lane SE. This reservoir is a strand-wound, circular, prestressed concrete reservoir with a nearly flat roof with an approximate diameter of 196 feet and a maximum height of retained water of 26 feet. The Lone Oak Reservoir serves the City's S2 Level.

The Lone Oak Reservoir Control Building (see Figure 3.182) is located west of the reservoir. The control building is a single-story building with reinforced concrete walls below grade, reinforced masonry walls above grade, and a plywood sheathed wood truss roof. The building is rectangular in plan, with approximate dimensions of 39 feet in north-south direction by 29 feet in east-west direction. The building houses piping and valves (including a seismic shutoff valve) that support the operation of the reservoir. The original design of the control building included a chlorination room and associated equipment, but the chlorination system is not currently used. Therefore, the chlorination system has not been included in the scope of the nonstructural assessment (with the exception of the large hot water heater).

Table 3.20 and Table 3.21 present a summary of potential seismic structural and nonstructural deficiencies identified by this evaluation. Based on the potential deficiencies identified in Table 3.20, the Lone Oak Reservoir is expected to achieve Immediate Occupancy structural performance and Operational nonstructural performance for a M9.0 CSZ earthquake. Based on the potential deficiencies identified in Table 3.21, the Lone Oak Reservoir Control Building may not achieve Immediate Occupancy structural performance and is not expected to achieve Operational nonstructural performance for a M9.0 CSZ earthquake. Similarly, based on the structural deficiencies identified, the Lone Oak Reservoir Control Building may not achieve Life Safety structural performance and may represent a potential safety hazard to City staff and contractors.

Table 3.20 Lone Oak Reservoir Evaluation Summary

| Potential Deficiencies | Description |
|------------------------|--------------------|
| Structural | • None identified. |
| Nonstructural | • None identified. |

Table 3.21 Lone Oak Reservoir Control Building Evaluation Summary

| Potential Deficiencies | Description |
|------------------------|--|
| Structural | <ul style="list-style-type: none"> • The original design drawings indicate that the design of the Lone Oak Reservoir Control Building masonry walls and roof structure was a deferred submittal item (see Figure 3.183). The deferred submittal drawings/calculations were not available for review as part of this project and the roof framing was not visible during SEFT's site visit. Based on the limited information available, the expected structural performance of the Lone Oak Reservoir Control Building could not be quantified. |
| Nonstructural | <ul style="list-style-type: none"> • Water system piping within the control building is not seismically braced (see Figure 3.184). • Valves in line with the water system piping are not braced (see Figure 3.185). • The pressure tank for the irrigation system is not anchored at the base (see Figure 3.186). • Anchorage of the control cabinet to the housekeeping pads was not visible from the outside of the cabinets and may not be adequate. Additionally, the control cabinet does not appear to be anchored or braced to the wall near the top of the cabinet to prevent it from tipping over during an earthquake (see Figure 3.187). • Anchorage of the battery cabinet to the top of the control cabinet (see Figure 3.187) was not visible from the outside of the cabinet and may not be adequate. Also, backup batteries in the battery cabinet may not be adequately restrained. • The horizontal arm of the SCADA antenna may not be adequately connected to the supporting pole to prevent the antenna from being misaligned or damaged after an earthquake (see Figure 3.188). • The suspended HVAC unit may not be adequately braced (see Figure 3.189). Potential bracing deficiencies include the bracing angle for one pair of cable braces is near vertical (resulting in a significant decrease in the capacity of the braces to resist horizontal seismic forces), some braces appear to load the bottom chord of the roof truss in the out-of-plane direction (blocking or other detailing to deliver these seismic forces to the roof diaphragm are unknown) and only a single cable clamp is used for the braces (no redundancy if the single clamp were to loosen) • The base skid for the large water heater and safety shower in the chlorine room does not appear to be adequately anchored (see Figure 3.190). |

Table 3.21 Lone Oak Reservoir Control Building Evaluation Summary (cont.)

| Potential Deficiencies | Description |
|------------------------------|---|
| Nonstructural (cont.) | <ul style="list-style-type: none"> The original design drawings indicate that the design of the chlorine room masonry walls and top of wall bracing was a deferred submittal item (see Figure 3.191). The deferred submittal drawings/calculations were not available for review as part of this project and the bracing at the top of these masonry walls was not visible during SEFT's site visit. Therefore, the adequacy of the masonry wall bracing is unknown. A ladder is unrestrained (see Figure 3.192) and may topple into and potentially damage valves or other components during an earthquake. No anchorage was observed between the electrical transformer and concrete support pad (see Figure 3.193). |



Figure 3.181 Lone Oak Reservoir



Figure 3.182 Lone Oak Reservoir Control Building




Figure 3.183 Design of Lone Oak Reservoir Control Building was a Deferred Submittal
(Source: Section B on Sheet B-15 of 2003 design drawings by CH2M Hill)



Figure 3.184 Unbraced Piping and Valves



Figure 3.185 Unbraced Seismic Valve



Figure 3.186 Unanchored Pressure Tank



Figure 3.187 Control Cabinet with Unknown Anchorage Details



Figure 3.188 SCADA Antenna



Figure 3.189 Suspended HVAC Unit



Figure 3.190 Inadequate Overturning Anchorage of Water Heater




Figure 3.191 Chlorine Room Ceiling Framing
(Source: Section C on Sheet B-15 of 2003 design drawings by CH2M Hill)



Figure 3.192 Unrestrained Step Ladder



Figure 3.193 Unanchored Electrical Transformer

3.2.7 Mill Creek #1 Reservoir and Control Building

The Mill Creek #1 Reservoir (see Figure 3.194) is a 2.2 MG tank built in 2013 at the Mill Creek #1 site off Deer Park Drive SE. This reservoir is a strand-wound, circular, prestressed concrete reservoir with a nearly flat roof, an approximate diameter of 140 feet and a maximum height of retained water of 20 feet. The Mill Creek #1 Reservoir serves the City's S1 Level and is supplied by the Deer Park Pump Station.

The Mill Creek #1 Reservoir Control Building (see Figure 3.195) is located southwest of the reservoir. The control building is a single-story building with reinforced concrete walls below grade, reinforced masonry walls above grade, and a plywood sheathed wood truss roof. The building is rectangular in plan, with approximate dimensions of 46 feet in north-south direction by 42 feet in east-west direction. The building houses piping and valves (including seismic shutoff valves) that support the operation of the reservoir and a small pump station that supports the City's College Reservoir (steel tank). The original design of the control building included a chlorination room and associated equipment, but the chlorination system is not currently used. Therefore, the chlorination system has not been included in the scope of the nonstructural assessment.

Table 3.22 and Table 3.23 present a summary of potential seismic structural and nonstructural deficiencies identified by this evaluation. Based on the potential deficiencies identified in Table 3.22, the Mill Creek #1 Reservoir is not expected to achieve Immediate Occupancy structural performance or Operational nonstructural performance for a M9.0 CSZ earthquake. Based on the potential deficiencies identified in Table 3.23, the Mill Creek #1 Reservoir Control Building is not expected to achieve Immediate Occupancy structural performance or Operational nonstructural performance for a M9.0 CSZ earthquake. Similarly, based on the structural deficiencies identified, the Mill Creek #1 Reservoir Control Building is not currently expected to achieve Life Safety structural performance and represents a potential safety hazard to City staff and contractors.

Table 3.22 Mill Creek #1 Reservoir Evaluation Summary

| Potential Deficiencies | Description |
|------------------------|--|
| Structural | <ul style="list-style-type: none"> The column vertical reinforcing lap splice length is less than the ASCE 41-17 Tier 1 specified minimum length for Immediate Occupancy structural performance (i.e., 50 bar diameters). |

Table 3.22 Mill Creek #1 Reservoir Evaluation Summary (cont.)

| Potential Deficiencies | Description |
|------------------------|--|
| Nonstructural | <ul style="list-style-type: none"> The pipe support concrete pedestals within the reservoir do not appear to be positively connected to the reservoir floor. Original design drawings show that the vertical reinforcing at the corners of the pedestal terminates at the top of the reservoir floor (see Figure 3.196). The steel framed roof access stair located on the southeast side of the reservoir is relatively flexible (see Figure 3.197). During an earthquake, the stair will likely pound against the reservoir and may damage the stair or locally damage the concrete reservoir. |

Table 3.23 Mill Creek #1 Reservoir Control Building Evaluation Summary

| Potential Deficiencies | Description |
|------------------------|---|
| Structural | <ul style="list-style-type: none"> The roof diaphragm spans in both directions exceed the ASCE 41-17 Tier 1 limit for unblocked wood structural panel diaphragms. The original design drawings indicate that the truss manufacturer was to provide truss blocking capable of transferring shear loads from the roof diaphragm to the masonry wall top plate (see Figure 3.198). The deferred submittal drawings/calculations were not available for review as part of this project and this area was not visible during SEFT's site visit. Therefore, the adequacy of the truss blocking is unknown. Out-of-plane bracing of the north and south gable end masonry walls is not adequate. Three bays of blocking are provided to transfer out-of-plane wall bracing forces to the ceiling level plywood sheathed diaphragm (see Figure 3.199). This blocking does not engage an adequate depth of the ceiling level diaphragm. |

Table 3.23 Mill Creek #1 Reservoir Control Building Evaluation Summary (cont.)

| Potential Deficiencies | Description |
|------------------------|---|
| Nonstructural | <ul style="list-style-type: none"> • Water system piping within the control building is not adequately seismically braced (see Figure 3.200). • Valves in line with the water system piping are not braced (see Figure 3.201). • The pressure tank for the irrigation system is not anchored at the base (see Figure 3.202). • Vertical pump motors are not braced above the center of gravity of the motors (see Figure 3.203). • There does not appear to be adequate flexibility in the piping that is attached to the pumps to accommodate potential relative movement between the piping and the pump, and to prevent the piping from adding additional load to the pump anchorage. • Backup batteries in the battery cabinet (for operation of the seismic valves) may not be adequately restrained. • The horizontal arm of the SCADA antenna may not be adequately connected to the supporting pole to prevent the antenna from being misaligned or damaged after an earthquake (see Figure 3.204). • The ceiling framing of the chlorine room inside the control building does not appear to provide adequate connections to transfer seismic forces from the ceiling to the masonry walls below. Also, the wood ledger attachment to the masonry wall is not detailed to avoid cross-grain bending (see Figure 3.205). • The electrical “room” partial height masonry walls are not laterally braced (see Figure 3.206). • Two ladders are unrestrained (see Figure 3.207) and may topple into and potentially damage valves or other components during an earthquake. • No anchorage was observed between the electrical transformer and concrete support pad (see Figure 3.208). |



Figure 3.194 Mill Creek #1 Reservoir



Figure 3.195 Mill Creek #1 Reservoir Control Building




Figure 3.196 Reservoir Pipe Support Detail
(Source: Detail 9 on Sheet S4 of 2014 design drawings by Westech Engineering)



Figure 3.197 Mill Creek #1 Reservoir Roof Access Stair




Figure 3.198 Inadequate Connection between Blocking and Masonry Wall Top Plate
(Source: Detail 5 on Sheet S-20 of 2014 design drawings by Westech Engineering)




Figure 3.199 Inadequate Transfer Length between Blocking and Ceiling Diaphragm
(Source: Detail 1 on Sheet S-20 of 2014 design drawings by Westech Engineering)



Figure 3.200 Unbraced Piping and Valves



Figure 3.201 Unbraced Seismic Valves



Figure 3.202 Unanchored Pressure Tank



Figure 3.203 Unanchored Pump Motor



Figure 3.204 SCADA Antenna




Figure 3.205 Chlorine Room Ceiling Framing
(Source: Section C on Sheet S-17 of 2014 design drawings by Westech Engineering)




Figure 3.206 Unbraced Partial Height CMU Walls in Electrical Room



Figure 3.207 Unrestrained Ladders



Figure 3.208 Unanchored Electrical Transformer

3.2.8 Mountain View Reservoir

The Mountain View Reservoir (see Figure 3.209) is a 10 MG tank built in 1971 near the intersection of Wallowa Avenue NW and Orchard Heights Road NW. This reservoir is a completely buried strand-wound, circular, prestressed concrete reservoir with a nearly flat roof, an approximate diameter of 292 feet and a maximum height of retained water of 20 feet. The Mountain View Reservoir serves the City's G0 Level and is hydraulically connected to both Franzen and Fairmount Reservoirs.

In 2008, Black & Veatch conducted a condition assessment and seismic evaluation of Mountain View Reservoir. SEFT reviewed the report associated with the 2008 condition assessment and seismic evaluation to help inform our seismic assessment.

Table 3.24 presents a summary of potential seismic structural and nonstructural deficiencies identified by this evaluation. Based on the potential deficiencies identified in Table 3.24, the Mountain View Reservoir is not expected to achieve Immediate Occupancy structural performance or Operational nonstructural performance for a M9.0 CSZ earthquake.

Table 3.24 Mountain View Reservoir Evaluation Summary

| Potential Deficiencies | Description |
|------------------------|--|
| Structural | <ul style="list-style-type: none"> No seismic cables or dowels were used to connect the base of the wall to the foundation (see Figure 3.210). Shear forces are only transferred from the wall to foundation by friction, which is likely inadequate to resist the earthquake-induced lateral force. The existing capacity of the horizontal prestressing strands on the wall of the reservoir is inadequate to resist the combination of hydrostatic and expected hydrodynamic hoop forces during an earthquake. The column vertical reinforcing lap splice length and tie spacing is less than the ASCE 41-17 Tier 1 specified values for Immediate Occupancy structural performance (i.e., minimum lap splice length of 50 bar diameters and minimum tie spacing of 8 bar diameters) |
| Nonstructural | <ul style="list-style-type: none"> Per the original drawings, some piping and fittings within the Reservoir may be cast-iron, which is a brittle material that may crack when subjected to earthquake shaking-induced forces and/or ground deformation. |



Figure 3.209 Mountain View Reservoir




Figure 3.210 Base of Wall to Foundation Connection without Dowels or Seismic Cables
(Source: Section C on Sheet 6 of 1971 design drawings by Stevens, Thomsen & Runyan)

4.0 Preliminary Seismic Structural and Nonstructural Mitigation Concepts

4.1 Pump Stations and Control Facilities

This section provides summary tables that describe preliminary seismic retrofit concepts to mitigate the potential structural and nonstructural seismic deficiencies identified for selected City pump stations and control facilities, described in Section 3.1. Where appropriate, these tables also provide recommendations for further investigation and/or analysis to potentially mitigate deficiencies through more detailed structural calculations or to infill gaps in the data that was available for this study.

4.1.1 ASR #1 and #2 Pump Station

Table 4.1 summarizes preliminary seismic retrofit concepts to mitigate the potential structural and nonstructural deficiencies described in Section 3.1.1 for the ASR #1 and #2 Pump Station.

Table 4.1 ASR #1 and #2 Pump Station Preliminary Mitigation Concepts

| Potential Deficiencies | Description |
|------------------------|--|
| Structural | <ul style="list-style-type: none"> • Install vertical steel angles where the east-west oriented CMU walls of the ASR #2 addition interface with the west wall of the original ASR #1 structure. • Remove existing gypsum board interior finish to investigate the load path to transfer seismic roof diaphragm forces at the roof step between the ASR #1 and ASR #2 portions of the structure to the masonry wall below. Likely add a combination of plywood sheathing, blocking, and metal connector hardware to provide an adequate load path. • Remove a small section of existing roofing to verify the adequacy of the existing roof sheathing to truss nailing. • Install new shaped blocking between the roof sheathing and masonry wall top plate. Provided boundary nailing between the roof sheathing and blocking, and Simpson A35 clip angles between the blocking and top plate and blocking and trusses. • Install Simpson A35 clips between truss bottom chord and masonry wall top plate in conjunction with cross tie retrofit described in next bullet item. |

Table 4.1 ASR #1 and #2 Pump Station Preliminary Mitigation Concepts (cont.)

| Potential Deficiencies | Description |
|---------------------------|---|
| Structural (cont.) | <ul style="list-style-type: none"> • Install a combination of plywood sheathing, blocking, steel straps, and metal connector hardware to provide adequate out-of-plane support for CMU walls (see Figure 4.1). • Conduct nondestructive scanning to verify the size and location of masonry wall vertical reinforcing. If vertical trim reinforcing is not provided adjacent to door openings, install face mounted steel plates through-bolted to masonry wall and anchored to foundation |
| Nonstructural | <ul style="list-style-type: none"> • Provide bracing for the piping. • Provide independent bracing for the valves. • Provide independent support and bracing for the air relief valve. • Perform additional analysis to evaluate the adequacy of the existing connection of the motor to the top of the steel motor support, the motor support, and the connection of the motor support to the steel well casing. • Add flexible couplings between the pumps and the connected piping. • Provide anchorage/bracing between the top of the electrical cabinets and wall. • Provide lens covers for light fixtures with safety devices that prevent the lens cover and light bulbs from falling. • Provide flexible couplings where conduits connect to the top of wall-mounted electrical panels and cabinets. • Verify the adequacy of the connection between the horizontal antenna and the supporting pole. • Add helical wall ties between the masonry veneer and the ASR #1 masonry walls. • Conduct nondestructive scanning to verify the size and spacing of reinforcing in the architectural concrete pillars and perform calculations to verify the adequacy of the existing reinforcing. If reinforcing is found to be inadequate, remove existing architectural concrete pillars. • Coordinate with electrical utility to anchor the utility owned electrical transformer to the concrete pad, as required. |




Figure 4.1 Sub-diaphragm Retrofit Concept
(Adapted From: Roof Plan on Sheet A1 of 1997 design drawings by Stettler Company)

4.1.2 ASR #4 Pump Station

Table 4.2 summarizes preliminary seismic retrofit concepts to mitigate the potential structural and nonstructural deficiencies described in Section 3.1.2 for the ASR #4 Pump Station.

Table 4.2 ASR #4 Pump Station Preliminary Mitigation Concepts

| Potential Deficiencies | Description |
|------------------------|---|
| Structural | <ul style="list-style-type: none"> • Remove a small section of existing roofing to verify the adequacy of the existing roof sheathing to truss nailing. • Install new shaped blocking between the roof sheathing and masonry wall top plate. Provided boundary nailing between the roof sheathing and blocking, and Simpson A35 clip angles between the blocking and top plate and blocking and trusses. • Perform additional analysis to investigate if the diaphragm has adequate capacity to transfer seismic forces from the roof diaphragm to the east masonry shear wall, considering the impact of the hatch opening adjacent to the wall. Note that this analysis will require information about the existing roof sheathing to truss nailing (i.e., size, and spacing). • Install Simpson A35 clips between truss bottom chord and masonry wall top plate in conjunction with cross tie retrofit described in next bullet item. • Install a combination of plywood sheathing, blocking, steel straps, and metal connector hardware to provide adequate out-of-plane support for CMU walls (see Figure 4.2). • Conduct nondestructive scanning to verify the size and location of masonry wall vertical reinforcing. If vertical trim reinforcing is not provided adjacent to door openings, install face mounted steel plates through-bolted to masonry wall and anchored to foundation. |
| Nonstructural | <ul style="list-style-type: none"> • Provide bracing for the piping. • Provide independent bracing for the valves. • Provide independent support and bracing for the air relief valve. • Perform additional analysis to evaluate the adequacy of the existing connection of the motor to the top of the steel motor support, the motor support, and the connection of the motor support to the steel well casing. • Add flexible couplings between the pump and the connected piping. |

Table 4.2 ASR #4 Pump Station Preliminary Mitigation Concepts (cont.)

| Potential Deficiencies | Description |
|------------------------------|---|
| Nonstructural (cont.) | <ul style="list-style-type: none"> • Provide anchorage/bracing of pump station control cabinet to floor and wall. • Provide lens covers for light fixtures with safety devices that prevent the lens cover and light bulbs from falling. • Coordinate with electrical utility to anchor the utility owned electrical transformer to the concrete pad, as required. |




Figure 4.2 Sub-diaphragm Retrofit Concept
(Adapted From: Roof Plan on Sheet A2 of 1998 design drawings by Stettler Company)

4.1.3 ASR #5 Pump Station

Table 4.3 summarizes preliminary seismic retrofit concepts to mitigate the potential structural and nonstructural deficiencies described in Section 3.1.3 for the ASR #5 Pump Station.

Table 4.3 ASR #5 Pump Station Preliminary Mitigation Concepts

| Potential Deficiencies | Description |
|------------------------|---|
| Structural | <ul style="list-style-type: none"> • Add shaped blocking or framing/sheathing with metal connector hardware to provide a load path between the roof of the steel framed pavilion and masonry shear walls of the pump station structure. • Perform an investigation to determine if the ceiling diaphragm is adequately connected to the interior masonry walls to engage the walls as part of the seismic force resisting system. If not, add blocking/framing to provide a load path between the ceiling diaphragm and interior masonry shear walls. • Perform an investigation of the existing ceiling nail size and spacing to verify the adequacy of the existing ceiling sheathing to joist nailing. • Perform an investigation to determine if adequate blocking and connections are provided between the ceiling sheathing and masonry wall top plate. Install new blocking with boundary nailing between the ceiling sheathing and blocking, and Simpson A35 clip angles between the blocking and top plate and blocking and ceiling joists, as appropriate. • Install Simpson A35 clips between ceiling joists and masonry wall top plate in conjunction with cross tie retrofit described in next bullet item. • Install a combination of blocking, steel straps, and metal connector hardware to provide adequate out-of-plane support for CMU walls (see Figure 4.3). • Conduct nondestructive scanning to verify the size and location of masonry wall vertical reinforcing. If vertical trim reinforcing is not provided adjacent to door openings, install face mounted steel plates through-bolted to masonry wall and anchored to foundation. • Perform additional analysis to investigate the adequacy of the free-standing masonry wall to resist seismic forces without additional bracing. |

Table 4.3 ASR #5 Pump Station Preliminary Mitigation Concepts (cont.)

| Potential Deficiencies | Description |
|---------------------------|---|
| Structural (cont.) | <ul style="list-style-type: none"> • Investigate extent and severity of the corrosion damage to the steel column, repair damage (as appropriate), and mitigate cause of moisture to prevent similar future damage. |
| Nonstructural | <ul style="list-style-type: none"> • Provide bracing for the piping. • Provide independent bracing for the valves. • Provide independent support and bracing for the air relief valve. • Perform additional analysis to evaluate the adequacy of the existing connection of the motor to the top of the steel motor support, the motor support, and the connection of the motor support to the steel well casing. • Add flexible couplings between the pumps and the connected piping. • Provide flexible couplings where conduits connect to the top of floor- and wall-mounted electrical panels and cabinets. • Provide anchorage/bracing of pump station control cabinet to floor and wall. • Provide lens covers for light fixtures with safety devices that prevent the lens cover and light bulbs from falling. • Coordinate with electrical utility to anchor the utility owned electrical transformer to the concrete pad, as required. |




Figure 4.3 Sub-diaphragm Retrofit Concept
(Adapted From: Detail 6 on Sheet A3 of 1997 design drawings by Stettler Company)

4.1.4 Boone Road Pump Station

Table 4.4 summarizes preliminary seismic retrofit concepts to mitigate the potential structural and nonstructural deficiencies described in Section 3.1.4 for the Boone Road Pump Station.

Table 4.4 Boone Road Pump Station Preliminary Mitigation Concepts

| Potential Deficiencies | Description |
|------------------------|--|
| Structural | <ul style="list-style-type: none"> • Perform an investigation to determine if the gable end framing, sheathing nailing, and connection details are adequate to deliver seismic forces from the upper roof to the lower roof. If not, add supplemental nailing, framing, blocking, and/or metal connector hardware, as appropriate. • Install a wood structural panel overlay on top of the existing straight sheathing. The joints of the wood structural panels should be placed so that they are near the center of the existing sheathing boards or at a 45-degree angle to the joints between existing sheathing boards. • Install a combination of sub-diaphragm framing and connection hardware at the roof level to provide adequate out-of-plane support for CMU walls (see Figure 4.4). |
| Nonstructural | <ul style="list-style-type: none"> • Provide bracing for the piping. • Provide independent bracing for the valves. • Perform additional analysis to evaluate the adequacy of the existing connection of the motor to the top of the steel motor support, the motor support, the connection of the motor support to the concrete pedestal, and the concrete pedestal. • Add flexible couplings between the pumps and the connected piping. • Provide longitudinal bracing for the cable tray. Reconfigure the anchorage of the transverse bracing strut to avoid anchorage into the masonry head joints. • Provide lens covers for light fixtures with safety devices that prevent the lens cover and light bulbs from falling. • Provide grating clip connections between the grating and steel support framing. • Verify the adequacy of the antenna connection to the supporting pole. |




Figure 4.4 Sub-diaphragm Retrofit Concept
(Adapted From: Detail 1 on Sheet S-8 of 2018 design drawings by Murraysmith)

4.1.5 Creekside Pump Station


Table 4.5 summarizes preliminary seismic retrofit concepts to mitigate the potential structural and nonstructural deficiencies described in Section 3.1.5 for the Creekside Pump Station.

Table 4.5 Creekside Pump Station Preliminary Mitigation Concepts

| Potential Deficiencies | Description |
|------------------------|--|
| Structural | <ul style="list-style-type: none"> • Remove a small section of existing roofing to verify the adequacy of the existing roof sheathing to truss nailing. • Add blocking to support the edges of the roof sheathing panels and provided boundary nailing between the roof sheathing and blocking. • Perform an investigation to determine if adequate blocking and connections are provided between the roof sheathing and masonry wall top plate. Install new shaped blocking between the roof sheathing and masonry wall top plate. Provided boundary nailing between the roof sheathing and blocking, and Simpson A35 clip angles between the blocking and top plate and blocking and trusses, as appropriate. Also, suggest engaging the shear resistance of the interior masonry wall by adding a combination of plywood sheathing, framing/blocking, and metal connector hardware to provide a load path between the roof diaphragm and the interior masonry wall. • Perform an investigation to verify the adequacy of the connection between the roof sheathing and gable end masonry wall top plate. • Install Simpson A35 clips between trusses and masonry wall top plate in conjunction with cross tie retrofit described in next bullet item. • Install a combination of plywood, blocking, steel straps, and metal connector hardware to provide adequate out-of-plane support for CMU walls (see Figure 4.5). |
| Nonstructural | <ul style="list-style-type: none"> • Provide bracing for the piping. • Provide independent bracing for the valves. • Provide independent support and bracing for the air relief valves. • Perform additional analysis to evaluate the adequacy of the existing connection of the motor to the top of the steel motor support, the motor support, the connection of the motor support to the concrete pedestal, and the concrete pedestal. • Add flexible couplings between the pumps and the connected piping. |

Table 4.5 Creekside Pump Station Preliminary Mitigation Concepts (cont.)

| Potential Deficiencies | Description |
|------------------------------|--|
| Nonstructural (cont.) | <ul style="list-style-type: none"> • Perform an investigation to evaluate the adequacy of the anchorage of electrical cabinets to housekeeping pads and housekeeping pads to slab on grade, and supplement anchorage (as required). Also, provide anchorage/bracing between the top of the electrical cabinets and masonry wall. • Provide anchorage/bracing for emergency generator air intake support frame, muffler, and exhaust pipe. • Coordinate with electrical utility to anchor the utility owned electrical transformer to the concrete pad, as required. |



NOTES:

- 1) PROVIDE BOUNDARY NAILING BETWEEN PLYWOOD SHEATHING & BLOCKING/FRAMING.
- 2) PROVIDE ADDITIONAL ANCHORS BETWEEN TOP PLATE & CMU WALL (AS REQUIRED).

Figure 4.5 Sub-diaphragm Retrofit Concept
(Adapted From: Roof Plan on Sheet A1.3 of 1997 design drawings by Multi/Tech Consultants)

4.1.6 Deer Park Pump Station

Table 4.6 summarizes preliminary seismic retrofit concepts to mitigate the potential structural and nonstructural deficiencies described in Section 3.1.6 for the Deer Park Pump Station.

Table 4.6 Deer Park Pump Station Preliminary Mitigation Concepts

| Potential Deficiencies | Description |
|------------------------|--|
| Structural | <ul style="list-style-type: none"> • Conduct nondestructive scanning to verify the size and location of masonry wall reinforcing and evaluate the adequacy of the masonry walls. • Based on the number of potential deficiencies identified that are associated with the wood framed roof, suggest removing existing roof and replacing with new plywood sheathed wood truss roof with appropriate seismic detailing (including consideration of cross ties between diaphragm chords and out of plane bracing for perimeter and interior masonry walls). |
| Nonstructural | <ul style="list-style-type: none"> • Provide bracing for the piping. • Provide independent bracing for the valves. • Install angles all around the perimeter of the pump support concrete pedestal with anchors into the floor slab. On two opposing sides, add a pair of steel straps that are welded to the angle and anchored up the face of the pedestal. • Add flexible couplings between the pumps and the connected piping. • Add anchors through the pipe support stanchion base plates into the slab-on-grade at locations with missing anchors. • Perform an investigation to evaluate the adequacy of the anchorage of electrical cabinets to housekeeping pads and housekeeping pads to slab on grade, and supplement anchorage (as required). Also, provide anchorage/bracing between the top of the electrical cabinets and masonry wall. • Re-install the restrainer bracket for the emergency generator starter batteries, as appropriate. • Verify the adequacy of the antenna connection to the supporting pole. • Coordinate with electrical utility to conduct further evaluation to validate the seismic performance of pole-mounted transformer and utility pole. |

4.1.7 Edwards Pump Station

Table 4.7 summarizes preliminary seismic retrofit concepts to mitigate the potential structural and nonstructural deficiencies described in Section 3.1.7 for the Edwards Pump Station.

Table 4.7 Edwards Pump Station Preliminary Mitigation Concepts

| Potential Deficiencies | Description |
|------------------------|--|
| Structural | <ul style="list-style-type: none"> • Perform a site-specific geotechnical study to further evaluate the potential earthquake-induced liquefaction and lateral spreading hazard at the site. If required, mitigate the potential permanent ground deformation hazard at the site with geotechnical improvement, or other appropriate techniques. • Based on the age of the structure and the number of potential deficiencies identified, it is recommended that the City consider replacing the Edwards Pump Station structure. |
| Nonstructural | <ul style="list-style-type: none"> • Mitigation of potential nonstructural deficiencies is dependent on the selected approach to mitigate structural deficiencies. If the pump stations is replaced, it is anticipated that new components would be installed satisfying current seismic design and detailing requirements. • Provide appropriate flexible joints where water system piping penetrates through the pump station floor to accommodate potential differential movement between the structure and the surrounding soil at or near the pipe penetration. • Provide bracing for the piping. • Provide independent bracing for the valves. • Perform additional analysis to evaluate the adequacy of the existing connection of the motor to the top of the steel motor support, the motor support, the connection of the motor support to the concrete pedestal, and the concrete pedestal. • Install Z-shaped brackets (fabricated from welded channel sections) anchored to the concrete slab on grade and bearing against top surface of the pump support steel base plate. Provide two brackets on each side of the concrete pedestal near the existing steel base plate anchors. • Add flexible couplings between the pumps and the connected piping. |

Table 4.7 Edwards Pump Station Preliminary Mitigation Concepts (cont.)

| Potential Deficiencies | Description |
|------------------------------|---|
| Nonstructural (cont.) | <ul style="list-style-type: none"> • Perform an investigation to evaluate the adequacy of the anchorage of electrical cabinets to housekeeping pads and housekeeping pads to slab on grade, and supplement anchorage (as required). Also, provide anchorage/bracing between the top of the electrical cabinets and masonry wall. • Provide flexible couplings where conduits connect to the top of floor- and wall-mounted electrical panels and cabinets. • Provide restraint for the emergency generator starter batteries. • Provide lens covers for light fixtures with safety devices that prevent the lens cover and light bulbs from falling. • Verify the adequacy of the antenna connection to the supporting pole. • Provide anchorage of the HVAC unit to the concrete pad. • Provide grating clip connections between the grating and steel support framing. • Provide restraint for the overhead bridge crane, when not in use. • Provide restraint for rolling lifts, when not in use. • Provide restraint for ladders (using straps to the wall, etc.), when not in use. • Coordinate with electrical utility to conduct further evaluation to validate the seismic performance of pole-mounted transformer and utility pole. |

4.1.8 Limelight Pump Station

Table 4.8 summarizes preliminary seismic retrofit concepts to mitigate the potential structural and nonstructural deficiencies described in Section 3.1.8 for the Limelight Pump Station.

Table 4.8 Limelight Pump Station Preliminary Mitigation Concepts

| Potential Deficiencies | Description |
|------------------------|--|
| Structural | <ul style="list-style-type: none"> • Perform an evaluation of the potential impact of the vertical cracks in the masonry shear walls on the seismic performance of the pump station and implement an appropriate repair concept. Implement repairs of localized deterioration of plywood sheathing and framing to restore these components to their original strength. • Remove a small section of existing roofing to verify the adequacy of the existing roof sheathing to truss nailing. • Add blocking to support the edges of the roof sheathing panels and provided boundary nailing between the roof sheathing and blocking. • Install new shaped blocking between the roof sheathing and masonry wall top plate. Provided boundary nailing between the roof sheathing and blocking, and Simpson A35 clip angles between the blocking and top plate and blocking and trusses. Also, suggest engaging the shear resistance of the interior masonry wall by adding a combination of plywood sheathing, framing/blocking, and metal connector hardware to provide a load path between the roof diaphragm and the interior masonry wall. • Perform an investigation to verify the adequacy of the connection between the roof sheathing, gable end triangular portion wood framed shear walls and masonry wall top plate below. • Install Simpson A35 clips between trusses and masonry wall top plate in conjunction with cross tie retrofit described in next bullet item. • Install a combination of plywood sheathing, blocking, steel straps, and metal connector hardware to provide adequate out-of-plane support for CMU walls. The concept is similar to that shown in Figure 4.5, for the Creekside Pump Station, except that all three sub-diaphragms should be installed with added plywood at the at the ceiling level, since the masonry portion of the gable end walls does not extend all the way to the roof level. |
| Nonstructural | <ul style="list-style-type: none"> • Provide bracing for the piping. • Provide independent bracing for the valves. |

Table 4.8 Limelight Pump Station Preliminary Mitigation Concepts (cont.)

| Potential Deficiencies | Description |
|------------------------------|--|
| Nonstructural (cont.) | <ul style="list-style-type: none"> • Provide independent support and bracing for the air relief valves. • Perform additional analysis to evaluate the adequacy of the existing connection of the motor to the top of the steel motor support, the motor support, the connection of the motor support to the concrete pedestal, and the concrete pedestal. • Add flexible couplings between the pumps and the connected piping. • Perform an investigation to evaluate the adequacy of the anchorage of electrical cabinets to housekeeping pads and housekeeping pads to slab on grade, and supplement anchorage (as required). Also, provide anchorage/bracing between the top of the electrical cabinets and masonry wall. • Verify the adequacy of the antenna connection to the supporting pole. • Coordinate with electrical utility to anchor the utility owned electrical transformer to the concrete pad, as required. |

4.1.9 Mountain View Pump Station

Table 4.9 summarizes preliminary seismic retrofit concepts to mitigate the potential structural and nonstructural deficiencies described in Section 3.1.9 for the Mountain View Pump Station.

Table 4.9 Mountain View Pump Station Preliminary Mitigation Concepts

| Potential Deficiencies | Description |
|------------------------|---|
| Structural | <ul style="list-style-type: none"> • Reconfigure roof trusses and framing/blocking to provide plywood shear wall between roof diaphragm and top plate of north masonry wall. Also, suggest engaging the shear resistance of the interior north-south oriented masonry wall by adding a combination of plywood sheathing, framing/blocking, and metal connector hardware to provide a load path between the roof diaphragm and the interior masonry wall. • Install Simpson A35 clips between trusses and masonry wall top plate in conjunction with cross tie retrofit described in next bullet item. • Install a combination of plywood sheathing, blocking, steel straps, and metal connector hardware to provide adequate out-of-plane support for CMU walls (see Figure 4.6). |
| Nonstructural | <ul style="list-style-type: none"> • Provide bracing for the piping. • Provide independent bracing for the valves. • Provide independent support and bracing for the air relief valves. • Perform additional analysis to evaluate the adequacy of the existing connection of the motor to the top of the steel motor support, the motor support, the connection of the motor support to the concrete pedestal, and the concrete pedestal. • Add flexible couplings between the pumps and the connected piping. • Add anchors through the pipe support stanchion base plates into the slab-on-grade at locations with missing anchors. • Provide additional anchors for chlorination equipment and repair/replace damaged curb. • Provide adequate anchorage between the strut and the masonry shear wall for seismic demands and provide positive connection between spacers and main strut. • Provide bracing for transformer hung from roof. |

Table 4.9 Mountain View Pump Station Preliminary Mitigation Concepts (cont.)

| Potential Deficiencies | Description |
|------------------------------|---|
| Nonstructural (cont.) | <ul style="list-style-type: none"> • Perform an investigation to evaluate the adequacy of the anchorage of electrical cabinets to the slab on grade, and supplement anchorage (as required). Also, supplement the existing anchorage between the top of the electrical cabinets and masonry wall. • Provide flexible couplings where conduits connect to the top of floor- and wall-mounted electrical panels and cabinets. • Provide restraint for the emergency generator starter batteries within the battery bins (e.g., strap) and anchorage of the battery bins. • Provide bracing for the emergency generator muffler. • Provide lens covers for light fixtures with safety devices that prevent the lens cover and light bulbs from falling. • Verify the adequacy of the antenna connection to the supporting pole. • Provide restraint for overhead trolley chain hoist, when not in use. • Provide restraint for ladders (using straps to the wall, etc.), when not in use. • Coordinate with electrical utility to anchor the utility owned electrical transformer to the concrete pad, as required. |




Figure 4.6 Sub-diaphragm Retrofit Concept
(Adapted From: Detail 1 on Sheet S4 of 1994 design drawings by KMC, Inc.)

4.1.10 Salem/Keizer Intertie #1 Pump Station

Table 4.10 summarizes preliminary seismic retrofit concepts to mitigate the potential structural and nonstructural deficiencies described in Section 3.1.10 for the Salem/Keizer Intertie #1 Pump Station.

Table 4.10 Salem/Keizer Intertie #1 Pump Station Preliminary Mitigation Concepts

| Potential Deficiencies | Description |
|------------------------|---|
| Structural | <ul style="list-style-type: none"> • Perform a site-specific geotechnical study to confirm the expected liquefaction-induced settlement. If required, mitigate the potential permanent ground deformation hazard at the site with geotechnical improvement, or other appropriate techniques. • Perform additional analysis to investigate the adequacy of the gap between the City of Salem pump station and the adjacent City of Keizer building. • Install shaped blocking at the ridge line to bridge over the existing gap in the roof sheathing. Provide boundary nailing between the roof sheathing and new blocking. Coordinate with architect for any necessary modifications to roof venting. • Install Simpson A35 clip angles between the blocking and top plate and blocking and trusses. • Install a combination of blocking and steel straps between truss bottom chord members in the two truss bays where blocking is not currently installed to provide continuous cross ties in the east-west direction. |
| Nonstructural | <ul style="list-style-type: none"> • Provide appropriate flexible joints where water system piping penetrates through the pump station floor to accommodate potential differential movement between the structure and the surrounding soil at or near the pipe penetration. • Provide bracing for the piping. • Provide independent bracing for the valves. • Add flexible couplings between the pumps and the connected piping. • Provide anchorage of the chlorination skid to the concrete slab on grade and anchorage of chlorination system components to the skid. • Perform an investigation to evaluate the adequacy of the anchorage of electrical cabinets to the concrete housekeeping pads, and supplement anchorage (as required). |

Table 4.10 Salem/Keizer Intertie #1 Pump Station Preliminary Mitigation Concepts (cont.)

| Potential Deficiencies | Description |
|------------------------------|--|
| Nonstructural (cont.) | <ul style="list-style-type: none"> • Remove the existing L-shaped strut brackets at the top of the electrical cabinets and replace with a more appropriate steel bracket. • Verify the adequacy of the antenna connection to the supporting pole. • Coordinate with electrical utility to anchor the utility owned electrical transformer to the concrete pad, as required. |

4.1.11 Turner Control Facility


Table 4.11 summarizes preliminary seismic retrofit concepts to mitigate the potential structural and nonstructural deficiencies described in Section 3.1.11 for the Turner Control Facility.

Table 4.11 Turner Control Facility Preliminary Mitigation Concepts

| Potential Deficiencies | Description |
|------------------------|---|
| Structural | <ul style="list-style-type: none"> • Perform a site-specific geotechnical study to confirm the expected liquefaction-induced settlement. If required, mitigate the potential permanent ground deformation hazard at the site with geotechnical improvement, or other appropriate techniques. • Add blocking to support the edges of the roof sheathing panels and provided boundary fasteners between the roof sheathing and blocking. • Perform an investigation to determine if adequate fasteners are provided for the roof sheathing to blocking and blocking to masonry wall top plate connections. Provide supplemental fasteners, as required. • Install additional fasteners between the roof sheathing and outriggers in conjunction with cross tie retrofit described in next bullet item. • Install a combination of blocking, steel straps, and metal connector hardware to provide adequate out-of-plane support for CMU walls in the direction perpendicular to the roof trusses (see Figure 4.7). |
| Nonstructural | <ul style="list-style-type: none"> • Provide appropriate flexible joints where water system piping penetrates through the control facility wall to accommodate potential differential movement between the structure and the surrounding soil at or near the pipe penetration. • Provide bracing for the piping. • Provide independent bracing for the valves. • Provide independent bracing for the valve actuators. • Provide anchorage of the control cabinet to the housekeeping pad. • Provide supplemental anchorage of the electrical transformer to the concrete slab on grade. • Provide restraint for backup batteries inside the battery cabinet. • Provide restraint for pendant supported lights to prevent excessive swing. • Provide lens covers for light fixtures with safety devices that prevent the lens cover and light bulbs from falling. |

Table 4.11 Turner Control Facility Preliminary Mitigation Concepts (cont.)

| Potential Deficiencies | Description |
|------------------------------|---|
| Nonstructural (cont.) | <ul style="list-style-type: none"> • Verify the adequacy of the antenna connection to the supporting pole. • Provide seismic bracing for the ceiling hung inline HVAC fan. • Provide anchors between the HVAC condenser unit and concrete support pad. • Provide anchorage or bracing for the storage shelving to the floor and/or the wall. • Provide appropriate restraint for the fire extinguisher in its cabinet. |



NOTES:

- 1) PROVIDE BOUNDARY FASTENERS BETWEEN PLYWOOD SHEATHING & BLOCKING/FRAMING.
- 2) PROVIDE ADDITIONAL ANCHORS BETWEEN TOP PLATE & CMU WALL (AS REQUIRED).

Figure 4.7 Sub-diaphragm Retrofit Concept
(Adapted From: Roof Plan on Sheet S6 of 2007 design drawings by Black & Veatch Corporation)

4.2 Reservoirs and Reservoir Control Buildings

This section provides summary tables that describe preliminary seismic retrofit concepts to mitigate the potential structural and nonstructural seismic deficiencies identified for selected City reservoirs and reservoir control buildings, described in Section 3.2. Where appropriate, these tables also provide recommendations for further investigation and/or analysis to potentially mitigate deficiencies through more detailed structural calculations or to infill gaps in the data that was available for this study.

4.2.1 Candalaria Reservoir

Table 4.12 summarizes preliminary seismic retrofit concepts to mitigate the potential structural and nonstructural deficiencies described in Section 3.2.1 for the Candalaria Reservoir.

Table 4.12 Candalaria Reservoir Preliminary Mitigation Concepts

| Retrofit Recommendations | Description |
|--------------------------|---|
| Structural | <p><u>Reservoir</u></p> <ul style="list-style-type: none"> • Perform a future ASCE 41 Tier 2 assessment to evaluate the adequacy of the provided column reinforcing lap splice length. <p><u>Valve Vault</u></p> <ul style="list-style-type: none"> • Install stainless steel plates and/or angles to connect riser, base, and lid precast components at the precast concrete construction joints. • Repair any leaking precast joints with polyurethane resin injection or other similar method after an earthquake, as required. |
| Nonstructural | <p><u>Reservoir</u></p> <ul style="list-style-type: none"> • Verify that piping, fittings, and valve bodies are constructed of steel or ductile iron. Replace any components that are suspected to be cast iron. • Perform additional analysis to evaluate the adequacy of the overflow pipe and valve operator riser shafts to resist seismic forces. Provide lateral bracing of the overflow pipe and valve operator riser shafts, as required. |

Table 4.12 Candalaria Reservoir Preliminary Mitigation Concepts (cont.)

| Retrofit Recommendations | Description |
|---------------------------------|--|
| Nonstructural (cont.) | <u>Valve Vault</u> <ul style="list-style-type: none">• Perform additional analysis to evaluate the adequacy of the piping and valve to resist seismic forces (e.g., span between vault walls). Alternatively, provide bracing for the pipe and valve inside the valve vault.• Provide restraint of backup batteries, as required. |

4.2.2 Champion Hill Reservoir

Table 4.13 and Table 4.14 summarizes preliminary seismic retrofit concepts to mitigate the potential structural and nonstructural deficiencies described in Section 3.2.2 for the Champion Hill Reservoir and the Champion Hill Reservoir Control Building, respectively

Table 4.13 Champion Hill Reservoir Preliminary Mitigation Concepts

| Retrofit Recommendations | Description |
|---------------------------------|---|
| Structural | <ul style="list-style-type: none"> • Perform a site-specific geotechnical study to further evaluate the potential earthquake-induced liquefaction hazard at the site. If required, mitigate the potential permanent ground deformation hazard at the site with geotechnical improvement, or other appropriate techniques. • Perform a future ASCE 41 Tier 2 assessment to evaluate the adequacy of the provided column reinforcing lap splice length. |
| Nonstructural | <ul style="list-style-type: none"> • Install connection brackets at the corners of the pipe support pedestals that are anchored to both the concrete pedestal and concrete floor slab. |

Table 4.14 Champion Hill Reservoir Control Building Preliminary Mitigation Concepts

| Retrofit Recommendations | Description |
|---------------------------------|---|
| Structural | <ul style="list-style-type: none"> • Perform a site-specific geotechnical study to further evaluate the potential earthquake-induced liquefaction hazard at the site. If required, mitigate the potential permanent ground deformation hazard at the site with geotechnical improvement, or other appropriate techniques. • Add blocking to support the edges of the roof sheathing panels and provided boundary nailing between the roof sheathing and blocking. • Install Simpson roof boundary clips (RBCs) between blocking and masonry wall top plate and Simpson A35 clip angles between the blocking and trusses. • Install Simpson A35 clip angles, at approximately 2-feet on center, between gable end truss bottom chord and masonry wall top plate. |

**Table 4.14 Champion Hill Reservoir Control Building Preliminary Mitigation Concepts
(cont.)**

| Retrofit Recommendations | Description |
|---------------------------------|--|
| Structural (cont.) | <ul style="list-style-type: none"> • Install appropriate metal connector hardware to provide a vertical connection between the blocking that the kicker brace frames into and the adjacent roof trusses. Provide local strengthening of trusses, as appropriate. |
| Nonstructural | <ul style="list-style-type: none"> • Provide appropriate flexible joints where water system piping penetrates through the control building wall to accommodate potential differential movement between the structure and the surrounding soil at or near the pipe penetration. • Provide bracing for the piping. • Provide independent bracing for the valves. • Provide independent bracing for the recirculation pump and associated piping. • Provide an additional anchor at the base of the pressure tank. • Provide restraint for backup batteries inside the battery cabinet. • Verify the adequacy of the antenna connection to the supporting pole. • Install a combination of blocking and metal connector hardware to provide adequate connections to transfer seismic forces from the ceiling to the masonry walls and eliminate the potential for cross-grain bending of wood ledgers. • Provide restraint for temporarily stored electrical cabinets and other components (using straps to the wall, etc.). • Coordinate with electrical utility to conduct further evaluation to validate the seismic performance of pole-mounted transformer and utility pole. |

4.2.3 Eola #1B Reservoir

Table 4.15 summarizes preliminary seismic retrofit concepts to mitigate the potential structural and nonstructural deficiencies described in Section 3.2.3 for the Eola #1B Reservoir.

Table 4.15 Eola #1B Reservoir Preliminary Mitigation Concepts

| Retrofit Recommendations | Description |
|--------------------------|--|
| Structural | <p><u>Reservoir</u></p> <ul style="list-style-type: none"> • Perform an evaluation of the potential impact of the circumferential concrete cracks adjacent to the roof to wall interface on the seismic performance of the reservoir. • Perform a future ASCE 41 Tier 2 assessment to evaluate the adequacy of the provided column reinforcing lap splice length. <p><u>Valve Vaults</u></p> <ul style="list-style-type: none"> • Investigate concrete deterioration near top of South Valve Vault wall to lid connection and develop appropriate repair concepts. • Install stainless steel plates and/or angles to connect riser, base, and lid precast components at the precast concrete construction joints. • Repair any leaking precast joints with polyurethane resin injection or other similar method after an earthquake, as required. |
| Nonstructural | <p><u>Reservoir</u></p> <ul style="list-style-type: none"> • Supplement existing bracing for vertical section of inlet pipe. <p><u>Valve Vaults</u></p> <ul style="list-style-type: none"> • Perform additional analysis to evaluate the adequacy of the piping and valves to resist seismic forces (e.g., span between vault walls). Alternatively, provide bracing for the piping and valves inside the valve vaults. |

4.2.4 Fairmount Reservoir

Table 4.16 and Table 4.17 summarizes preliminary seismic retrofit concepts to mitigate the potential structural and nonstructural deficiencies described in Section 3.2.4 for the Fairmount Reservoir and the Fairmount Reservoir Control Building/Pump Station, respectively.

Table 4.16 Fairmount Reservoir Preliminary Mitigation Concepts

| Retrofit Recommendations | Description |
|---|--|
| Structural (based on 2018 seismic study by Carollo Engineers) | <ul style="list-style-type: none"> • Add a 6-inch layer of shotcrete at the inside face of the perimeter walls and footings. • Provide stainless steel connections along the roof expansion joints to transfer shear forces between roof panels. Also, provide anchors between the roof slab and the walls to transfer roof seismic loads to the perimeter walls. |
| Additional Structural (based on SEFT Desktop assessment) | <ul style="list-style-type: none"> • It is recommended that if the future seismic retrofit of Fairmount Reservoir is designed for a reduced seismic hazard level (i.e., BSE-1E hazard level), the 2019 OSSC Chapter 34 exception that the seismic hazard level should not be taken as less than 75% of the BSE-1N seismic hazard level should be considered. • Perform a future structural assessment to evaluate the potential impact of the interaction between the Fairmount Reservoir and the integrally constructed Fairmount Reservoir Control Building/Pump Station. • Perform a future ASCE 41 Tier 2 assessment to evaluate the adequacy of the provided column reinforcing lap splice length. |
| Nonstructural | <ul style="list-style-type: none"> • Verify that piping, fittings, and valve bodies are constructed of steel or ductile iron. Replace any components that are suspected to be cast iron. |

Table 4.17 Fairmount Reservoir Control Building/Pump Station Preliminary Mitigation Concepts

| Retrofit Recommendations | Description |
|---------------------------------|--|
| Structural | <ul style="list-style-type: none"> • In coordination with the future detailed design for the seismic retrofit of the Fairmount Reservoir, perform a detailed structural seismic assessment of the Fairmount Reservoir Control Building/Pump Station and develop seismic mitigation concept recommendations for consideration by the City. |
| Nonstructural | <ul style="list-style-type: none"> • Provide bracing for the piping. • Provide independent bracing for the valves and valve actuators. • Provide bracing/restraint for vertical pump bells and valve operator riser shafts. • Replace any piping and valve components that are suspected to be cast iron. • Replace any corrosion damaged piping and valve components and connection hardware not already replaced by the bullet item above. • Provide anchorage between pump bases and concrete slab. • Perform additional analysis to evaluate the adequacy of the existing connection of the motor to the top of the steel motor support and the motor support. • Add flexible couplings between the pumps and the connected piping. • Provide bracing for the air vent vertical pipe. • Perform an investigation to evaluate the adequacy of the anchorage of electrical cabinets to concrete floor slab, and supplement anchorage (as required). Also, provide anchorage/bracing between the top of the electrical cabinets and concrete wall. • Provide flexible couplings where conduits connect to the top of floor-mounted electrical cabinets. • Verify the adequacy of the antenna connection to the supporting pole. • Coordinate with electrical utility to conduct further evaluation to validate the seismic performance of pole-mounted transformer and utility pole. |

4.2.5 Grice Hill Reservoir

Table 4.18 and Table 4.19 summarizes preliminary seismic retrofit concepts to mitigate the potential structural and nonstructural deficiencies described in Section 3.2.5 for Grice Hill Reservoir and the Grice Hill Reservoir Control Building, respectively.

Table 4.18 Grice Hill Reservoir Preliminary Mitigation Concepts

| Retrofit Recommendations | Description |
|---------------------------------|---|
| Structural | <ul style="list-style-type: none"> • Perform a future ASCE 41 Tier 2 assessment to evaluate the adequacy of the provided column reinforcing lap splice length. |
| Nonstructural | <ul style="list-style-type: none"> • Install connection brackets at the corners of the pipe support pedestals that are anchored to both the concrete pedestal and concrete floor slab. |

Table 4.19 Grice Hill Reservoir Control Building Preliminary Mitigation Concepts

| Retrofit Recommendations | Description |
|---------------------------------|--|
| Structural | <ul style="list-style-type: none"> • Add blocking to support the edges of the roof sheathing panels and provided boundary nailing between the roof sheathing and blocking. • Install Simpson roof boundary clips (RBCs) between blocking and masonry wall top plate and Simpson A35 clip angles between the blocking and trusses. • Install appropriate metal connector hardware to provide a vertical connection between the blocking that the kicker brace frames into and the adjacent roof trusses. Provide local strengthening of trusses, as appropriate. |
| Nonstructural | <ul style="list-style-type: none"> • Provide bracing for the piping. • Provide independent bracing for the valves. • Repair seismic valve so that is operational in the event of an earthquake. • Provide anchorage of the pressure tank. • Provide additional restraint for backup batteries inside the battery cabinet. • Install a combination of blocking and metal connector hardware to provide adequate connections to transfer seismic forces from the ceiling to the masonry walls and eliminate the potential for cross-grain bending of wood ledgers. |

Table 4.19 Grice Hill Reservoir Control Building Preliminary Mitigation Concepts (cont.)

| Retrofit Recommendations | Description |
|--------------------------|---|
| Nonstructural (cont.) | <ul style="list-style-type: none"> • Provide restraint for temporarily stored electrical cabinets and other components (using straps to the wall, etc.). • Provide restraint for ladder (using straps to the wall, etc.), when not in use. • Coordinate with electrical utility to anchor the utility owned electrical transformer to the concrete pad, as required. |

4.2.6 Lone Oak Reservoir

Table 4.20 and Table 4.21 summarizes preliminary seismic retrofit concepts to mitigate the potential structural and nonstructural deficiencies described in Section 3.2.6 for the Lone Oak Reservoir and the Lone Oak Reservoir Control Building, respectively.

Table 4.20 Lone Oak Reservoir Preliminary Mitigation Concepts

| Retrofit Recommendations | Description |
|---------------------------------|--|
| Structural | <ul style="list-style-type: none"> • No potential deficiencies were identified that require mitigation. |
| Nonstructural | <ul style="list-style-type: none"> • No potential deficiencies were identified that require mitigation. |

Table 4.21 Lone Oak Reservoir Control Building Preliminary Mitigation Concepts

| Retrofit Recommendations | Description |
|---------------------------------|--|
| Structural | <ul style="list-style-type: none"> • Coordinate with the City to attempt to locate deferred submittal design drawings and calculations from original construction. Supplement available drawings with a detailed field investigation (including localized removal of architectural finishes) to observe and document details of original construction. Once additional details of original construction are available, complete a follow-up ASCE 41 Tier 1 evaluation and develop preliminary concepts to mitigate the identified deficiencies. |
| Nonstructural | <ul style="list-style-type: none"> • Provide bracing for the piping. • Provide independent bracing for the valves. • Provide anchorage of the pressure tank. • Perform an investigation to evaluate the adequacy of the anchorage of control cabinet to housekeeping pad, and supplement anchorage (as required). Also, provide anchorage/bracing between the top of the control cabinet and masonry wall. • Perform an investigation to evaluate the adequacy of the anchorage of the battery cabinet to the control cabinet, and supplement anchorage (as required). Also, provide restraint for backup batteries inside the battery cabinet. |

Table 4.21 Lone Oak Reservoir Control Building Preliminary Mitigation Concepts (cont.)

| Retrofit Recommendations | Description |
|--------------------------|---|
| | <ul style="list-style-type: none"> • Verify the adequacy of the antenna connection to the supporting pole. • Perform an investigation to evaluate the adequacy of the bracing of the suspended HVAC unit, and supplement bracing (as required). • Perform an investigation to evaluate the adequacy of the anchorage of the water heater/safety shower base skid to the concrete slab, and supplement anchorage (as required). • Perform an investigation of the original deferred submittal design details for the chlorine room masonry wall reinforcing and top of wall bracing. Provide supplemental bracing of masonry walls, as required. • Provide restraint for ladder (using straps to the wall, etc.), when not in use. • Coordinate with electrical utility to anchor the utility owned electrical transformer to the concrete pad, as required. |

4.2.7 Mill Creek #1 Reservoir

Table 4.22 and Table 4.23 summarizes preliminary seismic retrofit concepts to mitigate the potential structural and nonstructural deficiencies described in Section 3.2.7 for the Mill Creek #1 Reservoir and the Mill Creek #1 Reservoir Control Building, respectively.

Table 4.22 Mill Creek #1 Reservoir Preliminary Mitigation Concepts

| Retrofit Recommendations | Description |
|---------------------------------|---|
| Structural | <ul style="list-style-type: none"> • Perform a future ASCE 41 Tier 2 assessment to evaluate the adequacy of the provided column reinforcing lap splice length. |
| Nonstructural | <ul style="list-style-type: none"> • Install connection brackets at the corners of the pipe support pedestals that are anchored to both the concrete pedestal and concrete floor slab. • Provide additional seismic separation between the steel framed stair landing platform and reservoir concrete roof and/or provide diagonal bracing between stair landing support posts. |

Table 4.23 Mill Creek #1 Reservoir Control Building Preliminary Mitigation Concepts

| Retrofit Recommendations | Description |
|---------------------------------|--|
| Structural | <ul style="list-style-type: none"> • Add blocking to support the edges of the roof sheathing panels and provided boundary nailing between the roof sheathing and blocking. • Coordinate with the City to attempt to locate deferred submittal design drawings and calculations from original construction. Supplement available drawings with a detailed field investigation (including potential localized removal of architectural finishes) to observe and document details of the truss blocking and associated connections. Once additional details of original construction are available, evaluate the adequacy of the load path to transfer seismic forces from the roof diaphragm to the masonry wall top plate and develop mitigation concepts, as appropriate. • Install a combination of blocking and steel straps between truss bottom chord members in four additional truss bays per line of blocking. |
| Nonstructural | <ul style="list-style-type: none"> • Provide bracing for the piping. • Provide independent bracing for the valves. • Provide anchorage of the pressure tank. |

Table 4.23 Mill Creek #1 Reservoir Control Building Preliminary Mitigation Concepts (cont.)

| Retrofit Recommendations | Description |
|-------------------------------------|--|
| <p>Nonstructural (cont.)</p> | <ul style="list-style-type: none"> • Perform additional analysis to evaluate the adequacy of the existing connection of the motor to the top of the steel motor support, the motor support, and the connection of the motor support to the concrete slab. • Add flexible couplings between the pumps and the connected piping. • Provide restraint for backup batteries inside the battery cabinet. • Verify the adequacy of the antenna connection to the supporting pole. • Install a combination of blocking and metal connector hardware to provide adequate connections to transfer seismic forces from the ceiling to the masonry walls and eliminate the potential for cross-grain bending of wood ledgers. • Perform additional analysis to evaluate the adequacy of the electrical room unbraced partial height masonry walls. • Provide restraint for ladders (using straps to the wall, etc.), when not in use. • Coordinate with electrical utility to anchor the utility owned electrical transformer to the concrete pad, as required. |

4.2.8 Mountain View Reservoir

Table 4.24 summarizes preliminary seismic retrofit concepts to mitigate the potential structural and nonstructural deficiencies described in Section 3.2.8 for the Mountain View Reservoir.

Table 4.24 Mountain View Reservoir Preliminary Mitigation Concepts

| Retrofit Recommendations | Description |
|--------------------------|--|
| Structural | <ul style="list-style-type: none"> • Install seismic restraint between the reservoir walls and foundation. Potential concepts include using brackets and high-strength rods installed from inside the reservoir or installing new seismic cables in a thickened wall section from the exterior of the reservoir. Both options would likely require modifying/enlarging the existing foundation ring. • Operate the reservoir at a lower maximum elevation to reduce hydrodynamic forces to a level that makes the seismic performance of the prestressing strands adequate without further retrofit. (Note that this option may not be practical due to how the water level in the Mountain View Reservoir is hydraulically connected to the level in Franzen and Fairmount Reservoirs. <p>OR</p> <p>Re-wrap the core wall with additional circumferential prestressing strands encased with shotcrete to provide additional capacity to resist the combination of hydrostatic and expected hydrodynamic hoop forces during an earthquake.</p> <ul style="list-style-type: none"> • Provide fiber reinforced polymer (FRP) wrapping of columns. |
| Nonstructural | <ul style="list-style-type: none"> • Verify that piping, fittings, and valve bodies are constructed of steel or ductile iron. Replace any components that are suspected to be cast iron. |

5.0 Next Steps

This technical memorandum summarizes the results of SEFT's preliminary seismic structural and nonstructural evaluation of selected City of Salem water system facilities (10 pump stations, Turner Control Facility, 8 reservoirs, and 5 reservoir control buildings). Based on the potential structural and nonstructural deficiencies identified, only one reservoir is expected to achieve Immediate Occupancy structural performance and Operational nonstructural performance. None of the other structures evaluated are expected to achieve either Immediate Occupancy structural performance or Operational nonstructural performance for a M9.0 CSZ scenario earthquake.

Due to project budget limitations, not all City of Salem water system structures were included in the scope of the preliminary seismic structural and nonstructural evaluations conducted as part of this project. It is recommended that the City conducts seismic evaluations of the remaining inventory of water system structures (e.g., pump stations, reservoirs, communications towers, etc.) as part of a future project.

The seismic evaluation findings presented in this report should be integrated with the findings of previous seismic studies of other water system components and future seismic assessments of the remaining water system components, to develop a holistic view of the expected seismic performance of the water system. This knowledge can be leveraged in developing a comprehensive long-term plan for implementing water system seismic resilience improvements. In the near-term, the City is strongly encouraged to implement a seismic retrofit program to address Life Safety seismic deficiencies for water system structures that are frequently accessed by City staff and contractors.

During this project it was observed that the City has installed seismic isolation valves on many reservoirs. These seismically activated valves are designed to close when they detect earthquake shaking and are intended to help prevent all the water stored in these reservoirs from leaking out of transmission and distribution system pipelines that may be damaged by the earthquake. The significant volume of water that will be preserved in the reservoirs that have seismic isolation valves will help to meet community water needs (e.g., firefighting, drinking, sanitation, etc.) after a major earthquake. However, once the seismic isolation valves shut, accessing the water stored in the reservoirs may be challenging. There does not appear to be hydrants (or other connection points) installed between the reservoirs and seismic isolation valves. In the near-term, the City should consider installing hydrants (or other connection points) between the reservoirs and seismic isolation valves, so that the stored water can be easily accessed by City staff and the City of Salem Fire Department. These hydrants and associated piping should be designed to accommodate the expected level of permanent ground deformation that may occur at the reservoirs. Also, in the near-term, the City should consider installing seismic isolation valves and associated hydrant connections for reservoirs that do not currently have seismic isolation valves.

If replacement of existing or construction of new water system structures is considered in the future to meet water demand or operational goals, then this would provide an opportunity to build more seismically resilient structures and associated support infrastructure that are capable of achieving the City's post-earthquake LOS goals. The selection of the location of any new water system structures and the foundation design for those structures should include appropriate consideration of potential earthquake-induced permanent ground deformation and related mitigation strategies to achieve the City's resilience goals.

In order to continue to advance the City's water system resilience planning process, we recommend that a follow-up study be conducted to identify and understand dependency relationships and develop appropriate strategies to manage them to minimize any associated cascading effects. Planning for and addressing issues such as where the City will get fuel for trucks and generators, how suppliers and contractors will be rapidly engaged and compensated, etc. will help improve resilience and speed the return to normalcy after a major disaster. The City of Salem should also continue to evaluate and implement alternative options to provide water to customers in the event that the water system is significantly damaged by a major earthquake and could take months to repair for more recently constructed structures to years to rebuild older structures.

6.0 Limitations

The opinions and recommendations presented in this report were developed with the care commonly used as the state of practice of the profession. No other warranties are included, either expressed or implied, as to the professional advice included in this report. This report has been prepared for the City of Salem to be used solely in its evaluation of the seismic safety of the water system components referenced. This report has not been prepared for use by other parties and may not contain sufficient information for purposes of other parties or uses.

7.0 References

- ACI. (2006). ACI 350.3-06, *Seismic Design of Liquid-Containing Concrete Structures and Commentary*, American Concrete Institute, Farmington Hills, MI.
- ASCE. (2017a). ASCE 7-16, *Minimum Design Loads for Buildings and Other Structures*, American Society of Civil Engineers, Reston, VA.
- ASCE. (2017b). ASCE 41-17, *Seismic Evaluation and Retrofit of Existing Buildings*. American Society of Civil Engineers, Reston, VA.
- AWWA. (2013). AWWA D110-13, *Wire- and Strand-Wound, Circular, Prestressed Concrete Water Tanks*. American Water Works Association. Denver, CO.
- Black & Veatch. (2021). *City of Salem Seismic Resiliency Analysis*, Lake Oswego, OR.
- Shannon & Wilson. (2021). *Seismic Geohazards Evaluation Report, City of Salem Seismic Resilience Study*, Lake Oswego, OR.
- TCLEE. (2002). TCLEE Monograph No. 22, *Seismic Screening Checklists for Water and Wastewater Facilities*. American Society of Civil Engineers, Technical Council on Lifeline Earthquake Engineering, Reston, VA.

Appendix D. Facility Vulnerability Assessment Summary

The following sections provide a brief description of each of the facilities and summaries of seismic assessments for each of these facilities. The seismic assessments focus on structural and geotechnical issues. Nonstructural deficiencies are not discussed in this section. Detailed descriptions of the structural and nonstructural assessment results are presented in the SEFT report in Appendix C.

ASR # 1 and #2 Pump Station

ASR #2 Pump Station was built in 1998 as an addition to the ASR #1 Pump Station which was constructed in 1995. The combined structure of the two pump stations is an above-grade, single-story, reinforced masonry shear wall structure with a plywood-sheathed wood framed roof. The single-story building has an approximate footprint of 12 feet by 54 feet.

Structural deficiencies comprise the following items:

- Design or construction drawings for the structure were not available, so the masonry connections of ASR #2 to the original structure #1 could not be verified.
- Structurally, the roof poses seismic concerns as roof anchorage and wall bracing could not be identified.
- The load path is incomplete to transfer in-plane shear forces from the roof diaphragm to the masonry walls.

ASR #4 Pump Station

The ASR #4 Pump Station structure is an above-grade, single-story, reinforced masonry shear wall structure that was built in 1998. It has a plywood sheathed wood framed roof. The single-story building has an approximate footprint of 12 feet by 30 feet.

Structural concerns comprise the following items:

- A positive connection does not appear to be provided between the masonry walls and the roof.
- An access hatch in the roof creates an incomplete load path, reducing the capacity to transfer seismic forces to the shear wall below.
- Additionally, wall bracing is inadequate for this structure.

ASR #5 Pump Station

The ASR #5 Pump Station structure was built in 1998 and consists of an above-grade, single-story, reinforced masonry shear wall structure with a plywood ceiling diaphragm. It has a footprint of approximately 40 feet by 12 feet. The pump station's masonry shear wall structure is integrated with a premanufactured, hexagonal steel framed visitor-pavilion. The City Parks Department uses the room at the south end of the pump station structure for storage. This room is out of the scope of the seismic assessment.

Structural deficiencies comprise the following items:

- There does not appear to be either a) an adequate load path to transfer the seismic forces generated by the steel framed pavilion to the masonry shear wall structure or b) an adequate seismic separation to prevent unintended interaction between the steel framed pavilion and masonry shear wall structure.
- The north-south horizontal span for the ceiling diaphragm exceeds the ASCE 41-17 Tier 1 limit.
- No ceiling plywood sheathing nailing schedule was available in the drawings; therefore, it was unable to verify the nailing system adequacy,
- It is unclear if blocking is provided between the ceiling sheathing and masonry wall top plate. Therefore, there may be an incomplete load path to transfer in-plane shear forces from the ceiling diaphragm to the masonry walls.
- There is inadequate out-of-plane bracing for the perimeter and interior masonry walls.
- There are inadequate crossties between diaphragm chords.
- Vertical trim reinforcing is missing at the sides of door and other openings.
- The free-standing masonry wall to the north of the pump station is unbraced.
- Corrosion damage was observed at the base of the northern-most steel tube section columns of the pavilion.

Boone Road Pump Station

The original Boone Road Pump Station structure is an above-grade, single-story, reinforced masonry shear wall structure with a straight-sheathed wood framed roof that was built in 1977. The building has an approximate footprint of 34 feet by 36 feet. The structure received a partial seismic retrofit as part of a recent expansion project at the Boone Road Pump Station site.

The new electrical building that services the pump station is excluded from the scope of this study.

Structural deficiencies comprise the following items:

- The roof is slightly offset from the masonry shear walls on the north and south ends of the structure. The current load path may not be adequate for withstand seismic forces.
- The roof diaphragm span and aspect ratio exceed the ASCE 41-17 Tier 1 limits.
- The crossties between diaphragm chords are inadequate to resist seismic forces.

Creekside Pump Station

The Creekside Pump Station is an above-grade, single-story, reinforced masonry shear wall structure with a plywood sheathed wood framed roof. The facility was built in 1998 and has an approximate footprint of 20 feet by 47 feet.

Structural deficiencies comprise the following items:

- The original design drawings did not provide the roof plywood sheathing nailing schedule; therefore, the adequacy of the nailing system could not be verified.
- The roof diaphragm span for east-west oriented seismic forces exceeds the ASCE 41-17 Tier 1 limit for unblocked wood structural panel diaphragms.
- The load path is likely inadequate to transfer in-plane shear forces from the roof diaphragm to the masonry walls.
- Out-of-plane bracing of perimeter and interior masonry walls is inadequate.
- Adequate cross ties between diaphragm chords are not provided in both directions.

Deer Park Pump Station

The Deer Park Pump Station is an above-grade, single-story, reinforced masonry shear wall structure with a plywood sheathed wood framed roof. It was originally constructed in 1982, with an electrical room addition (located to the south of the pump station) added between 2008 and 2010. Roll-up doors and associated modifications were added in 2013. The building has an approximate footprint of approximately 44 feet by 20 feet.

Structural deficiencies comprise the following items:

- Design drawings were unavailable for the original construction of the structure and the additions. Sizing, spacing, and detailing of the structure is unknown, and could result in further structural deficiencies.
- The roof diaphragm span for east-west oriented seismic forces exceeds the ASCE 41-17 Tier 1 limit for unblocked wood structural panel diaphragms.
- A positive connection between the roof and the masonry walls was not observed, resulting in inadequate load path to transfer in-plane shear forces from the roof to the walls.
- Out-of-plane bracing of perimeter and interior masonry walls is inadequate.
- There are inadequate cross ties between diaphragm chords in both directions.

Edwards Pump Station

The Edwards Pump Station structure was built in 1961, and structural and piping modifications were completed in 1966. This structure is an above-grade, single-story structure with a straight-sheathed wood framed roof. Structural clay research (SCR) brick shear walls are located at the perimeter of the building. Roof straight-sheathing is supported by a combination of steel frames, wood framing, and masonry walls. The L-shaped building has an overall footprint of 51 feet by 39 feet.

Structural deficiencies comprise the following items:

- There is evidence of soil settlement resulting from past uncontrolled water releases at the pump stations and uncertainty associated with the liquefaction potential of the soil in the area around the pump station.
- Design or construction drawings were not available for the original construction of the structure or for the additions. The structural detailing for the facility could not be ascertained; therefore, additional structural deficiencies may be revealed in the Tier 2 investigation. It is assumed that the brick walls are unreinforced. Therefore, the load path may be incomplete or inadequate to transfer seismic forces from the roof diaphragm to the masonry walls and/or steel frames.
- Cracking was observed in the masonry walls at the southwest corner of the building.
- Many components of the structure do not meet ASCE 41-17 Tier 1 limits. This includes the shear stress in the masonry walls, the height-to-thickness ratio for the masonry walls, the flexural stress in the steel moment frame beams, the steel moment frames, and the roof diaphragm.

Limelight Pump Station

The Limelight Pump Station is an above-grade, single-story, reinforced masonry shear wall structure with a plywood-sheathed wood framed roof. The structure was built in 1998 and has an approximate footprint of 20 feet by 41 feet.

Structural deficiencies comprise the following items:

- Vertical cracks were observed in all four exterior masonry walls.
- The roof diaphragm span for east-west oriented seismic forces exceeds the ASCE 41-17 Tier 1 limit.
- A positive connection between the roof and the masonry walls does appear to be provided. This may result in an inadequate load path to transfer in-plane shear forces.
- There is inadequate out-of-plane bracing of perimeter and interior masonry walls.
- Adequate crossties between diaphragm chords are not provided in both directions.

Mountain View Pump Station

The Mountain View Pump Station was built in 1995 and comprises an above-grade, single-story, reinforced masonry shear wall structure with a plywood-sheathed wood framed roof. The facility has an approximate footprint of 29 feet by 62 feet. A significant length of the north wall of the building is inset by approximately 4 feet. Roof framing at the north edge of the building is supported by a CMU beam that is then supported by three CMU square columns.

Structural deficiencies comprise the following items:

- The load path of the roof of this structure is incomplete to deliver seismic forces from the roof to the masonry walls.
- There is inadequate out-of-plane bracing of perimeter and interior walls.
- Adequate cross ties between diaphragm chords are not provided in both directions.

Salem/Keizer Intertie #1 Pump Station

The Salem/Keizer Intertie #1 Pump Station was built in 2013 and comprises an above-grade, single-story, reinforced masonry shear wall structure with a plywood-sheathed wood framed roof. The structure has an approximate footprint of 26 feet by 22 feet.

Structural and geotechnical deficiencies comprise the following items:

- There is a potential liquefaction hazard at the site. Liquefaction-induced permanent ground deformation may result in damage to the building structure.
- The pump station and the adjacent City of Keizer building are only separated by a 1/2-inch seismic joint. The two buildings are susceptible to earthquake-induced pounding because of this small separation.
- Roof sheathing is not continuous to the roof ridge line.
- The load path is incomplete to transfer in-plane shear forces from the roof diaphragm to the masonry walls, because a positive connection does not appear to be provided between the truss blocking and masonry wall top plate.
- Adequate crossties between diaphragm chords are not provided in both directions.

Turner Control Facility

The Turner Control Facility is mostly a new structure, as the original Turner Control Facility was substantially replaced in 2007. Only a small subgrade portion of the original structure integrated into the new structure. The facility is a single-story, above-grade reinforced masonry shear wall structure with a plywood-sheathed light-gauge metal framed roof. The building is constructed over two sections of concrete basement where the three water transmission lines and associated valves are located. The building has an approximate footprint of 36 feet by 52 feet.

Structural deficiencies comprise the following items:

- There is a potential liquefaction hazard at the site. Liquefaction-induced permanent ground deformation may result in damage to the building structure.
- The roof diaphragm spans in both directions do not meet ASCE 41-17 Tier 1 limits.
- At the gable end locations, the load path may be inadequate to transfer in-plane shear forces from the roof diaphragm to the masonry walls.
- Also at the gable end walls, the outrigger to roof diaphragm connection may not have adequate capacity to resist out-of-plane seismic forces from the masonry walls.
- There are no crossties between diaphragm chords in the direction perpendicular to the roof trusses.

Candalaria Reservoir

The 0.5 MG Candalaria Reservoir is a completely buried rectangular reinforced concrete reservoir, located at Candalaria Park, to the north of Candalaria Blvd S. This reservoir is approximately 123 feet in by 50 feet, with a maximum height of retained water of 15 feet. The reservoir was originally constructed in 1940 and was seismically retrofit in 2006. The scope of this retrofit included the addition of anchors to connect the roof of the reservoir to the walls. The 2006 retrofit also included the installation of a seismic shutoff valve in a new vault located on the north side of the reservoir. The assessment of the Candalaria Reservoir did not include the interior of the reservoir valve vault.

Structural deficiencies comprise the following items:

- The column vertical reinforcing lap splice length is less than the ASCE 41-17 Tier 1 specified minimum length for Immediate Occupancy.
- The valves may have structural deficiencies if they were constructed from precast concrete.
- Riser joints may separate and shift due to seismic forces, and sand, silt, and groundwater could infiltrate at these compromised locations.

Champion Hill Reservoir and Control Building

The Champion Hill Reservoir is a strand-wound, circular, prestressed concrete reservoir with a nearly flat roof. It has an approximate diameter of 140 feet and a maximum height of retained water of 20 feet.

The 2.2 MG tank and control building were built in 2005. The control building is a single-story structure that is approximately 37 feet by 46 feet in footprint. It has reinforced concrete walls below grade, reinforced masonry walls above grade, and a plywood sheathed wood truss roof.

Structural deficiencies comprise the following items:

- In the reservoir, the column vertical reinforcing lap splice length is less than the ASCE 41-17 Tier 1 specified minimum length for Immediate Occupancy structural performance.
- The control building does not show a positive connection between the gable end wall sheathing and the masonry wall top plate.
- There is an incomplete load path to transfer in-plane shear forces from the roof to the walls.
- The masonry walls indicate inadequate bracing.

Eola #1B Reservoir

The Eola #1B Reservoir was constructed in 1999 and has a capacity of 0.86 MG. The tank is 92 feet in diameter with a maximum water depth of 17 feet. The reservoir is partially buried: the west side is completely buried, whereas the east side of the reservoir is partially exposed. Two precast concrete valve vaults are located to the southeast of the reservoir.

Structural deficiencies comprise the following items:

- Around the circumference of the reservoir, concrete cracking was observed on the east side of the structure.
- In the reservoir, the column vertical reinforcing lap splice length is less than the ASCE 41-17 Tier 1 specified minimum length for Immediate Occupancy structural performance.
- The valve vaults show concrete deterioration.
- The vaults were constructed using precast concrete, which can result in water infiltration from shifted riser joints due to lateral earth pressures.

Fairmount Reservoir and Control Building

The Fairmount Reservoir and Control Building were constructed in 1936. The reservoir is a rectangular, reinforced concrete structure with two cells, each with a 5 MG capacity. The 10 MG reservoir is approximately 384 feet by 192 feet and has a maximum water depth of 21 feet. The reservoir is partially buried.

The Control Building/Pump Station is located on the south side of the reservoir and consists of a single-story above grade structure with a basement, constructed with reinforced concrete walls, and a reinforced concrete floor and roof. Two walls of the control building were constructed integrally with the Fairmount Reservoir. The building is approximately 21 feet by 21 feet.

Structural deficiencies comprise the following items (from 2018 seismic study by Carollo Engineers):

- Overstressed perimeter walls and footings, resulting from tension loads imposed by the bending moment loads caused by hydrodynamic forces.
- Lack of load path to transfer seismic forces from roof to walls.
- Shear forces cannot be transferred adequately between roof panels due to expansion joints
- Lack of positive connections between the roof and walls resulting in columns being overstressed.

In addition to these issues (which appear to be unmitigated), the following additional issues were noted about the reservoir in SEFT's Tier 1 assessment:

- "The 2018 Carollo study considered the BSE-1E seismic hazard level as defined by ASCE 41-13. Chapter 34 of the 2019 Oregon Structural Specialty Code (OSSC) indicates that the BSE-1E hazard level should not be taken as less than 75 percent of the BSE-1N seismic hazard level as defined by ASCE 41, much higher than what was considered in the 2018 Carollo study.
- Previous studies were preliminary in nature and did not include consideration of the potential interaction between the Fairmount Reservoir and adjacent Fairmount Reservoir Control Building/Pump Station.
- The column vertical reinforcing lap splice length is less than the ASCE 41-17 Tier 1 specified minimum length for Immediate Occupancy structural performance (i.e., 50 bar diameters)."

SEFT also noted the following structural issues related to the Control Building:

- The northeast and northwest walls of the control building/pump station were constructed integrally with the reservoir. Evaluation of the potential interaction between these two structures is beyond the scope of this preliminary ASCE 41 Tier 1 check-list based assessment but should be considered as part of a future detailed seismic evaluation and retrofit design.
- Several potential deficiencies are likely associated with detailing requirements for reinforcing steel (reinforcement ratio, maximum spacing limits, reinforcing around openings, reinforcing hooks at slab to wall connections, and foundation dowels).
- At the operating floor level, large stair openings are located adjacent to three of the four shear walls, limiting the connection length to transfer seismic forces from the floor slab to the concrete walls.

Grice Hill Reservoir and Control Building

The Grice Hill Reservoir is a strand-wound, circular, prestressed concrete reservoir with a nearly flat roof. The 2.2 MG reservoir has an approximate diameter of 140 feet and a maximum depth of 20 feet. The facility was constructed in 2001.

The Control Building is located to the west of the reservoir, comprising an above grade, single-story structure, with reinforced masonry shear walls and a plywood sheathed wood truss roof. The building has an approximate footprint of 45 feet by 37 feet.

The only structural issue identified with the reservoir is that the column vertical reinforcing lap splice length is less than the ASCE 41-17 Tier 1 specified minimum length for Immediate Occupancy structural performance.

Structural deficiencies comprise the following items:

- The ASCE 41-17 Tier 1 limit (unblocked wood structural panel diaphragms) was exceeded for the roof diaphragm spans in both directions.
- The sloped roof truss blocking and/or corners of top plate may be split as a result of the configuration of the toenail connection between the blocking and masonry wall top plate. This may have caused a reduced and inadequate load path to transfer in-plane shear forces from the roof diaphragm to the walls.
- The north and south gable end walls have inadequate out-of-plane bracing.

Lone Oak Reservoir and Control Building

The Lone Oak Reservoir is a strand-wound, circular, prestressed concrete reservoir with a nearly flat roof. The 5.6 MG reservoir has an approximate diameter of 196 feet and a maximum water depth of 26 feet.

The Lone Oak Reservoir Control Building is located to the west of the reservoir. The Control Building is a single-story building with reinforced concrete walls below grade, reinforced masonry walls above grade, and a plywood-sheathed wood truss roof. The building has an approximate footprint of 39 feet by 29 feet.

Structural deficiencies comprise the following items:

- No structural deficiencies were identified for the reservoir.
- Original design drawings for the control building were not available for review; therefore, an analysis of the structural deficiencies could not be completed.

Mill Creek #1 Reservoir and Control Building

The Mill Creek #1 Reservoir is a strand-wound, circular, prestressed concrete reservoir with a nearly flat roof. The 2.2 MG reservoir is approximately 140 feet in diameter, with a maximum water depth of 20 feet. The facility was built in 2013.

The Control Building is located to the southwest of the reservoir. The structure is a single-story building with reinforced concrete walls below grade, reinforced masonry walls above grade, and a plywood-sheathed wood truss roof. The building has an approximate footprint of 46 feet by 42 feet.

The only structural deficiency noted for the reservoir was that the minimum lap splice length according to ASCE 41-17 Tier 1 criteria are exceeded for reinforcing in the support columns.

Structural deficiencies comprise the following items:

- The ASCE 41-17 Tier 1 limit (unblocked wood structural panel diaphragms) was exceeded for the roof diaphragm spans in both directions.
- The adequacy of the truss blocking is unknown because submittal drawings/calculations from the roof truss manufacturer were not available for review. The trusses were not visible during SEFT's site visit.
- There is inadequate out-of-plane bracing for the north and south gable end masonry walls.

Mountain View Reservoir

The Mountain View Reservoir is a completely buried, strand-wound, circular, prestressed concrete structure with a flat roof. It has a capacity of 10 MG and was built in 1971. The reservoir has an approximate diameter of 292 feet and a maximum water depth of 20 feet.

Structural deficiencies comprise the following items:

- Seismic cables or dowels were not used to connect the base of the wall to the foundation. Therefore, the connection has inadequate strength to seismic lateral forces.
- The horizontal prestressing strands on the wall of the reservoir have inadequate capacity to resist hydrostatic and hydrodynamic hoop forces during an earthquake.
- The main structural deficiency of the reservoir is that the column vertical reinforcing lap splice length is less than the ASCE 41-17 Tier 1 specified minimum length for Immediate Occupancy.

Appendix E. Facilities Cost Estimate Summary

CLASS 5 OPINION OF PROBABLE CONSTRUCTION COST - BASIS OF ESTIMATE (CONFIDENTIAL)

City of Salem

Seismic Resiliency Study

B&V PROJECT NO. 406828

DATE PREPARED

22 MARCH 2023



BLACK & VEATCH
Building a **world** of difference.®

Table of Contents

| | | |
|------------|---|----------|
| 1.0 | Introduction | 1 |
| 1.01 | Project Description and Location..... | 1 |
| 1.02 | Purpose and Disclaimer | 2 |
| 1.03 | OPCC Organization and Work Breakdown Structure..... | 2 |
| 1.04 | OPCC Classification and Accuracy..... | 2 |
| 2.0 | Basis of Estimate..... | 2 |
| 2.01 | Estimating Methodology..... | 2 |
| 2.02 | Assumptions and Allowances | 3 |
| 2.03 | Direct Costs..... | 3 |
| 2.04 | Market Condition..... | 3 |
| 2.05 | Markups, Taxes and Insurance | 3 |
| 2.06 | Escalation..... | 3 |
| 2.07 | Engineering and Construction Management..... | 3 |
| 2.08 | Contingencies..... | 3 |
| 2.09 | Exclusions..... | 4 |
| 2.10 | OPCC Calculation Assumptions..... | 4 |

Attachment A Summary of Vertical Facilities Costs

1.0 Introduction

1.01 PROJECT DESCRIPTION AND LOCATION

Black & Veatch (BV) developed cost estimates associated with recommended seismic improvements for vertical facilities and replacement of Low to Very High Risk pipelines.

The scope for recommended seismic improvements for vertical facilities is based upon a Draft Technical Memorandum (TM): Pump Station and Reservoir Seismic Vulnerability Assessment, dated September 6th, 2021 (SEFT Project Number: B20028.00).

The scope of replacement work for horizontal facilities (pipelines) was based upon a risk assessment conducted and described in the Seismic Resiliency Analysis Report (main report). Pipelines were first assessed for their consequence and likelihood of failure, then an overall risk score was applied. Pipelines with Low to Very High Risk are proposed to be preventatively replaced over a period of 50 years to improve systemwide resiliency, while Very Low Risk Pipes are proposed to remain and be repaired if needed after a major earthquake occurs. Pipeline replacement costs are based upon Black & Veatch's cost library information and professional judgement. Assumptions for the pipeline replacement cost estimate are further described in the Seismic Resiliency Analysis Report.

1.02 PURPOSE AND DISCLAIMER

The Opinion of Probable Construction Cost (hereinafter “OPCC”) is based on a conceptual level of design detail and information and are generally prepared based on very limited information and subsequently have wide accuracy ranges. The Class 5 OPCC is prepared for any number of strategic business planning purposes, such as market studies, assessment of initial viability, evaluation of alternate schemes, project screening, project location studies, evaluation of resource needs and budgeting, long-range capital planning, etc. The OPCC is based on expected capital construction cost only and does not consider life cycle costs or extended operation, maintenance, design or owner costs unless specifically included in the estimate details. The OPCC does not represent a certainty, and the final project costs may vary from the OPCC cost range presented to clients.

1.03 OPCC ORGANIZATION AND WORK BREAKDOWN STRUCTURE

Improvements were listed in the order presented in the TM with costs applied on a per improvement basis. Where complexity of the improvement required more detail, the improvement was broken down into further line items for clarity of scope and cost.

1.04 OPCC CLASSIFICATION AND ACCURACY

The OPCC can be considered consistent with an Association for the Advancement of Cost Engineering (AACE) Class 5 estimate. Typical accuracy ranges for Class 5 OPCC are -20% to - 50% on the low side, and +30% to +100% on the high side, depending on the technical complexity of the project, and appropriate contingency determinations. Ranges could exceed those shown in unusual circumstances.

The expected accuracy range for the OPCC is based on confidence and assessment of the quality and reliability of information used by the estimator. The range for this project is expected to be -30% to +50% low to high.

2.0 Basis of Estimate

2.01 ESTIMATING METHODOLOGY

A combination of methods, techniques and data sources are used in development of the OPCC.

For areas where quantities are provided with the design criteria, the values are incorporated into the OPCC and compared along with pricing based on both historical unit costs and built-up estimated costs. For estimating scope where quantities are unknown or unclear, the OPCC uses a combination of parametric factoring of known costs for similar systems and analogous projects with comparable corresponding features and sizing.

Where estimating scope was required but specific sizing could not be determined, costs are based on expert judgement and the use of allowances to meet an expected range of accuracy. In some instances, the estimator consults with process or subject matter experts to more clearly define project requirements to meet the confidence level in the allowance made.

2.02 ASSUMPTIONS AND ALLOWANCES

Where assumptions have been made to cover gaps in the scope of work or supply of components, the assumptions have been identified in the OPCC with the leading term “assumed” or “assume” followed by a description of the work. Similarly, where allowances have been made for costs that are not quantifiable or lack sufficient detail to price, the allowances have been identified with the leading term “allow” or “allowance”.

2.03 DIRECT COSTS

The OPCC includes direct costs for labor, permanent and incidental materials, construction equipment based on unit pricing for similar projects in the West Coast US Region.

2.04 MARKET CONDITION

Where market conditions in the project location are volatile or known to have extremes, we include a Market Adjustment. This adjustment takes into account unusual project circumstances that would otherwise have little basis for inclusion, including labor shortages and market fluctuations.

2.05 MARKUPS, TAXES AND INSURANCE

The OPCC builds up costs from direct construction and adds markups to represent a complete price for the scope of work representing the methodology a prime contractor would use. The OPCC is only a representation of how contractors may apply markups.

From years of tracking projects, we have determined markup ranges that are applied to direct costs as an aggregate. The aggregate factor used has been calculated for this OPCC to be the appropriate amount based on our experience.

2.06 ESCALATION

All costs are in 2022 dollars.

2.07 ENGINEERING AND CONSTRUCTION MANAGEMENT

Engineering and construction management costs were calculated for each of the identified scope items in the SEFT Seismic Resiliency TM. A minimum 30% multiplier was applied to base construction costs for engineering and construction management for vertical facilities, and a multiplier of 20 to 30% was applied to base costs for pipelines. For many of the scope items, engineering and construction management cost factors higher than 30% were used, due to the high proportion of engineering that is likely required to provide design and engineering relative to the cost of construction for these items.

2.08 CONTINGENCIES

Contingency is included in the OPCC and evaluated based on how complete the scope of work and OPCC are. Contingency at Class 5 level is often assessed at 30%; this contingency was applied to vertical facility cost estimates. While there are norms for contingency, the OPCC considers several factors in the assessment including range of accuracy, completion of scope, quality of cost data and systemic or

perceived risk to the contractor. For pipelines, a contingency of 40% was applied, since less is known about the specific conditions for each pipeline.

In addition to this contingency applied at the end of the estimate, some scope items were identified as “contingency” scope additions; these items of work may be required after further study or assessment of the vertical facilities. These additional scope items may not be comprehensive to all required improvements at vertical facilities.

Through the process of creating the OPCC, any clarifications that would have a significant impact on the project were noted in the cost items comments.

2.09 EXCLUSIONS

Based on the discipline estimator’s understanding of the project some scope may be specifically excluded from the OPCC value. Where costs have been excluded, they are identified in the OPCC with the leading term “exclude”, “excluded”, “not in cost” or “NIC”. Exclusions that have not been explicitly identified in the OPCC are listed in this section by the estimator. The following exclusions are not expected to be required in the improvements scope of work.

- Electrical if required
- Instrumentation if required
- Communications if required
- Right of Way Acquisition

2.10 OPCC CALCULATION ASSUMPTIONS

Assumptions and markups for the pipelines and vertical facilities cost estimates are further described in the Seismic Resiliency Analysis Report (main report), in Section 6.2, “Basis for Establishing Opinion of Probable Construction Costs”.

The information contained in this document is proprietary and its contents may not be copied, disclosed to other parties not directly affiliated with this specific project, or used for other than the express purpose for which it was provided.

ATTACHMENT A

| Facility | Known issues | Additional Studies | Total Base Costs | Potential Work Resulting from Studies | Total Potential Costs |
|--------------------------------------|--------------------|--------------------|--------------------|---------------------------------------|-----------------------|
| ASR 1&2 | \$180,000 | \$49,000 | \$229,000 | \$100,000 | \$329,000 |
| ASR 4 | \$100,000 | \$36,000 | \$136,000 | \$0 | \$136,000 |
| ASR 5 | \$60,000 | \$65,000 | \$125,000 | \$170,000 | \$295,000 |
| Creekside PS | \$120,000 | \$94,000 | \$214,000 | \$80,000 | \$294,000 |
| Deer Park PS | \$130,000 | \$62,000 | \$192,000 | \$190,000 | \$382,000 |
| Mountain View PS | \$230,000 | \$11,000 | \$241,000 | \$30,000 | \$271,000 |
| Salem Keiser Intertie #1 | \$140,000 | \$21,000 | \$161,000 | \$10,000 | \$171,000 |
| Turner Control Facility | \$70,000 | \$29,000 | \$99,000 | \$100,000 | \$199,000 |
| Candalaria Reservoir | \$10,000 | \$101,000 | \$111,000 | \$240,000 | \$351,000 |
| Champion Hill Reservoir | \$100,000 | \$8,000 | \$108,000 | \$0 | \$108,000 |
| Champion Hill Reservoir Control Bldg | \$180,000 | \$6,000 | \$186,000 | \$10,000 | \$196,000 |
| Edwards PS | \$190,000 | \$11,000 | \$201,000 | \$810,000 | \$1,011,000 |
| Fairmount Reservoir | \$2,650,000 | \$29,000 | \$2,479,000 | \$390,000 | \$2,869,000 |
| Fairmount Res. Control Bldg | \$140,000 | \$18,000 | \$158,000 | \$30,000 | \$188,000 |
| Grice Hill Res Control Bldg | \$150,000 | \$0 | \$150,000 | \$0 | \$150,000 |
| Lone Oak Res. Cntrl Bldg | \$30,000 | \$44,000 | \$74,000 | \$10,000 | \$84,000 |
| Mill Creek Reservoir | \$40,000 | \$8,000 | \$48,000 | \$940,000 | \$988,000 |
| Mill Creek#1 Res. Cntrl. Bldg | \$60,000 | \$44,000 | \$104,000 | \$150,000 | \$254,000 |
| Mountain View Reservoir | \$3,790,000 | \$0 | \$3,590,000 | \$70,000 | \$3,660,000 |
| Eolia 1B Seismic Valve | \$200,000 | | | | \$200,000 |
| Subtotal - High Priority | \$8,570,000 | \$636,000 | \$8,606,000 | \$3,330,000 | \$12,136,000 |
| Boone Road PS | \$110,000 | \$25,000 | \$135,000 | \$140,000 | \$275,000 |
| Limelight PS | \$100,000 | \$67,000 | \$167,000 | \$310,000 | \$477,000 |
| Eolia #1B Reservoir | \$80,000 | \$8,000 | \$88,000 | \$20,000 | \$108,000 |
| Grice Hill Reservoir | \$20,000 | \$0 | \$20,000 | \$20,000 | \$40,000 |
| Lone Oak Reservoir | \$0 | \$0 | \$0 | \$0 | \$0 |
| Subtotal - Medium Priority | \$310,000 | \$100,000 | \$410,000 | \$490,000 | \$900,000 |
| Total Program Costs (rounded) | \$8,880,000 | \$740,000 | \$9,020,000 | \$3,820,000 | \$13,040,000 |

ATTACHMENT A

| ASR 1 & 2 | | | | | | | |
|--|---|--|----------|------------------------|-------------------|------------------|-------------------------|
| Remedial Action | Description | Category of Work (Base, Study, or Contingency) | Quantity | Unit | Construction Cost | Engineering Cost | Total Construction Cost |
| Correct Wall Connection | Install vertical steel angles where the east-west oriented CMU walls of the ASR #2 addition interface with the west wall of the original ASR #1 structure. | | 24 | LF | \$2,756 | \$1,575 | \$4,331 |
| Further Assessment Necessary | Remove existing gypsum board interior finish to investigate the load path to transfer seismic roof diaphragm forces at the roof step between the ASR #1 and ASR #2 portions of the structure to the masonry wall below. Likely add a combination of plywood sheathing, blocking, and metal connector hardware to provide an adequate load path. | Study | | | \$12,185 | \$8,400 | \$20,585 |
| Remediate Deficiency in Roof Truss to Sheathing Nailing. | | Contingency | 80 | hrs | \$20,717 | \$10,500 | \$31,217 |
| New Shaped Blocking | Install new shaped blocking between the roof sheathing and masonry wall top plate. Provided boundary nailing between the roof sheathing and blocking, and Simpson A35 clip angles between the blocking and top plate and blocking and trusses. | | 648 | SF Footprint | \$20,108 | \$7,875 | \$27,983 |
| Correct CMU Wall Support | Install a combination of plywood sheathing, blocking, steel straps, and metal connector hardware to provide adequate out-of-plane support for CMU walls | | 1 | LS | \$14,816 | \$6,300 | \$21,116 |
| Further Assessment Necessary | Conduct nondestructive scanning to verify the size and location of masonry wall vertical reinforcing. If vertical trim reinforcing is not provided adjacent to door openings, install face mounted steel plates through-bolted to masonry wall and anchored to foundation. | Study | 1 | 0 | \$7,488 | \$2,771 | \$10,259 |
| Repair Door Opening | | Contingency | 3 | EA - assumed openings | \$4,223 | \$6,300 | \$10,523 |
| Pipe Bracing | Provide bracing for the piping | | 8 | EA - assumed Locations | \$14,756 | \$5,460 | \$20,216 |
| Valve Bracing | Provide independent bracing for the valves. | | 4 | EA | \$10,014 | \$3,705 | \$13,719 |
| Valve Bracing | Provide independent support and bracing for the air relief valve | | 1 | EA | \$2,503 | \$2,100 | \$4,603 |
| Pump Bracing | Vertical pump motors are not braced above the center of gravity of the motor | Contingency | 2 | EA | \$8,446 | \$3,150 | \$11,596 |
| Pump Bracing | Brace Pump(s) motor(s). | Contingency | 3 | EA | \$12,670 | \$4,688 | \$17,357 |
| Further Assessment Necessary | Perform additional analysis to evaluate the adequacy of the existing connection of the motor to the top of the steel motor support, the motor support, the connection of the motor support to the concrete pedestal, and the concrete pedestal. | Study | | | \$0 | \$4,200 | \$4,200 |
| Wall Bracing Improvements | Provide anchorage/bracing between the top of the electrical cabinets and wall. | | 20 | LF | \$1,393 | \$1,575 | \$2,968 |
| Lens Cover | Provide lens covers for light fixtures with safety devices that prevent the lens cover and light bulbs from falling. | | 8 | EA | \$2,456 | \$909 | \$3,365 |
| Electrical Flexible Conduits | Provide flexible couplings where conduits connect to the top of wall-mounted electrical panels and cabinets. | | 10 | EA | \$7,538 | \$2,789 | \$10,327 |
| Further Assessment Necessary | Verify the adequacy of the connection between the horizontal antenna and the supporting pole. | Study | 1 | EA | \$4,133 | \$1,529 | \$5,663 |
| Contingency Item to seismically strengthen antenna. | | Contingency | 1 | LS | \$5,591 | \$2,100 | \$7,691 |
| Correct Wall Connection | Add helical wall ties between the masonry veneer and the ASR #1 masonry walls. | | | | \$16,224 | \$6,003 | \$22,227 |
| Further Assessment Necessary | Conduct nondestructive scanning to verify the size and spacing of reinforcing in the architectural concrete pillars and perform calculations to verify the adequacy of the existing reinforcing. If reinforcing is found to be inadequate, remove existing architectural concrete pillars | Study | | | \$0 | \$8,400 | \$8,400 |
| Contingency Item - Remediate structural Deficiencies in architectural concrete pillars | If assessment finds need to reinforce the columns, assume that steel bracing will be provided on outside of the columns. | Contingency | | | \$7,288 | \$6,300 | \$13,588 |
| Anchor Electrical Transformer | Coordinate with electrical utility to anchor the utility owned electrical transformer to the concrete pad, as required. | | 1 | LS | \$2,037 | \$3,150 | \$5,187 |
| Pump Flexible Couplings | Add flexible couplings between the pumps and the connected piping | | 2 | EA | \$26,537 | \$9,819 | \$36,356 |
| Total Cost | | | | | \$203,881 | \$109,597 | \$313,478 |

ATTACHMENT A

ASR #4

| Remedial Action | Description | Category of Work (Base, Study, or Contingency) | Quantity | Unit | Construction Cost | Engineering Cost | Total Construction Cost |
|--------------------------------|---|--|----------|------------------------|----------------------|---------------------|-------------------------------|
| Roof Truss Inspection | Remove a small section of existing roofing to verify the adequacy of the existing roof sheathing to truss nailing. | Study | | | \$6,470 | \$6,300 | \$12,770 |
| New Shaped Blocking | Install new shaped blocking between the roof sheathing and masonry wall top plate. Provided boundary nailing between the roof sheathing and blocking, and Simpson A35 clip angles between the blocking and top plate and blocking and trusses. | Contingency | 360 | SF Approx Footprint | \$7,548 | \$6,300 | \$13,848 |
| Further Assessment Necessary | Perform additional analysis to investigate if the diaphragm has adequate capacity to transfer seismic forces from the roof diaphragm to the east masonry shear wall, considering the impact of the hatch opening adjacent to the wall. Note that this analysis will require information about the existing roof sheathing to truss nailing (i.e., size, and spacing). | Study | | ENG ONLY | \$0 | \$8,400 | \$8,400 |
| Install Simpson A35 Clips | Install Simpson A35 clips between truss bottom chord and masonry wall top plate in conjunction with cross tie retrofit described in next bullet item | Contingency | | | \$2,964 | \$4,200 | \$7,164 |
| Correct CMU Wall Support | Install a combination of plywood sheathing, blocking, steel straps, and metal connector hardware to provide adequate out-of-plane support for CMU walls | Contingency | 1 | LS | \$10,643 | \$4,200 | \$14,843 |
| Further Assessment Necessary | Conduct nondestructive scanning to verify the size and location of masonry wall vertical reinforcing. If vertical trim reinforcing is not provided adjacent to door openings, install face mounted steel plates through-bolted to masonry wall and anchored to foundation. | Study | 1 | 0 | \$7,488 | \$2,771 | \$10,259 |
| Repair Door Opening | | Contingency | | EA - assumed openings | \$4,223 | \$6,300 | \$10,523 |
| Pipe Bracing | Provide bracing for the piping. | | 8 | EA - assumed Locations | \$14,756 | \$5,460 | \$20,216 |
| Valve Bracing | Provide independent bracing for the valves. | | 4 | EA | \$7,378 | \$2,730 | \$10,108 |
| Valve Bracing | Provide independent support and bracing for the air relief valve. | | 4 | EA | \$7,378 | \$2,730 | \$10,108 |
| Pump Bracing | Brace Pump(s) motor(s). | Contingency | 3 | EA | \$12,670 | \$4,688 | \$17,357 |
| Further Assessment Necessary | Perform additional analysis to evaluate the adequacy of the existing connection of the motor to the top of the steel motor support, the motor support, the connection of the motor support to the concrete pedestal, and the concrete pedestal. | Study | | | \$0 | \$4,200 | \$4,200 |
| Anchor Control Cabinet to Wall | Anchorage of pump station control cabinet to floor or wall | Yes | 6 | LF | \$517 | \$1,575 | \$2,092 |
| Lens Cover | Provide lens covers for light fixtures with safety devices that prevent the lens cover and light bulbs from falling. | | 4 | EA Assumed | \$1,228 | \$454 | \$1,682 |
| Flexible Coupling | Add flexible couplings between the pump and the connected piping. | | 1 | EA | \$13,269 | \$4,909 | \$18,178 |
| Anchor Electrical Transformer | Coordinate with electrical utility to anchor the utility owned electrical transformer to the concrete pad, as required. | | 1 | LS | \$2,037 | \$3,150 | \$5,187 |
| Total Cost | | | | | \$98,568 | \$68,367 | \$166,935 |

ATTACHMENT A

| ASR #5 | | | | | | | |
|---|--|--|----------|--|-------------------|------------------|-------------------------|
| Remedial Action | Description | Category of Work (Base, Study, or Contingency) | Quantity | Unit | Construction Cost | Engineering Cost | Total Construction Cost |
| Correct Wall Connection | Add shaped blocking or framing/sheathing with metal connector hardware to provide a load path between the roof of the steel framed pavilion and masonry shear walls of the pump station structure. | | 480 | SF Approx footprint | \$10,064 | \$3,724 | \$13,788 |
| Further Assessment Necessary | Perform an investigation to determine if the ceiling diaphragm is adequately connected to the interior masonry walls to engage the walls as part of the seismic force resisting system. If not, add blocking/framing to provide a load path between the ceiling diaphragm and interior masonry shear walls. | Study | 1 | LS - Remove & Replace existing finish for inspection | \$17,290 | \$8,400 | \$25,690 |
| Contingency - add ceiling to wall bracing if found necessary in investigation | | Contingency | 480 | SF Approx footprint | \$6,500 | \$8,400 | \$14,900 |
| Further Assessment Necessary | Perform an investigation of the existing ceiling nail size and spacing to verify the adequacy of the existing ceiling sheathing to joist nailing. | Study | | ENG ONLY | \$0 | \$2,100 | \$2,100 |
| Contingency - Add additional nailing | Repairs needed, as a result of item above | Contingency | 480 | SF Approx footprint | \$3,120 | \$3,150 | \$6,270 |
| New Shaped Blocking | Perform an investigation to determine if adequate blocking and connections are provided between the ceiling sheathing and masonry wall top plate. Install new blocking with boundary nailing between the ceiling sheathing and blocking, and Simpson A35 clip angles between the blocking and top plate and blocking and ceiling joists, as appropriate. | Study | | ENG ONLY | \$0 | \$2,100 | \$2,100 |
| Install Simpson A35 Clips | Install Simpson A35 clips between ceiling joists and masonry wall top plate in conjunction with cross tie retrofit described in next bullet item. | Contingency | | | \$0 | \$0 | \$0 |
| Correct CMU Wall Support | Install a combination of blocking, steel straps, and metal connector hardware to provide adequate out-of-plane support for CMU wall | Contingency | 1 | LS | \$24,180 | \$8,947 | \$33,127 |
| Further Assessment Necessary | Conduct nondestructive scanning to verify the size and location of masonry wall vertical reinforcing. If vertical trim reinforcing is not provided adjacent to door openings, install face mounted steel plates through-bolted to masonry wall and anchored to foundation. | Study | 1 | 0 | \$7,540 | \$2,790 | \$10,330 |
| Repair Door Opening | | Contingency | | EA - assumed openings | \$4,290 | \$6,300 | \$10,590 |
| Corrosion Assessment | Investigate extent and severity of the corrosion damage to the steel column, repair damage (as appropriate), and mitigate cause of moisture to prevent similar future damage. | Study | | | \$0 | \$3,150 | \$3,150 |
| Remediate steel Corrosion | | Contingency | 6 | ea | \$51,220 | \$18,951 | \$70,171 |
| Pipe Bracing | Provide bracing for the piping. | | 8 | EA - assumed Locations | \$14,820 | \$5,483 | \$20,303 |
| Valve Bracing | Provide independent bracing for the valves. | | 4 | EA | \$7,410 | \$2,742 | \$10,152 |
| Valve Bracing | Provide independent support and bracing for the air relief valve | | 4 | EA | \$1,950 | \$722 | \$2,672 |
| Pump Bracing | Brace Pump(s) motor(s). | Contingency | 3 | EA | \$12,740 | \$4,714 | \$17,454 |
| Further Assessment Necessary | Perform additional analysis to evaluate the adequacy of the existing connection of the motor to the top of the steel motor support, the motor support, the connection of the motor support to the concrete pedestal, and the concrete pedestal. | Study | | | \$0 | \$4,200 | \$4,200 |
| Flexible Coupling | Add flexible couplings between the pumps and the connected piping. | Contingency | 1 | EA | \$13,390 | \$4,954 | \$18,344 |
| Electrical Flexible Coupling | Provide flexible couplings where conduits connect to the top of floor- and wall-mounted electrical panels and cabinets | | 10 | EA | \$7,540 | \$2,790 | \$10,330 |
| Anchor Pump Station Control Cabinet | Provide anchorage/bracing of pump station control cabinet to floor and wall. | | 6 | LF | \$520 | \$1,575 | \$2,095 |
| Lens Cover | Provide lens covers for light fixtures with safety devices that prevent the lens cover and light bulbs from falling. | | 4 | EA Assumed | \$1,300 | \$481 | \$1,781 |
| Anchor Electrical Transformer | Coordinate with electrical utility to anchor the utility owned electrical transformer to the concrete pad, as required. | | 1 | LS | \$2,080 | \$3,150 | \$5,230 |
| Total Cost | | | | | \$185,954 | \$98,822 | \$284,776 |

ATTACHMENT A

| Boone Road Pump Station | | | | | | | |
|---|---|--|----------|------------|----------------------|---------------------|-------------------------------|
| Remedial Action | Description | Category of Work (Base, Study, or Contingency) | Quantity | Unit | Construction Cost | Engineering Cost | Total Construction Cost |
| Further Assessment Necessary | Perform an investigation to determine if the gable end framing, sheathing nailing, and connection details are adequate to deliver seismic forces from the upper roof to the lower roof. If not, add supplemental nailing, framing, blocking, and/or metal connector hardware, as appropriate. | Study | | | \$6,931 | \$8,400 | \$15,331 |
| Contingency Item - Remediate Gable | This is the cost to remediate the above repairs if needed. | Contingency | | | \$11,700 | \$8,400 | \$20,100 |
| Wood Structural Overlay | Install a wood structural panel overlay on top of the existing straight sheathing. The joints of the wood structural panels should be placed so that they are near the center of the existing sheathing boards or at a 45-degree angle to the joints between existing sheathing boards. | Contingency | | | \$58,760 | \$21,741 | \$80,501 |
| Correct CMU Wall Support | Install a combination of sub-diaphragm framing and connection hardware at the roof level to provide adequate out-of-plane support for CMU walls | Contingency | 140 | LF | \$3,640 | \$1,347 | \$4,987 |
| Pipe Bracing | Provide bracing for the piping. | | 3 | EA | \$11,180 | \$4,137 | \$15,317 |
| Valve Bracing | Provide independent bracing for the valves | | 3 | EA | \$11,180 | \$4,137 | \$15,317 |
| Pump Bracing | Brace Pump(s) motor(s). | Contingency | 3 | EA | \$12,740 | \$4,714 | \$17,454 |
| Further Assessment Necessary | Perform additional analysis to evaluate the adequacy of the existing connection of the motor to the top of the steel motor support, the motor support, the connection of the motor support to the concrete pedestal, and the concrete pedestal. | Study | | | \$0 | \$4,200 | \$4,200 |
| Flexible Coupling | Add flexible couplings between the pumps and the connected piping. | | 3 | EA | \$39,910 | \$14,767 | \$54,677 |
| Cable Tray Bracing | Provide longitudinal bracing for the cable tray. Reconfigure the anchorage of the transverse bracing strut to avoid anchorage into the masonry head joints. | | 1 | LS | \$9,360 | \$3,463 | \$12,823 |
| Lens Cover | Provide lens covers for light fixtures with safety devices that prevent the lens cover and light bulbs from falling | | 4 | EA Assumed | \$1,300 | \$481 | \$1,781 |
| Support Framing Bracing | Provide grating clip connections between the grating and steel support framing | | 16 | LF | \$1,950 | \$722 | \$2,672 |
| Further Assessment Necessary | Verify the adequacy of the connection between the horizontal antenna and the supporting pole. | Study | 1 | EA | \$4,160 | \$1,539 | \$5,699 |
| Contingency Item to seismically strengthen Antenna. | | Contingency | 1 | LS | \$5,720 | \$2,116 | \$7,836 |
| | Total Cost | | | | \$178,531 | \$80,163 | \$258,694 |

ATTACHMENT A

| Candalaria Reservoir and Valve Vault | | | | | | | |
|--------------------------------------|---|--|----------|------|----------------------|---------------------|-------------------------------|
| Remedial Action | Description | Category of Work (Base, Study, or Contingency) | Quantity | Unit | Construction Cost | Engineering Cost | Total Construction Cost |
| ASCE Tier 2 Assessment | Perform a future ASCE 41 Tier 2 assessment to confirm the adequacy of the provided column reinforcing lap splice length. SEFT indicates that they don't anticipate this being an issue. | Study | | | \$0 | \$8,400 | \$8,400 |
| Further Assessment Necessary | Verify that piping, fittings, and valve bodies are constructed of steel or ductile iron. Replace any components that are suspected to be cast iron. | Study | 3 | Days | \$53,950 | \$19,962 | \$73,912 |
| Contingency Item | Replace significant portion of reservoir Piping internals. | Contingency | | | \$168,740 | \$62,434 | \$231,174 |
| Further Assessment Necessary | Perform additional analysis to evaluate the adequacy of the overflow pipe and valve operator riser shafts to resist seismic forces. Provide lateral bracing of the overflow pipe and valve operator riser shafts, as required | Study | 3 | EA | \$13,390 | \$4,954 | \$18,344 |
| Backup Battery Restraints | Provide restraint of backup batteries, as required | | 1 | EA | \$520 | \$192 | \$712 |
| | Total Cost | | | | \$236,600 | \$95,942 | \$332,542 |

ATTACHMENT A

| Champion Hill Reservoir Control Building | | | | | | | |
|--|---|--|----------|--------------|----------------------|---------------------|-------------------------------|
| Remedial Action | Description | Category of Work (Base, Study, or Contingency) | Quantity | Unit | Construction Cost | Engineering Cost | Total Construction Cost |
| Blocking Support | Add blocking to support the edges of the roof sheathing panels and provided boundary nailing between the roof sheathing and blocking. | | 1,748 | SF Footprint | \$36,660 | \$13,564 | \$50,224 |
| Install Simpson A35 Clips | Install Simpson A35 clip angles, at approximately 2-feet on center, between gable end truss bottom chord and masonry wall top plate. | | 76 | LF | \$5,850 | \$2,165 | \$8,015 |
| Correct Wall Connection | Install appropriate metal connector hardware to provide a vertical connection between the blocking that the kicker brace frames into and the adjacent roof trusses. Provide local strengthening of trusses, as appropriate. | | 92 | LF | \$7,540 | \$2,790 | \$10,330 |
| Flexible Pipe Joints | Provide appropriate flexible joints where water system piping penetrates through the control building wall to accommodate potential differential movement between the structure and the surrounding soil at or near the pipe penetration. | | 2 | ea | \$31,590 | \$11,688 | \$43,278 |
| Pipe Bracing | Provide bracing for the piping. | | 8 | EA | \$17,420 | \$6,445 | \$23,865 |
| Valve Bracing | Provide independent bracing for the valves. | | 8 | EA | \$9,490 | \$3,511 | \$13,001 |
| Pump Bracing | Provide independent bracing for the recirculation pump and associated piping. | | 1 | LS | \$3,380 | \$1,251 | \$4,631 |
| Pressure Tank Bracing | Provide an additional anchor at the base of the pressure tank. | | 1 | LS | \$520 | \$192 | \$712 |
| Backup Battery restraints | Provide restraint for backup batteries inside the battery cabinet. | | 1 | LS | \$910 | \$337 | \$1,247 |
| Further Assessment Necessary | Verify the adequacy of the antenna connection to the supporting pole. | Study | 1 | EA | \$4,160 | \$1,539 | \$5,699 |
| | Jim indicates that enhancement of attachment between antenna and pole likely, not bracing. Cost includes cost for a bucket truck for installation. | Contingency | 1 | LS | \$5,720 | \$2,116 | \$7,836 |
| Correct Wall Connection | Install a combination of blocking and metal connector hardware to provide adequate connections to transfer seismic forces from the ceiling to the masonry walls and eliminate the potential for cross-grain bending of wood ledgers. | | 1 | LS | \$10,400 | \$3,848 | \$14,248 |
| Electrical Cabinet Restraint | Provide restraint for temporarily stored electrical cabinets and other components (using straps to the wall, etc.). | | 1 | LS | \$1,430 | \$529 | \$1,959 |
| Electrical Transformer Bracing | Coordinate with electrical utility to conduct further evaluation to validate the seismic performance of pole-mounted transformer and utility pole. | | | ENG | \$0 | \$175 | \$175 |
| | Total Cost | | | | \$135,070 | \$50,151 | \$185,221 |

ATTACHMENT A

| Champion Hill Reservoir | | | | | | | |
|-------------------------|---|--|----------|------|----------------------|---------------------|-------------------------------|
| Remedial Action | Description | Category of Work (Base, Study, or Contingency) | Quantity | Unit | Construction Cost | Engineering Cost | Total Construction Cost |
| ASCE Tier 2 Assessment | Perform a future ASCE 41 Tier 2 assessment to evaluate the adequacy of the provided column reinforcing lap splice length | Study | | ENG | \$0 | \$8,400 | \$8,400 |
| Connection Brackets | Install connection brackets at the corners of the pipe support pedestals that are anchored to both the concrete pedestal and concrete floor slab. | | | | \$71,890 | \$26,599 | \$98,489 |
| | Total Cost | | | | \$71,890 | \$34,999 | \$106,889 |

ATTACHMENT A

| Creekside Pump Station | | | | | | | |
|---|---|--|----------|--------------|----------------------|---------------------|-------------------------------|
| Remedial Action | Description | Category of Work (Base, Study, or Contingency) | Quantity | Unit | Construction Cost | Engineering Cost | Total Construction Cost |
| Further Investigation - Roof Truss Inspection | Remove a small section of existing roofing to verify the adequacy of the existing roof sheathing to truss nailing. | Study | 4 | days | \$57,857 | \$21,407 | \$79,264 |
| Roof Blocking | Add blocking to support the edges of the roof sheathing panels and provided boundary nailing between the roof sheathing and blocking. | Contingency | 940 | SF Footprint | \$19,760 | \$7,311 | \$27,071 |
| Further Assessment Necessary | Perform an investigation to verify the adequacy of the connection between the roof sheathing and gable end masonry wall top plate. | Study | | ENG | \$0 | \$10,500 | \$10,500 |
| Correct CMU Wall Support | Install a combination of plywood, blocking, steel straps, and metal connector hardware to provide adequate out-of-plane support for CMU walls | Contingency | 124 | LF | \$24,180 | \$8,947 | \$33,127 |
| Pipe Bracing | Provide bracing for the piping. | | 3 | EA | \$11,180 | \$4,137 | \$15,317 |
| Valve Bracing | Provide independent bracing for the valves. | | 3 | EA | \$11,180 | \$4,137 | \$15,317 |
| Valve Bracing | Provide independent support and bracing for the air relief valves. | | 3 | EA | \$3,640 | \$1,347 | \$4,987 |
| Pump Bracing | Brace Pump(s) motor(s). | Contingency | 3 | EA | \$12,740 | \$4,714 | \$17,454 |
| Further Assesment Necessary | Perform additional analysis to evaluate the adequacy of the existing connection of the motor to the top of the steel motor support, the motor support, the connection of the motor support to the concrete pedestal, and the concrete pedestal. | Study | | | \$0 | \$4,200 | \$4,200 |
| Flexible Coupling | Add flexible couplings between the pumps and the connected piping. | | 3 | EA | \$39,910 | \$14,767 | \$54,677 |
| Contingency Item - Cabinet Anchorage | This assumes the electrical cabinets in item above require seismic reinforcement. | Contingency | 6 | LF | \$520 | \$1,575 | \$2,095 |
| Correct Wall Connections | Provide anchorage/bracing between the top of the electrical cabinets and masonry wall. | | 6 | LF | \$520 | \$192 | \$712 |
| Emergency Generator Bracing | Provide anchorage/bracing for emergency generator air intake support frame, muffler, and exhaust pipe. | | 3 | EA | \$11,050 | \$4,089 | \$15,139 |
| Anchor Electrical Transformer | Coordinate with electrical utility to anchor the utility owned electrical transformer to the concrete pad, as required. | | 1 | LS | \$2,080 | \$3,150 | \$5,230 |
| Total Cost | | | | | \$194,617 | \$90,471 | \$285,089 |

ATTACHMENT A

| Deer Park Pump Station | | | | | | | |
|-------------------------------------|---|--|----------|---------------------------|----------------------|---------------------|-------------------------------|
| Remedial Action | Description | Category of Work (Base, Study, or Contingency) | Quantity | Unit | Construction Cost | Engineering Cost | Total Construction Cost |
| Further Assessment Necessary | Conduct nondestructive scanning to verify the size and location of masonry wall reinforcing and evaluate the adequacy of the masonry walls. | Study | 4 | ea | \$40,876 | \$15,124 | \$56,000 |
| Contingency Item - Replace Superstr | Entire CMU superstructure may need to be replaced with equipment in place. (44 ft x 2- ft structure) | Contingency | 1,280 | SF Area | \$43,290 | \$16,017 | \$59,307 |
| Roof Replacement | Based on the number of potential deficiencies identified that are associated with the wood framed roof, suggest removing existing roof and replacing with new plywood sheathed wood truss roof with appropriate seismic detailing (including consideration of cross ties between diaphragm chords and out of plane bracing for perimeter and interior masonry walls). | Contingency | 1,300 | SF Approx Roofing Area | \$88,660 | \$32,804 | \$121,464 |
| Pipe Bracing | Provide bracing for the piping. | | 3 | EA | \$11,180 | \$4,137 | \$15,317 |
| Valve Bracing | Provide independent bracing for the valves | | 3 | EA | \$11,180 | \$4,137 | \$15,317 |
| Pump Support/Bracing | Install angles all around the perimeter of the pump support concrete pedestal with anchors into the floor slab. On two opposing sides, add a pair of steel straps that are welded to the angle and anchored up the face of the pedestal. | | 3 | EA | \$18,070 | \$6,686 | \$24,756 |
| Flexible Couplings | Add flexible couplings between the pumps and the connected piping. | | 3 | EA | \$39,910 | \$14,767 | \$54,677 |
| Pipe Support Anchoring | Add anchors through the pipe support stanchion base plates into the slab-on-grade at locations with missing anchors. | | 12 | EA | \$3,640 | \$1,347 | \$4,987 |
| Contingency Item - Cabinet Anchor | This assumes the electrical cabinets in item above require seismic reinforcement. | Contingency | 6 | LF | \$520 | \$1,575 | \$2,095 |
| Emergency Generator bracing | Re-install the restrainer bracket for the emergency generator starter batteries, as appropriate. | Contingency | 1 | LS | \$3,900 | \$1,443 | \$5,343 |
| Further Assessment Necessary | Verify the adequacy of the antenna connection to the supporting pole. | Study | 1 | EA | \$4,160 | \$1,539 | \$5,699 |
| Anchor Electrical Transformer | Coordinate with electrical utility to conduct further evaluation to validate the seismic performance of pole-mounted transformer and utility pole. | | 1 | LS | \$2,080 | \$3,150 | \$5,230 |
| TOTAL COST | | | | | \$267,466 | \$102,725 | \$370,192 |

ATTACHMENT A

Edwards Pump Station

| Remedial Action | Description | Category of Work (Base, Study, or Contingency) | Quantity | Unit | Construction Cost | Engineering Cost | Total Construction Cost |
|---|---|--|----------|------------------------------------|----------------------|---------------------|-------------------------------|
| Replace Pump Station | Based on the age of the structure and the number of potential deficiencies identified, it is recommended that the City consider replacing the Edwards Pump Station structure. | Contingency | 1200 | SF Approx Building Footprint | \$569,140 | \$210,582 | \$779,722 |
| Flexible Pipe Joints | Provide appropriate flexible joints where water system piping penetrates through the pump station floor to accommodate potential differential movement between the structure and the surrounding soil at or near the pipe penetration. | | 3 | EA | \$39,910 | \$14,767 | \$54,677 |
| Pipe Bracing | Provide bracing for the piping. | | 3 | EA | \$10,790 | \$3,992 | \$14,782 |
| Valve Bracing | Provide independent bracing for the valves. | | 3 | EA | \$10,790 | \$3,992 | \$14,782 |
| Pump Bracing | Brace Pump(s) motor(s). | Contingency | 3 | EA | \$12,740 | \$4,714 | \$17,454 |
| Further Assessment Necessary | Perform additional analysis to evaluate the adequacy of the existing connection of the motor to the top of the steel motor support, the motor support, the connection of the motor support to the concrete pedestal, and the concrete pedestal. | Study | | | \$0 | \$4,200 | \$4,200 |
| Flexible Couplings | Add flexible couplings between the pumps and the connected piping. | | 3 | EA | \$39,910 | \$14,767 | \$54,677 |
| Further Assessment Necessary | Perform an investigation to evaluate the adequacy of the anchorage of electrical cabinets to housekeeping pads and housekeeping pads to slab on grade, and supplement anchorage (as required). Also, provide anchorage/bracing between the top of the electrical cabinets and masonry wall. | Study | 6 | LF | \$1,040 | \$385 | \$1,425 |
| Flexible Electrical Couplings | Provide flexible couplings where conduits connect to the top of floor- and wall-mounted electrical panels and cabinets. | | 20 | EA | \$15,080 | \$5,580 | \$20,660 |
| Emergency Generator Bracing | Provide restraint for the emergency generator starter batteries | | 1 | LS | \$2,470 | \$914 | \$3,384 |
| Lens Cover | Provide lens covers for light fixtures with safety devices that prevent the lens cover and light bulbs from falling. | | 4 | EA Assumed | \$1,300 | \$481 | \$1,781 |
| Further Assessment Necessary | Verify the adequacy of the antenna connection to the supporting pole. | Study | 1 | EA | \$4,160 | \$1,539 | \$5,699 |
| Contingency Item to seismically strengthen Antenna. | Jim indicates that enhancement of attachment between antenna and pole likely, not bracing. Cost includes cost for a bucket truck for installation. | Contingency | 1 | LS | \$5,720 | \$2,116 | \$7,836 |
| HVAC Anchoring | Provide anchorage of the HVAC unit to the concrete pad. | | 1 | LS | \$2,470 | \$914 | \$3,384 |
| Grating Clips | Provide grating clip connections between the grating and steel support framing. | | 16 | LF | \$1,950 | \$722 | \$2,672 |
| Crane Restraints | Provide restraint for the overhead bridge crane, when not in use. | | 1 | LS | \$4,420 | \$1,635 | \$6,055 |

ATTACHMENT A

| Edwards Pump Station | | | | | | | |
|-------------------------------|--|--|----------|------|----------------------|---------------------|-------------------------------|
| Remedial Action | Description | Category of Work (Base, Study, or Contingency) | Quantity | Unit | Construction Cost | Engineering Cost | Total Construction Cost |
| Rolling Lift Restraints | Provide restraint for rolling lifts, when not in use. | | 1 | LS | \$1,690 | \$625 | \$2,315 |
| Ladder Restraints | Provide restraint for ladders (using straps to the wall, etc.), when not in use. | | 1 | LS | \$780 | \$289 | \$1,069 |
| Anchor Electrical Transformer | Coordinate with electrical utility to conduct further evaluation to validate the seismic performance of pole-mounted transformer and utility pole. | | 1 | LS | \$2,080 | \$3,150 | \$5,230 |
| TOTAL COST | | | | | \$726,440 | \$275,363 | \$1,001,803 |

ATTACHMENT A

| Eola #1B Reservoir | | | | | | | |
|--------------------------------------|--|--|----------|------|----------------------|---------------------|-------------------------------|
| Remedial Action | Description | Category of Work (Base, Study, or Contingency) | Quantity | Unit | Construction Cost | Engineering Cost | Total Construction Cost |
| contingency Item - Repair roof Crack | Assume 1/3 of wall to roof connection will require roof dowels. This is a 92 ft dia reservoir that is completely buried, except for roof. | Contingency | 110 | ea | \$14,040 | \$5,195 | \$19,235 |
| ASCE Tier 2 Assessment | Perform a future ASCE 41 Tier 2 assessment to confirm the adequacy of the provided column reinforcing lap splice length. SEFT indicates that they don't anticipate this being an issue. | Study | | ENG | \$0 | \$8,400 | \$8,400 |
| Stainless Steel Plates | Install stainless steel plates and/or angles to connect riser, base, and lid precast components at the precast concrete construction joints. | | 1 | LS | \$13,650 | \$5,051 | \$18,701 |
| Pipe Bracing | Supplement existing bracing for vertical section of inlet pipe. | | 1 | LS | \$30,680 | \$11,352 | \$42,032 |
| Valve Bracing | Perform additional analysis to evaluate the adequacy of the piping and valves to resist seismic forces (e.g., span between vault walls). Alternatively, provide bracing for the piping and valves inside the valve vaults. | | 1 | ea | \$11,570 | \$4,281 | \$15,851 |
| | Total Cost | | | | \$69,940 | \$34,278 | \$104,218 |

ATTACHMENT A

| Fairmont Reservoir Control Building | | | | | | | |
|---|---|--|----------|------|----------------------|---------------------|-------------------------------|
| Remedial Action | Description | Category of Work (Base, Study, or Contingency) | Quantity | Unit | Construction Cost | Engineering Cost | Total Construction Cost |
| Pipe Bracing | Provide bracing for the piping. | | 1 | LS | \$26,650 | \$9,861 | \$36,511 |
| Valve Bracing | Provide independent bracing for the valves and valve actuators. | | 1 | LS | \$17,940 | \$6,638 | \$24,578 |
| Pump Bracing | Provide bracing/restraint for vertical pump bells and valve operator riser shafts. | | 1 | LS | \$4,290 | \$1,587 | \$5,877 |
| Pipe Replacement | Replace any piping and valve components that are suspected to be cast iron. | | 1 | LS | \$12,480 | \$4,618 | \$17,098 |
| Corrosion Assessment and Replacement | Replace any corrosion damaged piping and valve components and connection hardware not already replaced by the bullet item above. | Contingency | 1 | LS | \$12,480 | \$4,618 | \$17,098 |
| Pump Base Bracing | Provide anchorage between pump bases and concrete slab. | | 1 | LS | \$4,420 | \$1,635 | \$6,055 |
| Further Assessment Necessary | Perform additional analysis to evaluate the adequacy of the existing connection of the motor to the top of the steel motor support, the motor support, the connection of the motor support to the concrete pedestal, and the concrete pedestal. | Study | | | \$0 | \$4,200 | \$4,200 |
| Further Assessment Necessary | Perform additional analysis to evaluate the adequacy of the existing connection of the motor to the top of the steel motor support, the motor support, the connection of the motor support to the concrete pedestal, and the concrete pedestal. | Study | | | \$0 | \$4,200 | \$4,200 |
| Flexible Couplings | Add flexible couplings between the pumps and the connected piping | | 1 | LS | \$31,590 | \$11,688 | \$43,278 |
| Pipe Bracing | Provide bracing for the air vent vertical pipe | | 1 | LS | \$4,420 | \$1,635 | \$6,055 |
| Further Assessment Necessary | Perform an investigation to evaluate the adequacy of the anchorage of electrical cabinets to concrete floor slab, and supplement anchorage (as required). Also, provide anchorage/bracing between the top of the electrical cabinets and concrete wall. | Study | 12 | LF | \$2,990 | \$1,106 | \$4,096 |
| Further Assessment Necessary | Verify the adequacy of the connection between the horizontal antenna and the supporting pole. | Study | 1 | EA | \$4,160 | \$1,539 | \$5,699 |
| Contingency Item to seismically strengthen Antenna. | | Contingency | 1 | LS | \$5,720 | \$2,116 | \$7,836 |
| | Total Cost | | | | \$127,140 | \$55,442 | \$182,582 |

ATTACHMENT A

| Fairmount Reservoir | | | | | | | | |
|--|--|--|----------|------|--------------------|--------------------------------------|------------------|-------------------------|
| Remedial Action | Description | Category of Work (Base, Study, or Contingency) | Quantity | Unit | Construction Cost | Engineering Cost (% of Construction) | Engineering Cost | Total Construction Cost |
| Shotcrete | Add a 6-inch layer of shotcrete at the inside face of the perimeter walls and footings | | 683 | CY | \$1,704,768 | \$630,764 | \$630,764 | \$2,335,532 |
| Correct Roof Connections | Provide stainless steel connections along the roof expansion joints to transfer shear forces between roof panels. Also, provide anchors between the roof slab and the walls to transfer roof seismic loads to the perimeter walls. | | 73,728 | SF | \$80,340 | \$29,726 | \$29,726 | \$110,066 |
| Further Assessment Necessary | Perform a future structural assessment to evaluate the potential impact of the interaction between the Fairmount Reservoir and the integrally constructed Fairmount Reservoir Control Building/Pump Station. | Study | | ENG | \$0 | \$0 | \$21,000 | \$21,000 |
| ASCE Tier 2 Assessment | Perform a future ASCE 41 Tier 2 assessment to confirm the adequacy of the provided column reinforcing lap splice length. SEFT indicates that this is unlikely to result in remedial work | Study | | ENG | \$0 | \$0 | \$8,400 | \$8,400 |
| Contingency Item - Reservoir Mechanical Replacement of interior piping | Complete | Contingency | | | \$280,410 | \$103,752 | \$103,752 | \$384,162 |
| Electrical Transformer Bracing | Coordinate with electrical utility to conduct further evaluation to validate the seismic performance of pole-mounted transformer and utility pole. | | | ENG | \$0 | \$0 | \$175 | \$175 |
| | Total Cost | | | | \$2,065,518 | \$764,242 | \$793,817 | \$2,859,335 |

ATTACHMENT A

Grice Hill Reservoir Control Building

| Remedial Action | Description | Category of Work (Base, Study, or Contingency) | Quantity | Unit | Construction Cost | Engineering Cost | Total Construction Cost |
|-------------------------------|--|--|----------|--------------|-------------------|------------------|----------------------------|
| Blocking Support | Add blocking to support the edges of the roof sheathing panels and provided boundary nailing between the roof sheathing and blocking. | | 1,665 | SF Footprint | \$34,909 | \$12,916 | \$47,825 |
| Roof Truss Bracing | Install appropriate metal connector hardware to provide a vertical connection between the blocking that the kicker brace frames into and the adjacent roof trusses. Provide local strengthening of trusses, as appropriate. | | 1 | LS | \$23,400 | \$8,658 | \$32,058 |
| Pipe Bracing | Provide bracing for the piping. | | 6 | EA | \$11,180 | \$4,137 | \$15,317 |
| Valve Bracing | Provide independent bracing for the valves | | 3 | EA | \$5,590 | \$2,068 | \$7,658 |
| Valve Seismic Improvement | Repair seismic valve so that is operational in the event of an earthquake. | | 1 | LS | \$7,540 | \$2,790 | \$10,330 |
| Tank Bracing | Provide anchorage of the pressure tank. | | 1 | LS | \$1,430 | \$529 | \$1,959 |
| Backup Battery Restraints | Provide additional restraint for backup batteries inside the battery cabinet | | 1 | LS | \$780 | \$289 | \$1,069 |
| Correct Wall Connection | Install a combination of blocking and metal connector hardware to provide adequate connections to transfer seismic forces from the ceiling to the masonry walls and eliminate the potential for cross-grain bending of wood ledgers. | | 1 | LS | \$13,130 | \$4,858 | \$17,988 |
| Electrical Cabinet Restraints | Provide restraint for temporarily stored electrical cabinets and other components (using straps to the wall, etc.). | | 1 | EA | \$780 | \$289 | \$1,069 |
| Ladder Restraints | Provide restraint for ladder (using straps to the wall, etc.), when not in use. | | 1 | EA | \$390 | \$144 | \$534 |
| Anchor Electrical Transformer | Coordinate with electrical utility to anchor the utility owned electrical transformer to the concrete pad, as required. | | 1 | LS | \$2,080 | \$3,150 | \$5,230 |
| Total Cost | | | | | \$101,209 | \$39,828 | \$141,037 |

ATTACHMENT A

| Grice Hill Reservoir | | | | | | | |
|---------------------------|---|--|----------|------------|-------------------------------|------------|---------------------|
| Remedial Action | Description | Category of Work (Base, Study, or Contingency) | Quantity | Unit | Total Construction Cost | Study Work | Contingency Work |
| ASCE 24 Tier 2 Assessment | Perform a future ASCE 41 Tier 2 assessment to confirm the adequacy of the provided column reinforcing lap splice length. SEFT indicates that they don't believe this will result in remedial work | Study | 1 | Assessment | \$19,632 | \$0 | \$19,632 |
| | Total Cost | | | | \$35,127 | \$0 | \$19,632 |

ATTACHMENT A

Limelight Pump Station

| Remedial Action | Description | Category of Work (Base, Study, or Contingency) | Quantity | Unit | Construction Cost | Engineering Cost | Total Construction Cost |
|---|---|--|----------|--------------|----------------------|---------------------|-------------------------------|
| Further Assessment Necessary | Perform an evaluation of the potential impact of the vertical cracks in the masonry shear walls on the seismic performance of the pump station and implement an appropriate repair concept. Implement repairs of localized deterioration of plywood sheathing and framing to restore these components to their original strength | Study | 1 | LS | \$15,575 | \$5,763 | \$21,338 |
| Contingency Item - Replace superstructure | Replace pump Station superstructure. | Contingency | | | \$158,600 | \$58,682 | \$217,282 |
| New Shaped Blocking | Install new shaped blocking between the roof sheathing and masonry wall top plate. Provided boundary nailing between the roof sheathing and blocking, and Simpson A35 clip angles between the blocking and top plate and blocking and trusses. Also, suggest engaging the shear resistance of the interior masonry wall by adding a combination of plywood sheathing, framing/blocking, and metal connector hardware to provide a load path between the roof diaphragm and the interior masonry wall. | | 820 | SF Footprint | \$17,290 | \$6,397 | \$23,687 |
| Further Assessment Necessary | Perform an investigation to verify the adequacy of the connection between the roof sheathing, gable end triangular portion wood framed shear walls and masonry wall top plate below. | Study | | | \$23,010 | \$8,514 | \$31,524 |
| Correct CMU Wall Support | Install a combination of plywood sheathing, blocking, steel straps, and metal connector hardware to provide adequate out-of-plane support for CMU walls. The concept is similar to that shown in Figure 4.5, for the Creekside Pump Station, except that all three sub-diaphragms should be installed with added plywood at the at the ceiling level, since the masonry portion of the gable end walls | | 116 | LF | \$24,960 | \$9,235 | \$34,195 |
| Pipe Bracing | Provide bracing for the piping. | | 3 | EA | \$11,180 | \$4,137 | \$15,317 |
| Valve Bracing | Provide independent bracing for the valves. | | 3 | EA | \$11,180 | \$4,137 | \$15,317 |
| Valve Bracing | Provide independent support and bracing for the air relief valves. | | 3 | EA | \$3,640 | \$1,347 | \$4,987 |
| Pump Bracing | Brace Pump(s) motor(s). | Contingency | 3 | EA | \$12,740 | \$4,714 | \$17,454 |
| Further Assesment Necessary | Perform additional analysis to evaluate the adequacy of the existing connection of the motor to the top of the steel motor support, the motor support, the connection of the motor support to the concrete pedestal, and the concrete pedestal. | Study | | | \$0 | \$4,200 | \$4,200 |
| Flexible Couplings | Add flexible couplings between the pumps and the connected piping. | Contingency | 3 | EA | \$39,910 | \$14,767 | \$54,677 |
| Further Assessment Necessary | Perform an investigation to evaluate the adequacy of the anchorage of electrical cabinets to housekeeping pads and housekeeping pads to slab on grade, and supplement anchorage (as required). Also, provide anchorage/bracing between the top of the electrical cabinets and masonry wall. | Study | 20 | LF | \$2,990 | \$1,106 | \$4,096 |
| Contingency Item - Cabinet Anchorage | This assumes the electrical cabinets in item above require seismic reinforcement. | Contingency | 6 | LF | \$520 | \$1,575 | \$2,095 |
| Further Assesment Necessary | Verify the adequacy of the antenna connection to the supporting pole. | Study | 1 | EA | \$4,160 | \$1,539 | \$5,699 |
| Seismically strengthen Antenna | This is a contingency item in case work is needed as determined in the item above. | Contingency | 1 | LS | \$6,240 | \$2,309 | \$8,549 |
| Anchor Electrical Transformer | Coordinate with electrical utility to anchor the utility owned electrical transformer to the concrete pad, as required. | | 1 | LS | \$2,080 | \$3,150 | \$5,230 |
| | Total Cost | | | | \$334,075 | \$131,571 | \$465,646 |

ATTACHMENT A

| Lone Oak Reservoir Control Building | | | | | | | |
|-------------------------------------|---|---|----------|------|-------------------|------------------|-------------------------|
| Remedial Action | Description | Cost Estimating Assumptions | Quantity | Unit | Construction Cost | Engineering Cost | Total Construction Cost |
| Pipe Bracing | Provide bracing for the piping. | | 6 | EA | \$11,180 | \$4,137 | \$15,317 |
| Valve Bracing | Provide independent bracing for the valves. | Assume one floor mounted pipe | 3 | EA | \$5,590 | \$2,068 | \$7,658 |
| Anchor Pressure Tank | Provide anchorage of the pressure tank. | | 1 | LS | \$1,430 | \$529 | \$1,959 |
| Further Assessment Necessary | Perform an investigation to evaluate the adequacy of the anchorage of control cabinet to housekeeping pad, and supplement anchorage (as required). Also, provide anchorage/bracing between the top of the control cabinet and masonry wall. | | 1 | LS | \$1,300 | \$481 | \$1,781 |
| Further Assessment Necessary | Perform an investigation to evaluate the adequacy of the anchorage of the battery cabinet to the control cabinet, and supplement anchorage (as required). | | | ENG | \$0 | \$0 | \$0 |
| Backup Battery Restraints | Provide restraint for backup batteries inside the battery cabinet. | | 1 | LS | \$780 | \$289 | \$1,069 |
| Further Assessment Necessary | Verify the adequacy of the antenna connection to the supporting pole | | 1 | EA | \$4,160 | \$1,539 | \$5,699 |
| Further Assessment Necessary | Perform an investigation to evaluate the adequacy of the bracing of the suspended HVAC unit, and supplement bracing (as required). | | | ENG | \$0 | \$525 | \$525 |
| Contingency Item | Install HVAC Bracing for item above | | | 960 | \$1,560 | \$577 | \$2,137 |
| Further Assessment Necessary | Perform an investigation to evaluate the adequacy of the anchorage of the water heater/safety shower base skid to the concrete slab, and supplement anchorage (as required). | | | ENG | \$0 | \$525 | \$525 |
| Contingency Item | Install Bracing for item above | | | 960 | \$1,560 | \$577 | \$2,137 |
| Further Assessment Necessary | Perform an investigation of the original deferred submittal design details for the chlorine room masonry wall reinforcing and top of wall bracing. Provide supplemental bracing of masonry walls, as required | DC - Please add contractor cost for 4 days contractor crew time | 4 | Days | \$26,000 | \$9,620 | \$35,620 |
| Ladder Restraints | Provide restraint for ladder (using straps to the wall, etc.), when not in use. | | 1 | LS | \$650 | \$241 | \$891 |
| Anchor Electrical Transformer | Coordinate with electrical utility to anchor the utility owned electrical transformer to the concrete pad, as required. | | 1 | LS | \$780 | \$289 | \$1,069 |
| | Total Cost | | | | \$54,990 | \$21,396 | \$76,386 |

ATTACHMENT A

| Mill Creek #1 Reservoir Control Building | | | | | | | |
|--|--|--|----------|--------------|-------------------|------------------|-------------------------|
| Remedial Action | Description | Category of Work (Base, Study, or Contingency) | Quantity | Unit | Construction Cost | Engineering Cost | Total Construction Cost |
| Blocking Support | Add blocking to support the edges of the roof sheathing panels and provided boundary nailing between the roof sheathing and blocking. | Contingency | 1,932 | SF Footprint | \$40,507 | \$14,988 | \$55,495 |
| Source Drawings for Further Assessment | Coordinate with the City to attempt to locate deferred submittal design drawings and calculations from original construction. Supplement available drawings with a detailed field investigation (including potential localized removal of architectural finishes) to observe and document details of the truss blocking and associated connections. Once additional details of original construction are available, evaluate the adequacy of the load path to transfer seismic forces from the roof diaphragm to the masonry wall top plate and develop mitigation concepts, as appropriate. | Study | 4 | days | \$24,960 | \$9,235 | \$34,195 |
| Truss Bracing | Install a combination of blocking and steel straps between truss bottom chord members in four additional truss bays per line of blocking. | Contingency | 1 | LS | \$16,380 | \$6,061 | \$22,441 |
| Pipe Bracing | Provide bracing for the piping. | | 6 | EA | \$11,180 | \$4,137 | \$15,317 |
| Valve Bracing | Provide independent bracing for the valves. | | 3 | EA | \$5,590 | \$2,068 | \$7,658 |
| Anchor Pressure Tank | Provide anchorage of the pressure tank. | | 1 | LS | \$1,430 | \$2,220 | \$3,650 |
| Pump Bracing | Brace Pump(s) motor(s). | Contingency | 3 | EA | \$12,740 | \$4,714 | \$17,454 |
| Further Assessment Necessary | Perform additional analysis to evaluate the adequacy of the existing connection of the motor to the top of the steel motor support, the motor support, the connection of the motor support to the concrete pedestal, and the concrete pedestal. | Study | | | \$0 | \$4,200 | \$4,200 |
| Flexible Couplings | Add flexible couplings between the pumps and the connected piping. | | 1 | LS | \$14,820 | \$5,483 | \$20,303 |
| Backup Battery Restraints | Provide restraint for backup batteries inside the battery cabinet. | | 1 | EA | \$520 | \$192 | \$712 |
| Further Assessment Necessary | Verify the adequacy of the antenna connection to the supporting pole. | Study | 1 | EA | \$4,160 | \$1,539 | \$5,699 |
| Correct Wall Connection | Install a combination of blocking and metal connector hardware to provide adequate connections to transfer seismic forces from the ceiling to the masonry walls and eliminate the potential for cross-grain bending of wood ledgers. | Contingency | 1 | LS | \$23,400 | \$8,658 | \$32,058 |
| Contingency Item - Brace Walls | Assume 20 ft of freestanding masonry wall to be braced | Contingency | 280 | SF Footprint | \$15,340 | \$5,676 | \$21,016 |
| Ladder Restraints | Provide restraint for ladders (using straps to the wall, etc.), when not in use. | | 1 | LS | \$650 | \$241 | \$891 |
| Anchor Electrical Transformer | Coordinate with electrical utility to anchor the utility owned electrical transformer to the concrete pad, as required. | | 1 | LS | \$2,080 | \$3,150 | \$5,230 |
| | Total Cost | | | | \$173,757 | \$72,561 | \$246,319 |

ATTACHMENT A

Mill Creek #1 Reservoir

| Remedial Action | Description | Category of Work (Base, Study, or Contingency) | Quantity | Unit | Construction Cost | Engineering Cost | Total Construction Cost |
|-----------------------------------|--|--|----------|------|----------------------|---------------------|-------------------------------|
| ASCE 41 Tier 2 Assessment | Perform a future ASCE 41 Tier 2 assessment to confirm the adequacy of the provided column reinforcing lap splice length. SEFT does | Study | | ENG | \$0 | \$8,400 | \$8,400 |
| Contingency Item - Reinforce Wall | | Contingency | 8792 | SF | \$680,290 | \$251,707 | \$931,997 |
| Pipe Support Bracing | Install connection brackets at the corners of the pipe support pedestals that are anchored to both the concrete pedestal and concrete floor slab. | | 1 | LS | \$7,670 | \$2,838 | \$10,508 |
| Seismic Separation | Provide additional seismic separation between the steel framed stair landing platform and reservoir concrete roof and/or provide diagonal bracing between stair landing support posts. | | 1 | LS | \$19,370 | \$7,167 | \$26,537 |
| | Total Cost | | | | \$707,330 | \$270,112 | \$977,442 |

ATTACHMENT A

| Mountain View Pump Station | | | | | | | |
|---|---|--|----------|--------------|----------------------|---------------------|-------------------------------|
| Remedial Action | Description | Category of Work (Base, Study, or Contingency) | Quantity | Unit | Construction Cost | Engineering Cost | Total Construction Cost |
| Roof Truss Repair | Reconfigure roof trusses and framing/blocking to provide plywood shear wall between roof diaphragm and top plate of north masonry wall. Also, suggest engaging the shear resistance of the interior north-south oriented masonry wall by adding a combination of plywood sheathing, framing/blocking, and metal connector hardware to provide a load path between the roof diaphragm and the interior masonry wall. | | 372 | SF | \$15,128 | \$5,597 | \$20,725 |
| Correct CMU Wall Support | Install a combination of plywood sheathing, blocking, steel straps, and metal connector hardware to provide adequate out-of-plane support for CMU walls | | 1,798 | SF Footprint | \$37,700 | \$13,949 | \$51,649 |
| Pipe Bracing | Provide bracing for the piping. | | 4 | EA | \$16,120 | \$5,964 | \$22,084 |
| Valve Bracing | Provide independent bracing for the valves. | | 4 | EA | \$16,120 | \$5,964 | \$22,084 |
| Valve Bracing | Provide independent support and bracing for the air relief valves | | 4 | EA | \$7,410 | \$2,742 | \$10,152 |
| Pump Bracing | Brace Pump(s) motor(s). | Contingency | 3 | EA | \$12,740 | \$4,714 | \$17,454 |
| Further Assessment Necessary | Perform additional analysis to evaluate the adequacy of the existing connection of the motor to the top of the steel motor support, the motor support, the connection of the motor support to the concrete pedestal, and the concrete pedestal. | Study | | | \$0 | \$4,200 | \$4,200 |
| Flexible Couplings | Add flexible couplings between the pumps and the connected piping | | 4 | EA | \$53,170 | \$19,673 | \$72,843 |
| Anchor Pipe Support | Add anchors through the pipe support stanchion base plates into the slab-on-grade at locations with missing anchors. | | 8 | EA | \$780 | \$289 | \$1,069 |
| Anchor Chlorination Equipment | Provide additional anchors for chlorination equipment and repair/replace damaged curb. | | 1 | LS | \$1,820 | \$673 | \$2,493 |
| Wall Bracing | Provide adequate anchorage between the strut and the masonry shear wall for seismic demands and provide positive connection between spacers and main strut. | | 1 | LS | \$1,820 | \$673 | \$2,493 |
| Transformer Bracing | Provide bracing for transformer hung from roof. | | 2 | EA | \$1,690 | \$625 | \$2,315 |
| Further Assessment Necessary | Perform an investigation to evaluate the adequacy of the anchorage of electrical cabinets to the slab on grade, and supplement anchorage (as required). Also, supplement the existing anchorage between the top of the electrical cabinets and masonry wall. | Study | 6 | LF | \$780 | \$289 | \$1,069 |
| Electrical Flexible Coupling | Provide flexible couplings where conduits connect to the top of floor- and wall-mounted electrical panels and cabinets. | | 4 | EA | \$3,120 | \$1,154 | \$4,274 |
| Emergency Generator Bracing | Provide restraint for the emergency generator starter batteries within the battery bins (e.g., strap) and anchorage of the battery bins. | | 1 | LS | \$910 | \$337 | \$1,247 |
| Emergency Generator Bracing | Provide bracing for the emergency generator muffler | | 1 | LS | \$780 | \$289 | \$1,069 |
| Lens Cover | Provide lens covers for light fixtures with safety devices that prevent the lens cover and light bulbs from falling | | 4 | EA | \$1,300 | \$481 | \$1,781 |
| Further Assessment Necessary | Verify the adequacy of the antenna connection to the supporting pole. | Study | 1 | EA | \$4,160 | \$1,539 | \$5,699 |
| Contingency Item to seismically strengthen Antenna. | | Contingency | 1 | EA | \$4,160 | \$1,539 | \$5,699 |
| Trolley Restraints | Provide restraint for overhead trolley chain hoist, when not in use | | 1 | LS | \$4,420 | \$1,635 | \$6,055 |
| Ladder Restraints | Provide restraint for ladders (using straps to the wall, etc.), when not in use. | | 1 | LS | \$650 | \$241 | \$891 |
| Electrical Transformer Bracing | Coordinate with electrical utility to anchor the utility owned electrical transformer to the concrete pad, as required. | | 1 | LS | \$2,080 | \$3,150 | \$5,230 |
| | Total Cost | | | | \$186,858 | \$75,718 | \$262,575 |

ATTACHMENT A

| Mountain View Reservoir | | | | | | | |
|--|---|--|----------|------|----------------------|---------------------|-------------------------------|
| Remedial Action | Description | Category of Work (Base, Study, or Contingency) | Quantity | Unit | Construction Cost | Engineering Cost | Total Construction Cost |
| Seismic Restraints | Install seismic restraint between the reservoir walls and foundation. Potential concepts include using brackets and high-strength rods installed from inside the reservoir or installing new seismic cables in a thickened wall section from the exterior of the reservoir. Both options would likely require modifying/enlarging the existing foundation ring. | | 76 | CY | \$265,574 | \$98,263 | \$363,837 |
| | Excavation of Existing Reservoir for Seismic Improvements | | 3,985 | CY | \$1,129,653 | \$417,972 | \$1,547,625 |
| CHOICE 2 | Re-wrap the core wall with additional circumferential prestressing strands encased with shotcrete to provide additional capacity to resist the combination of hydrostatic and expected hydrodynamic hoop forces during an earthquake. | | 459 | CY | \$1,076,924 | \$398,462 | \$1,475,386 |
| FRP Wrap | Provide fiber reinforced polymer (FRP) wrapping of columns. | | 1 | LS | \$143,290 | \$53,017 | \$196,308 |
| Contingency Item - Replace Reservoir Piping | Lump Sum to replace interior piping | Contingency | 25 | lf | \$49,321 | \$18,249 | \$67,570 |
| | Total Cost | | | | \$2,664,763 | \$985,962 | \$3,650,725 |

ATTACHMENT A

| Salem/Keizer Intertie #1 Pump Station | | | | | | | |
|---------------------------------------|---|--|----------|--------------|----------------------|---------------------|-------------------------------|
| Remedial Action | Description | Category of Work (Base, Study, or Contingency) | Quantity | Unit | Construction Cost | Engineering Cost | Total Construction Cost |
| Futher Assessment Necessary | Perform additional analysis to investigate the adequacy of the gap between the City of Salem pump station and the adjacent City of Keizer building. | Study | | ENG | \$0 | \$8,400 | \$8,400 |
| New Shaped Blocking | Install shaped blocking at the ridge line to bridge over the existing gap in the roof sheathing. Provide boundary nailing between the roof sheathing and new blocking. Coordinate with architect for any necessary modifications to roof venting. | | 572 | SF Footprint | \$11,180 | \$4,137 | \$15,317 |
| Wall Bracing | Install a combination of blocking and steel straps between truss bottom chord members in the two truss bays where blocking is not currently installed to provide continuous cross ties in the east-west direction. | | 130 | LF | \$8,580 | \$3,175 | \$11,755 |
| Flexible Pipe Joints | Provide appropriate flexible joints where water system piping penetrates through the pump station floor to accommodate potential differential movement between the structure and the surrounding soil at or near the pipe penetration. | | 3 | EA Assumed | \$39,910 | \$14,767 | \$54,677 |
| Pipe Bracing | Provide bracing for the piping. | | 3 | EA | \$12,090 | \$4,473 | \$16,563 |
| Valve Bracing | Provide independent bracing for the valves. | | 3 | EA | \$12,090 | \$4,473 | \$16,563 |
| Fleixble Couplings | Add flexible couplings between the pump and the connected piping. | | 1 | EA Assumed | \$14,300 | \$5,291 | \$19,591 |
| Chlorination Bracing | Provide anchorage of the chlorination skid to the concrete slab on grade and anchorage of chlorination system components to the skid. | | 1 | EA | \$520 | \$192 | \$712 |
| Further Assessment Necessary | Perform an investigation to evaluate the adequacy of the anchorage of electrical cabinets to the concrete housekeeping pads, and supplement anchorage (as required). | Study | 1 | LS | \$5,200 | \$1,924 | \$7,124 |
| Electrical Cabinet Bracing | Remove the existing L-shaped strut brackets at the top of the electrical cabinets and replace with a more appropriate steel bracket. | Contingency | 12 | LF | \$520 | \$1,575 | \$2,095 |
| Further Aessment Necessary | Verify the adequacy of the antenna connection to the supporting pole. | Study | 1 | EA | \$4,160 | \$1,539 | \$5,699 |
| Electrical Transformer Bracing | Coordinate with electrical utility to anchor the utility owned electrical transformer to the concrete pad, as required. | Contingency | 1 | LS | \$2,080 | \$3,150 | \$5,230 |
| | Total Cost | | | | \$110,630 | \$53,096 | \$163,726 |

ATTACHMENT A

Turner Control Facility

| Remedial Action | Description | Category of Work (Base, Study, or Contingency) | Quantity | Unit | Construction Cost | Engineering Cost | Total Construction Cost |
|---|---|--|----------|------------|-------------------|------------------|-------------------------|
| Geotechnical and Structural Assessment | Perform a site-specific geotechnical study to further evaluate the potential earthquake-induced liquefaction and lateral spreading hazard at the site. If required, mitigate the potential permanent ground deformation hazard at the site with geotechnical improvement, or other appropriate techniques. This scope also includes for a high-level structural evaluation of the geotechnical investigation results. | Study | | ENG | \$0 | \$10,500 | \$10,500 |
| Blocking Support | Add blocking to support the edges of the roof sheathing panels and provided boundary fasteners between the roof sheathing and blocking. | Contingency | 1,872 | SF | \$39,260 | \$14,526 | \$53,786 |
| Further Assessment Necessary | Perform an investigation to determine if adequate fasteners are provided for the roof sheathing to blocking and blocking to masonry wall top plate connections. Provide supplemental fasteners, as required | Study | 54 | EA | \$4,550 | \$8,400 | \$12,950 |
| Install Fasteners | Install additional fasteners between the roof sheathing and outriggers in conjunction with cross tie retrofit described in next bullet item | Contingency | 60 | EA | \$5,850 | \$2,165 | \$8,015 |
| Correct CMU Wall Support | Install a combination of blocking, steel straps, and metal connector hardware to provide adequate out-of-plane support for CMU walls in the direction perpendicular to the roof trusses | Contingency | 200 | LF | \$12,350 | \$4,570 | \$16,920 |
| Flexible Pipe Joints | Provide appropriate flexible joints where water system piping penetrates through the control facility wall to accommodate potential differential movement between the structure and the surrounding soil at or near the pipe penetration | | 1 | EA Assumed | \$15,860 | \$5,868 | \$21,728 |
| Pipe Bracing | Provide bracing for the piping. | | | | \$13,130 | \$4,858 | \$17,988 |
| Valve Bracing | Provide independent bracing for the valves. | | 2 | EA | \$8,840 | \$3,271 | \$12,111 |
| Valve Bracing | Provide independent bracing for the valve actuators. | | 2 | EA | \$3,380 | \$1,251 | \$4,631 |
| Anchor Control Cabinet | Provide anchorage of the control cabinet to the housekeeping pad | | 1 | EA | \$780 | \$289 | \$1,069 |
| Electrical Transformer Bracing | Provide supplemental anchorage of the electrical transformer to the concrete slab on grade. | | 1 | EA | \$650 | \$241 | \$891 |
| Backup Battery Restraints | Provide restraint for backup batteries inside the battery cabinet. | | 1 | EA | \$520 | \$192 | \$712 |
| Lighting Restraints | Provide restraint for pendant supported lights to prevent excessive swing. | | 1 | LS | \$1,690 | \$625 | \$2,315 |
| Lens Cover | Provide lens covers for light fixtures with safety devices that prevent the lens cover and light bulbs from falling. | | 8 | EA Assumed | \$2,600 | \$962 | \$3,562 |
| Further Assessment Necessary | Verify the adequacy of the connection between the horizontal antenna and the supporting pole. | Study | 1 | EA | \$4,160 | \$1,539 | \$5,699 |
| Contingency Item to seismically strengthen Antenna. | | Contingency | 1 | LS | \$8,450 | \$3,127 | \$11,577 |
| HVAC Bracing | Provide seismic bracing for the ceiling hung inline HVAC fan. | | 1 | LS | \$780 | \$289 | \$1,069 |
| HVAC Bracing | Provide anchors between the HVAC condenser unit and concrete support pad. | | 1 | LS | \$650 | \$241 | \$891 |
| Shelving Bracing | Provide anchorage or bracing for the storage shelving to the floor and/or the wall. | | 1 | LS | \$650 | \$241 | \$891 |
| Fire Extinguisher Restraints | Provide appropriate restraint for the fire extinguisher in its cabinet. | | 1 | LS | \$390 | \$144 | \$534 |
| | Total Cost | | | | \$124,540 | \$63,296 | \$187,836 |